

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

Sr.DSTE/BKN acting for and on behalf of The President of India invites E-Tenders against Tender No **SnT-BKN-2026-27-07** Closing Date/Time 10/06/2026 15:00 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

1. NIT HEADER

Name of Work	S&T associated indoor and outdoor work in c/w provision of track machine siding at PSV & BECN stations under the Jurisdiction of SSE/Sig/BKN over Bikaner Division.		
Bidding type	Normal Tender		
Tender Type	Open	Bidding System	Single Packet System
Tender Closing Date Time	10/06/2026 15:00	Date Time Of Uploading Tender	15/05/2026 19:28
Pre-Bid Conference Required	No	Pre-Bid Conference Date Time	Not Applicable
Advertised Value	20891761.92	Tendering Section	TECH SIG
Bidding Style	Single Rate for Tender	Bidding Unit	Above/Below/Par
Earnest Money (Rs.)	417800.00	Validity of Offer (Days)	60
Tender Doc. Cost (Rs.)	0.00	Period of Completion	12 Months
Contract Type	Works - General	Contract Category	Expenditure
Bidding Start Date	27/05/2026		
Are JV allowed to bid	No	Number of JV Member Allowed	0
Are Consortium allowed to bid	No	Number of Consortium Member Allowed	0
Ranking Order For Bids	Lowest to Highest	Expenditure Type	Track Renewal works (PH-31)

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A-SOR Items							15577192.10	
1	Please see Item Breakup for details.				5881387.90	AT Par	5881387.90	
	Description:- CHAPTER-1: Electronic Interlocking, Design of circuits and drawings.							
2	Please see Item Breakup for details.				19561.20	AT Par	19561.20	
	Description:- Chapter-2: DATA Logger, RTU, FEP, CMU, FAS and Networking accessories							
3	Please see Item Breakup for details.				2460680.27	AT Par	2460680.27	
	Description:- Chapter -3: Indoor Relays, Timers, Flasher, KLCR							
4	Please see Item Breakup for details.				286674.34	AT Par	286674.34	
	Description:- Chapter-4: Relay racks, CT racks, Tag Blocks, Terminal, Fuses, Indoor cables and Jumper wires							
5	Please see Item Breakup for details.				121947.50	AT Par	121947.50	
	Description:- Chapter -5: Power Supply Equipments, Batteries, Surge protection, Program Switches, DG sets							
6	Please see Item Breakup for details.				542371.30	AT Par	542371.30	
	Description:- Chapter -06: Points Machine							
7	Please see Item Breakup for details.				791606.35	AT Par	791606.35	
	Description:- Chapter 7: Track Circuit equipment, HASSDAC, MSDAC etc.							
8	Please see Item Breakup for details.				398635.87	AT Par	398635.87	
	Description:- Chapter-8: LED Main & Subsidiary signals, CLS units, Route Indicators & foundation etc.							
9	Please see Item Breakup for details.				67329.36	AT Par	67329.36	
	Description:- Chapter-9: Level Crossing Gates, Interlocking of LC gates, ELBs, Accessories etc.							
10	Please see Item Breakup for details.				44027.42	AT Par	44027.42	
	Description:- Chapter-10 : Panel room equipments, VDUs (Video Display Units), Fire alarm equipments, Furnitures							
	Please see Item Breakup for details.				676011.10	AT Par	676011.10	

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

11	Description:- Chapter-11: Apparatus case, Outdoor installation, Fuses, ARA Terminal, Hylam Sheet, Phenolic Laminated sheets							
12	Please see Item Breakup for details.			2208718.09	AT Par	2208718.09		
	Description:- Chapter-12: Cable laying material, Cable protection, Cable execution, Jointing Kits items etc.							
13	Please see Item Breakup for details.			50784.82	AT Par	50784.82		
	Description:- Chapter-13: Earthing, Measuring Instruments, Multimeter, Earth Tester, Clamp meters, Fault Locators, ELD(Earth Leakage Detector) etc.							
14	Please see Item Breakup for details.			88697.57	AT Par	88697.57		
	Description:- Chapter 14: Miscellaneous Signalling items, Painting, lettering							
15	Please see Item Breakup for details.			1938759.01	AT Par	1938759.01		
	Description:- Chapter- 15: Telecom items (Conference system, IPIS, OFC equipments, Control equipments, LC gate phones etc.)							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () B-Non-SOR Items							5314569.82	
1	NS1	60.00	Numbers	8330.11	499806.60	AT Par	499806.60	
	Description:- Supply and installation of Earth Electrode, including MS flat for Signalling Equipment, such as lever frames, apparatus cases, signal, Relay Rack, Block Instrument, etc. (Supply and fixing of each earth electrode as per drawing no. RE/S&T/DRG/Tender/SK/398/94 for apparatus cases, signal post and other equipment as per instruction on the earthing of S&T equipment. Laying of earth lead mild steel flat of size 35 mm x 6mm and fixing of lead M.S. flat to earth electrode and lever frame, signal post and apparatus cases as per drg.no. CORE/S&T/ALD/SK/591/2008,592/2008, and 593/2008, respectively and instructions on earthing at S&T equipment and providing a cement enclosure for the earth electrode as per drawing no. RE/S&T/Sig/Tender/SK/13/85Alt.- 'A'.) Inspection: (i) RDSO/RITES if the value of the item in work is more than 5 lakhs or as per the extant policy. (ii) Consignee subject to procurement from RDSO-approved vendors if any available for the value of the whole item in work less than 5 lakhs or as per the extant policy. Inspection Charges: (i) Borne by Railways (ii) None Payment Terms: 80% after Supply and 20% after execution.							
2	NS2	400.00	Man-Days	324.96	129984.00	AT Par	129984.00	
	Description:- Arrangement of Unskilled labour for miscellaneous S&T works as per the site engineer's instructions. Work execution sheet comprising the details of labour and type of work done needs to be attached with the measurement for billing purposes. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after execution.							
3	NS3	300.00	Man-Days	537.55	161265.00	AT Par	161265.00	
	Description:- Arrangement of skilled labour for miscellaneous S&T works as per the site engineer's instructions. The work execution sheet, comprising the details of labour and the type of work done, needs to be attached with the measurement for billing purposes. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after execution.							
4	NS4	500.00	MT-Km	19.73	9865.00	AT Par	9865.00	
	Description:- Transportation of signalling materials by road as per the instructions of the railway representative at site. The work also includes loading and unloading of the materails. Transportation upto 100 Kms. Inspection: Consignee Inspection Charges: None Payment Terms: 100% on execution.							
5	NS5	4000.00	MT-Km	12.06	48240.00	AT Par	48240.00	
	Description:- Transportation of signalling materials by road as per the instructions of the railway representative at site. The work also includes loading and unloading of the materails. Transportation more than 100 Kms. Inspection: Consignee Inspection Charges: None Payment Terms: 100% on execution.							
6	NS6	25.00	Numbers	3312.21	82805.25	AT Par	82805.25	
	Description:- Supply of magneto Telephone Desk Type (push button) spec No. TC-79/2000 with Amendment No. 3 or the latest. Inspection: (i) RDSO/RITES if the value of the item in work is more than 5 lakhs or as per the extant policy (ii) Consignee subject to procurement from RDSO-approved vendors if the value of the whole item in the work is less than 5 lakhs or as per the extant policy Inspection Charges: (i) Borne by Railways (ii) None Payment Terms: 100% after Supply.							
7	NS7	100.00	Per Relay	778.37	77837.00	AT Par	77837.00	
	Description:- Fixing and wiring of outdoor relays as per the instructions of the site engineer. It also includes the supply of all the necessary materials like PVC wire, thread required for wiring of outdoor relays. It also includes arranging all the necessary materials like solder wire, solder iron, thread, and wire fastener as per requirements for wiring of outdoor relays. This also includes proper dressing of the wire as per the instructions of the site engineer. Wiring is to be done by PVC insulated multi strand, single core copper conductor of size 16/0.2 mm (0.5sqmm) as per IS 694:2010 and RDSO Specn. No. IRS: S-76/89 (Amnd-3) or latest. Note: Only Relay will be supplied by the railways, and the colour of the wire will be decided by the consignee of the work or the site in charge. Inspection: Consignee Inspection Charges: None Payment Terms: 100% on execution.							

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

8	NS8	150.00	Per Relay	301.75	45262.50	AT Par	45262.50	
	Description:- Supply of necessary wiring material and wiring of input from relay to existing datalogger equipment as per instruction of site engineer. It also includes arrangement of all the necessary material like solder wire, solder iron, thread, wire fastener as per requirement for wiring of relays. This also includes proper dressing of wire as per instruction of site engineer. Wiring is to be done by PVC insulated multi strand, single core copper conductor of size 16/0.2 mm (0.5sqmm) as per IS 694:2010 and RDSO Specn. No. IRS:S-76/89 (Amnd-3) or latest. Note : Relay, PVC wire (16/0.2 mm) and Tag block will be supplied by railways and colour of wire will be decided by consignee of the work or site incharge. Inspection: Consignee Inspection Charges: None Payment Terms: 100% on execution.							
9	NS9	7.00	Numbers	22972.88	160810.16	AT Par	160810.16	
	Description:- Supply of DC-DCconvertor 24-32 V, 5 Amp as per RDSO Spec. No. RDSO/SPN/165/2012 version -3 or latest and compatible to existing make IPS system. Inspection: RDSO Inspection Charges: Borne by railways. Payment Terms: 100% after supply.							
10	NS10	5.00	Numbers	9333.14	46665.70	AT Par	46665.70	
	Description:- Installation of a DC-DC converter 24-32 V, 5 Amp, in the existing IPS system. This includes wiring/alteration in the existing IPS as per the site requirement. This also includes the supply of all necessary materials for the Installation of the DC-DC converter in the existing IPS system. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after execution.							
11	NS11	7.00	Numbers	24677.72	172744.04	AT Par	172744.04	
	Description:- Supply of DC-DCconvertor 24-32 V, 10Amp as per RDSO Spec. No. RDSO/SPN/165/2012 version -3 or latest and compatible to existing make IPS system. Inspection: RDSO Inspection Charges: Borne by railways. Payment Terms: 100% after supply.							
12	NS12	5.00	Numbers	9105.77	45528.85	AT Par	45528.85	
	Description:- Installation of DC-DC convertor 24-32 V, 10 Amp, in the existing IPS system. This includes wiring/alteration in the existing IPS as per site requirement. This also includes the supply of all necessary materials for the Installation of the DC-DC converter in the existing IPS system. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after execution.							
13	NS13	10.00	Numbers	7158.83	71588.30	AT Par	71588.30	
	Description:- Supply of Relay AC Immune Plug in type style QNNA1 DC Twin DC Neutral line relay 24- volt 6F/2B for LH and RH front and back contact metal to carbon complete with plug board retaining clip and connector confirming to BRS 960, IRS:S-23, IRS:S-34 and IRS: S@45<45N46@ The interlocking pin code CDEHX. Inspection: RDSO Inspection Charges: Borne by Railways Payment Terms: 100% on Supply							
14	NS14	50.00	Numbers	7158.83	357941.50	AT Par	357941.50	
	Description:- Supply of Relay AC Immune Plug in type style QNNA1 DC Twin DC Neutral line relay 24- volt 4F/4B for LH and RH front and back contact metal to carbon complete with plug board retaining clip and connector confirming to BRS 960, IRS:S-23, IRS:S-34 and IRS: S@45<45N46@ The interlocking pin code ACDHJ. Inspection: RDSO Inspection Charges: Borne by Railways Payment Terms: 100% on Supply							
15	NS15	2.00	Job	445992.96	891985.92	AT Par	891985.92	
	Description:- Factory Acceptance Test (FAT) as per approved signal interlocking plan in connection with alteration for provision of TMS at EI stations. i.e. at Bikaner East and Parsneu stations of Bikaner Division. Inspection: Consignee Inspection Charges: None Payment Terms: 100% on execution and submission of FAT certificate jointly signed by Railway and OEM of EI.							
16	NS16	10.00	Set	206500.00	2065000.00	AT Par	2065000.00	
	Description:- Supply, Installation, Testing, and Commissioning of Modular Power Supply Arrangement for VDU (42" to 85") and Industrial PC (Embedded PC) with input and output redundancy arrangement and hot pluggable modules in a set. One set consists of:- 1. Input O-Ring diode Module with potential-free free-1 no contacts (PFC) for two 110V DC sources from IPS and a Single 110V DC Bus.Quantity: 1 No.2. Isolated Inverters (Master/Slave), Input 110 V DC, Output: 110/120 V AC 500 VA Quantity: 2 Nos. 3. Isolated DC-DCConverters, Input 110V DC, Out Put24V DC/10A, Quantity: 2 nos.4.3U SS Rack with back Panel mother Board/front panel powerconnectors inverter auto changerover switch and all required overswitch and all required protection circuits (3U height for main rack132.5mm +/- 10% & 1U height for mounting 44.5mm +/-10%) Quantity; 1 No. (Total 4 items) Make: Gallant or Superior. Inspection: RDSO Inspection charges: Borne by Railways Payment terms: 80% after supply & 20% after commissioning.							
17	NS17	10.00	Set	38999.00	389990.00	AT Par	389990.00	
	Description:- Supply of TABLET for SMMS with following specifications as per HQ guidelines. The details are as follows:- 1. Processor - 2 Ghz octa core processor or better. 2. Screen Size - 11 Inches or above. 3. RAM Size - 8 GB or more. 4. Inetrnal Storage - 128 GB or more. 5. GPS - Yes 6. Operating System Detail - Androind 11.0 or higher. 7. Connectivity Type - Wi-Fi + Cellular 5G 8. Camera - Atleast 8MP (Rear) 9. Processor Architecture - 64 Bit. This also includes supply of following items:- (i). Bag for carrying Tablet. (ii) Tablet cover with shoulder strap and 360 degree rotating stand. Preferred Tablet Make - SAMSUNG/One Plus/Apple only. Inspection - Consignee Payment terms - 100% after supply							

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

18	NS18	10.00	Numbers	5725.00	57250.00	AT Par	57250.00	
Description:- Supply of 3.5-digit Backlit LCD Hand Held True Rms Clamp Meter of UNI-T (UT210E) or superior. Suitable for measurement of AC current in mAmp ranging (20mA-2A). Inspection: Consignee Inspection Charges: None Payment terms: 100% after Supply.								

3. ITEM BREAKUP

Schedule		Schedule A-SOR Items					
Item- 1		CHAPTER-1: Electronic Interlocking, Design of circuits and drawings.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount	
		Design, manufacture and supply of Hot Standby Architecture Electronic Interlocking (EI) system complete as per RDSO specification No. RDSO/SPN/192/2019 Ver. 2 or latest, as per technical requirement & tentative approved Signalling Plans & Diagrams. Electronic Interlocking (EI) system mainly consisting of Central Processing Equipment, Interface Equipment/Relays etc as per requirements, Dual operator Industrial Grade VDU panel (42" LED) with Redundancy (Hot stand-by dual VDU Normally one system online and other system in standby mode), All Interfacing Relays suitable for EI, interconnecting cables and Jumper wires, Industrial grade maintenance Terminals (32" LED with UPS minimum 1 hr back up), required power supply converters for EI equipments, Housing for EI equipments and Relay Racks, fuses, screw less disconnecting type terminals, fixture mounting arrangements and accessories necessary to make the EI system functional as per approved signaling plan. The tenderer should furnish complete details of cards/ modules/ sub-modules connectors etc. for each station. Supply of 10% Essential spares of the EI equipments subject to minimum one of each type mainly consisting of processor, cards/ module, interface relay etc. Item wise detailed break up with unit and quantity to be provided in separate annexure. (THIS ITEM SHALL BE USED ONLY FOR ALTERNATION WORK IN EXISTING EI) Inspection: RDSO Inspection charges: Borne by Railways Payment terms:100% after Supply.					
1	01010701	For Station with routes less than 100(Per unit should be read as Per Vital Bit of Station)	Per Unit	50.00	87987.65	4399382.50	

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

2	01010800	Installation, wiring, programming, testing and commissioning of EI equipment supplied as per supply item in item no. 1.7 above of Chapter 1 of this SOR including transportation from Consignee's depot to site. The works and materials for installation, wiring, testing and commissioning, grouting, cutting of floors, walls, refilling of the same, re-plastering, required CC/ masonry works, fixing/ placing/ laying of insulated ladders/ casing-capping/ cable trays/ RCC/GI pipes / Cables, termination of cables with lugs/ connectors, painting,/ lettering are to be provided/ done by the contractor for the equipments supplied vide item no. 7 of Chapter 1 of SOR. This also covers the networking of built in EI Data loggers of all the stations to monitor the system to any other places where desired by Engineer-in-charge. (THIS ITEM SHALL BE USED ONLY FOR ALERTTION WORK IN EXISTING EI) Note: Installation shall be comply to RDSO Technical Advisory Note No STE/E/TAN/3012 dtd. 28.08.2014. Installation, wiring, programming, testing and commissioning of Operator VDU in Hot stand-by with Redundancy. Any Equipments/cards/Modules required for Hot stand-by with Redundancy shall be supplied & Installed by the Contractor. Note:- This also includes supply of Two nos. of composite computer & printer table (Godrej work station table) and one no Godrej make operator chair model PCH7001. Termination of indoor/ PIJF cables in relay room on relays, tag blocks, CT racks as per approved wiring diagram including alterations/ modifications as required at site. Soldering to be done at all required termination. Dressing/ lacing of wiring shall be done neatly with help of dressing thread / plastic self lock strip of suitable size. The tools/ equipments/ materials/ simulation boards required for testing shall be supplied / fabricated by contractor. This includes replacement of modules/ cards/ LEDs/ equipments going defective during testing. Necessary power supply boards with required capacity plugs, sockets, surge & lightning protection boxes shall be supplied and installed by the contractor. 230V supply shall be arranged by Railways. In case supplies are required to be extended, from Power room / relay room then same shall be extended by the contractor with his own materials such as 1X16 sq mm wires, cables, lugs, RCC/GI pipes, insulated ladders etc. After ST/LT testing, Factory Acceptance Tests (FAT) & Square Sheet testing system should be fault free while submitting to Railways, otherwise suitable necessary action can be taken by Engineer-in-charge. Inspection: Consignee Inspection charges: None Payment terms: 100% after commissioning.	Job	2.00	542784.93	1085569.86
---	----------	--	-----	------	-----------	------------

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

3	01011300	Design, preparation & supply of drawings in computer print copies and original tracing in AUTO CAD FORMAT for Electronic Interlocking at each station. After completion of the work, the completion drawings incorporating completion details are to be supplied as per Technical Specifications given in tender document (upto 6 Line). The technical specifications are as per ANNEXURE 1.13 of SOR. Inspection: Consignee Inspection charges: None Payment terms: 100% after execution	Station	2.00	175967.35	351934.70
4	01012100	Preparation of SWR literature in english alongwith associated mid-section interlocked gate with all corrections as per approved SWRD & approved SIP. For this all technical corrections, editing, grammatical correction etc. are to be carried out and one rough print to be given to railways for approval before printing, as required for final processing of CRS sanction. This also includes preparation of maintenance cards in format provided by Rly. Inspection: Consignee Inspection charges: None Payment terms:100% after execution.	Station	2.00	3598.62	7197.24
5	01012200	Translation of Station Working Rules from english to hindi and framing out in DIGLOT form (or similar software)as per extant Rly practice. The required SWR in english will be provided by the contractor and has been covered separately in item no. 1.21 of Chapter 1 of this SOR. Inspection: Consignee Inspection charges: None Payment terms:100% after execution.	Station	2.00	4478.18	8956.36
6	01012300	Making photocopies & binding of the SWR literature in English/hindi/Diglot form as per Railway practice. Inspection: Consignee Inspection charges: None Payment terms:100% after execution.	Set	12.00	178.52	2142.24
7	01013000	Addition/alteration in existing relay room wiring. It includes supply of PVC insulated indoor Railway signalling cable @40<45@Core/40-Core) of (1/0.6) sqmm as per RDSO Spec.No.IRS/S-76/89 (Amnd.2 or latest) for wiring between relay room and SM's/Panel room & Relay room to DP in SM office for block working. This also includes supply of PVC insulated jumper wires of multi strand 16/2 mm, tinned in all colours as per RDSO Specn.No.IRS-S-76/89(Amnd.2 or latest). This item will include bringing all the power supplies from power room to respective bus bars on relay racks by using 10/6 sqmm copper flexible wire as per instructions of engineer incharge. This will include wiring between control panel and relay room if required. All wiring will be done as per standard practice of North Western Railway with neat dressing & threading. The item includes supply & wiring of tag block, fuse with bases(G-Type and ND Type) and all other related material required for complete indoor wiring in relay room. Inspection: Consignee Inspection charges: None Payment terms:100% after commissioning.	Per Relay	50.00	524.10	26205.00

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

					Total	5881387.90
Item- 2	Chapter-2: DATA Logger, RTU, FEP, CMU, FAS and Networking accessories					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	02011100	Installation and commissioning of Failure Analysis & Fault Diagnostic software for data logger upto 4096 digital inputs. Inspection: Consignee, Inspection charges: None Payment terms:100% after commissioning	Set	2.00	9780.60	19561.20
					Total	19561.20
Item- 3	Chapter -3: Indoor Relays, Timers, Flasher, KLCR					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	03010100	Supply of Relay fail safe electronic time delay device with fixed timing (0 -10) seconds and conforming to RDSO Specn.No.IRS:S-61/2000 with Amnd .1 or latest mounted on Q-series relay base & covered complete with connectors, retaining clip etc. Inspection authority:- RDSO Inspection charges:- Borne by Railways Payment Terms:- 100% after supply.	Numbers	5.00	2161.33	10806.65
2	03010200	Supply of Relay fail safe electronic time delay device with fixed timing (0 -120) seconds and conforming to RDSO Specn.No.IRS:S-61/2000 with Amnd.1 or latest mounted on Q-series relay base & covered complete with connectors, retaining clip etc.The interlocking code for this unit shall be ""AFGKY"". Inspection authority:- RDSO Inspection charges:- Borne by Railways Payment Terms:- 100% after supply.	Numbers	5.00	1836.67	9183.35
3	03010300	Supply of Relay fail safe electronic time delay device with fixed timing (0 @45<41@ seconds and conforming to RDSO Specn.No.IRS:S-61/2000 with Amnd.1 or latest mounted on Q-series relay base & covered complete with connectors, retaining clip etc.The interlocking code for this unit shall be ""AFHKY"". Inspection authority:- RDSO Inspection charges:- Borne by Railways Payment Terms:- 100% after supply.	Numbers	5.00	2093.91	10469.55
4	03010400	Supply of Fail safe electronic flasher device as per RDSO Specn.No.RDSO/SPN/173/ 2002 Amnd.2 or latest. Inspection authority:- RDSO Inspection charges:- Borne by Railways Payment Terms:- 100% after supply.	Numbers	5.00	8260.00	41300.00
5	03010500	Supply of Q-Series Neutral Line Relay (QN1 Type), 12F/4B, 24V DC complete with plug board(base plate), connectors and retaining clips etc and conforming to BRS- 930 and RDSO Specn.No.IRS:S-34 & S-23 or latest. The interlocking code for this unit shall be ""ABCDE"". Inspection authority:- RDSO Inspection charges:- Bornee by Railways Payment Terms:- 100% after supply.	Numbers	25.00	3943.56	98589.00

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

6	03010600	Supply of Q-Series Neutral Line Relay (QN1 Type), 8F/8B, 24V DC complete with plug board(base plate), connectors and retaining clips etc and conforming to BRS-930 and RDSO Specn.No.IRS:S-34 & S-23 or latest. The interlocking code for this unit shall be ""ABCD""". Inspection authority:- RDSO Inspection charges:- Borne by Railways Payment Terms:- 100% after supply.	Numbers	100.00	3789.37	378937.00
7	03010700	Supply of Q-Series Twin Neutral Line Relay(QNN1 Type), 6F/2B, 24V DC complete with plug board(base plate), connectors and retaining clips etc and conforming to BRS-960 and RDSO Specn.No.IRS:S-34 & S-23 or latest. The interlocking code for this unit shall be ""ACDEK""". Inspection authority:- RDSO Inspection charges:- Borne by Railways Payment Terms:- 100% after supply.	Numbers	5.00	4985.33	24926.65
8	03010800	Supply of Q-Series Twin Neutral Line Relay(QNN1 Type), 4F/4B, 24V DC complete with plug board(base plate), connectors and retaining clips etc and conforming to BRS-960 and RDSO Specn.No.IRS:S-34 & S-23 or latest. The interlocking code for this unit shall be ""ACEHJ""". Inspection authority:- RDSO Inspection charges:- Borne by Railways Payment Terms:- 100% after supply.	Numbers	20.00	3938.00	78760.00
9	03010900	Supply of Q-Series Magnetically Latched Neutral Line Relay (QL1 Type), 11F/4B,24V DC complete with plug board(base plate), connectors and retaining clips and conforming to BRS-935A and RDSO Specn.No.IRS:S-34 & S-23 or latest.The interlocking code for this unit shall be ""ABDEG""". Inspection authority:- RDSO Inspection charges:- Borne by Railways Payment Terms:- 100% after supply.	Numbers	75.00	5701.45	427608.75
10	03011300	Supply of Q-Series LED ECR (Universal Type i.e.QECX-61), 4F/4B complete with plug board(base plate), connectors, retaining clips etc and conforming to BRS:941A STS/E/RELAYS/AC LIT LED SIGNAL/09-2002 ,Amdt.-1and RDSO Specn.No.IRS:S-34 & S-23 or latest.The interlocking code for this unit shall be ""ABDHK""". Inspection authority:- RDSO Inspection charges:- Borne by Railways Payment Terms:- 100% after supply.	Numbers	100.00	4983.53	498353.00
11	03011400	Supply of Sealing wire used for sealing of signaling relays & equipments. Inspection authority:- Consignee Inspection charges:- None Payment Terms:- 100% after supply.	Kg	1.00	175.27	175.27

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

12	03011500	Fixing of Q series relay base plate/metal to metal relay mini group and major group base plate, laying, bunching, lacing, dressing & packeting of 60/40 core PVC indoor cable/flexible wire and termination of 60/40 core cable/flexible wire on tag block/base plate & base plates & soldering. This includes fuse wiring, bus bar looping etc. required for keeping installation ready for circuit wiring work & panel throughing work. The work shall be done as per approved plan, extant practice on NWR & the instruction of Rly. Engineer at site. Inspection authority:- Consignee Inspection charges:- None Payment Terms:- 100% after Commissioning	Numbers	100.00	390.37	39037.00
13	03011700	Supply of Track Relay QBAT, AC immunized, 2F-2B contacts, 9 ohms. Complete with plug board, retaining clip & connectors as per RDSO/SPN/84 Ver 2.0 or latest. The interlocking code for this unit shall be ""ABEJX"". Inspection authority:- RDSO Inspection charges:- Borne by Railways Payment Terms:- 100% after supply.	Numbers	3.00	7080.00	21240.00
14	03011800	Supply of Q-Series Line Relay (QNA1 Type), AC immunized, 8F/8B, 24 V DC along with plug board (base plate), connectors, retaining clips etc and conforming to BRS-931A and RDSO Specn.No.IRS:S@45"44@ S-23 and S-60 or latest. The interlocking code for this unit shall be ""ABDGH"". Inspection authority:- RDSO Inspection charges:- Borne by Railways Payment Terms:- 100% after supply.	Numbers	100.00	3913.67	391367.00
15	03011900	Supply of Q-Series Line Relay (QNA1 Type), AC immunized, 12F/4B, 24 V DC along with plug board (base plate), connectors, retaining clips etc and conforming to BRS-931A and RDSO Specn.No.IRS:S@45"44@ S-23 and S-60 or latest. The interlocking code for this unit shall be ""ABDFH"". Inspection authority:- RDSO Inspection charges:- Borne by Railways Payment Terms:- 100% after supply.	Numbers	25.00	3805.50	95137.50
16	03012000	Supply of Q-Series Track Relay (QTA2 Type), AC immunized, 9 Ohms, 2F/1B along with plug board (base plate), connectors, retaining clips etc and conforming to BRS:939A & 966(Appendix F2) or latest.The interlocking code for this unit shall be ""FGHKX"". Inspection authority:- RDSO Inspection charges:- Borne by Railways Payment Terms:- 100% after supply.	Numbers	15.00	3734.70	56020.50
17	03012100	Supply of Q-Series Neutral Line Relay(QSPA1 Type), 24V DC,8F/4B along with plug board (base plate), connectors, retaining clips etc and conforming to BRS-933A and RDSO Specn.No.IRS:S@45"44@ S-23 & S 60 or latest.The interlocking code for this unit shall be ""ABDEJ"". Inspection authority:- RDSO Inspection charges:- Borne by Railways Payment Terms:- 100% after supply.	Numbers	15.00	5211.27	78169.05

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

18	03012200	Supply of Contactor Unit (QBCA1 Type), 24 V DC, 2HF/4B complete with plug board(base plate), connectors, retaining clips etc and conforming to BRS- 943 and RDSO Specn.No.IRS:S-34 & S-23 or latest.The interlocking code for this unit shall be ""BCEJK"". Inspection authority:- RDSO Inspection charges:- Borne by Railways Payment Terms:- 100% after supply.	Numbers	15.00	7080.00	106200.00
19	03012500	Supply of Key Lock Checking Relay (KLCR) working on 24V DC, AC Immunized with different ward combinations and contact configuration 4F/4B with 2 extra ward plates and with case, RDSO spec no. RDSO/SPN/219/2016 ver 1.0 or latest, confirming to IRS S-23, S-34 & S@45<44@ IRS S:46. Inspection authority:- For bare relay -RDSO, for key lock housing- consignee Inspection charges:-Bornee by Railways Payment Terms:- 100% after supply.	Numbers	10.00	9440.00	94400.00
					Total	2460680.27
Item- 4 Chapter-4: Relay racks, CT racks, Tag Blocks, Terminal, Fuses, Indoor cables and Jumper wires						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	04010100	Supply of PVC insulated multi strand, single core copper conductor of size 16/0.2 mm (0.5sqmm) as per IS 694:2010 and RDSO Specn.No.IRS:S-76/89 (Amnd-3) or latest. Each coil should be of 100/200/500 meters length. Colour of the wire which is required will be specified by the Engineer incharge. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply	Kilometre	1.00	5813.26	5813.26
2	04010200	Supply of 1 x 6 Sqmm (Red/Black/Green) multi strand copper power wire as per IS:694:2010 or latest, 84 conductor each dia 0.30 +/- 0.01 with insulation thickness of 0.8 mm and nominal conductor resistance of 3.3 ohms/km and test parameters as per RDSO Specn.No.IRS:S-76/89(Amnd.3) or latest.Colour of the wire which is required will be specified by the Engineer incharge. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways(ii) None Payment Terms: 100% on Supply	Metre	50.00	36.37	1818.50

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

3	04010300	Supply of 1 x 10 Sqmm (Red/Black/Green) multi strand copper power wire as per IS:694:2010 or latest, 140 conductor each dia 0.30 +/- 0.01 with insulation thickness of 1.0 mm and nominal conductor resistance of 1.91 ohms/km and test parameters as per RDSO Specn.No.IRS:S-76/89(Amnd.3) or latest.Colour of the wire which is required will be specified by the Engineer incharge. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply	Metre	50.00	57.53	2876.50
4	04010400	Supply of 1 x 16 Sqmm (Red/Black/Green) multi strand copper power wire as per IS:694:2010 or latest, 127 conductor each dia 0.40 +/- 0.01 with insulation thickness of 1.0 mm and nominal conductor resistance of 1.21 ohms/km and test parameters as per RDSO Specn.No.IRS:S-76/89(Amnd.3) or latest.Colour of the wire which is required will be specified by the Engineer incharge. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways(ii) None Payment Terms: 100% on Supply	Metre	50.00	99.45	4972.50
5	04010500	Supply of 1 x 25 Sqmm (Red/Black) multi strand copper power wire as per IS:694:2010 or latest, 197 conductor each dia 0.40 +/- 0.01 with insulation thickness of 1.2 mm and nominal conductor resistance of 0.78 ohms/km and test parameters as per RDSO Specn.No.IRS:S-76/89(Amnd.3) or latest.Colour of the wire which is required will be specified by the Engineer incharge. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply	Metre	50.00	155.29	7764.50

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

6	04010600	Supply of 1 x 35 Sqmm (Red/Black/Green) multi strand copper power wire as per IS:694:2010 or latest, 277 conductor each dia 0.40 +/- 0.01 with insulation thickness of 1.2 mm and nominal conductor resistance of 0.554 ohms/km and test parameters as per RDSO Specn.No.IRS:S-76/89(Amnd.3) or latest. Colour of the wire which is required will be specified by the Engineer incharge. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply	Metre	50.00	176.93	8846.50
7	04011000	Circuit wiring/jumpering as per circuit diagrams in the relay racks/IDF rack tag blocks. This includes preparation of Jumper sheets by wire man duly checked by firm's site supervisor & wire to wire testing as per circuit diagram. Any wrong jumper done by wireman will not be paid & correction shall be done free of cost. Jumper wires will be supplied & issued by Railways. Good quality solder resin core to be supplied by contractor for soldering of Jumper wires. Soldering of jumper wires to be done after completion of testing by Railways.This item is to be used for only Alterations in any EI/PI/RR1. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after execution(Per Unit should be read as Per Jumper)	Per Unit	75.00	12.52	939.00
8	04011100	Supply of Powder Coated Relay Racks as per Drg.No.CSTE/ NWR/SOR/01 with scaffolding and suitable grouting arrangements. The relay racks shall be supplied & completed with scaffolding, bus bars, fuse strips, fuses (G/NDT), fuse bases, resistors, capacitors, insulators and 200-Way tag blocks with poly carbonate covers, grouting bolts, tripods etc. It includes supply of Tag Blocks as per RDSO Specn.No.IRS:S-77/2006 (Rev.1) or latest and RDSO Drg.No.SA-24751. The top of relay racks will be supported through an angle iron with one side fixed on supporting wall. Inspection: (i) RITES if value of item in work more than 5 lakhs (ii) Consignee Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply	Numbers	1.00	46394.04	46394.04

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

9	04011200	Erection of Powder Coated Relay Racks as per Drg.No.CSTE/ NWR/SOR/01 with scaffolding and suitable grouting arrangements. The relay racks shall be completed with scaffolding, bus bars, fuse strips, fuses (G/NDT), fuse bases, resistors, capacitors, insulators and 200-Way tag blocks with poly carbonate covers, grouting bolts, tripods etc. It includes fixing of Tag Blocks as per RDSO Specn.No.IRS:S-77/2006 (Rev.1) or latest and RDSO Drg.No.SA-24751. The top of relay racks will be supported through an angle iron with one side fixed on supporting wall. After installation of relay racks, one coat of paint will be done by contractor before fixing the fuses. Scaffolding should include 1 relay rack position as spare at every Station/ Level Crossing Gate for future expansion. Inspection: Consignee Inspection Charges: None Payment Terms: 100% on execution	Numbers	1.00	11598.51	11598.51
10	04011300	Supply of Cable Termination(CT) racks as per Drg.No.CSTE/NWR/ SOR/02 complete along with fitting arrangements and also with arrangement for fixing four 8-way terminal strips/ Screw less terminals/ ARA terminals on each row having 16 such rows. Supply of 8 way terminal strips/ Screw less terminals / ARA terminals not covered under this item. Cable termination rack shall be Powder Coated. Inspection: (i) RITES if value of item in work more than 5 lakhs (ii) Consignee if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply	Numbers	1.00	22732.41	22732.41
11	04011400	Installation of Cable Termination Racks Assembly complete including wall supports, scaffolding and suitable grouting arrangements with installation of 8 way/ARA terminals /Screw less connectors, Tag blocks & other necessary accessories etc. The work shall be done as per approved plan, extant practice on NWR & the instruction of Rly engineer at site. Inspection: Consignee Inspection Charges: None Payment Terms: 100% on commissioning.	Numbers	1.00	8687.12	8687.12
12	04011500	Supply of ARA Terminal Block (M-6) made of PBT/Poly Carbonate as per RDSO Specn.No.IRS:S-75/2006 (Rev.2) or latest and RDSO Drg.No. SA-23741A(Alt. 4) or latest. Inspection: RDSO. Inspection Charges: Borne by Railways. Payment Terms: 100% on supply.	Numbers	500.00	87.41	43705.00
13	04011600	Supply of Cartridge Fuse Block made of PBT and as per RDSO Drg. No. SA-23748 (Alt. 4) or latest and RDSO Specn.No.IRS:S-75/2006 (Rev.2) or latest. Inspection: RDSO. Inspection Charges: Borne by Railways. Payment Terms: 100% on supply.	Numbers	150.00	152.98	22947.00

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

14	04011900	Supply of round head type non-deteriorating type low voltage cartridge fuse as per RDSO Specn.No.IRS:S-78/92 or latest and Capacity - 2/4/6/10A/16A/20A Amp. (material will be supplied only from approved vendors of RDSO). Inspection: Consignee Inspection Charges: Borne by Railways. Payment Terms: 100% on supply.	Numbers	500.00	54.64	27320.00
15	04012500	Termination of Outdoor Cables (Main Cables /tail cables) at both ends in location boxes, cable termination rack in relay room, station building, generator room etc. The item includes dressing of cables and wires with dressing threads as per standard practice. All material required for this item will be supplied by contractor. The outdoor cable shall be terminated in Relay Room, DG Room, ASM Room etc under supervision and instructions issued by Engg. incharge of the work. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after execution	Per Conductor	1000.00	8.46	8460.00
		Supply of Disconnect Terminal Block, Screw less type, as per RDSO Spec. No. RDSO/SPN/189/2004(Modular Terminal Blocks, Fuse Terminal Blocks &Miniature fuse link of international standard for Railway signaling) With latest amendments. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply				
16	04012801	Supply of Disconnect Terminal Block, Screw less type, 4-wire front entry (Two in-put & Two out-put) The colour will be decided by Engineer - in - Charge. (Preferably In Blue, Red & Grey Colors in the ratio of 1:2:3)	Numbers	1000.00	54.63	54630.00
17	04012802	Supply of End plate for item 4.28(i) of Chapter 4 of revised SOR 2.5mm/0.091 in thick as per site requirement.	Numbers	50.00	10.24	512.00
18	04012803	Supply of End Stopper for item 4.28(i) of Chapter 4 of revised SOR 10mm/0.0394 in width as per site requirement.	Numbers	50.00	10.24	512.00
19	04012804	Supply of Carrier Rails for item 4.28(i) of Chapter 4 of revised SOR 35mm x 7.5mm, 1mm/0.039 in thickness un-slotted type as per site requirement.	Metre	50.00	106.98	5349.00
20	04012805	Supply of Markers strip for item 4.28(i) of Chapter 4 of revised SOR	Numbers	50.00	15.93	796.50
					Total	286674.34
Item- 5	Chapter -5: Power Supply Equipments, Batteries, Surge protection, Program Switches, DG sets					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
		Supply of uncharged Low Maintenance Lead Acid (LMLA) secondary cell, shelf mounting type conforming to RDSO Specn.No.IRS:S-88/2004 or latest with inter cell connectors, nuts and bolts etc. Inspection: RDSO Inspection Charges: Borne by Railways Payment Terms: 100% after Supply.				
1	05012601	2V, 80 AH	Numbers	50.00	2067.93	103396.50

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

		Charging of Lead Acid Batteries with contractors own battery grade sulphuric acid and distilled water with minimum two charge - discharge cycles, installation of charged batteries in groups & their connection & wiring. The work shall be done as per extant practice of N.W.Rly & instruction of Engineer-in-charge. Detailed measurements of initial charging shall be recorded jointly by contractor & Rly's site-in-charge. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after Execution.				
2	05012701	2V 80AH	Numbers	50.00	371.02	18551.00
					Total	121947.50
Item- 6	Chapter -06: Points Machine					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	06010100	Supply of ELECTRIC POINT MACHINE 143 MM STROKE AC IMMUNITY 160V AC COMPLETE WITH LOCK DETECTOR AND SLIDES FOR LOCK DETECTOR NON - TRILABLE TO OPERATE ON 110 V DC ROTARY LOCKING WITH CRANK HANDLE UNIVERSAL TPE AS PER RDSO SPECN. NO. IRS:S-24/2002 (AMND 1) RDSO DRG. NO S-10800 (ALT.5) WITH JUNCTION BOX TELESCOPIC. THE MOTOR WILL BE AS PER RDSO SPECN. NO. IRS: S-37/82 (AMND. 3) WITH RDSO DRG. NO. S-10910. This includes supply of Set of tools as per para20.1 & 20.2 of RDSO SPECN. NO. IRS:S-24/2002 (AMND 1) 20.1 The following set of tools in a suitable tool box shall be supplied along with every set of eight point machines or less. i). Hand operated square drive socket wrenches of 12.5 mm driving square (short type) as per IS: 7381 for M8, M10, M12 & M18 threads. (One 250 mm long 12.5 mm square extension bar as per IS: 7991 alongwith compatible Tee handle Square drive as per IS: 7975 suitable for above socket wrenches shall also be provided.) ii). Open jaw wrenches (spanners) for M10, M12, M20, M24 & M33 threads as per IS: 2028. iii). Adjustable wrench. iv). Screw driver 300 mm long. 20.2 Junction box and two numbers of telescopic pipes of approved type shall be supplied as an integral part of the point machine. Inspection: RDSO Inspection Charges: Borne by Railways Payment Terms: 100% after Supply.	Numbers	5.00	60412.20	302061.00

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

2	06010300	Fixing, wiring, testing and commissioning of Electrical Point Machine on the extended sleepers at points as per std. practice and as per RDSO Drg No. SA 9151-52 or 9710 or 9161 or 10800 or 11000 as per section of rails used. Item includes fixing switch extension bracket, providing insulation for switch extension bracket, fixing ground connection, adjusting opening of the switches and adjusting the point machine with crank handle. The item also includes : (i) Complete material for installation like ground-connections, switch extension brackets, point insulation material, I pipes, wiring materials, various fixing nuts & bolts including castle nuts, spring washers (ii) All smithy & fitting works required at site for complete installation. (iii) Installation of gauge tie plate & providing insulation for gauge tie plate (Insulation in William Stretcher Bar will be Provide by Railways). (iv) Wiring inside the point machine, insertion and termination of tail cable in point machine and junction boxes / location box /cable hut as per extent practice on NWR and the instruction of Railway Engineer at site. (v) Supply and fixing of suitable size GI pipes with flange for taking cable into point machine. Note ; The ground connections shall be suitable to the Point Machines as specified by Engineer-in-charge and shall be suitable to the point lay out i.e. 60 Kg. / 52 Kg / 90R as per yard layout. Electrical Point Machine and M-6 / Screw less terminals will be supplied by Railways / covered in Schedule separately Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Commissioning.	Numbers	5.00	27586.01	137930.05
---	----------	---	---------	------	----------	-----------

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

3	06010400	Supply of Point insulation Complete set as per RDSO/SPN/168/2005 for 1.Switch bracket'D' bracket insulation for IRS point machine - One set comprises of (a)Side plate LH to Drg.No.S-3266 - 1 No. (b) Side plate RH to Drg.No.S-3265 - 1 No. (c)Insulating bush to Drg.No.S-3199 - 4 Nos. (d) Insulating washer to Drg.No.S-8640 - 4 Nos., 2. Split-Stretcher bar 2.1 Insulation for Leading stretcher bars(BG) each set comprising of (a) Insulating plate for leading insulated stretcher bars BG as per RDSO Drg.No.T-10384 - 2 Nos. (b) Insulating bushing for leadingg insulated stretcher bars for BG as per RDSO Drg.No.T-10535- 4 Nos. (c) Insulating Washer for insulated stretcher bar BG as per RDSO drg.No.T-10371 - 6 Nos. 2.2 Insulation for following stretcher bars BG. Each set comprising of: (a) Insulating side plate for insulated stretcher bars BG as per RDSO Drg.No.T-10367 - 3 No. (b) Insulating bushing for insulated stretcher bars BG as per RDSO Drg.No..T-10368 - 6 Nos. (c)Insulating washer for insulated stretcher bars BG as per RDSO Drg.No.T10371 - 12 Nos& 3. Gauge tie plates (52 Kg/60Kg as per site requirement) Insulation for (BG) complete with insulating bush and washer each set comprising of: (a) Insulating plate for insulated tie plate BG as per RDSO Drg.No.T-10372-1 No. (b) Insulating bushing for insulated stretcher bar BG as per RDSO Drg.No.T10368 - 3 Nos. (c) Insulating Washer for insulated stretcher bar BG to IRS 40/84 as perRDSO drg.No.T-10371 - 6 Nos. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply	Set	10.00	1290.61	12906.10
4	06010500	Supply of Gauge Tie plate insulation as per RDSO/SPN/168/2005 as per RDSO drg No: T- 10372Alt2, T- 10368, T- 10371Alt2, T-15083/88/Alt2 & T-11690/Alt2 and as per RDSO/SPN/168/2005 with latest amendments as applicable. Gauge tie plates (52 Kg/60Kg as per site requirement) Insulation for (BG) complete with insulating bush and washer each set comprising of: (a) Insulating plate for insulated tie plate BG as per RDSO Drg.No.T-10372-1 No. (b) Insulating bushing for insulated stretcher bar BG as per RDSO Drg.No.T10368 - 3 Nos. (c) Insulating Washer for insulated stretcher bar BG to IRS 40/84 as perRDSO drg.No.T-10371 - 6 Nos. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply	Set	10.00	1156.31	11563.10

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

5	06011400	Supply of William Stretcher Insulation Set (complete) as per RDSO/SPN/168/2005 with insulating bush and washer to suit point layout and conforming to RDSO Drg.No.T-10372 or latest, T-10368 or latest and T-10371 or latest. 1.1 Insulation for Leading stretcher bars(BG) each set comprising of (a) Insulating plate for leading insulated stretcher bars BG as per RDSO Drg.No.T-10384 - 2 Nos. (b) Insulating bushing for leadingg insulated stretcher bars for BG as per RDSO Drg.No.T-10535- 4 Nos. (c) Insulating Washer for insulated stretcher bar BG as per RDSO drg.No.T-10371 - 6 Nos. 1.2 Insulation for following stretcher bars BG. Each set comprising of: (a) Insulating side plate for insulated stretcher bars BG as per RDSO Drg.No.T-10367 - 3 No. (b) Insulating bushing for insulated stretcher bars BG as per RDSO Drg.No..T-10368 - 6 Nos. (c)Insulating washer for insulated stretcher bars BG as per RDSO Drg.No.T10371 - 12 Nos Inspection: (i) RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply	Set	30.00	386.13	11583.90
6	06011500	Supply of 110V DC motor with 400V AC immunity as per Specification No. IRS:S:37/82 Inspection: RDSO Inspection Charges: Borne by Railways Payment Terms: 100% after Supply.	Numbers	3.00	19180.48	57541.44
7	06011600	Removal of existing point motor and installation of immunised motor. Note: Supply of motor is not included in this item. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after execution.	Numbers	3.00	2928.57	8785.71
					Total	542371.30
Item- 7 Chapter 7: Track Circuit equipment, HASSDAC, MSDAC etc.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	07010100	Supply of Track feed Battery Charger as per RDSO Specn. No.IRS: S-89/2013 Ver.1.0 or latest. Charging Capacity Rating 10 Amps for Charging 80 AH Battery. Inspection: RDSO Inspection Charges: Borne by Railways Payment Terms: 100% after Supply.	Numbers	10.00	4505.12	45051.20
2	07010200	Supply of Adjustable Track Feed Resistance 30 Ohms (Disc Type) as per RDSO Drg. No.SA-20161-66/M or latest. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after Supply.	Numbers	10.00	1439.17	14391.70

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

3	07010300	Fixing and wiring of DC track circuit equipments i.e. track feed charger, resistance, track relay, battery, B type choke etc., in the Apparatus Case and battery box as per standard practice. Termination of tail cable on M 6 / Screw less terminals WAGO or FINOLEX or similar approved make teminals/ fuse blocks / HRC fuse. Item includes testing /commissioning of track circuit. Complete wiring material will be supplied by contractor. (Supply of Track feed battery charger, track feed battery, resistances & 'B' type choke & Track relays, ARA terminal/Modular terminals wago/phoenix contact type will be supplied by Railways / covered in Schedule separately). Inspection: Consignee Inspection Charges: None Payment Terms: 100% after execution.	Per Track Circuit	10.00	6354.01	63540.10
---	----------	--	-------------------	-------	---------	----------

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

4	07010400	Installation of DC track circuits covering all types of Track circuits including points zones also. The item includes provision of doubled continuity GI wire bonds on rail joints after drilling bond-hole of 7.0/7.2mm dia, skimming of fish plate, insertion of insulated block joint(if required), fixing of TLJB (separate for positive & negative rails) with angle iron for track feed/jumper/track relay ends of track circuits and also for fixing jumper cables as per approved Track Circuit Plan, making rail connections through suitable insulated sleeves from TLJB at TF, jumper & TR end with GI wire, rail clips for fixing bond wire on the TLJB as per standard practice, termination of tail cables on TLJB terminals etc. TF/TR wiring shall be fixed on the suitable arrangement on PRC sleepers with the help of Hooks. In case Engineer at site desires that jumpering from TLJBs is to be done using signalling cable 2 coreX 2.5 sqmm , contractor shall provide the jumpering cable using 2 X 2.5 sqmm signalling cable. The signalling cable will be supplied by Railways. Hooks shall be provided on PRC sleepers with the help of suitable steel bracket. This item also includes fixing & supply of channel pins, Hooks etc. The item does not include includes supply of TLJB as per RDSO Drg.No.RST-11509 or latest as per technical specs Installation of of Track Lead Junction Box(TLJB) as per Drg.No.RST-11509 or latest made from FRP material including brass bolts and hylam board sheet with terminals etc. (a) Installation and commissioning of TLJB complete with cover to be in black/red having approximate weight of 4.0 Kg with L-262mm W-212mm and H 90 mm and all the holes required for mounting on FRP stump (vertical two for each FRP angle) HDPE pipe , cable etc. (b) Installation and commissioning of Each TLJB having two bakelite terminal block fitted horizontally : each bakelite terminal block shall have two nickel chrome plate M10 brass terminal, 50mm long. Alongwith each TLJB , nickel chrome plated brass links(two nos. Of adequate strength for vertical linking of the terminals to be wired and fixed properly. (c) Installation of HDPE pipe of size 32/35mm , 380 mm long alongwith two nuts for fixing on the TLJB hole . (d) Installation of the FRP stump for mounting the TLJB to be made of one meter long 30mm X30mmX 4mm angle(2 nos.) and 300mm long 30mm X30mmX 4mm angle(1 no.) fixed at 50 mm from the bottom using galvanised nuts and bolts. The TLJB and the angles for stump should be fixed in given holes on them for fixing using galvanised nuts and bolts . Inspection: Consignee Inspection Charges: None Payment Terms: 100% after execution.	Per Track Circuit	10.00	7952.90	79529.00
---	----------	--	-------------------	-------	---------	----------

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

5	07010500	Supply of Track Lead Junction Box(TLJB) as per Drg.No.RST-11509 or latest made from FRP material including brass bolts and hylam board sheet with terminals etc. The technical specifications are as follows: (a) TLJB complete with cover to be in black/red having approximate weight of 4.0 Kg with L-262mm W-212mm and H 90 mm and all the holes required for mounting on FRP stump (vertical two for each FRP angle) HDPE pipe , cable etc. (b) Each TLJB shall have two bakellite terminal block fitted horizontally : each bakellite terminal block shall have two nickel chrome plate M10 brass terminal, 50mm long.Alongwith each TLJB , nickel chrome plated brass links(two nos.Of adequate strength for vertical linking of the terminals to be supplied. (c) HDPE pipe of size 32/35mm , 380 mm long alongwith two nuts for fixing on the TLJB hole . (d) The FRP stump for mounting the TLJB to be made of one meter long 30mm X30mmX 4mm angle(2 nos.) and 300mm long 30mm X30mmX 4mm angle(1 no.) fixed at 50 mm from the bottom using galvanised nuts and bolts.The TLJB and the agles for stump should come alongwith holes on them for fixing using galvanised nuts and bolts of adequate strength to be supplied alongwith TLJB drawing no. 11509. Inspection: (i) RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply	Numbers	250.00	1778.40	444600.00
6	07010600	Erection, Fitting and Rail connection of Track Lead Junction Box on two supports (FRP stumps) with contractor's fixing material .This will include drilling of holes for track lead/side connections on rail. The work shall be done as per instructions of Rly engineer at site. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after execution.	Numbers	25.00	1315.64	32891.00
7	07010700	Supply of B Type Choke as per RDSO Specn.No.IRS:S-65/83 (Amnd. 1) or latest. Inspection: RDSO Inspection Charges: Borne by Railways. Payment Terms: 100% after supply.	Numbers	20.00	4098.94	81978.80
8	07010800	Supply of Channel Pins MS (Galvanized) single groove, 7 mm suitable for 4mm dia bonding wire as per spec No IRS S 17 & RDSO Drg No. S-69/M. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after Supply.	Numbers	500.00	5.69	2845.00
9	07010900	Supply of GI wire 8 SWG (4mm dia) suitable for track circuit rail bonding. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after Supply.	Kg	250.00	66.01	16502.50

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

10	07011000	Provision/Installation of bonding with GI wire 4mm dia (8 SWG) for track jumper & fish plate joints bonds. This will include drilling of 7.0/7.1/7.2 mm dia holes in rails (4 Nos.) and provision of two jumpers for each bond, clipping of bonds etc. with contractors own tools as per instruction of Rly. Engineer at site. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after Execution.	Numbers	50.00	179.82	8991.00
11	07011100	Supply of Hydrometer, Exide make or similar for measuring specific gravity of Battery Graded acid with mounting stand in location Boxes. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after Supply.	Numbers	5.00	257.21	1286.05
					Total	791606.35
Item- 8	Chapter-8: LED Main & Subsidiary signals, CLS units, Route Indicators & foundation etc.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	08010400	Installation of LED signals lamps for auxiliary/subsidiary signals/main signals (i.e. route, shunt , calling on, Red , Yellow, Green) as per instructions given by engineer incharge. The contractor will supply all materials required for installation. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Commissioning.	Numbers	20.00	178.89	3577.80
2	08010500	Supply of Colour Light Signal Complete. This includes: - (1). Post Tubular 140 mm Dia, as per IRS: S-6/81 or Latest & RDSO Drg. No. SA-24625 (Advance). (2). CI Base (As per IRS S-10 & RDSO Drg. No. 2011/M with latest assembly). (3). Number plate to Drawing No. S 23149 Alt.1 =1 No , Number plate clamps to Drawing No. S 23148 Alt.1 =2 no (4). Ladder Assembly, as per RDSO Drg. No. SA-23156, with Base, Ladder Guard rail (complete) to Drawing No. SA 23138 Alt.1(1No), Platform to Drawing No. SA 23134 Alt.1(1 No), Front Maintenance Platform, MS Supporting bracket to Support Ladder.Ladder stay (small) to Drawing No. S 23159 Alt. 1 (2 Nos.) , Ladder stay (large) to Drawing No. S 23160 Alt. 1 (2 Nos.) , Ladder section to Drawing No. SA 23157 Alt. 1(1 Nos.)Stay clamp to Drawing No. SA 2062/M (2 no), Rail Clamp to Drawing No. S 2066/M (1 No.) (5). Signal Front Staging Complete Assembly for CLS Unit. (6). Signal back staging as per extent NWR Practice. Note: Note: Height of the Post shall be 5.5 Long. Inspection: (i)RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply	Numbers	5.00	10791.46	53957.30

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

		Erection of CLS Post with base and signal unit on top or on OFFset Bracket, fixing of front and back staging, ladder and guards, signal name plates / boards if any with contractor's own brackets and fixing materials. This also includes erection of auxiliary signals like calling on, shunt signal if any. The work shall be done as per instructions of Rly engineer at site. It also includes provision & fixing of maintenance platform as per design given by Engineer -In-Charge at site. The Item includes cutting of Signal post if required by Site In charge. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Commissioning.				
3	08010801	2/3/4 aspect signal unit mounted on offset bracket with junction type route indicator 1/2/3/4/5/6 or multilamp lamp route indicators/Stencil type rout indicator mounted on signal post.	Numbers	1.00	3227.65	3227.65
4	08010802	2/3/4 aspect signal unit mounted mounted directly on signal post.	Numbers	2.00	2187.43	4374.86
5	08010900	Supply of Non Metallic (FRP) colour light signal housing multi unit type for railway signaling suitable for RE area TWO Aspects. Complete without lenses, lamps and signal transformer as per RDSO DRG. No. SA 23001/A/M Adv. Alt- S and as per SPEC. No. RDSO/SPN/194/2006 (Rev 2.0) or latest and FRP material as per RDSO SPEC. No. RDSO/SPN/151/1997 or latest. Inspection: (i)RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply	Numbers	3.00	26768.11	80304.33
6	08011000	Supply of Non Metallic (FRP) colour light signal housing multi unit type for railway signaling suitable for RE area THREE Aspects. Complete without lenses, lamps and signal transformer as per RDSO DRG. No. SA 23001/A/M Adv. Alt- S and as per SPEC. No. RDSO/SPN/194/2006 (Rev 2.0) or latest and FRP material as per RDSO SPEC. No. RDSO/SPN/151/1997 or latest. Inspection: (i)RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply	Numbers	2.00	28042.78	56085.56

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

7	08011200	Supply of Position Light Shunt Signal Unit Complete with Post(made of GI Pipe of 80 mm Diameter Medium Class IS Spec. No. IS: 1239 Pt. 1/1990, Base, Hood, Cover etc as per Drg. No. SA-23840 suitable for LED Signal Lighting Unit.(Supply of LED Unit is not covered in this item) Inspection: (i)RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply	Set	3.00	4297.47	12892.41
8	08011300	Erection of Position Light Shunt signal with Base, Post, Signal unit and fixing of Number Plates. The work shall be done as per instructions of Rly engineer at site. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Commissioning.	Numbers	2.00	1779.99	3559.98
9	08011400	Supply of Position Light Shunt Signal Unit Complete, with offset bracket, hood, Cover etc as per Drg. No. SA-23840 suitable for LED Signal Lighting Unit. (Supply of LED Unit is not covered in this item)Inspection: (i)RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply	Numbers	3.00	3358.53	10075.59
10	08011500	Erection of Position Light shunt signal on Offset bracket on main signal. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Commissioning.	Numbers	2.00	1967.77	3935.54
11	08011700	Supply of Junction route indicator unit 2 way (Without Lenses & Holder) as per Drg. No. RDSO SA 23402 suitable for LED Signal Lighting Unit & as IRS:S-66/84 amndt-1 or latest.(Supply of LED Unit is not covered in this item) Inspection: (i)RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply	Numbers	1.00	20490.35	20490.35
12	08012300	Fixing of Junction type Route Indication 1-Way/2-Way/3-Way/4-Way/5-Way/6-Way on the top of the signal post. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Commissioning.	Numbers	1.00	590.67	590.67

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

13	08012400	Supply of Calling ON Signal Unit with Brackets & Fixing accessories. Calling On Signal Unit shall conform to RDSO Drg no 24351(Adv) Alt1 suitable to LED Signal Lighting Unit. Inspection: (i)RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply	Numbers	2.00	2550.48	5100.96
14	08012600	Fixing of Calling-on Signal/A-Sign/AG-Sign unit on signal post. The item includes fixing of Co- On signal /'A' sign/ 'AG' sign unit on signal post with bracket, hood etc. Item includes supply of bracket & fixing materials etc. by the contractor. The item also includes termination of cables & wiring inside Co- On signal /'A' sign/ 'AG' sign unit as per standard practice. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Commissioning.	Numbers	1.00	2325.14	2325.14
15	08012800	Supply of Different warning Boards / Calling on Board used for Railway Signalling system as per RDSO Drg. No. SA2380 (Adv). This includes Painting and retro reflective arrangement should be as per SEM. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply.	Numbers	5.00	4637.76	23188.80
16	08012900	Fixing of Stop Board, Block section limit Board, Shunting Limit Board, goods warning board , Calling on Board with contractors own material. This excludes supply of Stop Board / Block section limit Board / Goods warning board/Calling on board. The work shall be done as per instruction of Rly Engineer at site. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after installation.	Numbers	5.00	334.60	1673.00
17	08013000	Supply, Fabrication and fixing of Signal Number Plate(CSTE Drg No CSTE/6186) , 'A' Marker (Drg No. CSTE/6180), 'AG' Marker (Drg No. CSTE/6181), 'P' Marker (Drg No. CSTE/6182), Arrow Marker (Drg No. CSTE/6183), 'G' Marker (Drg No. CSTE/6184), 'C' Marker (Drg No. CSTE/6185). marker disk on signals as per standard practice All material required for this work shall be supplied by Contractor. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after installation.	Numbers	50.00	1223.46	61173.00
18	08013100	Supply and fixing of protective screen of expanded metal 12 SWG of size 1200 x 1500 mm on signals as per std. practice in RE Area. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after installation.	Numbers	1.00	5087.65	5087.65

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

19	08013200	Casting of CC Foundation for Signal Post in the ratio of 1:3:6 as per Drg.No.CSTE/NWR/SOR/21/A using standard size of foundation/galvanized holding down bolts required for erection of colour light signal post. Item includes excavation, ramming of CC using vibrator, curing and plastering with 1:4 cement-sand mixture (aggregate will not exceed 3.8 cm). Aggregate, cement, sand and holding down bolts will be supplied by contractor. Any machines & tools, if required for execution of this item, will be arranged/provided by contractor. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after installation.	Numbers	3.00	9361.50	28084.50
20	08013300	Casting of C.C. Foundation for Position Light Shunt Signal/ Indicator/SPI as per Drg.No.CSTE/NWR/SOR/ 22 in ratio 1:3:6 by using standard size of galvanized holding down/foundation bolts. Item includes excavation, ramming of CC using vibrator, curing and plastering with 1:4 cement sand mixture. Aggregate cement, sand and holding down bolts, will be supplied by contractor. Any machines and tools, if required for execution of this item, will be arranged/provided by contractor. Note: As per available site conditions, if sizes of foundations are required to be decreased/ increased and same has been approved/agreed by engineer incharge then variation in CC work will be calculated on volumetric basis as per rates of these items. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after installation. ."	Numbers	3.00	6310.26	18930.78
					Total	398635.87
Item- 9	Chapter-9: Level Crossing Gates, Interlocking of LC gates, ELBs, Accessories etc.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	09010300	Supply of Yellow Retro reflective sheet for LC Boom prismatic grade reflective sheets of size 305 x 290 mm one set consist 18 pieces. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% on Supply	Set	10.00	1707.15	17071.50
2	09010500	Supply of (02) nos. electrical lifting barrier booms of 9.76 meter each as per DRG RDSO/S 11600 . The material will be as per RDSO Specn.No.RDSO/SPN/208/2012/Ver.2.0 and Amendment 1 or latest. Inspection: Consignee subject to procurement from RDSO approved supplier. Inspection Charges: None. Payment Terms: 100% after Supply	Set	2.00	25128.93	50257.86
					Total	67329.36
Item- 10	Chapter-10 : Panel room equipments, VDUs (Video Display Units), Fire alarm equipments, Furnitures					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	10011100	Supply of Office Chair make Godrej CH-7B or similar of reputed brand. Inspection: Consignee Inspection Charges:None Payment Terms: 100% after Supply.	Numbers	2.00	2518.62	5037.24

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

2	10011200	Supply of Office Revolving Chair Godrej Make Model No.9u02r Bravo Or Similar of reputed brand. Inspection: Consignee Inspection Charges:None Payment Terms: 100% after Supply.	Numbers	1.00	7681.04	7681.04
3	10011300	Supply of Office table with laminated top with three drawers on left hand side and one locker on the right hand side. Olive brown with duplicate keys.Make: Godrej Model T-9 (136.5 cmX68cmX 75cm)or Superior of reputed brand. Inspection: Consignee Inspection Charges:None Payment Terms: 100% after Supply.	Numbers	1.00	15037.72	15037.72
4	10011400	Supply of Steel Plain Almirah with 4 adjustable slavesSize: 1980mm height, 915 mm width and 485 mm depth.Make: Godrej Storewel Plain Large or Similar of reputed brand. Inspection: Consignee Inspection Charges:None Payment Terms: 100% after Supply.	Numbers	1.00	16271.42	16271.42
					Total	44027.42
Item- 11	Chapter-11: Apparatus case, Outdoor installation, Fuses, ARA Terminal, Hylam Sheet, Phenolic Laminated sheets					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	11010100	Supply of Apparatus Case Single(Large) NE Rly Type as per Drg. No. CSTE/6088 fitted with two nos of E Type lock (ward No will be specified by Engineer-in Charge) as per RDSO Drg. No. SA 3376 and Key to Drg. No. 3377 as per RDSO drawing No. RDSO/S-11500. Note: This item includes the supply of 2 Nos E Type Lock fitted on both doors, along with two Keys. Inspection: (i) RITES if value of item in work more than 5 lakhs or as per extant policy (ii) Consignee subject to procurement from RECOMMENDED LIST OF FIRMS FOR MECHANICAL SIGNALLING ITEMS if value of whole item in work less than 5 lakhs or as per extant policy Inspection Charges:(i) Borne by Railways (ii) None Payment Terms: 100% after Supply.	Numbers	15.00	14945.53	224182.95
2	11010200	Installation of Apparatus Cases Single(Large) with 'E' type lock on CC foundation. This includes filling of location foundations with river bed sand and plastering on top of the sand. Supply of 'E' Type lock has been covered in supply of Apparatus case separately. It covers fixing of lamp holder , switch and lamp etc. in Apparatus Case. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after installation.	Numbers	15.00	1039.09	15586.35

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

3	11010300	Supply of Apparatus Case half (Medium) NE Rly Type as per Drg. No. CSTE/6088 fitted with two nos of E Type lock (ward No will be specified by Engineer-in-Charge) as per RDSO Drg. No. SA 3376 and Key to Drg. No. 3377 as per RDSO drawing No. RDSO/S-11507. Note: This item includes the supply of 2 Nos E Type Lock fitted on both doors, along with two Keys. Inspection: (i) RITES if value of item in work more than 5 lakhs or as per extant policy (ii) Consignee subject to procurement from RECOMMENDED LIST OF FIRMS FOR MECHANICAL SIGNALLING ITEMS if value of whole item in work less than 5 lakhs or as per extant policy Inspection Charges:(i) Borne by Railways (ii) None Payment Terms: 100% after Supply.	Numbers	10.00	9439.40	94394.00
4	11010400	Installation of Apparatus Cases Half (Medium) with 'E' type lock on CC foundation. This includes filling of location foundations with river bed sand and plastering on top of the sand. Supply of 'E' Type lock has been covered in supply of Apparatus case separately. It covers fixing of Location lamp holder , switch and lamp etc. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after installation.	Numbers	10.00	632.78	6327.80
		Excavation and Casting of Apparatus Case foundation in ratio 1:3:6 with contractor's own materials including cement and galvanized anchor bolts of standard size. The required scaffolding Ferma etc for Casting of foundation will have to be brought by the contractor at his own cost.The item also includes additional masonry work as well as earthwork if required on bank where there will be possibilities of foundation sinked, fallen or tilted. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after installation.				
5	11010801	Single (Large) Case Apparatus case / SS location box as per Drg No. CSTE/5074	Numbers	15.00	6888.92	103333.80
6	11010802	Half (Medium) Case Apparatus case / SS location box as per Drg No CSTE/5074	Numbers	10.00	5259.16	52591.60
7	11010900	Supply of Phenolic laminated Sheet, grade P3 in standard size of 1220 X 1220 x 20 mm as per spec. No IS 2036 of 1995 or latest. Test report of manufacture to be supplied. Inspection: (i) RITES if value of item in work more than 5 lakhs or as per extant policy (ii) Consignee Inspection Charges:(i) Borne by Railways (ii) None Payment Terms: 100% after Supply.	Numbers	5.00	9563.45	47817.25
8	11011000	Supply of Phenolic laminated Sheet, grade P3 in standard size of 1220 X 1220 x 12 mm as per spec. No IS 2036 of 1995 or latest. Test report of manufacture to be supplied. Inspection: (i) RITES if value of item in work more than 5 lakhs or as per extant policy (ii) Consignee Inspection Charges:(i) Borne by Railways (ii) None Payment Terms: 100% after Supply.	Numbers	10.00	4855.13	48551.30

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

		Fabrication and fixing of phenolic laminated sheet of size 10/12/20 mm thick in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated string rods at the back side for cable support with contractor's own materials. The work shall be done as per instructions of Rly engineer at site. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after installation.				
9	11011201	Single Case (Large Case)	Numbers	15.00	2344.49	35167.35
10	11011202	Half Case (Medium Case)	Numbers	10.00	684.00	6840.00
11	11011300	Fixing of ARA(M-6) Terminals /Screw less connectors / modular disconnect terminal blocks and fuse blocks on phenolic laminated sheets and fixing by stainless steel/brass nuts & bolts. This includes provision of two additional holes on the board on either side for cable conductor entry.(Supply of all above terminals have been covered separately in Chapter 4 of SOR) Inspection: Consignee Inspection Charges: None Payment Terms: 100% after installation.	Numbers	1000.00	12.52	12520.00
12	11011700	Supply of Tic-tac Piano type Switches , 5A (ISI mark of reputed make) Inspection: Consignee Inspection Charges: None Payment Terms: 100% after supply	Numbers	25.00	29.59	739.75
13	11011800	Supply of two pin Lamp holder Bakelite type for Apparatus Cases (ISI mark of reputed make) Inspection: Consignee Inspection Charges: None Payment Terms: 100% after supply	Numbers	25.00	44.39	1109.75
14	11011900	Supply of Miniature 'E' type lock complete with keys as per RDSO Drg. No. SA 3473, 3373 & spec. IRS(S) 30/64. Ward to be specified by Engineer - in - charge. Inspection: Consignee. Inspection Charges: None. Payment Terms: 100% after supply.	Numbers	10.00	2026.96	20269.60
15	11012000	Fixing of KLCR relays in field in half location boxes if Gate lodge is not provided or at any other location as decided by engineer in charge. Item includes supply and fixing of MS sheet and wiring of KLCR relays, push buttons and LEDs for KLCR circuit. The KLCR relays, push buttons, LEDs will be fixed on a MS sheet of min. 3mm in the half location box. The MS sheet will cover full length and breadth of the half location box and divided in two pieces of approx. 48cm x 46cm and 80cm x 46cm. The first piece to be fitted on top and will contain the KLCR relays, LEDs and push buttons. The second piece to be fitted below the first piece. (Supply of KLCR relays covered in separate item of SOR). Inspection: Consignee Inspection Charges: None Payment Terms: 100% after installation.	Numbers	3.00	2193.20	6579.60
					Total	676011.10
Item- 12	Chapter-12: Cable laying material, Cable protection, Cable execution, Jointing Kits items etc.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

1	12010200	Supply of Medium class GI pipes 100 mm dia(4.5 mm thickness) as per IS 1239 (Part 1) : 2004 with coupling on culverts bridges as per Drg.No.CSTE/NWR/SOR/06 to 12 or at any other locations as decided by Site Engineer. It includes supply of all material required for fixing arrangement. Contractor will also supply flexible/corrugated HDPE pipe at the end of GI pipe to protect the cables from sharp edges and sudden bends. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply.	Metre	18.00	760.66	13691.88
2	12010400	Supply of Medium class GI pipes 50 mm dia(3.6 mm thickness) as per IS 1239 (Part 1) : 2004 for use in ASM room and at any other location as decided by Site Engineer. It includes supply of all material required for fixing arrangement. At the ends of GI pipe, flexible/corrugated HDPE pipe will be provided by contractor to protect cables from sharp edges and sudden bends. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply.	Metre	18.00	390.52	7029.36
		Supplying and placing of one layer of standard size of B grade quality bricks of the local make spreading on cables laid. (minimum size of brick 200mm X 100mm X 70mm) Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Installation.				
3	12010601	Lengthwise (up to 2 cables).(Unit is per RM Running Meter)	Metre	500.00	14.80	7400.00
4	12010602	widthwise (more than 2 cables).(Unit is per RM Running Meter)	Metre	2000.00	31.87	63740.00
5	12010700	Supply of Double Walled Corrugated (DWC) HDPE Pipe/duct with associated collars etc. as per RDSO Specification No. RDSO/SPN/204/2011 or latest anti-rodent & anti-oxidant and non flame propagating type in 6 meters straight length and of size 120 mm outer dia,& 103.5 mm inner dia. (The manufacturers, suppliers must produce valid IS license and should be certified under ISO 9000 and shall submit copy of certificate). One of the following coupling arrangements should also be supplied with each pipe as per the site requirement. 1) Suitable snap fit coupler with rubber O-Ring 2) Spacers 3) Tees 4) Bend, 5) End-cap (The total quantity of above items is equal to no. of pipes supplied.) DWC pipe shall be marked at every 1 mtr length in such a way that manufacturer's name, vendor name and year of manufacture can be easily identified. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs or as per extant policy (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs or as per extant policy Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% after Supply	Numbers	50.00	1798.20	89910.00

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

6	12010800	Supply of Double Walled Corrugated (DWC) HDPE Pipe/duct with associated collars etc. as per RDSO Specification No. RDSO/SPN/204/2011 or latest anti-rodent & anti-oxidant and non flame propagating type in 6 meters straight length and of size 50 mm outer dia, & 38 mm inner dia. (The manufacturers, suppliers must produce valid IS license and should be certified under ISO 9000 and shall submit copy of certificate). One of the following coupling arrangements should also be supplied with each pipe as per the site requirement. 1) Suitable snap fit coupler with rubber 'O-Ring 2) Spacers 3) Tees 4) Bend, 5) End-cap (The total quantity of above items is equal to no. of pipes supplied.) DWC pipe shall be marked at every 1 mtr length in such a way that manufacturer's name, vender name and year of manufacture can be easily identified. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs or as per extant policy (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs or as per extant policy Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% after Supply	Numbers	50.00	360.78	18039.00
7	12010900	Supply of Double Wall Corrugated (DWC)-HDPE pipe/duct of size 200 mm outer dia, & 175 mm inner dia. It includes supply of Double Wall Corrugated -HDPE pipe/duct as per RDSO Specn.No. RDSO/SPN/204/2011 (version 1.1) or latest and conforming to ISI Spec. No.IS:14930, Part-II. (The manufacturers, suppliers must produce valid IS license and should be certified under ISO 9000 and shall submit copy of certificate). One of the following coupling arrangements should also be supplied with each pipe as per the site requirement. 1) Suitable snap fit coupler with rubber O-Ring 2) Spacers 3) Tees 4) Bend, 5) End-cap DWC pipe shall be marked at every 1 mtr length in such a way that manufacturer's name, vendor name and year of manufacture can be easily identified. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs or as per extant policy (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs or as per extant policy Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% after Supply	Metre	500.00	383.47	191735.00
8	12011600	Placing of DWC HDPE/RCC/GI pipes along with collars in trenches at places near track and road, crossings, platform cuttings etc. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution(Unit is RM running meter.)	Metre	500.00	29.59	14795.00
9	12012000	Supply of Thermo shrink Universal Jointing kit for Quad Cable (for straight joints) as per RDSO spec IRS/TC-77/2012 revision 3 With latest Amd. Inspection: RDSO Inspection Charges: Borne by Railways Payment Terms: 100% after Supply	Numbers	5.00	2148.73	10743.65

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

10	12012100	Jointing of 4 / 6 quad /Signaling cable with Heat Shrinkable straight through Jointing Kit. All the material required for the work are to be arranged by contractor himself at his own cost except Thermo shrinkable Joint Kit/Rapid Joint kit. After jointing the cable through test such as insulation test, continuity cable losses etc. to be carried out jointly with Railway Engineer. If any defect or any damage is observed during jointing, the contractor has to redo the joint free of cost. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution	Numbers	3.00	1157.45	3472.35
11	12012200	Horizontal direction drilling/boring without damage of surface road /track using Auger Machine(HDD machine). The bore shall be upto 200 mm dia & shall be done at the depth of minimum 1200 mm from the ground level. The ground level shall be considered ignoring the bank height of the bank of the road. The length of the bore shall be minimum 4 Mtrs long. This include insertion of different dia DWC-HDPE pipe/ GI pipes coupling etc. as per direction of Engineer In charge. Note:- Pipe Supply is not covered under this item. Contactor shall provide all material required for boring and adequate nos. of labours for proper laying of cables into the bore. Cable shall be laid cautiously so that it should not get damage due to rough handling & pressure on cable. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution.	Metre	500.00	1202.97	601485.00
12	12012300	Horizontal Drilling by using manual pushing method at minimum depth of 1.5 meter below the formation level of earth as per decision of Engineer in charge .Pipe Supply is not covered under this item Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution	Metre	500.00	122.74	61370.00
13	12012500	Supply of RCC cable route marker engraved and painted on both side along the route at every 50 meter and route diversion as per Drg. No 4014/00/CC4 or latest/ Stone marker. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply	Numbers	25.00	328.68	8217.00
14	12012600	Transportation at site and Installation of RCC cable route marker engraved and painted on both side along the route at every 50 meter and route diversion as per Drg. No 4014/00/CC4 or latest/ Stone marker. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution	Numbers	25.00	82.17	2054.25

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

15	12013200	Transferring of Signaling/Telecom cables from existing Location box to New Location box . The work include breaking/ Dismantling of Existing foundation of locations, excavating and removing / segregating coils of 2C/6C/12C/19C/24C/30C/Quad cables which may be about 10 mtrs. in length. These cables are to be disconnected and removed from the existing location one by one as per the instruction and under the supervision of Railway staff present at site. The cable is then to be inserted and terminated in new location box. The item includes neatly dressing of cable, making wiring tree etc.The material required to dressing /lacing will be arranged by contactor. The work is required to be done systematically and with due precaution during the block or disconnection within the time that may be allowed. The excavation work to be done carefully without damaging the cable to avoid undue failure. (Termination charges will be given separately). Note: Proportionate payment will be made if cable of other length. One No unit = One cable of 10 m length) Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution	Numbers	10.00	361.92	3619.20
16	12013700	Excavation of cable trench as per cable route plan, 1.2 Mtr. deep and of 0.3 Mtr. to 0.6 Mtr. wide at bottom as per RDSO sketch No. SDO/CABLE LAYING/003 or latest alongside the track in normal (all type) soil/strata, conforming to distances as per cable route plan and refilling. This work includes clearing of route from bushes etc, covering of cable laid in trench by loose soil for a layer of 50mm thickness approximately before covering by bricks. The work shall be done as per the extant practice on North Western Railway and instructions of Railway Engineer at site. In case 1.2m depth of trench is not achievable due to site conditions, specific approval of JA grade officer will be required for each site where trench depth of 1.2m is not possible. Without the approval of JA Grade officer, no payment for trenching will be made for trench depth less than 1.2m. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution(Unit is Cubic Meter)	cum	2000.00	274.28	548560.00

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

17	12014100	Laying of S&T Cables of various cores/ pairs/ quads in trenches/ GI pipes/ RCC pipes/ DWC pipes/ Trunking. This also includes laying of cables in track crossings & road crossings. Item includes provision of labels of coloured plastic adhesive tapes or any other identifiable material on each cable to give the cable number at each Gantry Post/hectometer post.(Cables will be meggered before and after its laying by contractor under supervision of Railway Representative and he will submit the meggering report of each testing). Length of the cable laid includes the length of the cable coiled for termination purposes. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution(unit is RM running meter)	Metre	60000.00	9.10	546000.00
18	12014200	Cement concrete work for miscellaneous items in the ratio 1 : 3 : 6 . Item includes excavation, ramming, curing and plastering with cement & sand mixture (aggregate not exceeding 3.8 cm.) (Aggregate cement & sand to be supplied by the contractor). Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution(Unit is cubic meter)	cum	3.00	3628.26	10884.78
19	12014300	Providing brick masonry in ratio 1:6 cement and mortar including plastering with 1:4 cement and sand mixture both sides, 20 mm thick each with contractor's owned class II bricks, including excavation, curing, grouting, bolting etc. wherever required. Bricks sand and cement to be supplied by the contractor. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution(Unit is cubic meter)	cum	3.00	1990.54	5971.62
					Total	2208718.09
Item- 13	Chapter-13: Earthing, Measuring Instruments, Multimeter, Earth Tester, Clamp meters, Fault Locators, ELD(Earth Leakage Detector) etc.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

1	13010300	Supply of basic material to construct unit maintenance free earth as per RDSO Specs. No RDSO/SPN/197/2008 or latest and conforming to RDSO Drg.No.SDO/RDSO/E&B/001 dtd.19.09.08 . It consist of following: (a) Copper bonded steel electrode of 3.0 m long, 17.2 mm dia with copper bonding thickness of minimum macrons and UL listed and marked = 1 no. (b) Earth enhancement material supplied in sealed bags of minimum 10 kg = 3 nos. © Copper strip of 150x25x6 mm, to terminate earth rod = 1 no. (d) Copper strip of 300x25x6 mm (MEEB) = 1 no. (e) Copper strip of 150x25x6mm (SEEB) = 1 no. (ii) Supply of 35 sq. mm multi strand single core PVC insulated copper cable as per IS: 694 for connecting main earth electrode to MEEB in the equipment room in duplicate.(minimum 10 meter) (iii) Supply of 16 sq. mm multi strand single core PVC insulated copper cable as per IS: 694 for connecting MEEB to SEEB and SPD to MEEB (minimum 10 meter) (iv) Supply of 10 sq. mm multi strand single core PVC insulated copper cable as per IS: 694 for connecting various equipments to SEEB (v) Supply of copper lug sleeve for 3/16 cable Inspection: RDSO Inspection Charges:Borne by Railways Payment Terms: 100% after Supply.	Lot	2.00	17530.73	35061.46
---	----------	---	-----	------	----------	----------

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

2	13010400	Installation of Unit Maintenance Free Earth as supplied under item no. 13.3 of Chapter 13 of SOR . It includes (i) Digging the earth to the required depth. (ii) Insertion of electrode. (iii) Filling of earth enhancing compound (Approx.30 Kg) (iv) Provision of exothermic weld connections to copper tape of 25 mm x 6 mm x 150 mm to the earth electrodes. All material tools and features required for weld will be arranged by contractor. (v) This also includes CC cover 1.5 ft x 1.5 ft. 1 ft wall thickness 2 inch with cover 3 inch thickness. Cables 35 Sq mm/ 16 Sq mm/10 sq mm for connecting earth to busbar, busbar to busbar and busbars to various equipments. Earth electrode of 17.20 mm dia and 3.00 meter long high tensile low carbon steel circular rods molecularly bonded with copper and outer surface (minimum copper bonding thickness of 250 microns to made requirement of under writer's laboratories (UL) 467-2007 or latest. Copper strips of 150 mm x 25 mm x 6 mm to be welded with each earth electrode, copper strips of 300 mm x 25 mm x 6 mm for main equip- potential busbar, copper strips of 150 mm x 25 mm x 6 mm sub equip-potential busbar in relay room, power room and panel room. GI strip 25 mm x 2 mm for ring formation of earth pits Earth enhancement material in bags for each Earth Electrode. Inspection chamber of site 300 mm x 300 mm x 300 mm (Inside dimension) of approximate 50 mm thick with pulling hooks to cover the earth pits. Note: The installation of this item shall be carried out by the contractor as per RDSO Specn.No.RDSO/SPN/ 197/2008 or latest and conforming to RDSO Drg.No.S DO/RDSO/E&B/001 or latest. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after execution and testing.	Set	2.00	7861.68	15723.36
Total					50784.82	
Item- 14	Chapter 14: Miscellaneous Signalling items, Painting, lettering					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	14010100	Supply of E type locks complete with keys as per RDSO Drg.No.SA-3376, 3377 & Spec.No.IRS(S) 30/64 or latest. Ward to be specified by Engineer-in-charge. Inspection:Consignee subject to procurement from RECOMMENDED LIST OF FIRMS FOR MECHANICAL SIGNALLING ITEMS if value of whole item in work less than 5 lakhs Inspection Charges: None Payment Terms: 100% after Supply	Numbers	10.00	1827.93	18279.30
2	14010200	Supply of seal plier as per sample got approved from site engineer incharge. Inspection:Consignee Inspection Charges: None Payment Terms: 100% after Supply	Numbers	3.00	1052.83	3158.49
3	14010400	Supply of Safety lock Godrej or Navtal make size as approved by site engineer. Inspection:Consignee Inspection Charges: None Payment Terms: 100% after Supply	Numbers	5.00	111.94	559.70
4	14010500	Supply of hand cuff lock Godrej or Navtal make size as approved by site engineer. Inspection:Consignee Inspection Charges: None Payment Terms: 100% after Supply	Numbers	100.00	344.34	34434.00

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

5	14010600	Supply of Obstruction test piece 3mm/5mm as per sample approved by Engineer incharge. Inspection:Consignee Inspection Charges: None Payment Terms: 100% after Supply	Numbers	3.00	2460.28	7380.84
		Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor's own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy paint will be supplied by Railways.NOTE:- The paint and primer should be from Asian Paints/ Nerolac / Dulux / Berger. The primer / enamel paints (Aluminum synthetic, black enamel, brilliant white and yellow) will be as per (IS 5660 of 1970) / (IS 2932 of 1974). Inspection:Consignee Inspection Charges: None Payment Terms: 100% after Execution				
6	14010801	Apparatus Case Full Size. (Outside & inside)	Numbers	15.00	253.80	3807.00
7	14010802	Apparatus case Half Size. (Outside & inside)	Numbers	10.00	229.90	2299.00
8	14010804	Main Signal Post with Signal Units, Surface base and complete fittings as per North Western Railways standard practice.	Numbers	3.00	350.53	1051.59
9	14010805	Shunt signal post with signal unit, surface base as per North Western Railway's Standard Practice.	Numbers	3.00	219.65	658.95
10	14010806	Track Lead Junction Box. (Black enamel outside only)	Numbers	50.00	60.32	3016.00
11	14010807	Point Machine with ground connections complete (Point Machine with Black enamel only outside and ground connections with Red Oxide)	Numbers	5.00	106.98	534.90
		Lettering / Numbering Termination particulars, equipments names etc., legibly and neatly inside location boxes. This includes supply of paints of Asian Paints/ Nerolac / Dulux / Berger make. Inspection:Consignee Inspection Charges: None Payment Terms: 100% after Execution				
12	14011001	Full Case.	Numbers	15.00	119.50	1792.50
13	14011002	Half Case	Numbers	10.00	81.94	819.40
14	14011900	Hiring of JCB machine(in good condition) for levelling and dressing ground/ dismantling structures including disposal of debris through dumpers etc with contractors labour , JCB machine , machine operator, fuel etc. The contractor shall arrange for road permit for all the states for operation as per instructions of engineer incharge and vehicle shall not be more than 3 years old . Payment shall be made for actual working hrs at site. Inspection:Consignee Inspection Charges: None Payment Terms: 100% after Execution	Hour	10.00	1090.59	10905.90
					Total	88697.57

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

Item- 15 Chapter- 15: Telecom items (Conference system, IPIS, OFC equipments, Control equipments, LC gate phones etc.)						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	15010100	Supply of UTP CAT-6 cable in a roll of 305 meter and make Siemen/ Systemax / Panduit/ Tyco/ Krone/ AMP. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply.	Metre	305.00	18.74	5715.70
2	15010200	Supply of 4/2 wire combined Portable Light Weight Emergency control telephones of metal body with 6-pin plug as per IRS-TC-75/99 (Amnd 4) or latest. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply.	Numbers	1.00	3316.73	3316.73
3	15010300	Supply of KRONE Punching tool, Krone or any reputed make only. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after supply.	Numbers	1.00	1401.40	1401.40
4	15010500	Supply of patch chord cable (10 meter long) with FC/PC connectors compatible with SDH equipments as per TEC Specn.No.GR/OFJ-02/01 May 2004 with latest Amendment. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after supply.	Numbers	3.00	947.11	2841.33
5	15010700	Supply of managed SDH (STM-1 Add/Drop MUX and upgradeable to STM-4) fully wired for 2 X 63 MB and equipped for 21E1s and a Virtual Container (VC)-12 with STM-1(L1.1) aggregate interface including power supply, order wire, Ethernet card, sub rack, inbuilt DDF, installation material and all other accessories, manuals etc. as per TEC. Specification GR SDH 04/02, March 02 or with latest amendment. The contractor will supply all other accessories as mentioned in the above said TEC Specifications and system will have provision of different redundancy cards as per the TEC Specifications. Note: It shall be possible to increase capacity from 21E1 to 63 E1s by adding / inserting tributary cards. This includes connecting all pig tails, optical patch cords etc. to the SDH equipment. This also includes connecting the SDH equipment with all cards to the 48V Bus including supply of wires and connectors. Termination of all E1s on DDF taking PVC cable over runway or a wall. At the terminal station, one port may be disabled if required as per instructions given by site engineer incharge. Inspection:(i) RDSO if value of item in work more than 5 lakhs or as per extant policy (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs or as per extant policy Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% after Supply.	Numbers	2.00	193957.98	387915.96

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

6	15010800	Installation, wiring, testing & commissioning of managed SDH (STM-1 Add/Drop MUX and upgradeable to STM-4) fully wired for 2 X 63 MB and equipped for 21E1s and a Virtual Container (VC)-12 with STM-1(L1.1) aggregate interface including power supply, order wire, Ethernet card, sub rack, inbuilt DDF, installation material and all other accessories, manuals etc. as per TEC. Specification GR SDH 04/02, March 02 or with latest amendment. The contractor will install all other accessories as mentioned in the above said TEC Specifications and system will have provision of different redundancy cards as per the TEC Specifications. Note: It shall be possible to increase capacity from 21E1 to 63 E1s by adding / inserting tributary cards. This includes connecting all pig tails, optical patch cords etc. to the SDH equipment. This also includes connecting the SDH equipment with all cards to the 48V Bus including supply of wires and connectors. Termination of all E1s on DDF taking PVC cable over runway or a wall. At the terminal station, one port may be disabled if required as per instructions given by site engineer incharge. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Commissioning.	Numbers	2.00	48489.50	96979.00
---	----------	--	---------	------	----------	----------

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

7	15010900	Supply of 2 Mb Programmable Primary Digital drop insert multiplexer as per RDSO Specs. IRS TC- 68/2004 (Amnd.1) or latest with conference facility and other stipulation to tender documents and fully wired for 30 channel complete with power supply card, remote control, supervision facility and all other accessories, installation material, manuals etc. It should have facilities to accommodate data interface card in multi drop mode and should be able to support cards needed for video conferencing and ISDN. It shall support NMS installed at Test Room and may operate local/remote location of entire section. It also includes submission of all technical documents, manuals and supply of all miscellaneous items which will be required for final testing and commissioning of system. The above MUX should be equipped with following circuits: - i) 2 wire/ 4 wire E&M VF circuits (minimum 16 nos ckts) ii) Subscriber loop circuits (minimum 4 nos ckts) iii) Exchange loop interface circuits (minimum 8 circuits) iv) This also includes connecting all pigtails, optical patch cords etc to the SDH equipments. This also includes connection of SDH and primary MUX equipment with all interface cards to the 48V Bus including supply of wires and connectors termination of all evens on DDF taking PVC cable over runway or a wall and termination of VF interface circuit to the Krone type. Inspection:(i) RDSO if value of item in work more than 5 lakhs or as per extant policy (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs or as per extant policy Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% after Supply	Numbers	2.00	253550.16	507100.32
---	----------	---	---------	------	-----------	-----------

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

8	15011000	Installation, wiring, testing and commissioning of 2 Mb Programmable Primary Digital drop insert multiplexer as per RDSO Specs. IRS TC- 68/2004 (Amnd.1) or latest with conference facility and other stipulation to tender documents and fully wired for 30 channel complete with power supply card, remote control, supervision facility and all other accessories, installation material, manuals etc. It should have facilities to accommodate data interface card in multi drop mode and should be able to support cards needed for video conferencing and ISDN. It shall support NMS installed at Test Room and may operate local/remote location of entire section. It also includes submission of all technical documents, manuals and supply of all miscellaneous items which will be required for final testing and commissioning of system. The above MUX should be equipped with following circuits: - i) 2 wire/ 4 wire E&M VF circuits (minimum 16 nos ckts) ii) Subscriber loop circuits (minimum 4 nos ckts) iii) Exchange loop interface circuits (minimum 8 circuits) iv) This also includes connecting all pigtails, optical patch cords etc to the SDH equipments. This also includes connection of SDH and primary MUX equipment with all interface cards to the 48V Bus including supply of wires and connectors termination of all evens on DDF taking PVC cable over runway or a wall and termination of VF interface circuit to the Krone type. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Commissioning.	Numbers	2.00	63387.54	126775.08
9	15011100	Supply of Pre-lubricated HDPE duct, 40 mm OD, 33 ID as per RDSO specification No. RDSO/SPN/TC/45/2013 Rev. 2.0 or latest. The item also includes supply of all the accessories of HDPE duct like end caps, collars, bends, couplers etc. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply	Kilometre	1.00	48313.26	48313.26
10	15011200	Laying of Pre-lubricated HDPE duct, 40 mm OD, 33 ID as per RDSO specification No. RDSO/SPN/TC/45/2013 Rev. 2.0 or latest. The item also includes installation of all the accessories of HDPE duct like end caps, collars, bends, couplers etc. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution.	Kilometre	1.00	12078.31	12078.31
11	15011300	Blowing/drawing of OFC cables in the HDPE duct along with all the protective work as per instructions of engineer incharge at site. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution.	Kilometre	1.00	10804.77	10804.77

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

12	15011400	Construction of brick chamber of optical fibre cable straight through joint as per Drg. No. CSTE/NWR/ SOR/23. It also includes supply and provision of all the material required for this item like bricks, sand, cement etc. The cement and sand should be in ratio 1:6. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution.	Numbers	1.00	5263.87	5263.87
13	15011500	Supply, installation and complete indoor wiring of 19 inch covered Rack of size 2035 mm x 600 mm x 600 mm (Approx.) as per Drg. No. CSTE/NWR/SOR/24. The rack shall be complete with all fittings for housing SDH equipments, Primary MUXES, DDF, MDF using crone modules and other equipments like runway ladders etc completely wired and equipped with integrated protection modules for all channels as per technical specifications and other stipulations of tender document. It should be possible to lock all the equipments with only order wire telephone remaining outside the rack. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution.	Numbers	1.00	36716.41	36716.41
14	15011600	Supply & Installation of Professional 19" Equipment Racks 4U for housing of network equipments. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after execution.	Numbers	1.00	4413.95	4413.95
15	15011700	Supply & Installation of Professional 19" Equipment Racks 12U for housing of network equipment. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution.	Numbers	1.00	7358.68	7358.68
16	15012000	Supply of SMPS based Battery Chargers as per RDSO Spec for Telecom use 48 volts, 25 Amps in 2+1 configuration modules of 25 Amps with ultimate expandable capacity 50 Amps, automatic switching between the modules as per RDSO Spec No. RDSO/SPN/TC/23/1999 version 4 or latest along with two potential free contacts. Inspection: (i) RDSO if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply	Numbers	2.00	127514.14	255028.28
17	15012100	Installation of Battery chargers, Power distribution Board along with MCBs of suitable ratings and wiring and commissioning of External alarm contacts through EMS. The work includes supply of battery rack, MCBs, battery cable and battery lugs and other accessories required for installation of power plant. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution.	Numbers	2.00	3666.60	7333.20

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

18	15012300	Supply of 48Volt/200AH maintenance free VRLA Batteries duly charged as per IRS Spec. No. S-93/96(A) with amendments-1 or latest Inspection: RDSO Inspection Charges: Borne by Railways. Payment Terms: 100% after Supply.	Numbers	2.00	77027.97	154055.94
19	15012400	Installation, wiring, testing & commissioning of 48Volt/200AH maintenance free VRLA Batteries duly charged as per IRS Spec. No. S-93/96(A) with amendments-1 or latest. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution.	Numbers	2.00	19256.99	38513.98
20	15012900	Supply, installation and complete wiring of Optical fiber cable termination box for 24 fibers complete with base housing, base mountings with fixing arrangement etc & splicing of fibers with low loss of pigtail cables as per detailed specification mentioned in respective tender documents. Two pairs of fibers shall be derived from either side of OFC cable at every OFC cable hut provided at wayside stations through pigtails with FC/PC connectors and remaining fibers on either side will be made through by splicing. At OFC terminal stations/MW repeater stations, all fibers shall be derived from either side and to be terminated in OFC termination box through pig tails and FC/PC connector. The OFC termination box to be supplied as per TEC No. G/FTB 01-02 March- 99 or latest. Splice losses in no case should be more than 0.1 dB. Necessary 0 dB connectors should be provided by contractor in OFC termination box. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution.	Numbers	2.00	24363.18	48726.36
21	15013100	Supply of LC/PC -LC/PC patch cord (5 meter) (3M, TE connectivity, R&M make or superior) Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply.	Numbers	3.00	147.63	442.89
22	15013200	Supply of SC/APC -LC/PC patch cord (5 meter) (3M, TE connectivity, R&M make or superior) Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply.	Numbers	3.00	146.69	440.07
23	15013300	Supply of SC-APC/SC-APC patch cord (1 meter) (3M, TE connectivity, R&M make or superior) Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply.	Numbers	3.00	119.54	358.62
24	15013700	Supply of 10 Pairs Krone type D.P. box as per Tech spec, make Hensel or superior. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply.	Numbers	1.00	1232.67	1232.67
25	15013800	Fixing and wiring of 10 Pairs Krone type D.P. box as per Tech spec, make Hensel or superior. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after execution.	Numbers	1.00	308.17	308.17
26	15013900	Supply of 20 Pairs Krone type D.P. box as per Tech spec, make Hensel or superior. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply.	Numbers	1.00	1963.08	1963.08

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

27	15014000	Fixing and wiring of 20 Pairs Krone type D.P. box as per Tech spec, make Hensel or superior. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after execution.	Numbers	1.00	490.77	490.77
28	15014700	Supply of DLP trunk 32X20mm with required all changeable internal/external angle, changeable flat angle, flat junction. Clips, joint for cover, end cap etc. make Legrand or superior. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply.	Metre	25.00	110.87	2771.75
29	15014800	Fixing & wiring (Laying) of DLP trunk 32X20mm with required all changeable internal/external angle, changeable flat angle, flat junction. Clips, joint for cover, end cap etc. make Legrand or superior. Cable will be supplied by Railway and all other fixing material will be supplied by contractor. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after execution.	Metre	25.00	27.72	693.00
30	15014900	Supply of frame, surface box and white cover plates for Two modules. This also includes supply of RJ-11 Telephone sockets with level holder Jack type, RJ-45 LAN sockets Jack Type (Tool less) and blanking plates for one modules. Make: Legrand or superior. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply.	Numbers	3.00	571.96	1715.88
31	15015000	Fixing of frame, surface box and white cover plates for Two modules. This also includes fixing of RJ-11 Telephone sockets with level holder Jack type, RJ-45 LAN sockets Jack Type (Tool less) and blanking plates for one modules. Make: Legrand or superior. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after execution.	Numbers	3.00	142.99	428.97
32	15015400	Supply of 19" covered rack of size 2035 X 600 X 600 mm (Approx) as per Drg.No.CSTE NWR SOR 24. The rake shall be complete with all fittings for housing SDH equipments, PDMUX, DDF, MDF using krone modules and other accessories like cable and connectors, runway ladders, locking arrangement, completely wired and equipped with IPM for all equipped channels. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after supply.	Numbers	2.00	29373.13	58746.26
33	15015500	Installation and complete indoor wiring of 19" covered rack of size 2035 X 600 X 600 mm (Approx) as per Drg.No.CSTE NWR SOR 24. The rake shall be complete with all fittings for housing SDH equipments, PDMUX, DDF, MDF using krone modules and other accessories like cable and connectors, runway ladders, locking arrangement, completely wired and equipped with IPM for all equipped channels. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after execution.	Numbers	2.00	7343.28	14686.56
34	15016200	Supply of OFC single mode 6 fibre unarmoured cable. Make Molex/ AMP/Finolex or similar. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after supply.	Metre	500.00	28.25	14125.00

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

35	15016700	Fabrication and erection of emergency rail post along the side of Rly track as per the location given by site engineer. It includes supply, fixing and wiring of socket box on emergency rail post. It includes supply of all the items except the Rails and Cable which will be arranged/provided by Railway. The contractor will complete all related work along with excavation if required for erection/installation of emergency rail post. 6-Pin emergency socket will be supplied as per RDSO Spen.No.IRS:TC42/87. Each socket box should have inbuilt universal lock facility with key as per sample approved by site engineer. Note: Contractor will supply the emergency socket box only after sample got approved from site engineer. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after execution.	Numbers	3.00	2249.41	6748.23
36	15016900	Painting of emergency post and sockets in sections as per instructions of the site engineer in charge. This shall include all material, labour and transportation required for painting of emergency post and sockets in section. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after execution.	Numbers	5.00	248.70	1243.50
37	15017000	Supply of VF Transformers (2T/3T), 1120/470 Ohms as per RDSO Spec. No. IRS: TC-76-2000 with Amnd. 1 or latest for emergency joints in 6-Quad Cable. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply.	Numbers	5.00	923.13	4615.65
38	15017600	Supply of wireless N 150 ADSL 2 Plus 4 port router MODEM make Techroutes/DIGISOL or superior. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply.	Numbers	5.00	1491.47	7457.35
39	15019400	Supply of power cable 3 core 2.5 sq mm multi strand (36/0.3 mm dia) cable as per IS 694:1990 reaffirmed 1995 or latest suitable for railway electrification area shall be of reputed make like Delton, LAPP, Finolex, or superior. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after supply.	Metre	200.00	33.02	6604.00
40	15019900	Supply of 2 core screened/shielded multistrand PVC insulated wire (24/0.2 mm dia) for speaker load line. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after supply.	Metre	200.00	35.22	7044.00
41	15020700	Supply of SFP Optical/Electrical 1 Gbps or 100/1000 Mbps Electrical as required. Make: Cisco, Eoptical or similar suitable for Neon. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply.	Numbers	1.00	4025.00	4025.00
42	15021300	Supply of 5 pair switchboard indoor cable 0.6 dia as per specification IRS:TC:24:91 or latest. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply.	Metre	200.00	23.62	4724.00

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

43	15021400	Supply of 10 pair switchboard indoor copper cable 0.6 dia as per specification IRS:TC:24:91. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply.	Metre	200.00	49.21	9842.00
44	15024000	Supply of Dual Channel VHF wireless Microphone Ahuja AWM-490V2 or superior with required all complete accessories for installation. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply.	Numbers	2.00	2328.39	4656.78
45	15025800	Supply, installation and complete wiring of optical fibre cable termination box for 6 fibres complete with base housing, base mountings with fixing arrangement etc. & splicing of fibre with low loss of pigtail cables. Splice losses in no case should be more than 0.1 dB. Necessary 0dB connectors should be provided in OFC termination box. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after execution.	Numbers	2.00	3347.14	6694.28
46	15025900	Supply of single mode single fibre optical media converter supports wavelength division multiplexing (WDM) upto 20 KM, wavelength supported 1310 & 1550 nm, 10/100/1000(Giga) RJ-45, model- DIGISOL DG-MC6123S or similar. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply.	Numbers	2.00	3356.35	6712.70
47	15026500	Supply of Small Form-Factor Pluggable(SFP) as per IEEE standard: IEEE 802.3z, Connector type: LC type, Wavelength(nm): 1310 nm, Fibre type: Single mode, Max cable distance: upto 20 km. Make & model DG-SA1133-20 DIGISOL/Netgear/Cisco or similar. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply.	Numbers	2.00	4667.65	9335.30
Total						1938759.01

4. ELIGIBILITY CONDITIONS

Standard Financial Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	: The tenderer must have minimum average annual contractual turnover of V/N or 'V' whichever is less, where V= Advertised value of the tender in crores of Rupees N= Number of years prescribed for completion of work for which bids have been invited. The average annual contractual turnover shall be calculated as an average of "total contractual payments" in the previous three financial years, as per the audited balance sheet. However, in case balance sheet of the previous year is yet to be prepared/ audited, the audited balance sheet of the fourth previous year shall be considered for calculating average annual contractual turnover. The tenderer shall submit requisite information as per Annexure-VIII given in tender document, along with copies of Audited Balance Sheets duly certified by the Chartered Accountant/ Certificate from Chartered Accountant duly supported by Audited Balance Sheet. As per Clause No. 10.2 of Tender Form (second Sheet) of Annex. I of Part-I of GCC-2022, with up to date correction slip.	No	No	Allowed (Mandatory)
1.1	If the tenderer submits/ upload Audited Balance sheet duly certified by a chartered accountant to fulfill the Standard Financial Criteria, the tenderer may also submit/ upload Form No. 26AS /16A along with the tender offer to certify the amount of contractual receipt.	No	No	Allowed (Optional)

Standard Technical Criteria

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	(a) The tenderer must have successfully completed or substantially completed any of the following categories of work(s) during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: (i) Three similar works each costing not less than the amount equal to 30% of advertised value of the tender, or (ii) Two similar works each costing not less than the amount equal to 40% of advertised value of the tender, or (iii) One similar work each costing not less than the amount equal to 60% of advertised value of the tender. (b) (1) In case of tenders for composite works (e.g. works involving more than one distinct component, such as Civil Engineering works, S&T works, Electrical works, OHE works etc. and in the case of major bridges - substructure, superstructure etc.), tenderer must have successfully completed or substantially completed any of the following categories of work(s) during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: (i) Three similar works each costing not less than the amount equal to 30% of advertised value of each component of tender, or (ii) Two similar works each costing not less than the amount equal to 40% of advertised value of each component of tender, or (iii) One similar work each costing not less than the amount equal to 60% of advertised value of each component of tender.	No	No	Allowed (Mandatory)
1.1	Note for b(1): Separate completed works of minimum required values shall also be considered for fulfillment of technical eligibility criteria for different components. (b) (2) In such cases, what constitutes a component in a composite work shall be clearly pre-defined with estimated tender cost of it, as part of the tender documents without any ambiguity. (b) (3) To evaluate the technical eligibility of tenderer, only components of work as stipulated in tender documents for evaluation of technical eligibility, shall be considered. The scope of work covered in other remaining components shall be either executed by tenderer himself if he has work experience as mentioned in clause 7 of the Standard General Conditions of Contractor through subcontractor fulfilling the requirements as per clause 7 of the Standard General Conditions of Contract or jointly i.e., partly himself and remaining through subcontractor, with prior approval of Chief Signal & Telecom Engineer in writing. However, if required in tender documents by way of Special Conditions, a formal agreement duly notarised, legally enforceable in the court of law, shall be executed by the main contractor with the subcontractor for the component(s) of work proposed to be executed by the subcontractor(s), and shall be submitted along with the offer for considering subletting of that scope of work towards fulfillment of technical eligibility. Such subcontractor must fulfill technical eligibility criteria as follows: The subcontractor shall have successfully completed at least one work similar to work proposed for subcontract, costing not less than 35% value of work to be subletted, in last 5 years, ending last day of month previous to the one in which tender is invited through a works contract. Note: for subletting of work costing up to Rs 50 lakh, no previous work experience of subcontractor shall be asked for by the Railway. In case after award of contract or during execution of work it becomes necessary for contractor to change subcontractor, the same shall be done with subcontractor(s) fulfilling the requirements as per clause 7 of the Standard General Conditions of Contract, with prior approval of Chief Signal & Telecom Engineer in writing.	No	No	Not Allowed
1.2	Note: A work experience certificate from a private individual shall not be considered. However, in addition to work experience certificates issued by any Govt. Organization, work experience certificate issued by Public listed company having average annual turnover of Rs 500 crore and above in last 3 financial years excluding the current financial year, listed on National Stock Exchange or Bombay Stock Exchange, incorporated/registered at least 5 years prior to the date of closing of tender, shall also be considered provided the work experience certificate has been issued by a person authorized by the Public listed company to issue such certificates. In case tenderer submits work experience certificate issued by public listed company, the tenderer shall also submit along with work experience certificate, the relevant copy of work order, bill of quantities, bill wise details of payment received duly certified by Chartered Accountant, TDS certificates for all payments received and copy of final/last bill paid by company in support of above work experience certificate. As per Clause No. 10.1 of Tender Form (second Sheet) of Annex.I of Part-I of GCC-2022, with up to date correction slip	No	No	Not Allowed

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

1.3	Defination of Similar Work :- Any RRI/PI/EI/MACLS Supply, Installation Testing, Commissioning Signalling work OR Any RRI/PI/EI/MACLS Alterations Signalling work OR Any CTC/TMS Work	No	No	Not Allowed
-----	--	----	----	-------------

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.
3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.
5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.
6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.
7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.
8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.
9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.
10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description
1	Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. (Click here to download the Format of Self Certification)

5. COMPLIANCE

Commercial-Compliance

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer must opt for payment by letter of credit (LC) as per the Railway Board's letter no. 2018/CE-I/CT/9 dated 04.06.18.	Yes	Yes	Allowed (Optional)
2	Tenderers are required to quote their Permanent Account Number in the tender document.	Yes	Yes	Allowed (Mandatory)
3	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)
4	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

General Instructions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	No garbage, dry leaves, paper, grass, bushes, or any other items shall be burnt. They shall only be disposed of at the nominated disposal point by prescribed methods, duly observing the Municipal Solid Wastes (Management and Handling) Rules, 2000 indicates under Schedule II- Management of Municipal Solid Wastes: Para I.I vii that Waste(garbage, dry leaves) shall not be burnt. Any violation of the provisions of the MSW rules,2000, attracts the penal provisions of the Environment(Protection) ACT,1986.CPCB and SPCBs have also issued various guidelines/orders against the practice of such open burning. If the contractor or anybody deployed by him for this work is found guilty of unregulated open burning of plastic, rubber, waste, and similar substances, a fine of Rs. 5000/- on each occasion shall be imposed in addition to the other rights and remedies available in the contract. The decision of the Engineerin-Charge shall be final and binding in this regard.	No	No	Not Allowed
2	The EI alteration work is to be done at the Parsneu & Bikaner East station of the BKN-RTGH section of the Bikaner Division. The EI alteration work is related to the provision of Track Machine Siding. The Mini-Plan of the PSV & BKNE station is attached to the document. EI OEM of PSV & BECN stations - M/s Kyosan India Private Limited.	No	No	Not Allowed

Special Conditions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	If the Tenderer is not an OEM, then the bidder shall submit the authorization/MoU of the EI OEM after the award of the Tender but before the agreement preparation stage. "MoU is to be done with the RDSO-approved EI OEM only, and the MoU covering the supply of the equipment of EI, installation, testing, and commissioning of EI by the same RDSO-approved source, including after-sales support required during the warranty period and beyond the warranty period. (EI OEM - M/s Kyosan India Private Limited for PSV & BECN stations) Note: - Authorization/MoU with OEM of EI is not mandatory at the time of the bidding process.	No	No	Not Allowed

Technical-Compliances

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	1) In case of a partnership deed, please submit copies of all previous/old/amended partnership deeds, also, if any. 2) In case of a company, please submit a copy of the certificate of incorporation issued by the Registrar of Companies. 3) In case of a company, please submit a copy of the MOA and AOA. 4) In case of a company, please submit a copy of the Resolution of the Board of Directors passed for Power of Attorney, along with a copy of the stamped and notarized POA (backed by the above Board Resolution). Please submit copies of the PAN and GSTIN.	Yes	Yes	Allowed (Optional)

Undertakings

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
-------	-------------	-----------------------	-----------------	---------------------

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

1	I/We have submitted full information in the prescribed format regarding membership/ employment of retired Gazetted officer and family members working in gazetted capacity in the Engineering or any other department of the railways. If no information is provided in this regard or if Annexure-XXIII is not submitted with the original offer, then I hereby certify that the information is nil as on the date of opening of tender. If it is found in the future, after award of LOA, that information in this regard, as required as per clause 16 a), b), c) of GCC-2022 has been deliberately concealed, the contract is liable to be dealt in accordance with the provisions of clause 62 of the Standard General Conditions of contract.	No	No	Not Allowed
2	I/ We have visited the worksite and I / We am/are aware of the site conditions.	No	No	Not Allowed

Custom

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Certificate to be submitted by tenderer along with the tender documents as per Annexure-II attached in tender Document.	Yes	Yes	Allowed (Mandatory)
1.1	The certificate to be submitted by the tenderer along with the tender documents as per Annexure-IIA is attached to the tender Document. (This certificate is to be given by the attorney/ authorized signatory/ each member of the Partnership firm/ Joint Venture (JV)/ Hindu Undivided Family (HUF)/ Limited Liability Partnership (LLP) etc.) The certificate to be submitted by the tenderer along with the tender documents as per Annexure-IIA is attached to the tender Document. (This certificate is to be given by the attorney/ authorized signatory/ each member of the Partnership firm/ Joint Venture (JV)/ Hindu Undivided Family (HUF)/ Limited Liability Partnership (LLP) etc.)	Yes	Yes	Allowed (Optional)
2	Declaration regarding constitution of firm & Bank Details as per Annexure-I attached in tender Document.	Yes	Yes	Allowed (Mandatory)
3	Mandatory undertaking Regarding Employment/ Partnership of Retired Railway Employees as per Annexure - XXIII attached in Tender Document.	Yes	Yes	Allowed (Mandatory)
4	Relevant Annexure is to be submitted in connection with status of their firms. i. e. Either for Sole Proprietorship/Partnership/Company registered under companies Act 2013/LLP (Limited Liability Partnership)) Registered under LLP Act 2008/Registered Society and Registered Trust/HUF (Hindu undivided Family) Firm's. Prescribed Format (Relevant Annexure) as per Firm's status is attached in tender document as per clause 16.2	Yes	Yes	Allowed (Mandatory)

6. Documents attached with tender

S.No.	Document Name	Document Description
1	SnT-BKN-2026-27-07.pdf	Tender Booklet
2	GCCCS5.pdf	GCC CS
3	GCCCS3.pdf	GCC CS
4	GCCCS1.pdf	GCC CS
5	GCCCS4.pdf	GCC CS
6	GCCCS2.pdf	GCC CS
7	GCCCS7.pdf	GCC CS
8	GCCCS6.pdf	GCC CS
9	GCCCS9.pdf	GCC CS
10	GCCCS8.pdf	GCC CS
11	IRGCCApril2022.pdf	GCC, 2022
12	GCCCS10.pdf	GCC CS
13	GCCCS11.pdf	GCC CS
14	EITAN300702.11.2012.pdf	EI TAN
15	EITAN301210.08.2016.pdf	EI TAN

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-07

Closing Date/Time: 10/06/2026 15:00

16	EITANoncybersecurity.pdf	EI TAN
17	MiniPLan-PSV.pdf	PSV Mini Plan
18	MiniPLan-BECN.pdf	BECN Mini Plan

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

Signed By: RAN SINGH GODARA

Designation : Sr.DSTEBKN