

**MUMBAI-CST-DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-BB-SNT-EAST-2026-26

Closing Date/Time: 22/06/2026 15:00

Sr.DSTE/Co acting for and on behalf of The President of India invites E-Tenders against Tender No **CR-BB-SNT-EAST-2026-26** Closing Date/Time 22/06/2026 15:00 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

1. NIT HEADER

Name of Work	Signaling work in connection with Provision of additional loop lines on UP side in Jite Station of Mumbai division.		
Bidding type	Normal Tender		
Tender Type	Open	Bidding System	Single Packet System
Tender Closing Date Time	22/06/2026 15:00	Date Time Of Uploading Tender	22/05/2026 16:14
Pre-Bid Conference Required	No	Pre-Bid Conference Date Time	Not Applicable
Advertised Value	42077295.61	Tendering Section	EAST
Bidding Style	[Decision at Schedule level]	Bidding Unit	
Earnest Money (Rs.)	841600.00	Validity of Offer (Days)	60
Tender Doc. Cost (Rs.)	0.00	Period of Completion	12 Months
Contract Type	Works - General	Contract Category	Expenditure
Bidding Start Date	08/06/2026		
Are JV allowed to bid	No	Number of JV Member Allowed	0
Are Consortium allowed to bid	No	Number of Consortium Member Allowed	0
Ranking Order For Bids	Lowest to Highest	Expenditure Type	Capital (Works)

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A-SOR ITEM							10619349.82	Above/ Below/P ar
01	011060	1.00	Per Alteration	2223143.0 0	2223143.00	18.00	2623308.74	
	Description:- Modification in existing EI system as per latest TAN, it includes:- Design and modification in existing interface and interlocking circuit of EI system, including modification in VDU,CCIP, MT, Data logger, EI, Relay rack complete wiring conforming to RDSO specification, as per technical requirement & tentative approved signaling plan/diagrams. Required hardware will be provided by railways except the wiring, material (i.e. connectors, interconnecting cable/wires, fuses etc.) The work includes supply of modified ST/LT, interface and logic circuit, CCIP/VDU diagram etc. to suit the approved interlocking plan. It also includes modification in data logger/MT, carrying out FAT, SAT jointly with railways and satisfactory commissioning of the modified EI with full complements as per approved IP and central railway practices. All plans and wiring diagrams shall be prepared on AUTOCAD and supplied in both soft copy and hard copies (6 sets.)Alteration involving modification in more than 11 and up to 20 routes NOTE : If the alteration involves modification of routes up to 10, fixed cost as per the Rate mentioned in (i) above shall be paid. If the alteration involves modification of routes are more than 10 up to 20 routes, then, fixed cost as per the Rate mentioned in (ii) above shall be paid.							
02	011040	1.00	Set	146679.00	146679.00	18.00	173081.22	
	Description:- Supply of Portable work station for Data input & configuration with necessary software/AutoCAD latest version programmes/Accessories, simulation and functional Testing, diagnostics and trouble shooting and commissioning of EI system. Suitable Table & Chair or reputed make shall be supplied by the contractor. The specifications of the PC / Laptop should be got approved from the Engineer in charge before supply. Note : Portable work station should strictly adhere to specification as per annexure-I.							
03	011070	1.00	Set	30325.00	30325.00	18.00	35783.50	

**MUMBAI-CST-DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-BB-SNT-EAST-2026-26

Closing Date/Time: 22/06/2026 15:00

			Description:- Supply of Relay rack assembly complete with scaffolding, fixtures and accessories including MS Bars for fixing of relay plug board, string rods, fuse strips with bracket, 11 way Bus bars with cover and mounting brackets, runway for cable/wires, frame, base assembly etc. Siemens type & as per extant practice on C.Rly. Typical part list as per Annexure-II and Rack arrangement as per sketch no SK-727 and Rack plan as approved by Engineer in charge.				
04	011080	10.00	Numbers	1217.00	12170.00	18.00	14360.60
			Description:- Supply of Tag blocks 200/160/120 way with polycarbonate cover as per IRS S 77-2006.(Rev.1) RDSO DRG. No.SA 24751, SA 24752 & SA 24753. Requirement of each type shall be specified by Engineer-in-charge.				
05	011100	1.00	Set	26006.00	26006.00	18.00	30687.08
			Description:- Supply of Main cable Termination rack complete with scaffolding, fixtures & accessories including square bars for mounting 8-way terminal blocks, ladder, string rods, frame, base assembly, insulators, J bolt , nut/bolts & fasteners, bakelite sheet, etc. Siemens type and as per extant practice of Central Railway. Typical part list as per Annexure-III and rack arrangement shall be as per sketch No.SK-727 with latest alterations.				
06	011110	64.00	Numbers	364.00	23296.00	18.00	27489.28
			Description:- Supply 8-way Terminal strips, made of PBT, isolating barrier type as per IRS-S-79/92 (Amd. 2) & Drg No SA24811 (Alt.2) & SA24812 (Alt.2) with latest amendment.				
07	011120	1.00	Set	572233.00	572233.00	18.00	675234.94
			Description:- Supply of Data logger for monitoring status of important relays, complete with processor Module to monitor following inputs as per spec. RDSO/SPN/99/2006 Spec. No: IRS:S-99/2006 (Amdt-3) with latest amendments including power supply of adequate capacity, battery and fault diagnostic software for failure analysis. Complete data logger & Processor Module (computer) as per Annexure-IV shall be placed in President rack of suitable size to be supplied. This also includes supply of one no. composite computer & printer table (work station table-Godrej/Durian/Transteele) for keeping processor module and one no. Godrej/Durian/Transteele make operator chair. i)1024 digital and 32 analog inputs.				
08	011240	1.00	Kilometre	246408.00	246408.00	18.00	290761.44
			Description:- Supply of PVC indoor cable 1x24x1 mm dia. Color coding of insulation of Inner conductor shall be in eight colour viz, Blue, Red, Grey, Green, Brown, Black, Yellow & white confirming to IRS 76/89 (Amd. 3) or latest.				
09	011250	10.00	Kilometre	7770.00	77700.00	18.00	91686.00
			Description:- Supply of Indoor Jumper wire of various colour as per Railways standard practice of type ATC 1x0.6 mm dia. Conforming to IRS/76/89 (Amd.3) of latest.				
10	011260	1.00	Kilometre	11585.00	11585.00	18.00	13670.30
			Description:- Supply of Indoor Jumper wire ATC 1x1 mm dia. Conforming to IRS/76/89 (Amd.3) of latest.				
11	011270	1.00	Kilometre	39345.00	39345.00	18.00	46427.10
			Description:- Supply of PVC flexible copper cable single core, multistrand 1x2.5 Sq.mm (50 conductor each diameter 0.25 +/- 0.01) as per IS 694/2010. with latest amendment if any with insulation thickness of 0.70 mm nominal conductor resistance 7.98 ohms/km and test parameters are as per IRS (S) 76/89 (Amd.3)or latest.				
12	011290	1.00	Kilometre	119222.00	119222.00	18.00	140681.96
			Description:- Supply of PVC flexible copper cable single core, multistrand 1x10 Sq.mm (80 conductor each diameter 0.40 +/- 0.01) as per IS 694/2010. with latest amendment if any with insulation thickness of 1.0 mm nominal conductor resistance 1.91 ohms/km and test parameters are as per IRS (S) 76/89 (Amd.3)or latest.				
13	011300	1.00	Kilometre	177112.00	177112.00	18.00	208992.16
			Description:- Supply of PVC flexible copper cable single core, multistrand 1x16 Sq.mm (126 conductor each diameter 0.40 +/- 0.01) as per IS 2465/1984 & IS: 694/2010. with latest amendment if any with insulation thickness of 1.0mm nominal conductor resistance 1.121 ohms/km and test parameters are as per IRS (S) 76/89 (Amd.3)or latest.				
14	011310	1.00	Kilometre	279653.00	279653.00	18.00	329990.54
			Description:- Supply of PVC flexible copper cable single core, multistrand 1x25 Sq.mm (196 conductor each diameter 0.40 +/- 0.01) as per IS 2465/1984 & IS: 694/2010. with latest amendment if any with insulation thickness of 1.2mm nominal conductor resistance 0.780 ohms/km and test parameters are as per IRS (S) 76/89 (Amd.3)or latest.				
15	011320	10.00	Kilometre	5605.00	56050.00	18.00	66139.00
			Description:- Supply of wire 16/0.2 (Blue, Red, Grey, yellow, Brown, Black, White as per site engineer instruction) finolex/polycab/delton make. IRS:S-76/89 (Amd.3), BS: 4808 Part-2. Wire to be procured from RDSO approved vender.				
16	011550	100.00	Kg	112.00	11200.00	18.00	13216.00
			Description:- Supply of Rubber Mat 5mm thick for use in signaling installation.				
	013600	20.00	Numbers	4321.00	86420.00	18.00	101975.60

**MUMBAI-CST-DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-BB-SNT-EAST-2026-26

Closing Date/Time: 22/06/2026 15:00

17	Description:- Supply of 4.5 kg CPO2 type fire extinguisher along with all accesories, extinguisher testing certificate has to be supplied along with - Supply of ISI marked Carbon Dioxide type (BC) fire extinguisher of 4.5 Kg capacity confirming to IS 2878: 2004 from seamless cylinder, with IS marked control value, high pressure mtr., Long discharge hose and horn complete with initial gas charged with carrying handle and wall mounting bracket etc. as required by site Engineer.
18	013450 5.00 Numbers 2710.00 13550.00 18.00 15989.00 Description:- Supply of Thermo-Shrink cable joining kit (Reinforced) TSF-2 type generally confirming to RDSO specification RDSO/SPN/TC/57/2015 Rev 1 with modified kit contents as per CSTE's Specification No.:CR/SPN/TC/57 (A)/2015 Dt: 06.01.2015 (Table-A) to be suitable for jointing both 10/20/50 pair PIJF and 4/6 Quad cables alongwith sub-kit (Table-B) for armour continuity.
19	011650 50.00 Numbers 654.00 32700.00 18.00 38586.00 Description:- Relay base plate complete with amphanol's, code pins, fixing screws etc. suitable for Metal to Metal K-50 mini groups/ECRs of Siemens Make or functional equivalent of other makes.Note : Relay Base plates, are to be procured from Relay manufacturer (OEM). Manufacturer's Certificate for procurement and guarantee in this regard should be furnished. The payment to be released only after Manufacturer's Certificate is submitted.
20	011760 2.00 Numbers 6780.00 13560.00 18.00 16000.80 Description:- Supply of Time Element Relay (Clock work type) AG timer Siemens make (No.RSSK 30/0052) or GIC make or functional equivalent.
21	011770 5.00 Numbers 7948.00 39740.00 18.00 46893.20 Description:- Supply of Key Lock Relay with different ward combinations (Three extra set of ward plate for point Machine to be supplied with each relay). Siemens make working on 60V DC/24 DC or functional equivalent without base plates. RDSO/SPN/219/2016 version 1.0 with Amendment No.1 or latest.
22	011830 10.00 Numbers 5859.00 58590.00 18.00 69136.20 Description:- Supply of Metal - To - Metal universal LED type ECR Siemens make (type A-RT-RG-A064) or functional equivalent without base plates, should be suitable for working with LED based signal lighting unit. IRS:S 46/74 with Amd. 1 & STS/E/RELAYS/AC LIT LED SIGNAL/09-2002 Amd.1
23	012100 2.00 Set 49941.00 99882.00 18.00 117860.76 Description:- Supply of Talk Back system DTMF Hand free type DUPLEX SYSTEM with slave to slave talking facility in addition to master - to - slave facility for Relay Room and panel Room. One Master and Three slave complete (with 20W speaker) to be supplied.
24	011780 40.00 Numbers 6915.00 276600.00 18.00 326388.00 Description:- Supply of Plug In type Relay Metal to Metal type neutral relay mini groups (Non AC Immunized) Siemens make (No.RSSK 30/0011) (Ref.IRS:S46/74 with Amd.1 & firms specification). or functional equivalent without base plates. Contact configuration 5F/3B or 6F/2B or 4F/4B to be specified by Engineer incharge.
25	011790 20.00 Numbers 7355.00 147100.00 18.00 173578.00 Description:- Supply of Plug In type Relay Metal to Metal type neutral relay mini groups (AC Immunised-1) Siemens make (No.RSSK 30/0078-1) (Ref.IRS:S46/74 with Amd.1 & firms specification). or functional equivalent without base plates. Contact configuration 5F/3B or 6F/2B or 4F/4B to be specified by Engineer incharge.
26	011810 20.00 Numbers 6822.00 136440.00 18.00 160999.20 Description:- Supply of Plug In type Relay Interlocked Siemens make (No. RSSK 30/0012) or functional equivalent (Ref. IRS:S46/74 with Amd. 1 & firms specification). Contact configuration 4F/4B.
27	011840 3.00 Numbers 3409.00 10227.00 18.00 12067.86 Description:- Fail safe Electronic Time delay unit (Plug In type) to operate 24VDC with only one fixed time setting of 30@ 47<47@ 120 seconds as per RDSO Specification No.IRS-S-61/2000 with Amendment No.3 or Latest.
28	011860 20.00 Numbers 3496.00 69920.00 18.00 82505.60 Description:- Supply of QNA1-K AC immunized relay, 12F-4B, 24 VDC along with plug, retaining clip and connectors conforming to BRS:931A & RDSO letter no STS/E/Relays/UEA/PI dated 30.05.97 Annexure-II IRS:S60, IRS:S34 & IRS:S23
29	011870 20.00 Numbers 3359.00 67180.00 18.00 79272.40 Description:- Supply of QNA1 AC immunized relay, 8F-8B, 24 VDC along with plug, board, retaining clip and connectors conforming to BRS:931A,IRS:S60/78 with Amendment no.1 , IRS:S34/68 with Amendment no.6 & IRS:S23/88 with Amendment no.1
30	011880 20.00 Numbers 3507.00 70140.00 18.00 82765.20 Description:- Supply of QN1 Non AC immunized neutral relay, 8F-8B, 24 VDC along with plug, board, retaining clip and connectors conforming to BRS:930, IRS:S60/78 with Amendment no.1 , IRS:S34/68 with Amendment no.6 & IRS:S23/88 with Amendment no.1
	011890 20.00 Numbers 3876.00 77520.00 18.00 91473.60

**MUMBAI-CST-DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-BB-SNT-EAST-2026-26

Closing Date/Time: 22/06/2026 15:00

31	Description:- Supply of QN1 Non AC immunized neutral relay, 12F-4B, 24 VDC along with plug, board, retaining clip and connectors conforming to BRS:930,IRS:S60/78 with Amendment no.1 , IRS:S34/68 with Amendment no.6 & IRS:S23/88 with Amendment no.1						
32	011900	20.00	Numbers	5322.00	106440.00	18.00	125599.20
33	Description:- Supply of QNN1 Twin neutral line relay, 24 V DC 4F- 4B/5F-3B/6F-2B contacts, complete with plug, board, retaining clip and connectors BRS:960						
34	011910	40.00	Numbers	3678.00	147120.00	18.00	173601.60
35	Description:- Supply of QSPA1 relay, 24 V DC Slow to pick up, 8F- 4B along with plug, board, retaining clip and connectors conforming to BRS:933 IRS:S60/78 with Amendment no.1 , IRS:S34/68 with Amendment no.6 & IRS:S23/88 with Amendment no.1)						
36	011920	20.00	Numbers	3241.00	64820.00	18.00	76487.60
37	Description:- Supply of QTA2 AC immunized track relay, 9 Ohm, 2F.1B, along with plug, board, retaining clip and connectors conforming to BRS:939A, 966 & Appendix F2, IRS:S34/68 with Amendment no.6 & IRS:S23/88 with Amendment no.1)						
38	011930	20.00	Numbers	5531.00	110620.00	18.00	130531.60
39	Description:- Supply of QBAT track Relay, AC immunized, 2F-2B, contacts, 9 ohms. Complete with plug, board, retaining clip and connectors as per RDSO/SPN/84 Ver. 2.0 with Amendment No.1 or latest.						
40	011940	20.00	Numbers	3317.00	66340.00	18.00	78281.20
41	Description:- Supply of Universal LED Lamp proving relay QECX61 relay, 4F-4B, AC conforming to BRS:941A STS/E/RELAYS/AC LIT LED SIGNAL/09-2002, Amdt.-1 (FOR ALL ASPECT ECR FOR AC LED SIGNAL)						
42	011950	4.00	Numbers	4578.00	18312.00	18.00	21608.16
43	Description:- Supply of QCJ1 neutral thermal time Element Relay, 24 VDC, 2F-1B, contacts Complete with plug board retaining clip & connectors BRS:937A						
44	012060	1.00	Numbers	15032.00	15032.00	18.00	17737.76
45	Description:- Supply of Fail safe Electronic Flasher Device 24V DC or 60V DC as per RDSO spec No.: RDSO/SPN/173/2002 amendment 2 or latest.Block Inst., UFSBI, & Control Phones.						
46	012110	5.00	Numbers	2501.00	12505.00	18.00	14755.90
47	Description:- Supply of Desk type Electronic Magneto Telephone as per spec No. IRS TC-79/2000 (Amd.4) with Amendment No.02 or with latest amendments.						
48	012260	100.00	Numbers	70.00	7000.00	18.00	8260.00
49	Description:- Supply of INDICATIVE TYPE OF FUSE INSERTS. IRS S:-78-92 With holder 1.6 A (System, Rapid or Malnad Make).						
50	012270	100.00	Numbers	68.00	6800.00	18.00	8024.00
51	Description:- Supply of INDICATIVE TYPE OF FUSE INSERTS. IRS S:-78-92 With holder 0.6 A (System, Rapid or Malnad Make).						
52	012280	40.00	Numbers	230.00	9200.00	18.00	10856.00
53	Description:- Supply of INDICATIVE TYPE OF FUSE INSERTS. IRS S:-78-92 With holder 6 A/10A (D-Type Bharat Linder, L&T or HEVELLS Make).						
54	012290	100.00	Numbers	20.00	2000.00	18.00	2360.00
55	Description:- Supply of INDICATIVE TYPE OF FUSE INSERTS. IRS S:-78-92 Without holder 1.6 A (System, Rapid or Malnad Make).						
56	012300	100.00	Numbers	20.00	2000.00	18.00	2360.00
57	Description:- Supply of INDICATIVE TYPE OF FUSE INSERTS. IRS S:-78-92 Without holder 0.6 A (System, Rapid or Malnad Make).						
58	012310	100.00	Numbers	82.00	8200.00	18.00	9676.00
59	Description:- Supply of INDICATIVE TYPE OF FUSE INSERTS. IRS S:-78-92 Without holder 6 A/10A (D-Type Bharat Linder, L&T or HEVELLS Make).						
60	012250	1.00	Set	15907.00	15907.00	18.00	18770.26
61	Description:- Supply of talk back loud speaker with press to talk, working on 110V AC/24 V DC, and bridge loss 0.5 db. Maximum power loss 25 dB, loud speaker output 0.5 W, maximum power consumption 3 watt suitable for use on underground cable. The material to be approved by Railway engineer before installation (ACES make or similar) (one post type and one table type in one set) Talk back loud speaker with press to talk working on 110V AC/12 V DC, bridge loss 0.5 db. Maximum power loss 25 db, loud speaker output 0.5 W, maximum power consumption 3 watt suitable for use on underground cable. The material to be approved by Railway engineer before installation (ACES make or similar) (one post type and one table type in one set)						
62	012360	1.00	Lot	46725.00	46725.00	18.00	55135.50
63	Description:- Supply of Resistors, condensers, Diodes, LEDs and lugs alongwith bracket and mounting arrangement as per standard Annexure-V of Central Railway.						
64	012370	20.00	Kg	1078.00	21560.00	18.00	25440.80

**MUMBAI-CST-DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-BB-SNT-EAST-2026-26

Closing Date/Time: 22/06/2026 15:00

48	Description:- Resin cored wire as per specification No.IS:1921-1975 with Alloying element percentage as 63% SN (Tin) and / 37% Pb (Lead) with percentage of various impurities not exceeding the values Sb (Antimony 0.2% maximum, Cu (Copper) 0.1% maximum, As (Arsenic) 0.05% maximum, Fe (Iron) 0.02% maximum & other impurities mainly Al, Zn & Cd shall be limited. The flux shall be free from corrosive action as per clause 5.2 & flux percentage may be used as per requirement.						
49	012380	50.00	Numbers	57.00	2850.00	18.00	3363.00
	Description:- Lacing thread rolls, black, wax coated (100 mtrs)						
50	012390	2.00	Sqm	6084.00	12168.00	18.00	14358.24
	Description:- Fabrication and supply of Boar made of White sunmica sheet over 12 mm thick particle/Laminated/wooden board covered with 5mm thick perspex transparent sheet in aluminium/ steel frame and painting of SWR / Track insulation plan etc.						
51	012440	4.00	Numbers	5979.00	23916.00	18.00	28220.88
	Description:- Supply of Main signal post 140 mm outer dia 4.6 Mtr Length as per spec No.IRS S 6/81 with latest amendments.						
52	012450	4.00	Numbers	8119.00	32476.00	18.00	38321.68
	Description:- Supply of Main signal post 140 mm outer dia 5.6 Mtr Length as per spec No.IRS S 6/81 with latest amendments.						
53	012470	8.00	Numbers	7944.00	63552.00	18.00	74991.36
	Description:- Supply of Cast Iron Main signal surface base 140mm as per spec No IRS: S-10 and Drg No 2011/M with latest amendments, with CLS Ladder assembly complete for CLS signal 5.5/4.5/3.5 mtrs long as per RDSO Drg no. SA 23156 (Adv), SA 23153 (Adv) & SA 23150 (Adv) Alt.1 respectively with Latest Amendment as the case may be for CLS unit & signal back staging as per extent C.Rly practice.						
54	012490	10.00	Numbers	447.00	4470.00	18.00	5274.60
	Description:- Supply of Signal No.Plates as per Drg No RST-11393/ SK-842						
55	012520	10.00	Numbers	476.00	4760.00	18.00	5616.80
	Description:- Supply of A/AG/C/P/G/IB Board as per Drg. RST-11444/1(A), RDSO Drg No SA-23460(AG), SA-23461(C) , RST-11445, SA 23456(P), SA 23477(G) & SA 23476-77 (IB) as applicable respectively with Latest Amendment.						
56	012530	2.00	Numbers	2763.00	5526.00	18.00	6520.68
	Description:- Supply of Stop Board / IB Board as per RST-11791 (STOP BOARD)/ RDSO Drg No 7235/B as per extent C.Rly practice.						
57	012540	4.00	Numbers	2795.00	11180.00	18.00	13192.40
	Description:- Supply of different warning Board as per Goods warning Board (SK-784) RDSO Drg No. SA 2380 (Adv), SA 2370/M-, Block section limit Board RDSO Drg No. SA 2373 - Paint and retroreflective arrangement as per Railways drawing.						
58	012550	50.00	Numbers	245.00	12250.00	18.00	14455.00
	Description:- Supply of Hand Cuff Locks / Godrej Navtal lock with Three common keys.						
59	012560	1.00	Numbers	25824.00	25824.00	18.00	30472.32
	Description:- Supply of "2 aspect" Signal Unit in FRP body without lenses and transformers as per RDSO Specification RDSO/SPN/194/2006/Rev.2.0 or latest complete and to suit LED signal Lamps and suitable for 140 mm dia post saves pigment finish on the back side of the and inside. white pigment finish inside the 2 aspect unit to avoid any extra paint cost						
60	012590	4.00	Numbers	11731.00	46924.00	18.00	55370.32
	Description:- Supply of Shunt Signal Position Light Type FRP complete as per RDSO Specification RDSO/SPN/194/2006/Rev.2.0 or latest with Off set bracket 3-1/2" to be fitted on 140 mm post drawing No.SA23840(Adv) Alt-2 for dependent type complete with signal unit bracket, terminals etc without lenses, lamp, lamp holder, and to suit LED signal lamps.						
61	012600	1.00	Numbers	29381.00	29381.00	18.00	34669.58
	Description:- Supply of 1 way junction Route Indicator in FRP body without lenses and transformers as per RDSO Specification RDSO/SPN/194/2006/Rev. 2.0 or latest complete and to suit LED signal Lamps						
62	012610	2.00	Numbers	36469.00	72938.00	18.00	86066.84
	Description:- Supply of 2 way junction Route Indicator in FRP body without lenses and transformers as per RDSO Specification RDSO/SPN/194/2006/Rev. 2.0 or latest complete and to suit LED signal Lamps						
63	012640	2.00	Numbers	7154.00	14308.00	18.00	16883.44
	Description:- Supply of "Calling On" Signal Unit in FRP body without lenses and transformers as per RDSO Specification RDSO/SPN/194/2006/Rev. 2.0 or latest complete and to suit LED signal Lamps						
	012650	2.00	Numbers	4381.00	8762.00	18.00	10339.16
64							

**MUMBAI-CST-DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-BB-SNT-EAST-2026-26

Closing Date/Time: 22/06/2026 15:00

64	Description:- Supply and Fixing of RE Protective Screens of expanded metal 12 SWG of size 1200 x 1500 mm on signals as per extent practice & as per instruction of Rly engineer at site DRG - No.SK-844						
65	012670	20.00	Numbers	5065.00	101300.00	18.00	119534.00
	Description:- Supply of FIBRE GLASS INSULATING FIRE RETARDENT SHEET OF 10 MM THICKNESS AS PER ISO: 10192-1982, Dielectric strenth -25KV/mm with glass content 25 to 34% in standard size of 1.10x1.10 Mtr as per spec. No.IS:10192-1982						
66	012680	1000.00	Numbers	65.00	65000.00	18.00	76700.00
	Description:- Supply of ARA Terminal blocks with links made of PBT Specn No.IRS/75/2006 (Rev - 2) with latest amendments and RDSO Drg.No.SA-23741A Alt.4., SA-23745 Alt.5, SA-23746, SA-23748 Alt.4, & SA-23756 Alt.3.						
67	012690	10.00	Numbers	144.00	1440.00	18.00	1699.20
	Description:- Supply of cartridge fuse block made of PBT as per RDSO Drg No SA-23748 Alt 4, SA-23749 & Spec No.IRS S 75/2006 Rev.02 with latest amendment. Fuse block shall be suitable for round head type voltage fuses.						
68	012700	50.00	Numbers	62.00	3100.00	18.00	3658.00
	Description:- Supply of round head type non deteriorating type low voltage cartridge fuse as per specn No. IRS/S/78/92 with latest amendments - 2A/4A/6A capacity						
69	012760	30.00	Numbers	951.00	28530.00	18.00	33665.40
	Description:- Supply of earth electrode assembly as per Drg.No.CR/S&T/SK-815						
70	012830	3.00	Set	11963.00	35889.00	18.00	42349.02
	Description:- Supply and Installation of Lightening & Surge protection device, Single phase + neutral (housed in a suitable impact resistance box) for providing B class protection as per RDSO spec No. RDSO/SPN/165/2012 (Ver 3.0)						
71	012840	3.00	Set	9200.00	27600.00	18.00	32568.00
	Description:- Supply and Installation of Lightening & Surge protection device, Single phase + neutral (housed in a suitable impact resistance box) for providing C class protection as per RDSO spec No. RDSO/SPN/165/2012 (Ver 3.0)						
72	012850	15.00	Set	15671.00	235065.00	18.00	277376.70
	Description:- Maintenance Free Earth as per RDSO/SPN/197/2008 or latest consisting of : 1) Copper bond steel electrode 3 Mtr long 17mm dia with copper bonding thickness of min. 250micron & UL listed & marked-01 No. (2) Earth enhancement compound RDSO Approved in sealed bag of 10 kgs - 03 No. (3) Copper strip 150 x 25 x 6mm - 02 No (4) Copper Strip 300 x 25 x 6mm- 01 No (5) 35 Sqmm Copper Cable to connect earth electrode to MEEB - 15Mtr Approx.						
73	012860	50.00	Metre	365.00	18250.00	18.00	21535.00
	Description:- Supply of 35 Sq. mm. multistrand single core PVC insulated copper for connecting earth bus bar to earth electrode.						
74	012870	50.00	Metre	711.00	35550.00	18.00	41949.00
	Description:- Supply of copper Tape 25x6 mm (Bonding ring conductor) mounted on insulated standoff (1 round).						
75	012880	8.00	Numbers	1181.00	9448.00	18.00	11148.64
	Description:- Supply of 300x25x6 mm Cu equipotential Bus Bar.						
76	012890	1.00	Numbers	118645.00	118645.00	18.00	140001.10
	Description:- Supply of Microprocessor based universal earth resistance sensing unit 12 channel AC/DC. As per RDSO/SPN/256/2002 with latest amendments.						
77	012900	30.00	Numbers	878.00	26340.00	18.00	31081.20
	Description:- Supply of Track Lead junction Boxes as per C.Rly Drg.No.RST 11509 made from fiber glass alongwith terminal blocks.						
78	012910	20.00	Numbers	3099.00	61980.00	18.00	73136.40
	Description:- Supply of B type choke to specn.No.IRS.S.65/83 (Amd.3) with latest amendments.						
79	012920	20.00	Numbers	1089.00	21780.00	18.00	25700.40
	Description:- Supply of adjustable Track Feed Resistance disc type 7.5/15/30 ohms as per RDSO Drg. No. SA 20161-66/M (Adv) with latest amendments (with phenolic moulded base).						
80	012930	10.00	Numbers	2001.00	20010.00	18.00	23611.80
	Description:- Supply of Track feed battery chargers, 110V AC input 2, 4 to 6 V DC Output to Specn. No.IRS.89/2013 Ver.1.0 with latest amendments. Charger shall be suitable for charging 80 AH battery.						
81	012940	500.00	Numbers	2.00	1000.00	18.00	1180.00
	Description:- Supply of Channel Pins single groove, galvanised, 7 mm suitable for 4mm dia bonding wire as per spec No. IRS: S 17-75 Revision 3.						
	012950	4000.00	Metre	46.00	184000.00	18.00	217120.00

**MUMBAI-CST-DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-BB-SNT-EAST-2026-26

Closing Date/Time: 22/06/2026 15:00

82	Description:- Supply of PVC jacketed wire rope for Track lead connections. PVC jacketed wire rope should be of Galvanised steel wire rope 6mm dia (6x19 stranded wire with steel core of 6 mm dia) sheathed with PVC 2mm wall thickness, overall thickness being 10 mm. PVC sheath should be made of type 6 compound as per IS 5831 of 1984 Reaffirmed 2001 and steel wire rope as per IS: 2266:2019. Reclaimed for recycled material should not be used.						
83	012960	100.00	Kg	75.00	7500.00	18.00	8850.00
	Description:- Supply of 8 SWG GI wire (4mm dia) suitable for track circuit rail bonding. As per IRS Specification S:13-62						
84	013130	50.00	Numbers	2387.00	119350.00	18.00	140833.00
	Description:- SUPPLY of Electronic timers for DAC reset arrangement 3 sec to 30 sec with 2NO/2NC contact working voltage 24V/60V DC. Siemens/ABB/L&T or SELEC(642X A programmable electronic timer switch) make.						
85	013140	2.00	Set	12606.00	25212.00	18.00	29750.16
	Description:- Supply of Multi strand twin twisted core shielded cable of 28 - 30/0.2 mm for Axle counter as per IRS spec. 76/89 with Amendment No.03 or latest amendments, if any. Unit(1 Set= Per 100 meters)						
86	013150	2.00	Numbers	8891.00	17782.00	18.00	20982.76
	Description:- Supply of Pre-wired Crank Handle cum key lock relay box (of metal) alongwith LEDs, with approved type push buttons, 8-way terminal strips, string rod, etc. as per Drawing No.RST.C.114						
87	013160	50.00	Set	452.00	22600.00	18.00	26668.00
	Description:- Supply of William stretcher nylon insulation set suitable for ground connection as per RDSO drg No T-10367, T-10368, T-10384 as applicable and to the spec IRS S 23/88 with Amendment No.01 & 40/84 with Amendment No.01 or latest amendments.						
88	013170	100.00	Set	287.00	28700.00	18.00	33866.00
	Description:- Supply of Tongue attachment nylon insulation set consisting of one insulating plate as per Drg no: RST-106961 & 3 nos of Ferrules with collars to suite rodding supplied as per RDSO spec & Drg.no: RST-10692						
89	013180	50.00	Set	207.00	10350.00	18.00	12213.00
	Description:- Supply of Gauge Tie Plate nylon insulation as per RDSO drg No: T-10372 Alt2, T-10368, T-10371 Alt2, T-15083/88/Alt2 & T-11690/Alt2 and to the spec IRS S 23/88 with Amendment No.01 & 40/84 with Amendment No.01 or latest amendments.						
90	013190	4.00	Set	7018.00	28072.00	18.00	33124.96
	Description:- Supply of Ground connections, complete set suitable for IRS type/appd. Point Machine for ordinary turnout with tongue attachment insulation and other insulation as per RDSO Drg.S/3361 /62 / 63 (for IRS type point machine) or RDSO Drg No.SA-9151/52 (for Siemens point machine) with latest amendments. However the ground connection shall be procured only after confirmation from Railway engineer as per site condition /type of machine/turnout.						
91	013200	1.00	Set	5707.00	5707.00	18.00	6734.26
	Description:- Supply of Ground connections, complete set suitable for IRS type/appd. Point Machine for derail switch with tongue attachment insulation as per RDSO Drg.S/3361 / 62 / 63 (for IRS type point machine) or RDSO Drg No.SA-9151/52 with latest amendments. However the ground connection shall be procured only after confirmation from Railway engineer as per site condition /type of machine/turnout.						
92	013210	10.00	Numbers	211.00	2110.00	18.00	2489.80
	Description:- Supply of GI bend pipe, B class, 50mm dia for cable entry in point machine alongwith required fixing arrangements as per standard practice on Central Railway. As per Drg No. RST.11835.						
93	013220	10.00	Numbers	761.00	7610.00	18.00	8979.80
	Description:- Supply of Point Machine Raised Bracket FRP make with cover as per drg no. SK-846.						
94	013230	300.00	Metre	908.00	272400.00	18.00	321432.00
	Description:- Supply of GI pipe, inner dia. 100mm dia. B-class as per spec. No.IS 1239 PT. 1/2004 or latest with sockets and fittings. TATA/JINDAL/ZENITH BIRLA make.						
95	013240	300.00	Metre	288.00	86400.00	18.00	101952.00
	Description:- Supply of DWC HDPE pipe with one snap fit coupler and 'O' ring fire resistant, anti rodent, in 6 meter length of size 120 mm outer dia as per RDSO/SPN/204/2011 Ver 1.1 with Amd.1 or latest.						
96	013250	500.00	Metre	640.00	320000.00	18.00	377600.00
	Description:- Supply of RCC Trunking with capping. Size 250mm x 200mm Drg.No.RST/C/291/A						
97	013260	500.00	Metre	698.00	349000.00	18.00	411820.00
	Description:- Supply of RCC Trunking with capping. Size 150mm x 150mm Drg.No.RST/C/291/A						
	013310	500.00	Numbers	100.00	50000.00	18.00	59000.00

**MUMBAI-CST-DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-BB-SNT-EAST-2026-26

Closing Date/Time: 22/06/2026 15:00

98	Description:- Supply of modular terminal block of 2.5 sq. mm 2 IN 2 OUT type disconnect type terminal along with as per RDSO SPN/189/2004 Rev 3.0. The current capacity of 16 Amps and more. The terminal should have marking at centre to view description from front. Material to be procured from RDSO approved firms only.							
99	013320	6.00	Numbers	187.00	1122.00	18.00	1323.96	
	Description:- Supply of DIN Channel for the terminals 1 Mtrs each							
100	013330	48.00	Numbers	20.00	960.00	18.00	1132.80	
	Description:- Supply of End plates for modular terminal block							
101	013340	48.00	Numbers	15.00	720.00	18.00	849.60	
	Description:- Supply of End Clamp for modular terminal block							
102	013350	3.00	Numbers	71.00	213.00	18.00	251.34	
	Description:- Supply of Marker Card as per customer spec (10x10)							
103	013360	50.00	Numbers	157.00	7850.00	18.00	9263.00	
	Description:- Fuse terminals block with LED indication up to 2.5 sqmm screw type one in one out (suitable for (400 mA, 630mA, 1 A, 1.6 A, 2 A, 4A, 6.3 A & 10 A) as per RDSO SPN/189/2004 Ver.03 or latest . (without fuse)							
104	013370	3.00	Numbers	12.00	36.00	18.00	42.48	
	Description:- End plate for through terminal block with LED indication.							
105	013380	200.00	Numbers	37.00	7400.00	18.00	8732.00	
	Description:- Fuse links of (400 mA, 630mA, 1 A, 1.6 A, 2 A, 4A, 6.3 A & 10A)							
106	013390	50.00	Numbers	13.00	650.00	18.00	767.00	
	Description:- Shorting link insulated Grey in colour							
107	013400	1.00	Numbers	7266.00	7266.00	18.00	8573.88	
	Description:- Operating tool (operating tool, screw driver & stripper) as per Annexure-VII.							
108	011580	4.00	Set	24091.00	96364.00	18.00	113709.52	
	Description:- Supply of Automatic changeover for individual supply. Automatic changeover unit of signal / Track / DC circuit supply of 32A, AC/DC consisting of 3TC44 contractors, LED Lamp, Push button, terminals, VSR, polarity switches. As per Rly. Drg.-SK-841/1-5 for IPS supply to manual discrete equipments with P/switch.							
109	011600	4.00	Set	41418.00	165672.00	18.00	195492.96	
	Description:- Supply of Automatic changeover for individual supply. Automatic changeover unit of signal / Track supply of 70A, consisting of 3TC47 contractors, LED Lamp, Push button, terminals, VSR, polarity switches. As per Rly. Drg.-SK-841/1-5 for IPS supply to manual discrete equipments with P/switch.							
110	012570	3.00	Numbers	26638.00	79914.00	18.00	94298.52	
	Description:- Supply of "3 aspect" Signal Unit in FRP body without lenses and transformers as per RDSO Specification RDSO/SPN/194/2006/Rev.2.0 or latest complete and to suit LED signal Lamps and suitable for 140 mm dia post saves pigment finish on the back side of the and inside. white pigment finish inside the 4 aspect unit to avoid any extra paint cost							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () B-SOR ITEM							6300240.66	Above/ Below/P ar
01	011040	1.00	Numbers	1258.00	1258.00	18.00	1484.44	
	Description:- Installation of Relay Rack Assembly including IDF pillars if any complete with wall supports, scaffolding, ladders, runway for cables, Relay/Relay group base plates, fixing of Tag blocks etc. The work shall be done as per approved plan, extant practice on C.Railways & the instructions of Rly engineer at site.							
02	011050	1.00	Numbers	1024.00	1024.00	18.00	1208.32	
	Description:- Installation of Cable Termination Rack Assembly complete including wall supports, scaffolding, Disconnecting links/ARA terminal, 96 way tag block with tag block cover & other necessary accessories etc. The work shall be done as per approved plan, extant practice on C.Railways & the instructions of Rly engineer at site.							
03	011060	1024.00	Numbers	9.00	9216.00	18.00	10874.88	
	Description:- Termination of cable cores on ARA terminal/disconnecting links in the cable termination rack. This includes all associated works of pulling out the cable from under ground, peeling off insulation, dressing of Cable core supported on sting rods with contractors own material. The work shall be done as per instructions of Rly engineer at site.							
	011070	1.00	Set	15627.00	15627.00	18.00	18439.86	

**MUMBAI-CST-DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-BB-SNT-EAST-2026-26

Closing Date/Time: 22/06/2026 15:00

04	Description:- Installation, wiring, testing and commissioning of Data logger complete along with accessories with contractors own wiring & fixing material as per following configuration. (It includes loading of NETWORKING software and networking of data logger. The requisite communication cable/channel for networking will be arranged by Railway. i) 1024 digital & 32 analog inputs						
05	011120	3.00	Lot	20768.00	62304.00	18.00	73518.72
	Description:- Installation of LT Power panel/power distribution panel/Auto Changeover Panel, power supply equipments such as Rectifiers Transformers, Battery chargers etc., mounting of program switches on bakelite sheet of size 300 mm x 300 mm x 8 mm fitted to MS angle (size 25mm x 25mm x 5mm) brackets, wiring as per requirements. Necessary wires to be supplied by Rlys, lugs & glands to be supplied by contractor.						
06	011130	20.00	Set	518.00	10360.00	18.00	12224.80
	Description:- Fixing of Q series relay base plate/metal to metal relay mini group and major group base plate, laying, bunching, lacing, dressing & packeting of 60/40 core PVC indoor cable/flexible wire and termination 60/40 core cable/flexible wire on tagblock/base plate & base plates & soldering. This includes fuse wiring, bus bar looping etc. required for keeping installation ready for circuit wiring work & panel throughing work. The work shall be done as per approved plan, extant practice on C.Rly & the instruction of Rly. Engineer at site. Unit(Per Tag Block=1 set)						
07	011140	1000.00	Set	11.00	11000.00	18.00	12980.00
	Description:- Circuit wiring/jumpering as per circuit diagrams in the relay racks/IDF rack tagblocks. This includes preparation of jumper sheets by wire man duly checked by firm's site supervisor & wire to wire testing as per circuit diagram. Any wrong jumper done by wireman will not be paid & correction shall be done free of cost. Jumper wires will be issued by Railways. Good quality solder resin core to be supplied by contractor for soldering of jumper wires. Soldering of jumper wires to be done after completion of testing by Railways. Unit(Per Jumper =1 set)						
08	011150	100.00	Per Route	315.00	31500.00	18.00	37170.00
	Description:- Plugging of relays, provision for temporary relays for NI working if any, laying of temporary cables for mock panel and wiring of Mock panel. Panel through testing of PI/RRi as per selection table, control table etc. This also includes alteration if any in panel wiring, laying & termination of indoor cables from panel to IDF/CT rack of relay room. Contractor shall depute supervisor & wiremen technically qualified to carryout panel through testing as per approved design. Technical knowledge of contractor's staff will be judged by Railways Engineer incharge before permitting them to do the testing.						
09	011160	25.00	Set	281.00	7025.00	18.00	8289.50
	Description:- Relay Contact break test of indoor relay wiring. Contractor shall depute Engineer, Supervisor & wiremen technically qualified to carryout contact break testing as per approved circuit diagrams. Firm Engineer to sign circuit diagrams for break testing after carrying out the test in presence of Railway's site supervisor/Engineer. Unit(Per A3 Size circuit per Sheet=1 set)						
10	011170	50.00	Per Route	295.00	14750.00	18.00	17405.00
	Description:- Functional testing of PI/RRi/IBS/Autosignal etc. as per Selection table, control table, square sheet etc. Contractor shall depute one Engineer, one supervisor & wiremen technically qualified to carryout functional testing as per approved design. Technical knowledge of contractor's staff will be judged by Railways Engineer incharge before permitting them to do the testing.						
11	011230	2.00	Numbers	2803.00	5606.00	18.00	6615.08
	Description:- Supply and installation of 20 pair CT box						
12	011250	1.00	Lot	13764.00	13764.00	18.00	16241.52
	Description:- Installation, wiring & Testing of Control cum Indication panel, & test board etc as applicable / as per instructions of Engineer-in-charge. This includes laying & termination of cable, if any from panel Room to Relay Room as per instruction of site incharge.						
13	011290	2.00	Rack	290.00	580.00	18.00	684.40
	Description:- Lettering & Numbering of detail and description writing of particulars of terminations & equipments on relay rack, relays, cable termination rack, battery & power equipment, IPS, operating panel, axle counter etc constituting entire system with contractor's own paint and writing material ("Asian/Dulux" make enamel paints to be used). The work shall be done as per extant practice on C.Rly & instruction of Rly engineer at site.						
14	011310	1.00	Lot	19613.00	19613.00	18.00	23143.34
	Description:- Preparation of cable route plan, cable coreage plan, location particulars, cable termination rack particulars, cable meggering report, earth resistance particulars, Traction bonding diagram, 1/2 wire count sheet and any other drawing in Autocad in A3/A4 size. The contractor shall initially supply 3 sets of circuits complete for approval of Railways. Railways will return one set to the contractor duly approved with alteration/corrections if any. The contractor shall incorporate Railways alterations/corrections in the tracings without any deviation and submit all tracings complete in all respects to the Railways. This includes submission of final cable route plan as per laid cable duly measured at every 30m clearly indicating distance of laid cable from fixed point of reference & indicating all track crossings and tail cables. This also include designing of cable coreage plan based upon I.P. in consultation with engineer-in-charge.(ii) For small/medium yards (<=100 routes)						

**MUMBAI-CST-DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-BB-SNT-EAST-2026-26

Closing Date/Time: 22/06/2026 15:00

15	011330	1.00	Lot	114292.00	114292.00	18.00	134864.56	
	Description:- Design and supply of Detailed signalling circuits including Panel diagram (if required), Route section plan, Selection table, Fuse & negative tag. analysis, Contact analysis, Relay rack arrangement and wire count sheets etc. in A3 size. Completion circuit shall be plotted in AutoCAD. The contractor shall initially supply 2 sets of circuits duly signed by the circuit designer having substantial experience on design side for making such circuits, complete for approval of Railways. Railways will return one set of circuit to the contractor duly approved with alterations / corrections, if any. The contractor shall incorporate Railway's alterations/corrections in the original tracings & CD without any deviation and submit two copies of the modified circuits. Original tracings so modified & final CD complete in all respects along with 6 sets of final approved circuits (out of which one set shall be supplied in transparent bags. Only two sheets of circuits shall be placed in one bag each) shall be submitted to the Railways in case there are no further alteration suggested by Railways. This also includes modification in yard. ii) for stations having Routes <=50							
16	012690	1.00	Lot	6550.00	6550.00	18.00	7729.00	
	Description:- Preparation of final ammonia prints of diagrams in A-3 size after tracings are approved by Railways, in four sets for final submission with one set of diagrams in transparent polythene bag/lamination. (only two sheets shall be placed on one polythene bag/laminated each). Every set shall be set in a plastic folder of A3 size and of good quality. The final approved tracings will be handed over to contractor by railway for this purpose and contractor will return back the same after taking out the prints for stations having less than 20 routes.(ii)for stations having Routes <=50							
17	011370	8.00	Numbers	7537.00	60296.00	18.00	71149.28	
	Description:- Excavation and Casting of main signal foundation as per Drg No SK 801 with contractor's own materials including cement and anchor bolts of standard size. The required scaffolding Ferma etc for casting of foundation will have to be brought by the contractor at his own cost.							
18	011420	8.00	Numbers	435.00	3480.00	18.00	4106.40	
	Description:- Fixing of stop Board, Block section limit Board, goods warning board with contractors own material. The work shall be done as per instruction of Rly engineer at site.							
19	011490	20.00	Numbers	1942.00	38840.00	18.00	45831.20	
	Description:- Fabrication and fixing of phenolic laminated/Fibre glass sheet in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated/with PVC pipe covered string rods at the back side for cable support with contractor's own materials. The work shall be done as per drg and arrangement similar to SK 783- 1& 2. with latest alterations & as per instructions of Rly engineer at site. a) Single Case							
20	011500	20.00	Numbers	1647.00	32940.00	18.00	38869.20	
	Description:- Fabrication and fixing of phenolic laminated/Fibre glass sheet in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated/with PVC pipe covered string rods at the back side for cable support with contractor's own materials. The work shall be done as per drg and arrangement similar to SK 783- 1& 2. with latest alterations & as per instructions of Rly engineer at site. b)Half Case							
21	011510	4.00	Numbers	462.00	1848.00	18.00	2180.64	
	Description:- Fixing of cutting in relay bases & wiring of relays with Contractors own material obtained from approved sources in location box as per the instructions of Engineer in charge.							
22	011520	500.00	Per Conductor	12.00	6000.00	18.00	7080.00	
	Description:- Fixing of ARA Terminals and fuse blocks on phenolic laminated sheets and fixing by stainless steel/brass nuts & bolts. This includes provision of two additional holes on the board on either side for cable conductor entry.							
23	011530	1000.00	Per Conductor	9.00	9000.00	18.00	10620.00	
	Description:- Termination of cable cores on ARA terminal/fuse blocks in the apparatus cases/ cable termination rack. This includes all associated works of pulling out the cable from underground. The work shall be done as per location plans and instructions of Rly engineer at site.							
24	011540	20.00	Numbers	8500.00	170000.00	18.00	200600.00	
	Description:- Excavation and Casting of Apparatus case foundation with contractors Anchor bolts, cement, ballast and other materials. The required scaffolding ferma etc for Casting of foundation will have to be brought by the contractor at his own cost. i) Single Case as per Drg No SK-803							
25	011550	20.00	Numbers	8024.00	160480.00	18.00	189366.40	
	Description:- Excavation and Casting of Apparatus case foundation with contractors Anchor bolts, cement, ballast and other materials. The required scaffolding ferma etc for Casting of foundation will have to be brought by the contractor at his own cost. ii)Half Case as per Drg No SK-804							
26	011560	20.00	Numbers	945.00	18900.00	18.00	22302.00	
	Description:- Erection of Apparatus cases. This includes filling of location foundations and plastering .i)Single Case							

**MUMBAI-CST-DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-BB-SNT-EAST-2026-26

Closing Date/Time: 22/06/2026 15:00

27	011570	20.00	Numbers	703.00	14060.00	18.00	16590.80	
	Description:- Erection of Apparatus cases. This includes filling of location foundations and plastering. ii)Half Case							
28	011580	20.00	Numbers	1266.00	25320.00	18.00	29877.60	
	Description:- Installation of Eqpt. (Relays, resistance, chargers batteries etc. as applicable) & wiring of the same in apparatus cases as per location diagrams & circuit diagrams, as per Instruction of site incharge and practice. i) Single Case							
29	011590	20.00	Numbers	830.00	16600.00	18.00	19588.00	
	Description:- Installation of Eqpt. (Relays, resistance, chargers batteries etc. as applicable) & wiring of the same in apparatus cases as per location diagrams & circuit diagrams, as per Instruction of site incharge and practice. ii)Half Case							
30	011600	30.00	Numbers	2088.00	62640.00	18.00	73915.20	
	Description:- Installation of earth electrode assembly as per Drg.No.RE/S&T/SIG/Tender/SK726/85 including earth wire connected through GI wire 8 SWG supported on M.S. flat of size 6mm x 40 mm to earth electrode as per drg. No.CR/S&T/SK-815 for sigg. Equipment such as lever frames, apparatus case, signals, relay racks, block instruments, and etc. as per RE manual. The earth value should be less than 10 Ohms including the lead wire. The value should be measured in presence of Rly. supervisor. It should be documented and painted on earth enclosure made of concrete.(only earth electrode will be supplied by Railway). All other material required for provision of earthing will be brought by the contractor.							
31	011640	15.00	Set	4382.00	65730.00	18.00	77561.40	
	Description:- Installation of unit earth as per RDSO/SPN/197/ver I or latest, to construct earthing of </=1 Ohm consisting of a digging the earth to required depth, insertion of electrode, filling of earth enhancing compound & construction of chamber, measurement of earth value and all other work of earthing as per code of practice. All the consumables for mounting the copper tape inside the relay room, Exothermic weld materials and tools & fixtures for the welding copper tapes nd Electrodes etc shall be arranged by the contractor.							
32	011650	50.00	Metre	79.00	3950.00	18.00	4661.00	
	Description:- Connecting main earth electrode to BRC using 35 sqmm copper cable.							
33	011660	50.00	Metre	174.00	8700.00	18.00	10266.00	
	Description:- Installation of 25x6 mm copper tape (bonding ring conductors) mounted on insulated standoffs (1 round).							
34	011670	8.00	Numbers	364.00	2912.00	18.00	3436.16	
	Description:- Installation of 300x25x6 mm Cu equipotential Bus Bar.							
35	011680	1.00	Numbers	5783.00	5783.00	18.00	6823.94	
	Description:- Installation, wiring, testing and commissioning of Microprocessor based universal earth leakage detector unit 12 channel AC/DC.							
36	011690	30.00	Numbers	1012.00	30360.00	18.00	35824.80	
	Description:- Erection, Fitting and Rail connection of Track Lead juntion Box on two supports (M.S.angle) with contractor's fixing material and PVC jacketed wire for track lead connection including angles of size 40x40x5mm 1200mm length. This will include drilling of holes for track lead/side connections of rail. The work shall be carried out as per Drg. No.SK-845 or / & instructions of Rly engineer at site.							
37	011700	50.00	Numbers	134.00	6700.00	18.00	7906.00	
	Description:- Provision of bounding with contractor's PVC jacketed wire rope for Track Lead connections. PVC jacketed wire rope should be of Galvanised steel wire rope 6 mm dia (6x19 stranded wire with steel core of 6mm dia) sheathed with PVC 2mm wall thickness, overall thickness being 10 mm. PVC sheath should be made of type 6 compound as per IS 5831 of 1984 Reaffirmed 2001 and steel wire rope as Per IS:2266:2019. Reclaimed or recycled material should not be used. This will include drilling of 7.1mm dia holes in rails (4 Nos) and provison of two jumpers for each bond, clipping of bonds etc. with contractors own materials and tools as per instruction of Rly engineer at site.							
38	011710	50.00	Numbers	122.00	6100.00	18.00	7198.00	
	Description:- Provision of bounding with GI wire 4mm dia (8 SWG) for track jumper & fish plate joints bonds. This will include drilling of 7.1mm dia holes in rails (4 Nos) and provision of two jumpers for each bond, clipping of bonds etc. with contractors own tools as per instruction of Rly engineer at site.							
39	011800	4.00	Set	19374.00	77496.00	18.00	91445.28	

**MUMBAI-CST-DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-BB-SNT-EAST-2026-26

Closing Date/Time: 22/06/2026 15:00

	Description:- Installation of Axle counter (Digital)/Central Evaluator,wiring from CT rack to central evaluator, installation and wiring of indoor & outdoor reset box and wiring the power supply including supply of 2 core shielded cable of required size copper conductor as per IRS S 76/89 or IS694/1977 as applicable with other accessories. NOTE: Installation/programming/configuration/commissioning of Axle counter equipment to be carried out in accordance with latest guidelines issued by Railway/RDSO preferably by Authorised representative of OEM.						
40	011810	10.00	Set	10841.00	108410.00	18.00	127923.80
	Description:- Installation of EJB and Track devices of Digital Axle counter including digging of trench, drilling of holes, if required on rail, laying of Doubled walled antirodent corrugated pipe, Medium class from track device to location box and making its terminations. (DWC pipe made up of High density polyethylene of 60mm outer dia of suitable length and all other accessories as per site requirement to be supplied by firm.) NOTE: Installation/programming/configuration/commissioning of Axle counter equipment to be carried out in accordance with latest guidelines issued by Railway/RDSO preferably by Authorised representative of OEM.						
41	011820	10.00	Set	9250.00	92500.00	18.00	109150.00
	Description:- Fixing of track devices (Transmitter coil and receiver coil) to the rails, fixing of EJB in the location connection of track device to EJB using DWC pipe of suitable length and wiring of EJB, testing and adjustment of transmitter and receiver to obtained required channel level as per standard practices on C.rly and instruction of Rly Engineer on site.						
42	011830	10.00	Per Detection Point (DP)	2269.00	22690.00	18.00	26774.20
	Description:- Installation, wiring & /commissioning of Multi section Digital Axle counters's central unit/Evaluator/Processor for the section/at station including its associated all indoor equipments, Indication panel, monitoring console/interface computer and wiring the same to integrate with the relay circuits including supply required power cable of multistrand 10 sq.mm or more from power room to central evaluator, 2 core shielded cable of required size copper conductor as per as per IRS (S)76/89(Amd.3). or IS 694/2010. with latest amendment as applicable with other accessories as per the instruction of Rly engineer at site and earthing as per OEM's technical requirement and specifications. This also includes laying & termination of cable, if any from panel Room to Axle counter room/Relay room in DWC pipe with contractor's material/existing ladder.						
43	011840	1.00	Station	5895.00	5895.00	18.00	6956.10
	Description:- Installation, wiring & Testing / commissioning of Axle counters Reset Box of all types in Cabin/Panel Room and wiring the same to integrate with the axle counter as per instructions of Railway Engineer at site. This includes laying & termination of cable, if any from Panel Room/Axle counter room/ Relay Room to Reset Box in DWC pipe/existing ladder.						
44	011870	20.00	Per Detection Point (DP)	731.00	14620.00	18.00	17251.60
	Description:- Installation of complete assembly of deflectors on either side of Track Device/Double Rail Contact Unit including drilling of required sizes holes on rails for fixing these.						
45	011880	1.00	Station	36538.00	36538.00	18.00	43114.84
	Description:- Supply, fixing & Wiring of mismatch panel depicting Indication panel/VDU layout with contractors own material like LEDs for each track section, flexible wire, connecting terminals, buzzer etc. The work shall be done as per extant practice on C.Rly & the instruction of Rly engineer at site.						
46	011910	5.00	Set	2709.00	13545.00	18.00	15983.10
	Description:- Fixing of point machine on newly laid turnout on Wooden/MBC sleepers, fixing of ground connections, adjustment and testing with crank handle operations, Removal of ground connection & point machines duly numbered. This will include fixing of bend pipes with welded frame for cable entry to machine. This will also includes necessary adjustment and smithy work, drilling of holes to tounge rails, fitting of insulation for tounge attachment, gauge plate & stretcher bars, cable termination & wiring if required. The work shall be done as per extant practice on C.Rly & the instruction of Rly engineer at site. Unit(PER T/O=1 set)						
47	011920	2.00	Numbers	2451.00	4902.00	18.00	5784.36
	Description:- Installation, fixing and wiring of Boxes for key Lock Relays with contractor's wiring & fixing material. The work shall be done as per extant practice on C.Rly & the instruction of site engineer.						
48	011930	5000.00	cum	291.00	1455000.00	18.00	1716900.00

**MUMBAI-CST-DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-BB-SNT-EAST-2026-26

Closing Date/Time: 22/06/2026 15:00

	Description:- Excavation of cable trench as per cable route plan, 1.0 mt. deep and 300mm wide along side the track in normal soil/strata, conforming to distances as per cable route plan and refilling after cable laying. This work includes covering of cable laid to trench by loose soil for a layer of 50mm thickness after clearing of route, bushes etc. It shall be ensured that top of the cables laid is at a depth of 0.8 m or more. If it is less, then the width and depth shall be suitably increased and accordingly proportionate payment shall be made. In case depth of trench is not achievable due to site conditions, proportionate payment will be made as per procedure. The work shall be done as per extant practice on C.Rly & the instruction of Railway engineer at site. Drg No SK 805						
49	011940	500.00	cum	491.00	245500.00	18.00	289690.00
	Description:- Excavation of cable trench as per cable route plan, 1.0 mt. deep and 300mm wide along side the track in hard soil, conforming to distances as per cable route plan and refilling after cable laying. This work includes covering of cable laid to trench by loose soil for a layer of 50mm thickness after clearing of route, bushes etc. It shall be ensured that top of the cables laid is at a depth of 0.8 m or more. If it is less, then the width and depth shall be suitably increased and accordingly proportionate payment shall be made. In case depth of trench is not achievable due to site conditions, proportionate payment will be made as per procedure. The work shall be done as per extant practice on C.Rly & the instruction of Railway engineer at site. Drg No SK 805						
50	011950	500.00	cum	2438.00	1219000.00	18.00	1438420.00
	Description:- Cutting of all types of Roads/platforms (except concrete type) for trenching and excavation to depth of 300mmx300mm wide approx. and refilling after laying of RCC/GI/DWC pipe & to restore them to original condition. The work shall be done as per extant practice on C.Rly & the instruction of Railway engineer at site. Drg No SK 807						
51	011960	200.00	Metre	60.00	12000.00	18.00	14160.00
	Description:- Fixing of GI pipes for crossing the culverts, bridges etc. and concreting of ends with brick masonry at both ends as per the instruction of Rly engineer at site.						
52	011970	200.00	cum	504.00	100800.00	18.00	118944.00
	Description:- Digging of trench 1.0 M deep from rail flange/road level (for LC) and, 0.3 Mtr to 0.6 Mtrs wide and back filling after placing of DWC/RCC/GI pipe. (Placing of DWC/RCC/GI pipe covered separately). The ballast disturbed be screened and dressed as required by Engineer-in-charge or his representatives and road tarred immediately. Drg No SK 806						
53	011980	500.00	Metre	49.00	24500.00	18.00	28910.00
	Description:- Laying of DWC/RCC pipes alongwith collars / RCC Half round pipes in trenches at places of track and road crossings, platform cutting etc.						
54	011990	48.00	Kilometre	4542.00	218016.00	18.00	257258.88
	Description:- Laying of signalling/Power/Telecom cable of various cores/sizes in trenches.						
55	012010	1000.00	Numbers	56.00	56000.00	18.00	66080.00
	Description:- Laying of RCC Trunking and capping and sealing after cable laying as per std practice on C.Rly & the instruction of site engineer.						
56	012030	5.00	Numbers	3005.00	15025.00	18.00	17729.50
	Description:- Jointing of 4 / 6 quad cable with Heat shrinkable straight through jointing kit for 4/6 quad cable.						
57	012050	100.00	cum	4419.00	441900.00	18.00	521442.00
	Description:- "Where ever depth of 0.5 m cable trench is not feasible, cable shall be protected as under:- Preparation of cement mixture 1:3:6 with contractor's own materials and spreading cement concrete mixture layer of 100 mm thick over the already laid cables in the excavated trench."						
58	012060	550.00	Numbers	16.00	8800.00	18.00	10384.00
	Description:- Fixing of modular terminal/fuse blocks alongwith all accessories with provision of fixing holes on hylam sheets/side angles of Loc Box and fixing by galvanised nuts & bolts. This includes fixing on DIN channel alongwith PVC Comb type 'C' channel (size 2 inch x 2 inch) for cable termination of modular terminal. The PVC channel with cover to be supplied by firm as required. The work shall be done as per the instruction of Rly engineer at site.						
59	012070	1100.00	Numbers	6.00	6600.00	18.00	7788.00
	Description:- Termination of cable cores on ARA terminal/Disconnecting link/fuse blocks, in the apparatus Cases/ cable termination rack. This includes all associated works of pulling out the cable from underground. The work shall be done as per location plans and instructions of Rly engineer at site.						
60	012350	1.00	Set	5109.00	5109.00	18.00	6028.62
	Description:- Painting two coats of enamel paint over one coat of Red Oxide primer on the following items after scrapping and cleaning of the surface wherever necessary. Primer and paints both of any reputed make are to be supplied by Contractor. The work shall be done as per instructions of Rly engineer at site and extant practice on C Rly on location boxes, signal posts, TLJB. This includes lettering / Numbering Termination of signals, TLJB & Block joints if any, apparatus cases, gate booms, etc, Description writing, legibly and neatly inside location boxes, relay hut, gate lodge etc. - for LC Gate. Unit(Per LOT/GATE=1 SET)						

**MUMBAI-CST-DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-BB-SNT-EAST-2026-26

Closing Date/Time: 22/06/2026 15:00

61	012360	30.00	Numbers	360.00	10800.00	18.00	12744.00	
	Description:- Painting two coats of synthetic enamel paint over one coat of primer on the following after scrapping and cleaning of the surface wherever necessary with contractor own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy will be supplied by Railways. NOTE:- The paint and primer should be from M/s Asian paints Co. Ltd.,. The paints will be primer (IS 5660 of 1970) the Aluminium synthetic black enamel (IS 2932 of 1974) brilliant white and yellow Painting two coats of enamel paint over one coat of primer.(i)Apparatus Cases Full size.							
62	012370	20.00	Numbers	265.00	5300.00	18.00	6254.00	
	Description:- Painting two coats of synthetic enamel paint over one coat of primer on the following after scrapping and cleaning of the surface wherever necessary with contractor own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy will be supplied by Railways. NOTE:- The paint and primer should be from M/s Asian paints Co. Ltd.,. The paints will be primer (IS 5660 of 1970) the Aluminium synthetic black enamel (IS 2932 of 1974) brilliant white and yellow Painting two coats of enamel paint over one coat of primer.(ii)Apparatus Cases Half size.							
63	012380	10.00	Numbers	594.00	5940.00	18.00	7009.20	
	Description:- Painting two coats of synthetic enamel paint over one coat of primer on the following after scrapping and cleaning of the surface wherever necessary with contractor own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy will be supplied by Railways. NOTE:- The paint and primer should be from M/s Asian paints Co. Ltd.,. The paints will be primer (IS 5660 of 1970) the Aluminium synthetic black enamel (IS 2932 of 1974) brilliant white and yellow Painting two coats of enamel paint over one coat of primer.(iii)Main signal post with signal Units, Surface base and complete fittings as per Centre Railways standard practice.							
64	012390	8.00	Numbers	141.00	1128.00	18.00	1331.04	
	Description:- Painting two coats of synthetic enamel paint over one coat of primer on the following after scrapping and cleaning of the surface wherever necessary with contractor own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy will be supplied by Railways. NOTE:- The paint and primer should be from M/s Asian paints Co. Ltd.,. The paints will be primer (IS 5660 of 1970) the Aluminium synthetic black enamel (IS 2932 of 1974) brilliant white and yellow Painting two coats of enamel paint over one coat of primer.(iv)Shunt signal post with signal unit, surface base as per central Railway's Standard Practice.							
65	012400	40.00	Numbers	69.00	2760.00	18.00	3256.80	
	Description:- Painting two coats of synthetic enamel paint over one coat of primer on the following after scrapping and cleaning of the surface wherever necessary with contractor own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy will be supplied by Railways. NOTE:- The paint and primer should be from M/s Asian paints Co. Ltd.,. The paints will be primer (IS 5660 of 1970) the Aluminium synthetic black enamel (IS 2932 of 1974) brilliant white and yellow Painting two coats of enamel paint over one coat of primer.(v)Track lead Junction Box. (Black enamel outside only)							
66	012410	12.00	Numbers	122.00	1464.00	18.00	1727.52	
	Description:- Painting two coats of synthetic enamel paint over one coat of primer on the following after scrapping and cleaning of the surface wherever necessary with contractor own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy will be supplied by Railways. NOTE:- The paint and primer should be from M/s Asian paints Co. Ltd.,. The paints will be primer (IS 5660 of 1970) the Aluminium synthetic black enamel (IS 2932 of 1974) brilliant white and yellow Painting two coats of enamel paint over one coat of primer.(vi)Point Machine with ground connections complete (Point Machine with Black enamel only outside and ground connections with Red Oxide)							
67	012420	25.00	Numbers	87.00	2175.00	18.00	2566.50	
	Description:- Painting two coats of synthetic enamel paint over one coat of primer on the following after scrapping and cleaning of the surface wherever necessary with contractor own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy will be supplied by Railways. NOTE:- The paint and primer should be from M/s Asian paints Co. Ltd.,. The paints will be primer (IS 5660 of 1970) the Aluminium synthetic black enamel (IS 2932 of 1974) brilliant white and yellow Painting two coats of enamel paint over one coat of primer.(vii)Axle counter devices.							
68	012430	145.00	Numbers	47.00	6815.00	18.00	8041.70	
	Description:- Lettering / Numbering of Signals, Point Machine, Track Lead junction Boxes, Block joints, Apparatus Cases etc.(each item to be taken as One Unit) This work will be carried out as per the standard practice being followed in Central Railway.							
69	012440	10.00	Numbers	220.00	2200.00	18.00	2596.00	
	Description:- Lettering / Numbering Termination particulars, equipments names etc., legibly and neatly inside location boxes.(a)Full Case.							
70	012450	5.00	Numbers	121.00	605.00	18.00	713.90	

**MUMBAI-CST-DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-BB-SNT-EAST-2026-26

Closing Date/Time: 22/06/2026 15:00

70	Description:- Lettering / Numbering Termination particulars, equipments names etc., legibly and neatly inside location boxes.(b)Half Case.							
71	012460	2.00	Numbers	7155.00	14310.00	18.00	16885.80	
	Description:- Instllation testing & commissioning of the 25 W VHF system including the erection of mast, antenna, charging of the battery with all contractor's materials.							
72	012470	1.00	Lot	25736.00	25736.00	18.00	30368.48	
	Description:- Installation Testing and Commissioning of Fire Detection, Aspiration including flame sensor, LHS Cable flame sensor aspiration type smoke sensor as per RDSO SPN No.RDSO/SPN/217/2018 Version No.: 2.0. This includes Control module for the Control Unit, Monitor Module for the Control Unit. LHS Interface should be a microprocessor based start point device that communicates between LHS Cable and Control Unit should be an intelligent device that will monitor LHS cable for continuity and over temperature fire signatures. This also includes supply, Installation, Testing and Commissioning of Integrated Remote Monitoring System Software for complete as per specifications, for integrating, Fire Alarm System, VESDA System for monitoring at Division head quarter.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () C-NON SOR ITEM							13007481.13	Above/ Below/P ar
01	Please see Item Breakup for details.				13007481.13	AT Par	13007481.13	
	Description:- SUPPLY & EXECUTION							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () D-NON SOR ITEM							2375340.00	Above/ Below/P ar
01	Please see Item Breakup for details.				2375340.00	AT Par	2375340.00	
	Description:- SUPPLY & EXECUTION							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () E-NON SOR ITEM							9774884.00	Above/ Below/P ar
01	Please see Item Breakup for details.				9774884.00	AT Par	9774884.00	
	Description:- SUPPLY							

3. ITEM BREAKUP

Schedule Schedule C-NON SOR ITEM						
Item- 01 SUPPLY & EXECUTION						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	01	Supply of Smoke detector (Optical) (RDSO approved source only).(Inspection Agency-Consignee)	Numbers	200.00	4504.90	900980.00
2	02	Supply of Design set for circuits as per Annexure XVII(Inspection Agency-Consignee)	Set	1.00	129951.91	129951.91
3	03	Supply of industrial grade PC with 42" VDU & 1 KVA UPS , Specification should be approved by engineer incharge of the work before supply of material(Inspection Agency-Consignee)	Set	4.00	513000.00	2052000.00
4	04	Supply of lateral filling cabinet 3ft to store circuit diagrams(godrej) or similar(Inspection Agency-Consignee)	Numbers	2.00	14227.24	28454.48
5	05	Supply of panel operator record table Model T102 (Godrej) (Inspection Agency-Consignee)	Numbers	4.00	10265.27	41061.08
6	06	Supply of panel operator Chair model PCH-7001 (Godrej) (Inspection Agency-Consignee)	Numbers	10.00	10576.84	105768.40

**MUMBAI-CST-DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-BB-SNT-EAST-2026-26

Closing Date/Time: 22/06/2026 15:00

7	07	Supply of Steel cupboard(plain store wel) size 6'x3' Godrej make for SM store (Inspection Agency-Consignee)	Numbers	4.00	15574.96	62299.84
8	08	Supply and installation of Microprocessor based MiniLogger/Cloud based RTU including non-intrusivecurrent sensors and temperature & Humidity sensors,16 Voltage,8 Current Points Non-Intrusive,16 digitalinput (Relay Contract),Local storage of 7 days,DisplayLCD minimum 4x20 characters, toggle switches tooperate Display LCD,Works on 110V AC & 24 VDC,Voltage (AC/DC) measurement module forTC/PM/SG/Bus - 16 Voltages included - configurable asper selected gears, GPS module for timesynchronization (will be installed in existing locationBox) Inspection - RITES,Points : The following data shall be recorded for each end of the Point : i) DCoperating Current. li) DC operating Voltage.,DC TrackCircuits : The following data shall be recorded for eachTrack Circuit : i) DC feed end and relay end voltage.ii)DC feed end and relay end current.iii) Track relayposition.iv) input voltage & Output current of trackfeed battery charger,voltage & charging /discharging current of battery. (Inspection Agency-rites)	Numbers	25.00	39703.83	992595.75
9	09	Data communication Module with 3G/4G support along with antenna per location. (Inspection Agency-RITES)	Numbers	25.00	7465.67	186641.75
10	10	Non- intrusive current transducer sensors to measure one (Inspection Agency-RITES)	Numbers	100.00	5090.23	509023.00
11	11	Provision of cloud based application with standard IOT protocol support for monitoring of signal assets with satndard protocols and analysis health data. Application shall accomodate at least 10 station data. User ID and Login credentials shall be given to S&T inspector and officers. Vender shall maintain the cloud application for the perid of 2 years for free of cost. (Inspection Agency-Consignee)	Numbers	1.00	320345.41	320345.41
12	12	Installation, commissioning of Mini logger including all necessary fittings, joints and cabinets per location box and its integration with cloud based IOT application.(Inspection Agency-Consignee)	Numbers	25.00	10180.47	254511.75
13	13	Supply of Surge Protection Device (Type I+II) for Single Phase with unique feature of Progressive Indication of the arrester. limp (10/3500s) (L-N) = 25 KA limp (10/3500s)) (N-PE) = 52KA In (8/200s) (L-N) = 60KA In (8/200s) (N-PE) = 100KA Voltage Protection Level (L-N) with I (25KA) ; 1.25kV Voltage Protection Level (N-PE) ; 1.50kV Along with potential free contact for D/L wiring. Approval certificate from national/international labs like KEMA, VDE etc shall be submitted.It also includes installation as per requirement in supervision of OEM.(Inspection Agency-Consignee)	Numbers	3.00	28007.62	84022.86
14	14	WELD LESS MODULAR TYPE SS MEDIUM SIZE LOCATION BOX(Inspection Agency-Consignee)	Numbers	20.00	89252.50	1785050.00
15	15	WELD LESS MODULAR TYPE SS POST BOX LOCATION BOX(Inspection Agency-Consignee)	Numbers	20.00	83239.00	1664780.00

**MUMBAI-CST-DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-BB-SNT-EAST-2026-26

Closing Date/Time: 22/06/2026 15:00

16	16	Supply of polyolefin cable channel 2434 with following dimensions, height (internal/external) 155/230mm x width 240mm/340 mm x length 1000mm with suitable detachable cover having fire protection class K1 in accordance with DIN 53438 part 2 and electrical characteristic Dielectric strength 48KV/cm in accordance with DIN VDE 0303-21 (As per annexure)for laying of all types of S&T cables. (Inspection Agency-Consignee)	Metre	1000.00	2337.55	2337550.00
17	17	Bumpless Automatic power source change over Device DC 20V-150V, 45A (2 input sources) Model no. PTRSA - HL-DC-03 (Inspection Agency-Consignee)	Numbers	4.00	54516.00	218064.00
18	18	"12V 42AH LEAD ACID SMF BATTERY (GEM OFFER EXIDE 12.0 Volt Volt Lead Acid Battery (EXIDE) Model Exide Power safe Plus EP 42-12 AS PER GEM CONTRACT)(Inspection Agency-Consignee)"	Numbers	20.00	3259.20	65184.00
19	19	Battery Operated Rail bolt tightening machine.(Inspection Agency-Consignee)	Numbers	1.00	86633.90	86633.90
20	20	"Supply and installation of Cable ID Printer (FERRULE PRINTING MACHINE) with standard accessories like: Soft case, black ink ribbon (40m, cassette), tube attachment, inbuilt cutter unit, USB cable) similar to model number - Brother PT-E850TKW(Inspection Agency-Consignee)"	Numbers	1.00	51743.00	51743.00
21	21	"D type Fuse complete set with base & holder 2A,4A,6A, 10A,16A,25A (Inspection Agency-Consignee)"	Numbers	200.00	320.50	64100.00
22	22	Design, supply and manufacturing of static switch as per drawing no MRVC/S&T/16 OR SIMILAR (Inspection Agency-Consignee)	Numbers	20.00	53336.00	1066720.00
					Total	13007481.13

Schedule Schedule D-NON SOR ITEM

Item- 01 SUPPLY & EXECUTION

S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	01	"Supply of - [i] SMPS based Integrated Power Supply System without MFVRLA Battery set conforming to RDSO Specifications RDSO/SPN/165/2012 Version 3.0 with later amendment for PI station as per Central Rly. Drg.No.PA/DRG/EI/IPS/03(L)/01 with later correction if any, . Scope of Supply, Checking of Installation, testing and commissioning of IPS shall be as per RDSO letter No.STS//E/IPS/Genl Dated 03/04/2008 or Latest if any. [ii] Sealed Maintenance free VRLA battery set of 60 Cells (Stackable), in combination of 55+5 Cells for SMPS based integrated power supply system, each cell of 2 Volt/300 AH Capacity, fully charged conforming to RDSO Specification No.IRS:S:93/96(A) with later amendment, complete with connecting links and suitably numbered in stackable racks along with user manuals."(Inspection Agency-RDSO)	Set	2.00	1187670.00	2375340.00
					Total	2375340.00

Schedule Schedule E-NON SOR ITEM

Item- 01 SUPPLY

S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
-------	---------	---------------------	------	-----	------	--------

**MUMBAI-CST-DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-BB-SNT-EAST-2026-26

Closing Date/Time: 22/06/2026 15:00

1	01	Supply, Transportation, installation, Testing and Commissioning of Multi Section Digital Axle Counter (MSDAC) for 5 Detection Point and 04 track sections complete with all accessories, cable required with each track device & card (Viz, Axle detector, Track side electronic/DAC field units, central evaluator (central evaluator unit shall be housed in a pre-fabricated rack to be supplied along with the system) Reset unit (with LV Box), Event logger & diagnostic terminal etc. Required for different detection points & Track section as per RDSO specification No. RDSO/SPN/176/2013 (ver.3) or latest. (Inspection Agency-RDSO)	Set	4.00	2443721.00	9774884.00
Total						9774884.00

4. ELIGIBILITY CONDITIONS

Standard Financial Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer must have minimum average annual contractual turnover of V/N OR 'V' Whichever is less; where. V= Advertised value of the tender in crores of Rupees N= Number of years prescribed for completion of work for which bids have been invited. The average annual contractual turnover shall be calculated as an average of "total contractual payments" in the previous three financial years, as per the audited balance sheet. However, in case balance sheet of the previous year is yet to be prepared/ audited, the audited balance sheet of the fourth previous year shall be considered for calculating average annual contractual turnover. The tenderers shall submit requisite information as per ANNEXURE-XXXIII, along with copies of Audited Balance Sheets duly certified by the Chartered Accountant/ Certificate from Chartered Accountant duly supported by Audited Balance Sheet.	No	No	Allowed (Mandatory)

Standard Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	a)The tenderer must have successfully completed or substantially completed any one of the following categories of work(s) during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: (i)Three similar works each costing not less than the amount equal to 30% of advertised value of the tender, or (ii)Two similar works each costing not less than the amount equal to 40% of advertised value of the tender, or (iii)One similar work costing not less than the amount equal to 60% of advertised value of the tender.	No	No	Allowed (Mandatory)
1.1	Defination of Similar Work :- Trenching, cable laying, location and signal foundation/ erection/ termination/ wiring in connection with any signalling work. OR Any Indoor or combined indoor/ outdoor signalling including supply, installation, testing and commissioning of relay interlocking (RRI/PI) system for passenger carrying lines.	No	No	Not Allowed

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.
3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.

**MUMBAI-CST-DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-BB-SNT-EAST-2026-26

Closing Date/Time: 22/06/2026 15:00

5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.
6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.
7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.
8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.
9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.
10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description
1	Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. (Click here to download the Format of Self Certification)

5. COMPLIANCE

Commercial-Compliance

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)

General Instructions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Tender document, Scope of work & GCC 2022 are attached with the tender.	No	No	Not Allowed

Undertakings

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	I have read the entire tender document including uploaded documents.	No	No	Not Allowed
2	I/we have visited the site and I am/We are aware about site condition.	No	No	Not Allowed

Custom

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Mandatory documents as per clause 1.0.2 of the Tender documents are required to be submitted along with bid. Offer not accompanied by these documents will be summarily rejected.	No	No	Allowed (Mandatory)
2	GST Registration Certificate	No	No	Allowed (Mandatory)

**MUMBAI-CST-DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-BB-SNT-EAST-2026-26

Closing Date/Time: 22/06/2026 15:00

3	PAN CARD	No	No	Allowed (Mandatory)
4	If the tenderer want to submit any other documentary evidence in support of the offer like list of men, material, tools & plant availability etc.	No	Yes	Allowed (Optional)
5	Tenderer Remarks if any.	No	Yes	Allowed (Optional)
6	All the bidders/tenderers should ensure that they are GST complaint and their quoted tax structure/rates are as per GST LAW	Yes	Yes	Allowed (Optional)

6. Documents attached with tender

S.No.	Document Name	Document Description
1	FINALNEWTENDERDOC2026-261_1.pdf	Tender document
2	GCC_April-2022.pdf	GCC 2022
3	CORRECTIONSLIP1to11GCC2022_compressed.pdf	GCC CORRECTION SLIP 1 TO 11

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

Signed By: HITESH PATIDAR
Designation : Sr.DSTE EAST BB