

Closing Date/Time: 07/07/2026 15:00

**NER HQ-S AND T/NORTH EASTERN RLY
TENDER DOCUMENT**

Tender No: NER_SnT_Proj_BSB_03_2026

Closing Date/Time: 07/07/2026 15:00

1	Description:- Design, Manufacture, Supply of Hot Standby Architecture Electronic Interlocking (EI) System complete as per RDSO Spec. No. RDSO/SPN/192/2019 Version 2 with latest amendment, if any. Mainly consisting of CPU Cards, Input Cards, Output Cards, Interfacing Equipments and all required accessories for controlling Automatic Signals from mid-section Auto Relay Huts and communicating directly through OFC (laid in redundancy with route diversity) with adjoining Auto Relay Huts & EI/PI of stations as per Schematic Diagram of ABS scheme given in Annexure-I and SIP/ Roll Plan of ABS section attached. For system 'A' & 'B' of EI, segregation between the DC-DC converters should be made so that in case of failure, only one system is affected and DC-DC converters shall be provided in N+1 configuration. Dual VDU for Operation (2 No. of Fanless Embedded Industrial Grade PCs, 2 nos. industrial grade 55" 4KHD LED VDU and 1 no. Maintenance console (Fanless embedded industrial grade PC and Industrial Grade 55" 4KHD LED VDU with UPS, backup Min. 1 Hr. & Printer Color LaserJet with Scanning facility Similar to HP MFP 3303sdw) as per RDSO'S TAN No. STS/E/TAN/3007 Ver. 2.0 Dt.22.04.2026(Latest). This also includes supply of all types of interconnecting cables, Racks/Cabinets for EI, Relay Racks, Connectors, Fixtures, mounting Arrangements, media converters, networking switches, surge & lighting protection devices compatible to RDSO standards & as recommended by OEM, wiring materials, consumables, communication equipment etc. & all required accessories to make EI System functional for ARH as per Approved SIP. Note:(i).Tenderer should submit details of Individual Cards/ Modules with Item wise details, Rate and Quantity Prior to CA in Proforma attached as Annexure-'B'.(ii)Item wise rates are only for indicative purpose & will not be used for evaluation of Tender.(iii).The EI System including its Equipments and Sub systems shall be under Warranty for 3Years from the Date of Completion of each EI.(iv).CTR, Ext. Datalogger and all types of Ext. Relays for this item such as QN1,QNA1, LEDECRs,QSPA1, QL1, KLCRs will be provided by Railway.(Any specific type of relay, other than Q-series relays, which is system-specific, shall be provided by the contractor under this schedule item at no additional cost).(v)All peripherals and accessories required for the EI system, i.e. connecting cables, patch cords/cards, interface modules ,etc., shall be supplied by the EI OEM. Alternatively, such items may be supplied only with prior certification and approval of the concerned EI OEM.(vi)Suitable furniture (make: Godrej Interio /IKEA or equivalent) and fixtures shall be provided for the Indication VDU at stations as per IRSEM appendix II Drawing No. 21 D3 incorporating the actual site requirement.. MT furniture, including a computer table with three drawers and a chair, shall also be supplied by Contractor as per direction of Site Engineer.(vii)EI system must be followed the instruction as per Railway Board Letter No. 2018/Sig/18/EI/Gen.Dt. 04.09.2024 and RDSO letter No. RDSO-SIG0MISC(GEN)/1/2021 Part(1)Dt. 17.8.2024. (Inspection by RDSO).(Items not covered under RDSO/RITES inspection will be inspected by consignee with manufacturer(OEM) test certificate.)						
	A1002	14.00	Numbers	3620711.78	50689964.92	AT Par	50689964.92
2	Description:- Design, Manufacture and Supply of Electronic Interlocking System (Hot Standby)) equipments as per RDSO specification no. RDSO /SPN/192/2019 Ver 2.0 with latest amendments (I/O gatherer or object controller OC, CIU (if required)) for mid section Relay, Huts/ Goomties for Auto-Signalling EI working in conjunction and in tandem with Auto E.I. being provided at Stations/HUT in North Eastern Railway Relay Room/End Goomties etc. (item wise break up cost and details to be supplied with unit, rate, quantity and brief description of their function should be listed by tenderer in Annexure - 'C' Prior to CA. Item wise Rates are only for Indicative Purpose & will not be used for Evaluation of Tender. Any extra item required for commissioning of EI system will be borne by the contractor without any extra cost.. This also includes supply of all types of interconnecting cables, Racks/ Cabinets for EI/OC, Relay Racks, Connectors, Fixtures, mounting Arrangements, media converters, networking switches, surge & lighting protection devices, power supply module compatible to RDSO standards & as recommended by OEM, wiring materials, consumables, communication equipment etc. & all required accessories to make Electronic Interlocking System compatible with Auto Relay Hut as per Approved Signal Interlocking Plan. All peripherals and accessories required for the Electronic Interlocking (EI) system, i.e. connecting cables, patch cords/cards, interface modules, etc., shall be supplied by the EI OEM. Alternatively, such items may be supplied only with prior certification and approval of the concerned EI OEM. The Input/output of Auto E.I. and other related informations shall be send/received to other adjacent Auto EI or Existing E.I. to take corresponding inputs/outputs wherever required for Indications/Interlocking processing purposes. The EI System including its Equipments and Subsystems shall be under Warranty for THREE Years from the Date of Commissioning of Complete System. Inspection- RDSO (Items not covered under RDSO/RITES inspection will be inspected by consignee with manufacturer(OEM) test certificate.) Note:- OC System must be followed the instruction as per Railway Board Letter No. 2018/Sig/18/EI/Gen. Dt. 04.09.2024 and RDSO letter No. RDSO-SIG0MISC(GEN)/1/2021 Part(1) Dt. 17.8.2024 .						
	A1003	19.00	Station	5789143.75	109993731.25	AT Par	109993731.25

**NER HQ-S AND T/NORTH EASTERN RLY
TENDER DOCUMENT**

Tender No: NER_SnT_Proj_BSB_03_2026

Closing Date/Time: 07/07/2026 15:00

3	Description:- Modification/Alteration in existing EI (Electronic Interlocking) at Stations as per latest RDSO guidelines/TAN. It includes design and modification in existing Interface and Interlocking circuits and logic of EI system including modification in the VDU (Video Display Unit), Maintenance Terminal (MTC), Data Logger, Relay rack wiring. The complete work should comply with the latest RDSO specifications and guidelines and as per approved SIP and circuit diagrams. All the material (Object Controller/Interface cards/relays/wiring/ material/ connectors/ fuses/ relay rack/ communication devices etc.) for interfacing the auto EI and Stations EI shall be provided by the contractor. The work also includes the supply of modified Selection table, Interface Circuits, VDU etc. to suit the modified SIP. It also includes the carrying out of FAT, SAT (as applicable) jointly with Railways and satisfactory commissioning. Note: Tenderer should submit details of Individual Cards/ Modules with Item wise details, Rate and Quantity in Proforma attached as Annexure - D " for Item No.1 Prior to CA. Item wise Rates are only for Indicative Purpose & will not be used for Evaluation of Tender. Any extra item required for commissioning of EI system will be borne by the contractor without any extra cost. Item wise details are only for indicative purpose. All plans/ drawings/ circuits etc. should be prepared on AUTOCAD, approved softcopy to be supplied on Pen Drive and 06 sets of approved hard copies are also to be supplied. (Inspection by RDSO. However, items not covered under RDSO inspection will be inspected by consignee with manufacturer (EI) test certificate.) Note:- This item includes alteration in relay rack, existing EI (19 Stns.)from CPR Jn to Aunrihar Jn Station.						
4	A1004	7.00	Station	1755594.9 9	12289164.93	AT Par	12289164.93
	Description:- Modification/Alteration in existing EI (Electronic Interlocking) at Stations for phase working as per latest RDSO guidelines/TAN. It includes design and modification in existing Interface and Interlocking circuits and logic of EI system including modification in the VDU (Video Display Unit)/ CCIP (Control Cum Indication Panel), Maintenance Terminal (MPC), Data Logger, Relay rack wiring. The complete work should comply with the latest RDSO specifications and guidelines and as per approved SIP and circuit diagrams. All the material (Interface cards/relays/wiring/ material/ connectors/ fuses/ relay rack / communication devices etc.) shall be provided by the contractor. The work also includes the supply of modified Selection table, Interface Circuits, VDU/ CCIP diagram etc. to suit the modified SIP. It also includes the carrying out of FAT, SAT (as applicable) jointly with Railways and satisfactory commissioning. All plans/ drawings/ circuits etc. should be prepared on AUTOCAD, approved softcopy to be supplied on Pen Drive and 06 sets of approved hard copies are also to be supplied. Inspection by RDSO. However, items not covered under RDSO/RITES inspection will be inspected by consignee with manufacturer certificate.)						
5	A1005	18.00	Per Block Section	411852.20	7413339.60	AT Par	7413339.60
	Description:- Installation, wiring, testing & commissioning of complete Electronic Interlocking System as per RDSO Specification No. RDSO/SPN/192/2019 Version 2 (with latest amendment/ revision, if any) with Hot Standby and all other required accessories for functioning of Signalling System of Auto Relay Huts at mid sections (ARJ-SYH-TRN-NDJ- ASK-GCT-GZT-YFP-KMDR-CBN-PEP-BUI-BCD-STW-SIP-BKLA-MHT-GTST-CPR). (ONE Job = One block section). e.i. All huts falling within one block section will be considered together as one block section work for installation purposes. Note:-This also includes (i)the installation of additional hardware at station/HUT as supplied in item no. 2 (ii)installation of OC in the additional HUTs 3.: It includes all the related material transportation from SSE/Depot to site of work.						
6	A1006	19.00	Set	215547.64	4095405.16	AT Par	4095405.16
	Description:- Supply of Tools for EI System of standard make as per Annexure-F. (Inspection By RITES.)						
7	A1007	18.00	Set	1457684.9 7	26238329.46	AT Par	26238329.46
	Description:- Supply of Set of Spares for Electronic Interlocking System of RDSO Specification No. RDSO/SPN/192/2019 Version 2 with latest amendments/revisions, if any. Each set shall consist of 10% of each type of cards & sub- assemblies of EI system used in one EI Auto Relay Hut of each block section subject to minimum one card if 10% is less than one. Note: For this item, Tenderer should submit details of Individual Cards/ Modules with Item wise details, Proforma attached as Annexure -G Prior to CA. (Inspection by RDSO. However, items not covered under						
8	A1008	14.00	Numbers	342346.30	4792848.20	AT Par	4792848.20
	Description:- Supply of embedded fanless PC based Maintenance terminal/Datalogger terminal as per RDSO spec. No. RDSO/SPN/192/2019 Ver. 2.0 or latest & RDSO TAN No. STS/E/TAN/3007 Ver 2.0 dated 22.04.2026 or latest. The size of VDU shall be minimum 55" inch, LED 4K resolution. Note: One table of suitable size along with revolving chair should be supplied with Maintenance terminal (make Godrej/Methodex or similar of reputed make). (Inspection by Consignee.)						
9	A1009	14.00	Numbers	95321.59	1334502.26	AT Par	1334502.26
	Description:- Installation, wiring, testing and commissioning of embedded fanless PC based Maintenance terminal as per RDSO spec. No. RDSO/SPN/192/2019 Ver. 2 or latest & RDSO TAN No. STS/E/TAN/3007 Ver 2.0 dated 22.04.2026 . Note: (i)Technical requirements shall be mentioned in the tender document.						

**NER HQ-S AND T/NORTH EASTERN RLY
TENDER DOCUMENT**

Tender No: NER_SnT_Proj_BSB_03_2026

Closing Date/Time: 07/07/2026 15:00

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A2- (Supply, Installation, Testing, installation & Commissioning of Multi section Digital Axle counter (MSDAC) at 19 stations)							380836022.49	Above/ Below/P ar
1	A2001	1148.00	Numbers	328235.15	376813952.20	AT Par	376813952.20	
	Description:- Supply of Multi section Digital Axle Counter (MSDAC) complete System including central evaluators, processors, final track clearance relay for each track section, Rest Boxes, Monitoring consoles, Diagnostic Desktop (All-in-One desktop computer of 23.8 screen size, equipped with Intel Core™ i7 processor of minimum 13th generation or higher, minimum 8 GB RAM and minimum 1 TB SSD, of suitable configuration, make HP / Dell or equivalent, complete with UPS having minimum 1-hour power backup. One monochrome laser jet printer of make HP or equivalent shall also be provided) at each evaluator location(5 Set) and supply of LV boxes, detection points, mushroom housing for track side electronic, deflector plates and all other accessories as per RDSO's specification No. RDSO/SPN/176/2013 (Ver.3) with latest amendment/revision as per Technical Specification and Scope of Work mentioned in Tender Document. (Unit is per Detection Point (DP). Note: 1. There will be 32 Auto Relay Hut(ARH) in complete section where MSDAC systems are to be installed. There shall be minimum TWO nos. Central Evaluators at each location (auto hut) with all required accessories 2. Detection points are to be provided in redundancy on UP & DN line as per SIP/Roll Plan of ABS section enclosed. One Central Evaluator shall control main Detection Points of one line and standby Detection Points of another line and vice versa. For the communication between evaluator to evaluator (Hut to Station/HUT) OFC Link (dark fiber) will be provided by Railway. Any other Networking equipment if required will be supplied by contractor at no extra cost. 3. Track sections controlled by one Central Evaluator of HUT will vary depending upon nos. of auto signals controlled from Auto HUT. 4. Auto preparatory reset shall be provided in main & standby track section in case one system fails as well as supervisory reset feature. In case of both system failing simultaneously, manual preparatory reset through cooperation to be provided.5. If any housing is required to keep outdoor equipment, it has to be supplied with the equipment with no extra cost. 6. Any earthing (supply and installation)if required for track device/mushroom housing etc to be done by the contractor if required by system design. No extra cost/ payment will be made by this Railway. 7. Relay Rack & Relays (supply and installation)if required for system to be done by the contractor if required by system design. No extra cost/ payment will be made by this Railway. Supply of Tool set for wheel sensor mounting and maintenance of MSDAC consisting of torque wrench, ratchet, testing plate , measuring tape , screw driver, gloves and multimeter fluke-115 (@ 1 Set. per 14 DP) . The Railway will provide power supply up to the Power Distribution Board only and From the Power Distribution Board to the MSDAC equipment, the work, including supply and laying of cables/wires, shall be carried out by the contractor at no additional cost. Tenderer should submit details of Individual Cards/ Modules with Item wise details, Rate and Quantity in Proforma attached as Annexure - 'G' Prior to CA.							
2	A2002	19.00	Numbers	114385.41	2173322.79	AT Par	2173322.79	
	Description:- Supply of Tool Kit for Digital Axle Counter (suitable for MSDAC complying to the RDSO Specification No. RDSO/SPN/176/2013/Ver.3 or latest) & Test Panel including Meter for testing of track equipment, tools for monitoring & adjustment of track equipment and standard jig for drilling holes in a rail. It should be as per principal manufacturing (OEM) recommended list adequate for installation, day to day maintenance and adjustment of indoor and outdoor gears. The tool kit shall be equipped with the atleast following minimum equipments: (i). All mechanical tools shall be of reputed make like Taparia/Bosch etc. (ii). Digital multimeter true RMS type of make Fluke 189 or similar reputed make with probe set- 1 no. (iii). Adjustable Torque Wrenches 25-135 N/mtr with 13 mm and 19 mm inserts-1 Set. (iv). Set of spanners screw drivers and soldering iron -1 set. (v). Dummy wheel- 1 no. (vi). Marking jig -1 no. (vii). Adapter card-1 no. (viii). Extended wired socket to interface with diagnostic plug -1 no. (ix) Selector switch on panel base-1 no. (x). DAC EC card puller. (xi). Any other tools required for maintenance purpose.(Inspection by consignee).							
3	A2003	38.00	Numbers	48651.25	1848747.50	AT Par	1848747.50	
	Description:- Supply of one set of Track Device (including Tx and Rx) with 10 metre cable length suitable for one Detection Point of MSDAC as spare as per RDSO's specification No. RDSO/SPN/176/2013 (Ver.3) or latest.(Inspection by RDSO)							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A3- (Items of Supply, Installation, Testing & Commissioning of Electrically Operated Lifting Barriers (ELB) along with Sliding Boom Barriers)							10276798.36	Above/ Below/P ar
	A3001	22.00	Set	331225.50	7286961.00	AT Par	7286961.00	

**NER HQ-S AND T/NORTH EASTERN RLY
TENDER DOCUMENT**

Tender No: NER_SnT_Proj_BSB_03_2026

Closing Date/Time: 07/07/2026 15:00

1	Description:- Supply of Electrically Operated Lifting Barriers (110V AC operated) complete set along with pedestal driving and driven mechanism boom of 32 feet long, balancing weight, boom support and boom locking, limit switches/circuit controllers, gate operating panel, 2 booms of 32 feet length etc. along with all accessories complete in all respect as per RDSO Specification No. RDSO/SPN/ 208/ 2012/ver.2 with latest amendments/revision, if any from RDSO approved sources. Tool kit shall be supplied free of cost with each set of ELB as per Para 10.2 of RDSO specification. Note: Required nos. of limit switches are to be provided including 2 nos. of 0-50 limit switch for redundancy.) (Inspection by RDSO. However, items not covered under RDSO will be inspected by consignee).							
2	A3002	22.00	Set	46802.42	1029653.24	AT Par	1029653.24	
	Description:- Installation, testing & commissioning of Sliding Boom Barriers with posts & E type of locks as per standard drawing of Railway including casting of concrete foundations for boom supporting posts & boom lock post. (Note: Sliding Boom Barriers with required accessories will be supplied by Railway. All types of nut-bolts to be used for installation of sliding boom barriers will be supplied by contractor.)							
3	A3003	43.00	Numbers	28482.12	1224731.16	AT Par	1224731.16	
	Description:- Supply, installation, wiring, testing & commissioning of domino type LC gate signal control panel suitable for ABS territory as per drawing approved by NE Railway Drg No. NER/TYP/LC-DOMINO PNL/2021/31 (and as per instruction in Letter No. N/571/1/Drg./Policy/Pt.-13 dated 31.12.2021) and as per technical specification & scope of work mentioned in tender document. (Inspection by RDSO. However, items not covered under RDSO will be inspected by consignee)							
4	A3004	22.00	Job	33429.68	735452.96	AT Par	735452.96	
	Description:- Installation, wiring, testing and commissioning electrically operated lifting barrier complete with casting of concrete foundation for pedestal and boom rest post. This includes cabling, power supply connection wiring and all the associated outdoor activities. All materials except signalling cable shall be supplied by contractor as per technical specification & scope of work mentioned in tender document. Foundation drawings of pedestal & boom rest post shall be got approved by Railway Engineer. Installation, wiring, testing & commissioning shall be done in presence of technical representative by OEM of ELB.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A4- (Supply of various types Signalling & Telecom Items)							249405999.91	Above/ Below/P ar
1	A4001	360.00	Numbers	22724.98	8180992.80	AT Par	8180992.80	
	Description:- Supply of Colour Light Signal Post, Tubular Mild Steel, 4.6 m length, 140 mm Dia, as per RDSO Spec. No. IRS: S- 6/81 with latest amendments/ revision and Supply of cast iron Main signal surface base (As per RDSO Drg. No. 2011/M with latest amendments/ revision), with CLS ladder assembly suitable for colour light signal of 4.6 m long, as per RDSO drg. No. SA 23154,SA23159 and complete assembly of signal front & back staging for CLS unit. (Inspection by RITES.)							
2	A4002	38.00	Numbers	1084.91	41226.58	AT Par	41226.58	
	Description:- Supply of Offset Bracket for colour light signal Main unit, with fixing U clamps & nuts etc., as per RDSO Drg. No. SA 23080 (Adv.) with latest amendments. (Inspection by Consignee.)							
3	A4003	25.00	Numbers	39972.87	999321.75	AT Par	999321.75	
	Description:- Supply of Junction route indicator unit 1 way, made of FRP (without lenses & holder) as per Drg No. SA 23401-06 (Adv) (as applicable) suitable for LED Signal Lighting unit and as per RDSO Spec. IRS:S-66/84 Amd.-1 or latest and RDSO/SPN/194/2006 (Rev.2) or latest. (Inspection by RITES.)							
4	A4004	10.00	Numbers	31638.46	316384.60	AT Par	316384.60	
	Description:- SUPPLY OF Non Metallic ARM TYPE JUNCTION ROUTE INDICATOR COMPLETE WITHOUT LENSES AND LIGHT UNIT 2 WAY SUITABLE FOR LED SIGNAL UNITS as per RDSO/SPN/194/2006 rev.or latest IRS:S:66/84 & RDSO DRG. NO. 23403 (ADV.) 4 WITH LATEST AMENDMENT IF ANY & as per technical specification attached,							
5	A4005	8.00	Numbers	37234.61	297876.88	AT Par	297876.88	
	Description:- Supply of Junction route indicator unit 3 ways made of FRP (Without Lenses & Holder) as per Drg. No. RDSO SA 23403 suitable for LED Signal Lighting Unit & as IRS:S-66/84 amndt-1 or latest. (Supply of LED Unit is not covered in this item) Inspection: (i)RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board.							
6	A4006	360.00	Numbers	37972.09	13669952.40	AT Par	13669952.40	
	Description:- Supply of Four Aspect Non Metallic (FRP) colour light signal housing multi unit type for Railway Signalling suitable for RE area, complete without lenses, lamps and signal transformer as per RDSO Drg No. SA 23001 A/M (Adv) and as per RDSO Spec No.RDSO/SPN/194/2006 (Rev 2.0) or latest and FRP material as per RDSO Spec No. RDSO/SPN/151/1997 or latest.(Inspection by RDSO.)							
	A4007	40.00	Numbers	2172.95	86918.00	AT Par	86918.00	

**NER HQ-S AND T/NORTH EASTERN RLY
TENDER DOCUMENT**

Tender No: NER_SnT_Proj_BSB_03_2026

Closing Date/Time: 07/07/2026 15:00

7	Description:- Supply of elbow for home signal 5.5" as per RDSO Drawing No. SA23080(Adv) with latest amendment with any(Inspection by Consignee)						
8	A4008	1080.00	Numbers	147.97	159807.60	AT Par	159807.60
	Description:- Supply of hand cuff lock with key of approved type & standard make for locking signal unit door. (Inspection by Consignee)						
9	A4009	1600.00	Numbers	24726.61	39562576.00	AT Par	39562576.00
	Description:- Supply of Apparatus Cases (full location box) as per RDSO Drawing No. RDSO/S-11500 or latest with miniature E type locks & keys. The key & handle shall be supplied at the rate of one set per four Apparatus Case. The miniature'E' type lock shall be as per RDSO Specification No. IRS: S-30/64 or latest and of ward no 41or as required by consignee & RDSO Drg No SA 3473/M & SA3474A or latest and key as per RDSO Drawing No. 3377/M or latest. E type locks are to be fitted on both front & back doors of location box. (Inspection by RITES.)						
10	A4010	350.00	Numbers	448.07	156824.50	AT Par	156824.50
	Description:- Supply of 'E' - Type Lock of Different Wards as per IRS: S 30-64 & as per RDSO Drg. No. SA 3377 procured from RDSO Approved Firms as perTech. Spec.(ward No. will be as per instruction of site incharge.						
11	A4011	900.00	Numbers	5173.31	4655979.00	AT Par	4655979.00
	Description:- Supply of Phenolic laminated Sheet, resin bonded, grade P3 in standard size of 1220 X 1220 x 10 mm as per specification No IS 2036 of 1995 or latest. Test report of manufacture to be supplied. (Inspection by Rites)						
12	A4012	2400.00	Numbers	107.41	257784.00	AT Par	257784.00
	Description:- Supply of Fuse Block made of PBT/Polycarbonate material as per RDSO Specification No. IRS:S 75/2006 (Rev.2) & RDSO Drg.no SA-23748 or latest from RDSO approved sources. (Inspection by RDSO.)						
13	A4013	2600.00	Numbers	33.19	86294.00	AT Par	86294.00
	Description:- NDT low voltage electric fuse non indicating type fuse as per IRS S:78/92 round edge 14 mm dia, 51 mm length rating 2 Amp (Inspection by RDSO.)						
14	A4014	3100.00	Numbers	24.41	75671.00	AT Par	75671.00
	Description:- NDT low voltage electric fuse non indicating type fuse as per IRS S:78/92 round edge 14 mm dia, 51 mm length rating 4/6 Amp(Inspection by RDSO.)						
15	A4015	2600.00	Numbers	32.06	83356.00	AT Par	83356.00
	Description:- NDT low voltage electric fuse non indicating type fuse as per IRS S:78/92 round edge 14 mm dia, 51 mm length rating 10 Amp(Inspection by RDSO.)						
16	A4016	3400.00	Numbers	238.27	810118.00	AT Par	810118.00
	Description:- Supply of ARA Terminal Block made of PBT - 6 Way as per RDSO Spec. No. IRS: S75/2006 (Rev. 2) or latest & Drg. No.SA-23756 (Alt-4) or latest from RDSO approved sources. (Inspection by RDSO.)						
17	A4017	1600.00	Numbers	62.92	100672.00	AT Par	100672.00
	Description:- Supply of ARA terminal block PBT 1 Way 60mm centre as per RDSO DRG. No. SA-23745 ALT. 5 and spec No. IRS:S:75/2006 with latest amendment if any. (Inspection by RDSO.)						
18	A4018	75.00	Numbers	602.39	45179.25	AT Par	45179.25
	Description:- Supply of Bus Bar 50-Way as per CSTE/Con/Gkp/ Sketch No. CSTE/Con/95/ SK- 3 Inspection: Consignee						
19	A4019	16000.00	Metre	43.11	689760.00	AT Par	689760.00
	Description:- Supply of 1 x 6 Sq mm (Red/Black/Green) multi strand copper power wire, 85 conductor each dia 0.30 +/- 0.01 with insulation thickness of 0.8 mm and nominal conductor resistance of 3.3 ohms/km as per RDSO Specn.No.IRS:S- 76/89 (Amnd.3) or latest and IS: 2465/1984 and IS:694:2010 or latest. Colour of the wire will be specified by the Engineer incharge.(Inspection by RDSO.)						
20	A4020	16000.00	Metre	112.87	1805920.00	AT Par	1805920.00
	Description:- Supply of 1 x 10 Sq mm (Red/Black/Green) multi strand copper power wire, 101 conductor each dia 0.45 +/- 0.01 with insulation thickness of 1.2 mm and nominal conductor resistance of 1.127 ohms/km as per RDSO Specn.No.IRS:S-76/89(Amnd.3) or latest and IS: 2465/1984 and IS:694:2010 or latest. Colour of the wire will be specified by the Engineer incharge.(Inspection by RDSO.)						
21	A4021	13000.00	Metre	132.81	1726530.00	AT Par	1726530.00
	Description:- Supply of 1 x 16 Sq mm (Red/Black/Green) multi strand copper power wire, 101 conductor each dia 0.45 +/- 0.01 with insulation thickness of 1.2 mm and nominal conductor resistance of 1.127 ohms/km as per RDSO Specn.No.IRS:S-76/89(Amnd.3) or latest & and IS: 2465/1984 and IS:694:2010 or latest. Colour of the wire which is required will be specified by the Engineer incharge.(Inspection by RDSO.)						
	A4022	550000.00	Metre	9.78	5379000.00	AT Par	5379000.00

**NER HQ-S AND T/NORTH EASTERN RLY
TENDER DOCUMENT**

Tender No: NER_SnT_Proj_BSB_03_2026

Closing Date/Time: 07/07/2026 15:00

22	Description:- Supply of 16/0.2 mm (0.5 sq mm) PVC insulated, multi strand single core, tinned copper conductor as per RDSO Specification No. IRS: S-76/89 (Ammdet-3) or latest from RDSO approved sources. Each coil shall be of 100 meters.(Inspection by RDSO)						
23	A4023	1600.00	Numbers	5935.26	9496416.00	AT Par	9496416.00
	Description:- Supply of Q-Series Universal type QECX-61 AC LED lamp proving relay (ECR) of 4F-4B contacts with plug board (base plate), connectors, retaining clip etc. and conforming to BRS:941A, STS/E/RELAYS/AC LED SIGNAL/09- 2002, Amndt.1 o r latest and R D S O Specification No. IRS:S@45"45@68 & Amendment 6, S-23-88 & Amendment 1 or latest as applicable from RDSO approved sources.(Inspection by RDSO)						
24	A4024	3250.00	Numbers	3654.91	11878457.50	AT Par	11878457.50
	Description:- Supply of Q-Series Neutral Line Relay, non-AC immunized (QN1 type), 8F.8B/12F.4B, 24V/50V DC complete with plug board (base plate), connectors, retaining clip etc. and conforming to BRS:930 and Specification No. IRS:S@45"45@ 68 & Amendment 6, S-23-88 & Amendment 1, S@45<45@78 & Amendment 1 or latest as applicable from RDSO approved sources. (Inspection by RDSO.)						
25	A4025	2650.00	Numbers	4005.58	10614787.00	AT Par	10614787.00
	Description:- Supply of Q-Series Line Relay, AC immunized (QNA1 type), 8F.8B/12F.4B, 24V DC complete with plug board (base plate), connectors, retaining clip etc. and conforming to BRS:931 and Specification No. IRS:S@45"45@68 & Amendment 6, S-23-88 & Amendment 1, S@45<45@78 & Amendment 1 or latest as applicable from RDSO approved sources. (Inspection by RDSO.)						
26	A4026	88.00	Numbers	9443.51	831028.88	AT Par	831028.88
	Description:- Supply of Key Lock Checking Relay (KLCR) working on 24V DC, AC Immunized with different ward combinations and contact configuration 4F/4B with 2 extra ward plates and with case, RDSO spec no. RDSO/SPN/219/2016 ver 1.0 or latest, confirming to IRS S-23, S-34 & S@45<44@ IRS S:46. Inspection authority:- Inspection -RDSO						
27	A4027	360.00	Numbers	8891.11	3200799.60	AT Par	3200799.60
	Description:- Supply of main LED signal lamps of Green aspect with inbuilt current regulator as per RDSO Specification No. RDSO/SPN/199/2010 Revision 1.1 or latest retrofittable in existing CLS housing & compatible with AC LED ECR from RDSO approved sources. (Inspection by RDSO.)						
28	A4028	410.00	Numbers	7835.25	3212452.50	AT Par	3212452.50
	Description:- Supply of main LED signal lamps of Red aspect with inbuilt current regulator as per RDSO Specification No. RDSO/SPN/199/2010 Revision 1.1 or latest retrofittable in existing CLS housing & compatible with AC LED ECR from RDSO approved sources. (Inspection by RDSO.)						
29	A4029	770.00	Numbers	7839.36	6036307.20	AT Par	6036307.20
	Description:- Supply of main LED signal lamps of Yellow aspect with inbuilt current regulator as per RDSO Specification No. RDSO/SPN/199/2010 Revision 1.1 or latest retrofittable in existing CLS housing & compatible with AC LED ECR from RDSO approved sources. (Inspection by RDSO.)						
30	A4030	310.00	Numbers	5416.11	1678994.10	AT Par	1678994.10
	Description:- Supply of Route LED Signal lighting unit 110V AC retrofittable in existing CLS housing and compatible with AC LED ECR as per RDSO Specification No. RDSO/SPN/153/2023 revision 5 or latest. (Inspection by RDSO.)						
31	A4031	38.00	Numbers	7248.74	275452.12	AT Par	275452.12
	Description:- Calling On signal lighting unit 110vAC, retrofittable in existing CLS housing and compactible with AC LED ECR as per RDSO specification No. RDSO/SPN/153/2011 Revision 4.1 draft OR LATEST ACCEPTED(Inspection by RDSO.)						
32	A4032	270.00	Numbers	5376.23	1451582.10	AT Par	1451582.10
	Description:- Supply of "A" & "AG" Marker LED Signal Lighting Unit retrofittable in existing CLS housing and compatible with AC LED ECR as per RDSO Specification No. RDSO/SPN/153/2011 revision 4.1 or latest. (Inspection by Consignee.)						
33	A4033	1000.00	Metre	891.34	891340.00	AT Par	891340.00
	Description:- Supply of Medium class GI pipes of 100 mm diameter (4.5 mm thickness) with thread collars as per IS 1239 (Part 1) 2004 or latest along with couplers at one side in 6 meter length & along with test report of manufacturer. (Inspection by RITES.)						
34	A4034	20000.00	Metre	276.06	5521200.00	AT Par	5521200.00
	Description:- Supply of Double Walled Corrugated (DWC) pipe with associated collars etc. as per RDSO Specification No. RDSO/SPN/204/2011 Ver. 1.1 & Amendment 1 or latest, anti-rodent & anti-oxidant and non-flame propagating type of size 103.5 mm inner dia and 120 mm outer dia in 6 metre length suitable for taking underground communication/signalling cables. One coupler with suitable rubber O-ring for jointing shall be supplied with each 6 mtrs. length. (Note: DWC pipe shall be marked at every ONE meter length in such a way that manufacturer's name & year of manufacturing can be easily identified. (Inspection by RITES.)						
	A4035	50000.00	Metre	375.26	18763000.00	AT Par	18763000.00

**NER HQ-S AND T/NORTH EASTERN RLY
TENDER DOCUMENT**

Tender No: NER_SnT_Proj_BSB_03_2026

Closing Date/Time: 07/07/2026 15:00

35	Description:- Supply of Double Walled Corrugated (DWC) pipe with associated collars etc. as per RDSO Specification No. RDSO/SPN/204/2011 Ver. 1.1 & Amendment 1 or latest, anti-rodent & anti-oxidant and non-flame propagating type of size 175 mm inner dia and 200mm outer dia in 6 metre length suitable for taking underground communication/ signalling cables. One coupler with suitable rubber O-ring for jointing shall be supplied with each 6 mtrs. length. (Note: DWC pipe shall be marked at every ONE meter length in such a way that manufacturer's name & year of manufacturing can be easily identified. (Inspection by RITES.)						
36	A4036	721.00	Kilometre	69033.98	49773499.58	AT Par	49773499.58
	Description:- Supply of HDPE duct of 40/33 mm in Drum length of 500/1000 meter length as per RDSO Specification RDSO/SPN/TC/ 45/ 2013 revision 2.0 (Amdt. 2.0) or latest either from RDSO or TEC approved firms along with test report of manufacturer.(Inspection by RITES.)						
37	A4037	180000.00	Numbers	87.29	15712200.00	AT Par	15712200.00
	Description:- Supply of 4 conductor disconnect terminal block with screwing cage/ clamp type, sliding switch disconnect as per RDSO Specification No. RDSO/SPN/189/2004 Ver 3.0 or latest for each conductor size upto 2.5 sqmm from RDSO approved sources. (Inspection by RDSO.)						
38	A4038	180000.00	Numbers	19.23	3461400.00	AT Par	3461400.00
	Description:- Supply of end and intermediate plate 2.5 mm/0.098 in thick as per RDSO Specification No. RDSO/SPN/189/2004 Ver 3.0 or latest. Make Wago or Phoenix make or similar. (Inspection by RDSO.)						
39	A4039	6000.00	Numbers	19.21	115260.00	AT Par	115260.00
	Description:- Supply of screwless end stop 10 mm/0.394 in wide carrier wide rail din 35 of Wago or Phoenix make or similar.(Inspection by RDSO.)						
40	A4040	2550.00	Metre	156.29	398539.50	AT Par	398539.50
	Description:- Supply of steel carrier rail of size 35x7.5 mm of Wago or Phoenix make or similar. (Inspection by RDSO.)						
41	A4041	600.00	Numbers	1898.85	1139310.00	AT Par	1139310.00
	Description:- Supply of Thermo Shrink Jointing Kit (RTSF4) as per RDSO Specification No. IRS TC-77-2012 (Rev.3) or latest suitable for 6 quad jelly filled cables for straight through/ derivation joints including supply of all the accessories from RDSO/TEC approved sources & along with test report of manufacturer. (Inspection by consignee)						
42	A4042	250.00	Numbers	826.15	206537.50	AT Par	206537.50
	Description:- Supply of V.F.Transformer (2T/3T) 1120:470 Ohms as per RDSO Specification No. IRS TC-76-2021 (Ver.1) (Cylindrical Type) or latest suitable for 6 quad jelly filled cables for derivation and Termination of underground Telecom Cable Circuit. (Inspection by RITES)						
43	A4043	200.00	Numbers	1639.92	327984.00	AT Par	327984.00
	Description:- Supply of VF transformer 470:600 (Rack Mountable) as per Spec. No. IRS:TC:22/76 with latest amendment. Inspection: RITES						
44	A4044	32.00	Numbers	5125.85	164027.20	AT Par	164027.20
	Description:- Supply of Proximity Switches for Single Door along with 2 Way Rigid Connector for wire Termination between Proximity Switches and Data Logger, Tag Block and Testing of Door Contacts and Validation of Proximity Switch Data through Data Logger including Embedded Software Development in Data Logger. Inspection: Consignee						
45	A4045	107.00	Numbers	7102.10	759924.70	AT Par	759924.70
	Description:- Supply of Fibre Distribution Management system (FDMS)/LIU for 48 Fiber as per drawing No:RDSO/TCDO170(a) complete with allaccessories as per TEC Spec.GR/FDM/01/02 April'2007 or latest. This include supply of installation accessories as per technical specification. (Inspection by RITES)						
46	A4046	450.00	Numbers	1560.77	702346.50	AT Par	702346.50
	Description:- Supply of 48 Fiber OFC Joint Closure similar to Specification No.RDSO/SPN/TC/68/2014 Rev 1.0 or latest. (Inspection by RITES)						
47	A4047	2100.00	Metre	29.63	62223.00	AT Par	62223.00
	Description:- Supply of STP CAT-6 Cable (Shielded Twisted Pair) STP compliant with latest /-568-82-1. (Inspection by Consignee)						
48	A4048	18.00	Numbers	60743.67	1093386.06	AT Par	1093386.06
	Description:- Supply of Maintenance Console alongwith Failure Analysis Software for Datalogger with one set of chair and table for online tracking and monitoring of station position. It consist of a PC (Reputed Brand only) with following configuration: Core i5 or higher version, processor speed 3.1 Ghz or higher, 4 MB Cache Memory, minimum 8 GB RAM, 500 GB HDD, Two Front and Two Rear USB Port, One Parellel Port, 1 VGA Port, TFT/LED Colour Monitor (17" or Higher), Sound Card with Speaker, Network Card with 1000 Mbps, Key Board, Optical Mouse, 10/100T LAN Card, UPS, Combo Drive, Window - 11 Professional Operating Licence Software + Antivirus Software, Laser Jet Printer (as per site engineer). Note:- I t i s inclusive o f installation, testing a n d commissioning o f t h e system. Inspection: Consignee						
	A4049	10.00	Numbers	214822.49	2148224.90	AT Par	2148224.90

**NER HQ-S AND T/NORTH EASTERN RLY
TENDER DOCUMENT**

Tender No: NER_SnT_Proj_BSB_03_2026

Closing Date/Time: 07/07/2026 15:00

49	Description:- Supply of Micro Processor based Remote Terminal Unit (RTU) with 128 digital input & 16 analog input as per RDSO Spec. No. IRS (S) 99/2006 (Amdt. 3) or latest. It includes supply of all the items required for complete indoor relay room wiring from RTU to relay rack tag blocks, drawing/extension of power supply upto RTU. It includes supply of relay room door lock checking arrangement, commercial power supply monitoring arrangement & monitoring of DG sets, ELD, MSDAC, IPS etc., interlinking and networking of RTU. Note: Total numbers of relays and other signalling functions/gears required to be wired as per list circulated vide RDSO Letter No.STS/E/Data logger dtd.12.09.2011 or latest guidelines. (Inspection by RDSO.)						
50	A4050	10.00	Numbers	20638.44	206384.40	AT Par	206384.40
	Description:- Supply of T-Networking Modem for connecting RTU/data logger with existing Data logger/RTU as per RDSO Spec. No. IRS (S) 99/2006 (Amdt. 3) or latest. (Inspection by Consignee.)						
51	A4051	50.00	Numbers	3111.34	155567.00	AT Par	155567.00
	Description:- Supply of Magneto Telephone Desk Type as per RDSO Spec IRS-TC-79/2000 or latest. (Inspection by Consignee.)						
52	A4052	96.00	Numbers	654.90	62870.40	AT Par	62870.40
	Description:- RR Cell -6-I (Primary Cell SITEL) for railway signalling and telecom application as per Specification No. IRS:S- 95/96 Amd-1 (Inspection- Consignee)						
53	A4053	5000.00	Metre	270.22	1351100.00	AT Par	1351100.00
	Description:- Supply of PVC Indoor Cable 1x60x0.6mm dia Colour coding of insulation of inner core shall be in six colour viz Blue, Red, Grey, Green, Brown & Black conforming to IRS 76/89 (Amd. 3) or latest from RDSO approved sources. (Inspection by Consignee.)						
54	A4054	3000.00	Metre	177.70	533100.00	AT Par	533100.00
	Description:- Supply of PVC Indoor Cable 1x 40x0.6mm dia. Colour coding of insulation of inner core shall be in eight colour viz Blue, Red, Grey, Green, Brown, Black, Yellow & White conforming to IRS 76/89 (Amd. 3) or latest from RDSO approved sources. (Inspection by Consignee.)						
55	A4055	4.00	Numbers	25744.67	102978.68	AT Par	102978.68
	Description:- Supply of Laserjet Printer for taking print out of various field data for analysis as per Technical Specifications mentioned in Tender Documents of make- HP/Canon/Epson or superior (Model and Spec as : HP Laser 335dw or similar). (Inspection by Consignee)						
56	A4056	2.00	Numbers	611456.89	1222913.78	AT Par	1222913.78
	Description:- Supply of Cable fault locator.Model Sidekick plus 1155- 5001or similar make stanley. as per specification -Inspection Authority -RITES .Make model before supply approved by Railway. Inspection authority RITES						
57	A4057	6.00	Numbers	498037.58	2988225.48	AT Par	2988225.48
	Description:- Supply of Cable route locator/tracer set suitable for detecting underground armoured optic fibre cable (OFC) and signalling cables with LCD Graphic.Display active/passive modes and depth range .3M-10 M. Model STLOC10 GPS make stanlay or equivalent.It should be with Minimum 12 watt transmitter with Li-ion battery pack . Inspection: RITES						
58	A4058	1600.00	Numbers	152.11	243376.00	AT Par	243376.00
	Description:- Supply of SC/APC-LC/PC patch Cord 5/10 mtr.long of standard make.(Suitable for interconnect S&T equipment's of work) (Inspection by Consignee)						
59	A4059	2.00	Numbers	195156.49	390312.98	AT Par	390312.98
	Description:- Supply of Fusion Splicing Machine model Fujikura FSM- 60S /Stanlay L3 or similar / upgraded. Inspection: Consignee						
60	A4060	2.00	Numbers	170458.49	340916.98	AT Par	340916.98
	Description:- Supply of Optical Time Domain Reflectometer (OTDR)(Type-I)(1310nm & 1550nm wavelength) for Long Haul applications with FDD adapter FC-PC and SCPC as per TEC/GR/TX/OTD-01/04/APR-2010 or latest with report generation tool and software as per annex in tender doc. Inspection: Consignee						
61	A4061	2.00	Numbers	15946.10	31892.20	AT Par	31892.20
	Description:- Supply of Laser source and Power meter. FOD make (Source FOD 2107 and Power meter FOD 1202) or similar. Inspection: Consignee						
62	A4062	43.00	Numbers	4537.47	195111.21	AT Par	195111.21
	Description:- Supply of Electrical Key Transmitter (EKT) Rotary Type as per RDSO Spec. No. IRS:S- 21/01 & RDSO Drawing No. SA- 22601 (Alt.4) or Latest with the keys and ward as per approved signal interlocking plan (SIP) or as per instructions given by site engineer in charge. Inspection Authority:- RITES Inspection.						
63	A4063	15.00	Kg	1643.09	24646.35	AT Par	24646.35
	Description:- Supply of Resin core 60/40, 18 SWG (Philco/Khosla or similar reputed make)						
64	A4064	19.00	Numbers	30729.53	583861.07	AT Par	583861.07
	Description:- Supply of Office Almira of size 914.4 (W) x 1981.2 (H) x 533.4 (D) mm as per model No. KD MNOR with metal top of Godrej make or similar. (Inspection by consignee)						

**NER HQ-S AND T/NORTH EASTERN RLY
TENDER DOCUMENT**

Tender No: NER_SnT_Proj_BSB_03_2026

Closing Date/Time: 07/07/2026 15:00

65	A4065	38.00	Numbers	15257.70	579792.60	AT Par	579792.60	
	Description:- Supply of Table of size 1370 (W)x740(H)x690 (D) mm as per Model No. T-9 of Godrej Make or similar. (Inspection by Consignee.)							
66	A4066	19.00	Numbers	14689.24	279095.56	AT Par	279095.56	
	Description:- Supply of Chair of model OXBO with High Back of Godrej make or similar. (Inspection by Consignee.)							
67	A4067	80.00	Numbers	3396.90	271752.00	AT Par	271752.00	
	Description:- Supply of Chair Superior Quality with Arm and Cane seated of size 57(D)x58(W)x88(H) and seat height of 45 mm of model no. classic CH-7 of Godrej make or similar. (Inspection by Consignee.)							
68	A4068	19.00	Numbers	1895.42	36012.98	AT Par	36012.98	
	Description:- Supply of Steel Stool Godrej make no ST2 for Relay room or Similar reputed make. (Inspection Agency: Consignee)							
69	A4069	19.00	Numbers	10872.93	206585.67	AT Par	206585.67	
	Description:- Supply of Lateral Filing Cabinet Godrej make or Similar reputed make. (Inspection Agency: Consignee)							
70	A4070	5.00	Numbers	16025.26	80126.30	AT Par	80126.30	
	Description:- Supply of Insulation Resistance Tester 500V DC, 100 Mega ohm, hand generator type. Make: Meco/Motwane/Waco or similar. (Inspection by Consignee.) Supply of Insulation Resistance Tester 500V DC, 100 Mega ohm, hand generator type. Make: Stanone/Meco/Motwane/Waco or similar. (Inspection by Consignee.)							
71	A4071	5.00	Numbers	14103.14	70515.70	AT Par	70515.70	
	Description:- Supply of Insulation Resistance Tester 100V DC, 100 Mega ohm, hand generator type. Make: Stanone/Meco/Motwane/Waco or similar. (Inspection by Consignee.)							
72	A4072	5.00	Numbers	103303.01	516515.05	AT Par	516515.05	
	Description:- Supply of Digital Clamp Earth Tester/Meter with storage facility of Model CET500 Stanone/Model DET20 of Motwane make or Meco or Fluke or better. (Inspection by Consignee.)							
73	A4073	6.00	Numbers	67041.33	402247.98	AT Par	402247.98	
	Description:- Supply of Digital Multimeter of model No. Fluke 287 of Fluke/Stanone SMM180 make or better. (Inspection by Consignee.)							
74	A4074	2.00	Numbers	52367.96	104735.92	AT Par	104735.92	
	Description:- Supply of Digital AC/DC Leakage Current Clamp on Meter of Model CL360 of Yokogawa or DCM 39A of Fluke make or similar model of Motwane make or better. (Inspection by Consignee.)							
75	A4075	200.00	Numbers	1271.62	254324.00	AT Par	254324.00	
	Description:- Supply of Tag blocks 120 way with Polycarbonate cover as per IRS: S-77/2006 (Rev. 1) or latest, as per drawing no. SA-24751, SA-24752, SA-24753 respectively. (Inspection by Consignee.)							
76	A4076	107.00	Numbers	84577.36	9049777.52	AT Par	9049777.52	
	Description:- Supply, installation & fixing of FDMS (02 no of 48 F) as per GR No. G/FDM-01/02 April-2007 of TEC or latest. it includes the supply of Splicing of 19inch 42U rack (01 No. of Rack) with mounting arrangement. it will also include all Supply & installation of material, splicing, termination, testing of all 2x48 fibers. (Inspection of supply portion by RITES)							
77	A4077	5.00	Numbers	3287.56	16437.80	AT Par	16437.80	
	Description:- Supply of Rodometer [Analog] Spec: Mechanical 5 digits counter, ABS Plastic wheel with rubber tyre, measure Forward & Backward, Telescopic handle, 38 P38recision measuring wheel. Make/Brand: Stanley or Boschor JCB or Freeman or Equivalent. (Inspection by Consignee)							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A5- (Supply & Execution Items)							87072245.26	Above/ Below/Par
1	A5001	64.00	Numbers	30241.34	1935445.76	AT Par	1935445.76	
	Description:- Supply and installation of Cable Termination (CT) rack as per drawing of NE Railway, complete along with fitting arrangements, wall supports, scaffolding and suitable grouting arrangements and also with arrangement for fixing Disconnect type terminal blocks/ ARA terminals. The CT rack shall be covered with Phenolic Laminated Sheet of minimum 10 mm thickness for fixing of Disconnect type terminal blocks/ ARA terminals. Cable termination rack shall be corrosive resistant and power coated. Note: Supply of Disconnect type terminal blocks/ ARA terminals not covered under this item. (Inspection by Consignee)							
	A5002	32.00	Numbers	22485.84	719546.88	AT Par	719546.88	

**NER HQ-S AND T/NORTH EASTERN RLY
TENDER DOCUMENT**

Tender No: NER_SnT_Proj_BSB_03_2026

Closing Date/Time: 07/07/2026 15:00

2	Description:- Fabrication, supply and installation of Power Supply Distribution Rack made of MS Angle of Size 40mm x 40mm x 6mm (similar to Cable Termination rack) as per drawing of NE Railway, complete along with fitting arrangements, wall supports, scaffolding and suitable grouting arrangements in IPS Room. The Power Supply Distribution rack shall be covered with Phenolic Laminated Sheet of minimum 10 mm thickness for fixing of Fuse terminal blocks/ ARA terminals. This includes supply & fixing of standard size ladder suitable for indoor cable made of MS angle of size 25mm x 25mm x 5mm from Battery Room to IPS Room and from IPS Room to Relay room for taking power cables. Power Supply Distribution Rack & ladder rack shall be corrosive resistant and power coated. This also includes fixing of required nos. Fuse Terminal Blocks & ARA Terminals on laminated sheet as per power supply distribution diagram and laying of required nos. of power cables from Power Supply Distribution Rack to Relay Room & Battery Room of various supply in ring protection & terminating with help of crimped copper lugs of suitable sizes duly supported on ladder with proper lacing & dressing. Various sizes of lugs for terminating power cables are to be supplied by contractor. Note: Power cables, fuse terminal blocks & ARA terminals not covered under this item. (Inspection by Consignee)							
	A5003	32.00	Numbers	150394.01	4812608.32	AT Par	4812608.32	
3	Description:- Supply, installation, wiring, testing commissioning of Earth Leakage Detector (ELD) of 8/12 channel, voltage of 110 Volt/60 V/24V/12V in AC/DC as per RDSO Spec. No. RDSO/SPN/256/2002 or latest. This includes supply of fuse terminal strip for incoming supply wires. Installation to be done on 19-inch sub-rack along with insulation resistance meter, indication & buzzer.(ELD to be inspected by RDSO.)							
	A5004	32.00	Numbers	79335.43	2538733.76	AT Par	2538733.76	
4	Description:- Supply, installation, wiring, testing & commissioning of Microcontroller based Quad cable conductor Earth Resistance sensing unit for 24 nos. of conductors having NO & NC contact for remote monitoring as per Technical Specification mentioned in Tender Document. (Inspection by RITES)							
	A5005	32.00	Numbers	95639.04	3060449.28	AT Par	3060449.28	
5	Description:- Supply, Installation, Wiring, Testing & Commissioning of Networkable type Microprocessor based Addressable, Automatic Fire Detection & Alarm System (AFDAS) consisting of Control Panel & other accessories as per RDSO spec. No. RDSO/SPN/217/2021 Ver 3 or latest and RDSO TAN 3009 Ver 1.0 Dt. 10/12/2024. The number of detector and devices per loop should be up to 159. The AFDAS shall include a backlit min 360-character liquid crystal display, individual, color coded system status LEDs, 2 Nos sounder circuit for audiovisual devices and alphanumeric keypad for the field programming and control of the fire alarm system. The AFDAS shall have provision for GSM based dialer to send automated SMS to at least 5 pre-selected mobile numbers. The AFDAS shall also have provision to network on LAN & communicate to the graphical application on TCP/IP. The AFDAS shall have built in power supply, battery charger and battery backup for 24 hours normal operation. The panel shall be UL/LPCB/VDS approved and comply to NFPA-72/EN54 requirement. This also consists of supply execution of following items to make complete system functional as per RDSO specification. All required accessories to make the AFDAS fully functional are to be supplied by contractor. (Inspection by RDSO.)							
	A5006	320.00	Numbers	2988.30	956256.00	AT Par	956256.00	
6	Description:- Supply, Installation, Wiring, Testing & Commissioning Analogue Addressable Multi sensor Detector with inbuilt isolator/ isolator base having photo, fixed heat and ROR heat detection feature and 360-degree view LED and minimum 5 level of sensitivity setting, complying to RDSO/SPN/217/2021 Ver 3 or latest and RDSO TAN 3009 Ver 1.0 Dt. 10/12/2024. Operating temperature - 10 to 60 degree Celsius, humidity up to 85%, as per latest UL/LPHB/VDS approved/listed. (8 nos. per Auto Relay Hut) (Inspection by RDSO.)							
	A5007	32.00	Numbers	4104.31	131337.92	AT Par	131337.92	
7	Description:- Supply, Installation, Wiring, Testing & Commissioning of Analogue Addressable type & Resettable Manual Call Point (Red colour) with back box & with inbuilt fault isolator or alternate arrangement which shall isolate the MCP in case of short circuit. The MCP should have visual indication for its operation. Approval/listed - UL/ LPCB/ VDS and shall comply to RDSO/SPN/217/2021 Ver 3 and RDSO TAN 3009 Ver 1.0 Dt. 10/12/2024. (Inspection by RDSO.)							
	A5008	64.00	Numbers	6373.35	407894.40	AT Par	407894.40	
8	Description:- Supply, Installation, Wiring, Testing & Commissioning Isolator Modules as per RDSO Specification No. RDSO/SPN/217/2021 Ver 3 or latest and RDSO TAN 3009 Ver 1.0 Dt. 10/12/2024, suitable for Automatic fire detection & Alarm system(AFDAS).(Inspection of supply portion by RDSO)							
	A5009	32.00	Numbers	6446.93	206301.76	AT Par	206301.76	
9	Description:- Supply, Installation, Wiring, Testing & Commissioning of Control Module with backbox & inbuilt fault isolator to address sounder cum strobe as per RDSO Specification No. RDSO/SPN/217/2021 Ver 3 or latest and RDSO TAN 3009 Ver 1.0 Dt. 10/12/2024.suitable for Automatic fire detection & Alarm system(AFDAS).(Inspection of supply portion by RDSO)							
	A5010	3200.00	Metre	185.97	595104.00	AT Par	595104.00	

**NER HQ-S AND T/NORTH EASTERN RLY
TENDER DOCUMENT**

Tender No: NER_SnT_Proj_BSB_03_2026

Closing Date/Time: 07/07/2026 15:00

10	Description:- Supply, fixing, laying of Fire survival integrity cable 2x1.5 sq.mm un-armoured as per RDSO specification No. RDSO/SPN/217/2021, Ver.3 or latest and RDSO TAN 3009 Ver 1.0 Dt. 10/12/2024. This work involves supply, fixing & laying of cables inside PVC pipe/capping casing duly connecting all the detectors/ sensors, sensing cable, manual call points, control panel. This also include supply & fixing of PVC pipe/ casing capping of 25mm size of IS standards on wall/roof including supply of all accessories like bents, screw, nails etc. as directed by the Railway Site Engineer. (Inspection of supply portion by RDSO)						
11	A5011	32.00	Numbers	6977.15	223268.80	AT Par	223268.80
	Description:- Supply, Installation, Wiring, Testing & Commissioning of Audio-Visual Alarm (Electronic Hooter & Strobe) with back box controlled through addressable control panel. It shall be preferably flashing type of Red/White colour. The sound level shall be preferably adjustable type up to 90dB at a distance of 1 meter and shall be complying to RDSO/SPN/217/2021 Ver 3 and RDSO TAN 3009 Ver 1.0 Dt. 10/12/2024. (Inspection by RDSO.)						
12	A5012	32.00	System	249529.83	7984954.56	AT Par	7984954.56
	Description:- Supply, installation and testing and commissioning of Aspiration Type smoke Detection System complete. (As per RDSO Specification no. RDSO/SPN/217/2021ver 3.0 or latest), Inspection-RDSO.						
13	A5013	1000.00	Numbers	1012.37	1012370.00	AT Par	1012370.00
	Description:- Supply, Testing & Commissioning of PVC pipe having 25mm dia for aspiration detection supply portion (Number = 03 Meter length), Inspection-RDSO.						
14	A5014	64.00	Numbers	4600.23	294414.72	AT Par	294414.72
	Description:- Supply, installation & commissioning of CO2 Fire Extinguisher 4.5 Kg capacity confirming to IS 15685 with ISI mark provided with all fittings & accessories. Make: Safex, Bharat or similar.(Inspection of supply portion by Consignee.)						
15	A5015	360.00	Numbers	710.33	255718.80	AT Par	255718.80
	Description:- Fabrication, Supply and fixing of Retro reflective Signal Number Plates fabricated as per SEM-II Drawing No. 19- D10 (Sheet No. as applicable). All fixing accessories including clamps, nut, bolts etc. are to be supplied by contractor. (Inspection by Consignee.)						
16	A5016	250.00	Numbers	846.63	211657.50	AT Par	211657.50
	Description:- Supply and fixing of retro-reflective P/G/C/A markers/board/plate with complete fittings as per IRSEM App-II Drg. No. 19-D10. All material require for the job such as MS sheet, MS Angle ,Nut and bolts, paint & painting materials will be supplied by the contractor as per direction of site engineer.(Inspection by Consignee)						
17	A5017	1200.00	Numbers	637.29	764748.00	AT Par	764748.00
	Description:- Fabrication, supply and fixing of MS-C channel of minimum size 10mmx50mmx1200mm with suitable clamps as per drawing No. S&T/RE/78/2/76 and fitting to GI pipes with suitable clamps on girder bridges for sturdy fixing with girders. MS-C channels are to be fabricated as per site requirement.(Inspection by Consignee)						
18	A5018	32.00	Numbers	106478.89	3407324.48	AT Par	3407324.48
	Description:- Supply, installation & commissioning of active lightening arrester of class-A for building protection-as per Latest RDSO TAN 3006 ver 3.1,d. 30.06.2025 or latest. A non-resettable type counter shall also be supplied to count the number of lightening occurrences. The device shall be installed on top of the building on a GI mast and shall be connected to the earth pit through a copper tape of 25mm x 2mm or better. The copper tape shall not touch the building throughout and shall be connected to the earth electrode by exothermic welding. Class-A arrester should be fixed at least 3 meter above all the metallic structure including VHF antenna. Material shall be procured from RDSO recommended sources & to be supplied along with manufacturer test report. Supply & installation one Maintenance Free Earth as per RDSO Spec. No. RDSO/SPN/197 Ver. 1.0 or latest is also the part of schedule for that no extra cost will be paid.(Inspection RDSO.)						
19	A5019	2000.00	Numbers	3291.06	6582120.00	AT Par	6582120.00
	Description:- Supply and installation of Earth Electrode as per SEM-II Drawing No. 19-D5. It includes supply of GI pipe of 3m length. It includes connecting the earth electrode to the equipments which are required to be earthed including digging of earth pit 3 meter deep and fixing earth electrode pipe, casting of cement concrete enclosure with cover (cover as per NER drawing no. S&T/CONST/6.3/97). It includes supply, installation & fixing of 8 SWG wires as earth lead wires, supported on MS flat size 5mm x 40/32 mm, soldering and nut bolt both, one end of both earth lead wire and MS flat to earth electrode and other end to Location boxes, block equipments, power equipments, cable sheath, signals etc. as per site requirement and as per instructions given by engineer in-charge. (Earth Electrode to be inspected by RITES.)						
20	A5020	1650.00	Numbers	394.75	651337.50	AT Par	651337.50
	Description:- Supply of and Fixing of MS Flat size 32 mm x 5 mm as Earth lead on location boxes and interlocked LC gate. All required materials will be supply by the contractor.						
21	A5021	350.00	Numbers	1183.00	414050.00	AT Par	414050.00
	Description:- Supply of and Fixing of MS Flat size 32 mm x 5 mm as Earth lead on Signal Post. All required materials will be supply by the contractor. inspected by Consignee.)						

**NER HQ-S AND T/NORTH EASTERN RLY
TENDER DOCUMENT**

Tender No: NER_SnT_Proj_BSB_03_2026

Closing Date/Time: 07/07/2026 15:00

22	A5022	6.00	Numbers	30929.04	185574.24	AT Par	185574.24	
	Description:- Supply & Installation of Maintenance Free Earth as per RDSO Spec. No. RDSO/SPN/197 Ver. 1.0 or latest to achieve a resistance less than 1 ohm consisting of supply of following basic materials: (a) Copper bonded steel electrode of minimum 3.0 m long, minimum 17.0 mm dia with copper bonding thickness of minimum 250 microns and UL listed and marked = 1 no. (b) Earth enhancement material supplied in sealed bags of minimum 10 kg = 3 nos. (c) Copper strip of 150x25x6 mm, to terminate earth rod 1 no. (d) Copper strip of 300x25x6 mm (MEEB) = 1 no. (e) Copper strip of 150x25x6mm (SEEB) =1 no. (ii) Supply of 35 sq. mm multi strand single core PVC insulated copper cable as per IS: 694 for connecting main earth electrode to MEEB in the equipment room in duplicate. (minimum 10 meter) (iii) Supply of 16 sq. mm multi strand single core PVC insulated copper cable as per IS: 694 for connecting MEEB to SEEB and SPD to MEEB (minimum 10 meter) (iv) Supply of 10 sq. mm multi strand single core PVC insulated copper cable as per IS: 694 for connecting MEEB to SEEB and SPD to MEEB (minimum 10 meter) (iv) Supply of 10 sq. mm multi strand single core PVC insulated copper cable as per IS: 694 for connecting various equipments to SEEB. (v) Supply of copper lug sleeve for 3/16 cable. Installation of Maintenance Free Earth should include following: (i) Digging the earth to the required depth. (ii) Insertion I of electrode. (iii) Filling of earth enhancing compound (Approx.30 Kg) (iv) Provision of exothermic weld connections to copper tape of 25 mm x 6 mm x 150 mm to the earth electrodes. All material tools and features required for weld will be arranged by contractor. (v) This also includes CC cover 1.5 ft x 1.5 ft. 1 ft wall thickness 2 inch with cover of 3 inch thickness. (Inspection of supply portion by RDSO.)							
23	A5023	32.00	Per Goomty/IB H/ Auto Hut	229578.19	7346502.08	AT Par	7346502.08	
	Description:- Provision of Ring Earth for EI system and OFC/Telecom system which includes supply of all components of earthing & bonding system like earth electrode, earth enhancement material, earth pit, equi-potential earth busbar, connecting cables and tape/strips and other associated accessories in accordance with RDSOSpec.No.RDSO/SPN/197/2008 or latest (with a min. of 8 maintenance free earth electrodes for Signal equipments and min. 4 maintenance earth for Class-A along with fencing (With 50mmx5mm MS Flat and required channel (100mmx5mm) in interval of 2.5 mtr with provision of Gate with locking arrangement as per site in charge) & Painting of earthing diagram as replica of the ground on backside wall of relay room etc) to achieve less than 1 Ohms earth resistance for connecting EI equipments, relay racks, panel, power equipments as per Signal Engineering Practice. Diagram of ring earth should be supplied to Railway for Approval before execution. All related material as recommended by RDSO in Specn. No.RDSO/SPN /197/2008 or latest, will be supplied by the contractor. basic material for oneearth pit is given below: (a) Copper bonded steel electrode of3.0 m long, 17.2 mm dia with copper bonding thickness of minimum macrons and UL listed and marked = 1 no. (b) Earth enhancement material supplied in sealed bags of minimum 30kg © Copper strip of 150x25x6 mm, to terminate earth rod = 1 no. (d) Copper strip of 300x25x6 mm (MEEB) =1 no. (e) Copper strip of 150x25x6mm (SEEB) = 1 no. (f)Supply of 35 sq. mm multi strand single core PVC insulated copper cable as per IS: 694 for connecting main earth electrode to MEEB in the equipment room in duplicate.(minimum 10 meter) (g) Supply of 16 sq. mm multi strand single core PVC insulated copper cable as per IS: 694 for connecting MEEB to SEEB and SPD to MEEB (minimum 10meter) (h) Supply of 10 sq. mm multi strand single core PVC insulated copper cable as per IS: 694 for connecting various equipments to SEEB (i) Supply of copper lug sleeve for 3/16cable Note:Earthing arrangement for EI must be as per RDSO guidelines issued by RDSO vide RDSO TAN 3006 ver 3.1 dt. 30.06.2025 or latest. Inspection: RDSO							
24	A5024	3400.00	Numbers	409.18	1391212.00	AT Par	1391212.00	
	Description:- Fabrication, Supply and Fixing of Cable Route Marker made with reinforced concrete in the ratio 1:3:6, engraved with "NER-S&T" on the top portion on both the side duly painted. Cable Route Markers are to be made and grouted as per IRSEM appendix-II Drg No. 15-D1.(drawing attached). (Inspection by consignee.)							
25	A5025	68.00	Numbers	213116.98	14491954.64	AT Par	14491954.64	
	Description:- Supply, Installation, Wiring, Testing & Commissioning of Modular Power Supply Arrangement for VDU (42" -85") and Industrial PC (Embedded PC) with Input and Output Redundancy Arrangement and Hot Pluggable Modules according to RDSO letter No. RDSO-SIGOEI(GEN)/1/2020 dated 11/07/2022 of Gallant make or similar and consisting of followings: 1. Input O-Ring Diode Module with Potential Free-1 No. contacts (PFC) for two 110VDC Sources from IPS and Single 110VDC bus. 2. Isolated Inverters (Master/Slave) - 2 Nos. Input: 110VDC, Output: 120VAC/220VAC 500VA 3. Isolated DC-DC Converters-2 Nos. Input: 110VDC, Output:24VDC/10A. 4. 3U SS Rack with back Panel Mother Board/ Front Panel Power Connectors Inverter Auto Change Over Switch and all required over Switch and all required protection circuits as per RDSO specification. (Inspection by RITES.)							
26	A5026	86.00	Numbers	2830.97	243463.42	AT Par	243463.42	
	Description:- Supply, fixing, wiring, testing & commissioning of Electronic Hooter Unit (24V DC/110V AC operated) of approved design/make along with 2 nos. of outdoor speaker of 15W 8 ohms to warn road users during operation gate. (Inspection by Consignee)							
	A5027	32.00	Numbers	368808.12	11801859.84	AT Par	11801859.84	

**NER HQ-S AND T/NORTH EASTERN RLY
TENDER DOCUMENT**

Tender No: NER_SnT_Proj_BSB_03_2026

Closing Date/Time: 07/07/2026 15:00

27	Description:- Supply, installation, testing and commissioning of Micro Processor based Data Logger System with 512 digital inputs and 32 analog inputs with protocol converter as per RDSO Spec. No. IRS (S) 99/2006 (Amnd. 3) or latest. It includes supply of all the items required for complete indoor relay room wiring from data logger to relay rack tag blocks, drawing/extension of power supply up to Data Logger. It includes relay room door lock checking arrangement, commercial power supply monitoring arrangement & monitoring of DG sets, ELD, IPS, UFSBI, ELD, MSDAC etc., interlinking and networking of Data logger, interfacing with EI. It also includes installation of MODEM and other interfacing cards, if required for networking of Data Logger. Item includes networking of data logger with divisional centralized datalogger system. Note: 1. Total numbers of relays and other signalling functions/gears required to be wired as per list circulated vide RDSO Letter No. STS/E/Data logger dtd.12.09.2011 or latest guidelines. 2. Railway will provide fibre connectivity at the location. The interfacing connectivity requirement with the adjacent station/HUT Data Logger (Efftronics make) shall be provided by the contractor free of cost. (Inspection by RDSO)							
28	A5028	38.00	Numbers	7339.20	278889.60	AT Par	278889.60	
	Description:- Supply installation, wiring, testing & commissioning of Two wire Talk-Back System (Signal Post Telephone) consisting of one master and one slave of standard make to work in 25KV RE area (Operating on 24v/110V) up to distance of 10Kms. On Quad cable without any interference/noise.(Inspection by Consignee)							
29	A5029	66.00	Numbers	7595.30	501289.80	AT Par	501289.80	
	Description:- Supply and installation of 19" 9 U covered Rack as per direction of engineer. Make Tata Tronx/D-Link/Comrack or equivalent. Inspection- RITES							
30	A5030	160.00	Numbers	445.67	71307.20	AT Par	71307.20	
	Description:- Supply and fixing of P/G/C markers with complete fittings. All material require for the job such as MS sheet, MS Angle ,Nut and bolts, paint & painting materials will be supplied by the contractor as per direction of site engineer.							
31	A5031	200.00	cum	3246.55	649310.00	AT Par	649310.00	
	Description:- Cement concrete work for miscellaneous items i n the ratio 1:3:6. Item includes excavation ,ramming, curing and plastering with cement sand mixture (aggregate not exceeding 3.8 cm).Aggregate ,cement a n d t o b e supplied by contractor. Note This Items used for at Bridges/culvert/station area etc. as per direction of site engineer.							
32	A5032	4000.00	Metre	3236.31	12945240.00	AT Par	12945240.00	
	Description:- Protective works at Girder Bridges as per IRSEM Drg. No. 15-D6 Arrangement for fixing of steel trough is indicated in drg. No Drg. No. 15-D6. Separate troughs shall be mounted for laying of OFC and Quad/PIJF cables.(IRSEM at Drawing 15 -D6. attached)							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A6- (Execution Items)							276461001.35	Above/ Below/P ar
1	A6001	360.00	Numbers	15908.75	5727150.00	AT Par	5727150.00	
	Description:- Casting, concreting and curing of foundation for Main Signal Post in the ratio of 1:3:6 as per IRSEM Drg. No. 19-D3, using standard size of foundation/galvanized anchor bolts complete, required for erection of colour light signal post. Anchor bolts complete should comply with the IRSEM Drg. No. 19-D3. Item includes excavation, ramming of CC using vibrator, curing and plastering with 1:4 cement-sand mixture (aggregate will not exceed 3.8 cm). Aggregate, cement, sand and holding down bolts will be supplied by contractor. Any machines & tools, if required for execution of this item, will be arranged/provided by contractor.							
2	A6002	360.00	Numbers	6924.44	2492798.40	AT Par	2492798.40	
	Description:- Erection of CLS Post with base and signal unit on top or on Offset Bracket including erection of auxiliary signals like 'A' marker, Calling On, shunt signal if any. It includes fixing of all LEDs and wiring of complete signal including route and auxiliary signals, if any. It includes fixing of front and back staging, ladder and guards, signal name plates / boards, with contractor's own brackets and fixing materials. The work shall be done as per instructions of Rly engineer at site. It also includes provision & fixing of maintenance platform as per design given by Engineer -In- Charge at site. The Item includes cutting of Signal post if required by Site In charge.							
3	A6003	43.00	Numbers	1309.80	56321.40	AT Par	56321.40	
	Description:- Fixing of Junction type Route Indicator on top of signal post and complete wiring, 1-Way/ 2-Way/ 3-Way/ 4-Way/ 5- Way/ 6- way/ Theater type.							
4	A6004	1600.00	Numbers	14455.17	23128272.00	AT Par	23128272.00	

**NER HQ-S AND T/NORTH EASTERN RLY
TENDER DOCUMENT**

Tender No: NER_SnT_Proj_BSB_03_2026

Closing Date/Time: 07/07/2026 15:00

	Description:- Excavation, casting, curing of foundation and installation & erection of Apparatus case Full (IRSEM Appendix-II Drawing No.19-D1) with contractor's own frame, anchor bolts & nuts, cement and other material in the ratio 1:3:6 s foundation drawing of Railway. 'E' type lock to be supplied and installed with App. case. This includes filling of location foundations with river bed sand and plastering on top with a mixture of 1:4 of cement and sand, ramming of loose soil around foundation and disposal of loose dugged soil from site. It covers fixing of lamp holder, switch and lamp etc. in Apparatus Case.						
5	A6005	1600.00	Numbers	802.89	1284624.00	AT Par	1284624.00
	Description:- Painting of two coats of Enamel paint over one coat of Red Oxide primer after scrapping and cleaning of the surface of Full size Apparatus Case. Paint to be of reputed make Asian/Delux/Berger or similar. Painting of Apparatus Cases from inside and outside to be done by Silver colour.						
6	A6006	360.00	Numbers	1076.63	387586.80	AT Par	387586.80
	Description:- Painting of two coats of Enamel paint over one coat of Red Oxide primer after scrapping and cleaning of the surface of Main Signal post, base, unit and complete fittings of Signal. Paint to be of reputed make Asian/Dulux/Berger or similar.						
7	A6007	900.00	Numbers	5272.70	4745430.00	AT Par	4745430.00
	Description:- Fabrication and fixing of phenolic laminated sheet of grade P3, minimum 10 mm thickness, as per Apparatus case diagram/plan, in full size location box (full size apparatus case) by providing all fixtures like ARA/Disconnect terminals, fuse blocks, fuses, relays on square bars etc. including fixing of PVC coated string rods at the back side for cable support with contractor's own material like iron angle, nuts, bolts etc. The iron angle for fixing shall be minimum 3 mm thick. This also includes fixing of teak wood shelf minimum 25 mm thick for holding track circuit equipments. The work shall be done as per instructions of Rly engineer at site.						
8	A6008	3400.00	Numbers	21.32	72488.00	AT Par	72488.00
	Description:- Fixing of ARA(M-6) Terminals /Screw less connectors / modular disconnect terminal blocks and fuse blocks on phenolic laminated sheets and fixing by stainless steel/brass nuts & bolts. This includes provision of two additional holes on the board on either side for cable conductor entry. The work shall be carried out a per instructions of railway Engineer in-charge. (Supply of all above terminals has been covered separately)						
9	A6009	180000.00	Numbers	17.39	3130200.00	AT Par	3130200.00
	Description:- Termination of Outdoor Cables (Main Cables /tail cables) at ARA/Disconnect type terminals provided in Apparatus Cases, Cable termination rack in relay room, station building etc. The item includes dressing of cables and wires with dressing threads as per standard practice. All material required for this item will be supplied by contractor. The outdoor cable shall be terminated in Relay Room, ASM Room etc. under supervision and instructions issued by Engr. in-charge of the work.						
10	A6010	3200.00	Numbers	100.76	322432.00	AT Par	322432.00
	Description:- Lettering and Numbering of Signals, TLJB, Mushroom housing, Apparatus Cases, Point Machine, Glued/Block Joints etc. (Each item to be taken as one unit). Work is to be carried out as per standard practice.						
11	A6011	32.00	Station	11103.44	355310.08	AT Par	355310.08
	Description:- Lettering and numbering of detail and description writing of particulars of terminations and equipments on relay rack, relays, cable termination rack, battery and power equipments, IPS, operating panel, axle counter, inside location boxes as per location chart etc. constituting entire system with contractor's own paint and writing material (Asian make paint to be used). This includes supply and fixing of Teflon strip 3 mm thick and 25 mm wide for each row of relays and cable termination. This work shall be done as per existing practice of the Railway.						
12	A6012	255000.00	Metre	517.25	131898750.00	AT Par	131898750.00
	Description:- Horizontal direction drilling (HDD)/ Trenchless digging/ machine drilling without damage to surface road/ track without laying/insertion of HDPE pipe along with the coupler required. The bore width should be of 120 mm and shall be done at the depth of minimum 2000 mm from the ground level. The ground level shall be considered ignoring the bank height of the bank of the road/ track. Contactor shall provide all material required for work and adequate nos. of labours for proper laying of cables into the duct. Cable shall be laid cautiously so that it should not get damage due to rough handling & pressure on cable. Note: laying of signalling cable/ quad cable/ telecom duct will be paid separately under different scheduled items.						
13	A6013	1000.00	Metre	150.36	150360.00	AT Par	150360.00
	Description:- Laying and fixing of Medium class GI pipes 100 mm dia (4.5 mm thickness) as per IS 1239 (Part 1) 2004 or latest with coupling on culverts/bridges, perforated at a distance of 20 cm or less with 10 mm dia hole, or at any other locations as decided by Site Engineer. The GI pipe is to be filled with chattered compound. It includes supply of all material required for fixing arrangement. Contractor will also supply flexible/corrugated HDPE pipe at the end of GI pipe to protect the cables from sharp edges and sudden bends. The laying and fixing to be done as per RDSO drawings no. SDO/cable laying/011 and SDO/cable laying/012, issued vide RDSO document no. RDSO/SI/G/2010 Version 1.1 dated 04.02.2014, or latest.						

**NER HQ-S AND T/NORTH EASTERN RLY
TENDER DOCUMENT**

Tender No: NER_SnT_Proj_BSB_03_2026

Closing Date/Time: 07/07/2026 15:00

14	A6014	200000.00	Metre	44.80	8960000.00	AT Par	8960000.00	
	Description:- "Excavation of cable Trench of 120cms depth and 30cms wide in all kinds of soil within station limit & block section both for main and tail cables as per cable route chart to be given by engineer at site and its refilling with the same excavated soft soil. Note:- Depth of the cable duct to be measured from the hard soil level of the ground."							
15	A6015	5000.00	Metre	63.03	315150.00	AT Par	315150.00	
	Description:- Excavation of cable trench of 100 cm depth and 30cm width at level /track crossing as per cable route chart to be given by Engineer at site and its refill is same excavated soil consolidating by ramming to the level of 20cm above the ground level over the trench as per specification							
16	A6016	1000.00	Metre	187.06	187060.00	AT Par	187060.00	
	Description:- Cutting of all types of platforms/ road crossing and trenching and excavation to a width and depth of 300 mm x 300 mm, laying of DWC/HDPE/GI pipe in the trench and refilling and concreting it afterwards as per original condition. In hard rocky ground area, cables will be laid normally on layer of soft earth of at least 5cm thickness previously deposited at bottom of the trench. The cutting to be filled and finished with cement/concrete, as per the RDSO drawing no. SDO/Cable laying/008, issued vide RDSO document no. RDSO/SI/G/2010 Version 1.1 dated 04.02.2014 or latest.							
17	A6017	600.00	Numbers	1499.84	899904.00	AT Par	899904.00	
	Description:- Installation of Thermo shrink jointing kit as per RDSO specn No. IRS: TC 77-2012 (Rev 3.0) with (Amdt-1 to 3) or latest suitable for 6 quad /jelly filled cables for straight through/derivation joints from OEM trained staff as per procedure specified by RDSO and standard practices of Railway including excavation of pit for joint.							
18	A6018	19.00	Job	5911.32	112315.08	AT Par	112315.08	
	Description:- Breaking of RCC concrete in Relay Room/ Panel Room at station for drawing various sizes of cables.							
19	A6019	721.00	Kilometre	7673.24	5532406.04	AT Par	5532406.04	
	Description:- Laying of HDPE duct 40/33 mm as per the approved cable route plan in the excavated trenches/HDD/ other protected works/RCC channel etc. including all accessories like end caps, collars, bends, couplers etc. The ends of the duct to be sealed with end plugs till OFC blowing is done. Note: The laying of OFC cable independently or along with Quad cable/PIJF cable in the same trench shall be governed by the RDSO drawings no. RDSO/TCDO/COP-6(a) and RDSO/TCDO/COP-8(a) respectively, issued vide Chapter-XIII of the Telecomm Manual.							
20	A6020	721.00	Kilometre	10900.69	7859397.49	AT Par	7859397.49	
	Description:- Blowing/drawing of OFC cable in the HDPE pipe duct and protective work already provided in the trench. The cable shall be laid only after the successful completion of the DIT (Duct Integrity test). The DIT should be certified by the Railway engineer at site. All the equipments/machinery required shall be arranged by the contractor.							
21	A6021	375.00	Numbers	7367.39	2762771.25	AT Par	2762771.25	
	Description:- Construction of OFC jointing pit of size 1mx1mx0.6m, using bricks, sand and cement in the ratio 1:3 including excavation of pit for joint enclosure. The thickness of the wall shall be 120 mm. The top cover shall be of concrete of thickness 75 mm with two iron handles on top of it. The pit shall be covered with sand after putting the joint enclosure. All construction material to be supplied by contractor.							
22	A6022	26546.00	CORE	105.86	2810159.56	AT Par	2810159.56	
	Description:- Splicing of 48 core optic fibre cable and making the splicing joint with contractors own machine and tools. Joint should be prepared in such a way that the top of the enclosure should be at a depth of minimum 1.2 meter and the enclosure should be covered with soft soil and bricks. Splice loss of each fibre should be less than 0.05 dB.							
23	A6023	2800.00	Kilometre	8053.02	22548456.00	AT Par	22548456.00	
	Description:- Laying of S&T Cables of various cores/ pairs/ quads in trenches/ GI pipes/ RCC pipes/ DWC pipes/ HDD portion etc. as per the site requirement and as per approved cable route plan. This also includes laying of cables in track crossings & road crossings. (Cables will be meggered before and after its laying by contractor under supervision of Railway Representative and contractor shall submit the meggering report of each testing). Length of the cable laid includes the length of the cable coiled for termination purposes.							
24	A6024	30.00	Man-Days	3870.15	116104.50	AT Par	116104.50	
	Description:- Training of Sr. Engineers/ Engineers/ Technicians/Jr. Engineers regarding installation, testing, commissioning maintenance, repairing and troubleshooting of EI, MSDAC and other equipments. (Hard and Soft Copies of Training Material/ Course Modules on each subject shall given to Each Participant).							
	A6025	1500.00	Numbers	459.60	689400.00	AT Par	689400.00	

**NER HQ-S AND T/NORTH EASTERN RLY
TENDER DOCUMENT**

Tender No: NER_SnT_Proj_BSB_03_2026

Closing Date/Time: 07/07/2026 15:00

25	Description:- Fixing of Q series relay base plate & relay, laying, bunching, lacing & dressing PVC indoor cable/ flexible wire and termination of cable/flexible wire on tag block/ base plates & soldering. This includes fuse wiring, bus bar looping etc. required for keeping installation ready with circuit wiring work in locations/station. PVC wire, ARA terminal, Relays with base, resistors, condensers shall be supplied by Railways. All other material required for the purpose(LUGs etc). The work shall be done as per approved plan, extant practice on NER & the instruction of Rly. Engineer at site.						
26	A6026	22.00	Numbers	10777.44	237103.68	AT Par	237103.68
26	Description:- Dismantling and releasing of existing Electrically operated L C gate/Mechanically operated LC gate and all other associated fittings. All the released material will be transported to the SSE/Consignee depot.						
27	A6027	250.00	Numbers	1144.47	286117.50	AT Par	286117.50
27	Description:- Dismantling and releasing of existing Location boxes/Apparatus cases/Jn boxes and all other associated fittings. All the released material will be transported to the SSE/Consignee depot.						
28	A6028	110.00	Numbers	1800.98	198107.80	AT Par	198107.80
28	Description:- Dismantling and releasing of existing Signals and all other associated fittings. All the released material will be transported to the SSE/Consignee depot.						
29	A6029	32.00	Station	208690.81	6678105.92	AT Par	6678105.92
29	Description:- (a). Design, preparation and supply of the following Technical documents: (i). Installation, Testing, Commissioning and Maintenance manuals. (ii). Functioning and System overview manuals (b). Design, preparation and supply of the following the following completion documents: (i). Application Logic circuits (ii). VDU/CCIP diagram (iii). Interface Circuit/Wiring diagrams consisting of Relay contact analysis chart, Relay disposition chart, Relay contact to contact wire list chart, VDU/CCIP cable termination chart, Power supply diagram, Electronic signalling equipment and Power supply layout diagram, Relay rack and Cable termination rack layout diagram, Relay rack and Cable termination rack particulars, Fuse, Resistors, Condensers etc. particulars, Details of Analog and digital inputs to be supplied to Data logger, Wiring diagrams for SSDAC/ HASSDAC/MSDAC etc. (iv). Cable Route plan with overlaid Location Boxes placement as per standard practices of NER. (v). Cable Core plan with overlaid Location box placement (vi). Location huts/Gate Lodge wiring diagrams. (vii). Location boxes wiring diagrams (viii). Track circuit bonding plan (ix). Earthing particulars plan (x). Station working rule diagram (SWRD) (xi). Station working rule (SWR) (xii). Selection table/ Route control chart (xiii). panel diagram (gate and station).(xiv). Location wiring diagram and termination chart. Note: All the above completion documents should be supplied as follows: (i). Four sets Printout of documents as per requirement of site in-charge initially for approval and commencement of work. (ii). One set in soft copy (in editable AUTOCAD format) in Pen drive. (iii). One set of original tracings. (iv). Six sets of final 'As Made' completion plans/diagrams in proper bounded form.						
30	A6030	20000.00	Metre	6.41	128200.00	AT Par	128200.00
30	Description:- Placing of DWC HDPE (below 200 mm (OD))/ Both half cut pieces DWC pipe / RCC/GI pipes along with collars in trenches at places near track and road, crossings, platform cutting etc.						
31	A6031	50000.00	Metre	57.28	2864000.00	AT Par	2864000.00
31	Description:- Cutting of DWC pipe, of various size, into 2 No. of split DWC pipe - includes transportation and loading / unloading required for cutting of DWC pipe as advised by supervisor in charge and LAYING OF DWC PIPE (200 MM) WITH SOCKET COUPLER /Both half cut pieces of DWC pipe in TRENCHES AS PER DIRECTION OF SITE ENGINEER.						
32	A6032	1810.00	Numbers	132.26	239390.60	AT Par	239390.60
32	Description:- Fitting of LED Signal with all accessories and its wiring as per direction of site engineer. All material required for fitting and wiring except LED signals and PVC wire shall be supplied by contractor.						
33	A6033	450.00	Set	444.78	200151.00	AT Par	200151.00
33	Description:- Installation of lever lock DW Type fitted with Crank Handle/ E Type lock/ KLCR lock relay assembly as per technical specification.						
34	A6034	107.00	Set	6165.75	659735.25	AT Par	659735.25
34	Description:- Installation and commissioning of Fibre Distribution Management System (FDMS) for 4 8 fibre complete with all accessories with patch cord & pigtail as per TEC spec. with latest amendment. This include supply of installation accessories as per technical specification.						
35	A6035	170.00	Kilometre	760.70	129319.00	AT Par	129319.00
35	Description:- Final location survey of cable route and final preparation of route plan as per code of practice for installation & commissioning of optic fiber & Quad cable system (STT/FO/1 issued by RDSO, Lucknow) including supply of final cable route plan giving all necessary details as per following. (i). Two sets initially for approval and commencement of work on A3 size paper. (ii). One set in soft copy (in editable AUTOCAD format) in Pen drive. (iii). One set of original tracings. (iv). Five sets of final 'As Made' completion plans/diagrams on white bond paper of A3 size in proper bounded form.						

**NER HQ-S AND T/NORTH EASTERN RLY
TENDER DOCUMENT**

Tender No: NER_SnT_Proj_BSB_03_2026

Closing Date/Time: 07/07/2026 15:00

36	A6036	170000.00	Kilometre	41.17	6998900.00	AT Par	6998900.00	
	Description:- Transportation of less heavy material and man power, supply and running of 1 MUV to the sites of work as per requirement and direction of engineer in-charge of work along with driver. The rate includes all tax, license fee, road permit, driver wages, fuel, repair and maintenance cost etc.							
37	A6037	170000.00	Kilometre	64.34	10937800.00	AT Par	10937800.00	
	Description:- Loading, Transportation/Carriage and Unloading of various S&T material by a 9 MT truck, from/to the consignee depot to/from various locations, as decided by the site incharge of work of Railway. The rate includes all tax, license fee, road permit, driver wages, fuel, repair and maintenance cost etc.							
38	A6038	10.00	Numbers	27328.40	273284.00	AT Par	273284.00	
	Description:- Installation, wiring, testing and commissioning of Micro Processor based Remote Terminal Unit (RTU) with 128 digital input and 16 analog input as per RDSO Spec. No. IRS (S) 99/2006 (Amdt. 3) or latest. It includes supply of all the items required for complete indoor relay room wiring from RTU to relay rack tag blocks, drawing/extension of power supply up to RTU. It includes supply of relay room door lock checking arrangement, commercial power supply monitoring arrangement & monitoring of DG sets, ELDS, IPS, interlinking and networking of RTU. It also includes installation of MODEM and other interfacing cards, if required for networking of RTU. Note: Total numbers of relays and other signalling functions/gears required to be wired as per list circulated vide RDSO Letter No. STS/E/Data logger dtd.12.09.2011 or latest guidelines.							
39	A6039	500.00	Metre	7.28	3640.00	AT Par	3640.00	
	Description:- Laying of GI/HDPE Pipe for passing the cables at level/track crossing and platform etc. Only GI/HDPE pipe and socket will supplied by railway. Other activity will be done by contractor as per tech. specification.							
40	Please see Item Breakup for details.				10982400.00	AT Par	10982400.00	
	Description:- Installation of Terminal board for terminating main/tail cable including supply of terminal board. Note-(1).Termination board of hylem sheet IS:2036 grade P-4 size 6 mm thick. (2).Angle Iron Size 40mmX40mmX5mm at station.(3)Angle Iron size 25mmX25mmX3mm suit the size of cases ie. Single case, Half Case, 50 way JB and as for requirements							
41	A6041	2500.00	Man-Days	579.00	1447500.00	AT Par	1447500.00	
	Description:- Provision of Skilled worker for maintaining records etc. for progress of day to day assisting in preparing detail paper works etc (For 'B' class area) as specified by ministry of labor and employment ,government of India ,office of chief labor commissioner's case No 1/6(1)/2025-LS-II dt.30.03.26 .							
42	A6042	6000.00	Metre	1275.40	7652400.00	AT Par	7652400.00	
	Description:- Horizontal Boring/Manual moling without damage to surface road/track for laying/insertion of DWC/GI/HDPE pipe.The bore shall be done at the depth of minimum 1400 mm from the ground level. The ground level shall be considered ignoring the bank height of the bank of the road/track. Contractor shall provide all materials required for work and adequate no. of labours for proper laying of cables into the bore. Cables shall be laid cautiously so that these should not get damage due to rough handling and pressure on cable. Payment of boring shall be made only after laying of DWC/HDPE/GI pipe in the bore.(Note:- DWC/HDPE/GI Pipe supply is not covered under this item.).Laying of cable in bore will be paid under item cable laying.							

3. ITEM BREAKUP

Schedule		Schedule A6- (Execution Items)					
Item- 40		Installation of Terminal board for terminating main/tail cable including supply of terminal board. Note-(1).Termination board of hylem sheet IS:2036 grade P-4 size 6 mm thick.(2).Angle Iron Size 40mmX40mmX5mm at station.(3)Angle Iron size 25mmX25mmX3mm suit the size of cases ie. Single case, Half Case, 50 way JB and as for requirements					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount	
1	1	Execution	Square Foot	16000.00	135.18	2162880.00	
2	2	Supply	Square Foot	16000.00	551.22	8819520.00	
					Total	10982400.00	

4. ELIGIBILITY CONDITIONS

Important : All documents uploaded and remarks / confirmation entered by the bidders against any eligibility condition shall be opened as part of technical bid only

5. COMPLIANCE

**NER HQ-S AND T/NORTH EASTERN RLY
TENDER DOCUMENT**

Tender No: NER_SnT_Proj_BSB_03_2026

Closing Date/Time: 07/07/2026 15:00

Important All documents uploaded and remarks / confirmation entered by the bidders against any : compliance condition shall be opened as part of technical bid only.

Commercial-Compliance

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)

General Instructions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Tenderer(s) on award of contract will have to enter into agreement with Railway in format of above mentioned original tender documents. Tenderer(s) shall not have any right/claim to insist on signing of contract agreements in format on which tender document were forwarded by him on e-tendering website.	No	No	Not Allowed
2	If during process of tender finalization, it is detected that tenderer has submitted tender documents after making any changes / additions / deletions in the tender documents on e-tendering website, then, the earnest money deposited by the tenderer shall be forfeited by the Railway. Further, if after award of contract, it is detected that tenderer has submitted tender documents after making any changes/additions/deletions in the tender documents etendering website then Railway will take action to remove the contract from the work in terms of clause 62 of GCC 2022 and initiate such further legal action against contractor as it considered necessary.	No	No	Not Allowed
3	False/Incomplete statement: Any statement/declaration made by the Tenderer, if proved wrong or false or incomplete or such as to withhold any information relevant to the award of the tender, at any stage of the tender or in the event of his tender having been accepted at any stage of the contract, shall tender his/their tender(s)/contractors) liable to be cancelled/rescinded, in addition to the following: (i) If such statement is found at the stage of tender his total earnest money shall be forfeited. (ii) In case such a statement is found at the contract stage rights available to the Railways under clause 62 of the GCC-2022 shall be applicable.	No	No	Not Allowed

Special Conditions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Rates of Schedules A1, A2, A3, A4, A5 and A6 are to be mentioned % Above/At Par/Below. Item wise rates for different schedule items shall not be acceptable and if item wise rates are quoted, the tender will be summarily rejected. Proforma for Quoting Rates mentioned in Annexure-K in Financial Bid should also be filled up in both figure & words.	No	No	Not Allowed
2	Details of Cards/ Modules/ Sub-Assemblies of EI, OC/EI and spares of EI & MSDAC are to be given in the format mentioned in Annexure-A,B, C, D ,E,F & G in Financial Bid only.	No	No	Not Allowed
3	The details breakup of items quoted as per schedule are to be uploaded with the Financia Bid only and not with the Technical Bid. Any attempt to upload the financial bid/rates/cost along the technical bid will cause the summarily rejection of the offer.	No	No	Not Allowed
4	Price Variation Clause (PVC) shall not be applicable for this tender.	No	No	Not Allowed

Technical-Compliances

**NER HQ-S AND T/NORTH EASTERN RLY
TENDER DOCUMENT**

Tender No: NER_SnT_Proj_BSB_03_2026

Closing Date/Time: 07/07/2026 15:00

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Tender Form :- First Sheet & Second Sheet of Tender Form: Tender Forms shall embody the contents of the contract documents either directly or by reference and shall be as per specimen form, Annexure-I of ITT of GCC-2022 and as mentioned in Tender Documents. (Note: Proposal without signed First sheet and second sheet on prescribed proforma will be summarily rejected.)	No	No	Allowed (Mandatory)
2	Bid Security : Through e-Payment or Bank Guarantee. The Bid Security shall be deposited either in cash through e-payment gateway or submitted as Bank Guarantee bond from a scheduled commercial bank of India or as mentioned in tender documents. The Bank Guarantee bond shall be as per Annexure-1.1 of Tender Documents and shall be valid for a period of 90 days beyond the bid validity period. (Note: Proposal without Bid Security will be summarily rejected.)	No	No	Allowed (Mandatory)
3	Bid Capacity : Tenderer(s) must submit Bid Capacity according to stipulations mentioned in Annexure-22 & supporting details in Performa mentioned in Annexure-16 & Annexure-17 of Tender Documents as per Para 10.3 of Tender Form (Second Sheet) of Annexure I of ITT of GCC-2022. (Non submission of Bid Capacity along with Technical Bid will cause summarily rejection of offer.)	No	No	Allowed (Mandatory)
4	Constitution of Firm : The Tenderer(s) shall clearly specify whether the tender is submitted on his own (Proprietary Firm) or on behalf of a Partnership Firm / Company / Joint Venture (JV) /Registered Society/ Registered Trust/ HUF etc. and submit details in Proforma mentioned in Annexure-4 of Tender Documents. {Ref: Para 14 Tender form (Second Sheet) of GCC-2022)}	No	No	Allowed (Mandatory)
5	Declaration Form regarding familiarization with site etc.: The tenderer shall furnish Declaration in the proforma given in this Annexure-8 that he has visited the site of work and familiarized himself fully with the conditions at site.	No	No	Allowed (Mandatory)
6	List of Plant & Machinery available on hand and proposed to be inducted and hired for the tendered work shall be submitted in the Proforma mentioned in Annexure-9 of Tender Documents as per Para 11 of Second Sheet of annexure-I of GCC-2022. (Note: Non compliance with this condition set forth therein is liable to result in the tender being rejected.)	No	No	Allowed (Mandatory)
7	List of personnel / organization on hand and proposed to be engaged for the tendered work shall be submitted in the Performa mentioned in Annexure-10 of Tender Documents as per Para 11 of Second Sheet of annexure-I of GCC-2022. Note: Non compliance with this condition set forth therein is liable to result in the tender being rejected.	No	No	Allowed (Mandatory)
8	Bank Detail/ RTGS	No	No	Allowed (Optional)
9	Annexure-14.1 to 14.14 (Only to show that contractor is eligible to participate in BID) As applicable in Contractor's case. (Proprietary Firm or on behalf of a Partnership Firm / Company /Joint Venture (JV) / Registered Society/Registered Trust/HUF etc.)	No	No	Allowed (Optional)
10	Certificate of Information regarding Employment / Partnership etc. of Retired Railway Employees with the tenderer. This Annexure-15 is mandatory otherwise offer shall be considered as incomplete and will be rejected summarily.	No	No	Allowed (Mandatory)
11	Annexure-16 -List of Existing commitment and balance amount of ongoing works with the Tenderer.	No	No	Allowed (Mandatory)
12	Annexure-17-Break up of Maximum value of Construction work executed and payment received in any one financial in any one of the previous three financial years or the current financial year (up to date of inviting tender)	No	No	Allowed (Mandatory)

**NER HQ-S AND T/NORTH EASTERN RLY
TENDER DOCUMENT**

Tender No: NER_SnT_Proj_BSB_03_2026

Closing Date/Time: 07/07/2026 15:00

13	Annexure-18-Annual Contractual Turnover Data for the Previous 3-4 Years: The tenderers shall submit requisite information as per this Annexure along with copies of Audited Balance Sheets duly certified by the Chartered Accountant/ Certificate from Chartered Accountant duly supported by Audited Balance Sheet for calculating average annual contractual turnover to decide Financial Eligibility Criteria	No	No	Allowed (Mandatory)
14	Technical Eligibility Criteria: Certificate & documents in support of successfully completed or substantially completed similar nature of work as per Technical Eligibility Criteria mentioned in Para 10 of second sheet of annexure-I of GCC2022 & Tender Documents. (Details are to be submitted in Proforma mentioned in Annexure-11 & Annexure -13 of Tender Documents.) (Non submission of certificates & documents in support of Technical Eligibility Criteria along with Technical Bid will cause summarily rejection of offer.)	No	No	Allowed (Mandatory)
15	Annexure-2.2:-To be submitted in standard proforma certificate to be downloaded from IREPS Website by the each member of a partnership Firm /Joint Venture (JV) /Hindu Undivided Family(HUF) /Limited Liability Partnership (LLP) etc (Ref: Para 6.1 of ITT, Annexure-V & V(A) of GCC-2022)	No	No	Allowed (Mandatory)
16	CHECKLIST FOR UPLOADING DOCUMENTS FOR TECHNICAL BID(As Mentioned in Tender Document)	No	No	Allowed (Optional)

Undertakings

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	JPO:- North Eastern Railway. NER/S&T JPO No.01/2024 Sub:- Joint Procedure Order for undertaking Earth Work/Digging work in the vicinity of Signaling, Electrical and Telecommunication Cables etc. Ref:- Railway Board L.No.2021/'lelel5(2)13-Pt-I (3425647) dated 12.06.2023. This JPO shall be applicable to Construction Department, Open line, RVNL, IRCON, RITES. RE, State/Central Government Agencies/Organizations, Private Parties working in North- Eastern Railway Jurisdiction for Earth work/digging work in the vicinity of Signaling, Electrical & Telecommunication cables. This JPO shall supersede earlier instructions issued (if any) for NER in connection with undertaking Earth Work/Digging work in the vicinity of Signaling, Electrical and Telecommunication Cables etc.	No	No	Not Allowed
1.1	General	No	No	Not Allowed
1.1.1	For all new works, cable shifting should be a mandatory part of DPR and Estimate. For ongoing works, if required, separate work for cable shifting maybe sanctioned through contingency /supplementary /revised estimate, where provision does not exist. Cost of shifting of cables may be charged to sanctioned estimate and Executing Agency shall be conveyed charging of the same.	No	No	Not Allowed
1.1.2	Necessary utility mapping/ tracing shall be undertaken by Executive Department (Construction, Project, RVNL, IRCON, RE & Gati Shakti units etc.) to cater the requirement of project. All cables/utilities coming in way shall be shifted/protected before starting any excavation work.	No	No	Not Allowed

**NER HQ-S AND T/NORTH EASTERN RLY
TENDER DOCUMENT**

Tender No: NER_SnT_Proj_BSB_03_2026

Closing Date/Time: 07/07/2026 15:00

1.1.3	Engineering Department in consultation with S&T Department and Electrical Department of concerned Division shall give permission to the State Government Undertakings, National Highway Authority of India etc. for excavation work in the railway area,/ near the railway track. In such cases, Executing agency shall approach in writing to Sr. DEN with a copy of application/request to Sr.DSTE and Sr.DEE. Immediately after receiving request from Executing agency, Sr.DSTE and Sr.DEE will conduct survey of the proposed locations of excavation work, if there is a need for cable shifting then its cost will be informed to Sr. DEN, and subsequently it shall be communicated to Executing Agency for inclusion of cable shifting cost in their estimate. Thereafter, Sr. DEN/C will grant permission to the Executing Agency with the condition that the excavation work should be carried out in the presence of the concerned open line railway staff of the S&T and Electrical Department.	No	No	Not Allowed
1.1.4	Contract for utility shifting shall be awarded in advance for the excavation/earth work. The Scope may include shifting/removal of infringements including cables, signals, LC equipment, location boxes etc. and get the shifting done well in advance before start of excavation /earth work.	No	No	Not Allowed
1.1.5	In cases where it has already been decided jointly by Division (Sr.DSTE, Sr.DEE & Sr.DEN with the approval of ADRM) not to shift cables (due to any reasons), then protection of cable, shall be ensured by Executing Agency in consultation with nominated representative of Sr.DSTE/Sr.DEE.	No	No	Not Allowed
1.1.6	Any provision not covered in this JPO shall be decided based on the Telecom Circular 09.1.2023 issued from Railway Board vide letter under reference.	No	No	Not Allowed
1.1.7	It must be ensured that provisions contained in this JPO shall become part of future Tender Documents for such work within one month of issue of this JPO.	No	No	Not Allowed
1.2	Procedure of permission for undertaking works in vicinity of Earth/work/Digging work in the vicinity- of Signaling, Electrical and Telecommunication Cables etc.	No	No	Not Allowed
1.2.1	Cable route plan of all types of Cable must be made available block section wise on Railnet by Sr DSTE/Sr DEE (Nodal officer) of the Division. Regular updation of Cable route plan on Railnet must be ensured by Sr DSTE/Sr DEE. Executing agency / contractor may download these plans from Railnet(www.ner.indianrailways.gov.in > Divisions > S&T) or may obtain from Nodal Officer.	No	No	Not Allowed
1.2.2	Executing agency/Official shall approach for permission in writing by submission of request in prescribed format (Annexure- 1) to Sr.DSTE/Sr.DEE(Nodal officer) at least 10 working days in advance. This request shall be communicated through MEMO or App or at designated Mobile number for this purpose.	No	No	Not Allowed

**NER HQ-S AND T/NORTH EASTERN RLY
TENDER DOCUMENT**

Tender No: NER_SnT_Proj_BSB_03_2026

Closing Date/Time: 07/07/2026 15:00

1.2.3	On receiving the request of permission from Executing Agency/official, cases shall be initially scrutinized for availability of Cable Route Plan. In cases, where cable route plan is not available at Railnet, nodal officers shall arrange to issue detailed cable route plan of requested section /area within 3 working days in pdf, gif etc. or any other agreed format (showing locations of cables at an interval of 200 m for block section or 25 m in format (showing locations of cables at an interval of 200 m for block section or 25 m in station yard or where there is change in alignment) to the Executing Agency/official on e-mail id mentioned in Annexure-I. Nodal officer (Sr.DSTE/Sr.DEE) shall immediately depute competent supervisors for Joint inspection of the proposed site with Executing officials. Joint inspection shall be invariably completed within 10 days of receipt of request. Nodal Officer shall also communicate to the Executing Agency in regard to Joint inspection along with contact information of deputed Supervisors. In cases, where cable route plan is not available with nodal officer, this should be immediately informed to Executing Agency/official and in such cases Joint inspection shall be done with Executing officials. Joint inspection shall be invariably completed within 10 days of receipt of request for permission. The cable route makers at site, suitable cable route tracer and, if required, by digging of cross trenches/cross pits and provide physical cable marking on the ground may be undertaken for this purpose. Digging of cross trenches/cross pits shall be arranged by the Executing agency. After ascertaining the cable route/ alignment, the representatives of Division and Executing Agency shall prepare and sign the joint inspection report.	No	No	Not Allowed
1.2.4	Based on the Joint Inspection report, permission request shall be finalized by Nodal officer within 10 working days and must be communicated to Executive Agency/official clearly mentioning the locations requiring supervision by S&T /Electrical supervisors. Also mentioning that other locations will not require any supervision. In absence of any intimation to Executive agency/official within stipulated time limit the permission of excavation/earthwork shall be deemed granted after 10 working days presuming that there are no cables in such stretches. Nodal Officer shall be also advised in writing on 11th working day that no response has been received from Nodal Officer against the request submitted and Executing Agency may start the works. Records of request /application from Executive agency and permission granted by Division shall be maintained by Nodal Officer. No change in working location is permitted without written permission of the nodal officer.	No	No	Not Allowed
1.2.5	For doing Engineering work in embankment or station area or Railway boundary, where no excavation (only earth filling) is involved, NOC will be given after Joint Inspection of supervisors as mentioned above, within 10 days of receipt of the letter of intention.	No	No	Not Allowed
1.2.6	Before allowing contractor for any work (earthwork, trenching, drain work, earthing, Horizontal directional drilling etc.) near the track/ in the vicinity of cables, the work Executing Agency (Like Dy CE/Con, Dy CSTE/Con, DyCEE/Con, Dy CSTE/Proj, Sr. DEN/Sr. DSTE/ Sr. DEE/ RVNL, IRCON, RE / GatiShakti units, State/Central govt. Agencies, Private Parties etc.) shall ensure that the permission had been granted by the Division to the contractor for that stretch.	No	No	Not Allowed
1.3	Guidelines for Protection of Cables while doing the work in vicinity of Signaling, Electrical and Telecommunication Cables etc.	No	No	Not Allowed

**NER HQ-S AND T/NORTH EASTERN RLY
TENDER DOCUMENT**

Tender No: NER_SnT_Proj_BSB_03_2026

Closing Date/Time: 07/07/2026 15:00

1.3.1	Concerned open line S&T/Electrical/P.Way supervisors of the section shall be informed by Executing Agency official for commencement of excavation work at least 3 days in advance and subsequently on everyday in writing the location of the work (through Memo or App or at mobile number designated by nodal officer for this purpose). S&T/Electrical supervisor shall verify the site marking and give a go ahead to executing agency for excavation in consultation with P.Way/Engineering supervisor including deputation of S&T/Electrical supervisor for supervision of the location mentioned in the permission within prescribed period of three days. Records of such request and permissions granted shall also be maintained in the office of Nodal Officer. In case of works where supervision is required Divisional supervisor will invariably arrange to depute a person to supervise the excavation work.	No	No	Not Allowed
1.3.2	Engineering control, S&T and Electrical Control shall keep all the information regarding any digging/earth work being done near the track. Engineering's and Electrical control shall exchange the information among them on regular basis and coordinate to ensure that no work is done in the vicinity of the track without proper permission. Executing agency should provide daily information on prescribed Performa as mentioned in Para 1.3.3.	No	No	Not Allowed
1.3.3	Daily information proforma 1. Date of work. 2. Section. 3. Block section 4. Location 5. Nature of work 6. Contractor 7. Name of supervisor 8. Authorized representative of Contractor.	No	No	Not Allowed
1.3.4	Normally earth work by contractor is done by mechanized earth moving machineries i.e. JCB Poclain /Spreader etc. However, if cables are present in the area i.e. Home signal to Home signal territory in station yard, earthwork(digging) to be done manually within 2 m of cable except in following cases: i) Cable has been traced & diverted. ii) Cable has been traced but not diverted in such case earthwork with machine to be done in supervision/presence of S&T and Electrical supervisor. Such cable diversion work shall be done by S&T/Electrical wing of the Executing Agency under supervision of representatives of Nodal Officers.	No	No	Not Allowed
1.3.5	In case of minor works such as foundation work for Bridges, ROB's, FOB's, RUB work, Drain works etc., the executing Contractor shall be advised to takeout the cables (if extra loop length is available) carefully in the presence of supervisors of nodal officers and place it properly alongside at a safe location in separate trench before starting the earth work. Further, till such time these cables are in exposed condition, they will be guarded by executing agency to avoid theft and damage. The time for keeping cables in exposed condition should preferably be limited to one month. Where extra loop length of cable(s) is not available, cables shall have to be shifted by executing agency enclose coordination /supervision of open line S&T/Electrical Deptt.	No	No	Not Allowed
1.3.6	At each excavation site, Executing Agency shall keep at least one Cable Route Tracer and one Cable Fault Locator to reduce the time taken to locate the fault in case of cable cuts.	No	No	Not Allowed
1.3.7	To minimize the adverse impact of cable cuts on safety and punctuality, executing agency shall always keep skilled manpower and materials in readiness for ensuring expeditious restoration of cable cuts under supervision of Divisional officials.	No	No	Not Allowed
1.3.8	The concerned SE (P.Way/Works/Sig/Tele/RCIL) supervising the earthwork/excavation work shall ensure that apart from cables, existing emergency sockets are not damaged as emergency sockets are essential for providing communication during accident/ emergency.	No	No	Not Allowed
1.4	Procedure of Imposing Penalty for Cable Cut/Damage Cases.	No	No	Not Allowed

**NER HQ-S AND T/NORTH EASTERN RLY
TENDER DOCUMENT**

Tender No: NER_SnT_Proj_BSB_03_2026

Closing Date/Time: 07/07/2026 15:00

1.4.1	In case of any cable cut during the working, It will be the responsibility of work Executing Agency to inform concerned S&T/Electrical officials without any delay through concerned supervisor. Executing agency shall extend all possible support by deploying manpower/machines for identifying cable cut location/making pits etc. to ensure prompt action and early restoration. Any effort of hiding/running away from the site will be viewed seriously, and additional penalty may be levied as per provisions of contract in place under which the work is being carried out.	No	No	Not Allowed
1.4.2	Penalty should be levied on the contractor when they worked without permission or resort to careless working without making arrangement for protecting cables and other utilities. Penalty to be imposed for damages to cable shall be as under: Type of damaged cable Penalty amount per location Quad cable only/signaling cable: Rs 1.00 lakh Only OFC : Rs.1 .25 lakh OFC and Quad both : Rs. 1.50 lakh Electrical cable : Rs. 1.00 lakh	No	No	Not Allowed
1.4.3	Penalty shall not be levied in following cases: (i) Contractor has ensured compliance as per Para 1.3 of this JPO. (ii) Cable Route Plan for the section is not provided	No	No	Not Allowed
1.4.4	For each cable cut/damage case, a Joint report shall be made in prescribed format (Annexure-II of this JPO), on the same day by supervisors of concerned departments i.e. open line S&T/Electrical (as the case may be) and Supervisor of concerned Executing Agency. Concerned Supervisors must ensure that specific remarks/comments about the various issues /items mentioned in Para 5.4.3(above) of this JPO are covered in Joint Note. Joint Note shall be the basis of levying penalty and fixing responsibility.	No	No	Not Allowed
1.4.5	Joint Report duly signed by concerned supervisors (Engineering, Electrical, S&T and RPF department) in prescribed format (Annexure-II of this JPO) should be submitted to respective Sr DSTE/Sr.DEE. Joint Note shall be forward by Sr DSTE/Sr.DEE to the Executive in charge of the work. Executive in-charge of the work should act and decide on the cable cut case within 15 days under information to Sr DSTE/Sr.DEE.	No	No	Not Allowed
1.4.6	Within one month of the notice of imposition of penalty, the contractor can appeal against the penalty to the ADRM of the concerned Division for the cases other than the construction unit. For Construction/Project works CE/(Con)/CSTE(Proj)/CEE(Proj) shall be the appellate authority. Decision of ADRM/ CE (Con)/CSTE(Proj)/CEE(PLOj) shall be final and binding upon both the parties. The appeal must be disposed of by competent authority preferably, within 15 days after receipt of appeal.	No	No	Not Allowed
1.4.7	Necessary debit in this regard shall be raised on the department undertaking the work who shall in turn levy the penalty on the defaulting contractor. The mode of recovery of penalty shall be (a) From latest running bills, in case of working contractor under Railway, (b) In form of demand Draft/Banker's Cheque payable in case of state/Central Govt. agencies and private Parties. The recoveries shall be based on amount mentioned in the Joint report and to be recovered after disposal of appeal by ADRM(For Divisional work) (if any) and for construction work concerned CE/(Con)/ CSTE(Proj.) CEE(Proj). S&T department shall raise the debits in case of damages to OFC or Quad or Signaling cable and Electrical department shall raise the debits in case of damages to Electrical cable.	No	No	Not Allowed
1.4.8	In cases, cable is damaged due to negligence of Railway Supervisor(s), action shall be taken against them by concerned controlling authority.	No	No	Not Allowed
1.4.9	Railways will not lodge FIR with RPF in cases works being executed by authorized contractors of Railways who have been duly permitted to execute the works.	No	No	Not Allowed
1.4.10	Monthly records of the action taken on the basis of Joint Note for recovery of penalty from the concerned Executing Agency should be kept in the Divisions.	No	No	Not Allowed

6. Documents attached with tender

**NER HQ-S AND T/NORTH EASTERN RLY
TENDER DOCUMENT**

Tender No: NER_SnT_Proj_BSB_03_2026

Closing Date/Time: 07/07/2026 15:00

S.No.	Document Name	Document Description
1	GCC2022UPTOACS11f.pdf	GCC 2022
2	ARJ-CPRTentativeROLLDIAGRAM-Model.pdf	Roll Diagram ARJ to CPR
3	IRSEM-AppendixIIJune2021_compressed.pdf	IRSEM Drawing
4	ACS1to11.pdf	ACS 1 to 11
5	TenderdocumentARJCPR.pdf	Tender Document

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

Signed By: ASHUTOSH KUMAR PANDEY

Designation : Dy.CSTE/Project/BSB