

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWKS2026-27SIG05

Closing Date/Time: 19/06/2026 15:00

Sr.DSTESr. DSTE acting for and on behalf of The President of India invites E-Tenders against Tender No **BPLNWKS2026-27SIG05** Closing Date/Time 19/06/2026 15:00 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

1. NIT HEADER

Name of Work	Alteration of phase working of Shri Singaji Thermal power project at Khandwa Silo siding work, Shifting of signalling gears in connection with ROB on Bunti Nagar at KM 891/31-892/1 & ROB AT KM 1084/27-29 in between Pagara-Maban Railway station		
Bidding type	Normal Tender		
Tender Type	Open	Bidding System	Single Packet System
Tender Closing Date Time	19/06/2026 15:00	Date Time Of Uploading Tender	27/05/2026 13:50
Pre-Bid Conference Required	No	Pre-Bid Conference Date Time	Not Applicable
Advertised Value	12311420.91	Tendering Section	SNT SIG
Bidding Style	Single Rate for Tender	Bidding Unit	Above/Below/Par
Earnest Money (Rs.)	246200.00	Validity of Offer (Days)	60
Tender Doc. Cost (Rs.)	0.00	Period of Completion	9 Months
Contract Type	Works - General	Contract Category	Expenditure
Bidding Start Date	05/06/2026		
Are JV allowed to bid	No	Number of JV Member Allowed	0
Are Consortium allowed to bid	No	Number of Consortium Member Allowed	0
Ranking Order For Bids	Lowest to Highest	Expenditure Type	Deposit Work

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () 01-Supply portion-I							6809555.91	
01	Please see Item Breakup for details.				6809555.91	AT Par	6809555.91	
	Description:- Total Supply portion-I							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () 02- Supply portion-II							379013.14	
02	Please see Item Breakup for details.				379013.14	AT Par	379013.14	
	Description:- Total Supply portion-II							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () 03-Execution Portion							5122851.86	
03	Please see Item Breakup for details.				5122851.86	AT Par	5122851.86	
	Description:- Total Execution Portion							

3. ITEM BREAKUP

Schedule	Schedule 01-Supply portion-I					
Item- 01	Total Supply portion-I					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	01	Supply of Route Group (Ref: IRS: S-46) without base plate along with guide rail conforming to specification No. IRS:S23, S34, S46 as applicable. Integra make compatible with existing system (Material inspected by RDSO)	Numbers	4.00	56303.66	225214.64

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWS2026-27SIG05

Closing Date/Time: 19/06/2026 15:00

2	02	Supply of Major relay group base plate complete with fedlister (20 No. per base plate, guide rails and other accessories). (i) For major point group (ii) Three aspect signal group (iii) Two aspect signal group (iv) Shunt group (v) Route Group as per instruction of SSE in charge. Integra make compatible with existing system. (Material inspected by Consignee)	Numbers	11.00	18607.44	204681.84
3	03	Supply of Point Group RRI (Ref: IRS: S-46) without base plate confirming to specification No. IRS:S23, S34, S46 as applicable. Integra make compatible with existing system. (Material inspected by RDSO)	Numbers	4.00	100925.72	403702.88
4	04	Supply of Shunt Signal Group (Suitable for LED Signal) (Ref: IRS:S-46) without base Plate. Integra make compatible with existing system. (Material inspected by RDSO)	Numbers	3.00	63433.09	190299.27
5	05	Supply of Apparatus Case with miniature 'E' type locks with keys (1 key per 5 location boxes) of ward No. 22 (E type lock & key as per spec. No. IRS S 30 & RDSO Drg. No. SA 3376/M& 3377/M respectively with latest amendment) on both the doors duly painted with red oxide. Single case as per Drg No. WS-8842/A with latest alteration. (Material inspected by Consignee)	Numbers	10.00	19455.69	194556.90
6	06	Supply of Hylem sheet resin bonded 10mm thick, grade P3 in standard size of 1.22X1.22 Mtr as per spec. No. IS 2036 of 1974. (Material inspected by Consignee)	Numbers	10.00	4569.29	45692.90
7	07	Supply of Thermo Shrinkable Straight through joint for under ground cables with all accessories as per RDSO IRS/TC/77/2012 or latest, joint suitable for 6 Quad Cable (0.9 mm dia). (Material inspected by RDSO)	Numbers	14.00	2501.00	35014.00
8	08	Supply of two in two out (4 conductor) Knife edge disconnect terminal block as per RDSO/SPN/189/2004 Ver. 3.0 with latest amendment. (Material inspected by RDSO)	Numbers	5500.00	101.84	560120.00
9	09	Supply of End plate suitable for disconnect terminal as per RDSO/SPN/189/2004. (Material inspected by Consignee)	Numbers	250.00	14.04	3510.00
10	10	Supply of End stop suitable for disconnect terminal as per RDSO/SPN/189/2004. (Material inspected by Consignee)	Numbers	500.00	12.29	6145.00
11	11	Supply of steel carrier DIN rail suitable for fixing disconnect terminal 1 meter long, 1 mm thick. (Material inspected by Consignee)	Metre	21.00	172.07	3613.47
12	12	Supply of earth electrode assembly as per Drg. No. CR/SK-753. (Material inspected by Consignee)	Numbers	14.00	1148.00	16072.00
13	13	Supply of Double Walled Corrugated pipe fire resistant and anti- rodent made up of Polyethylene of Size 103.5 mm inner dia and 120 mm outer dia in 6M straight length as per RDSO specification Nos. RDSO/SPN/204/2011 with latest amendment along with one coupler per every 6 meters. (Material inspected by Consignee)	Metre	90.00	316.03	28442.70
14	14	Supply of GI pipe as per Specn. No. IS 1239 (Part-1)/1990 medium class normal bore of 100 mm, nominal mass of Tube 12.5 Kg (+/-) 10% per meter and complying parameters of specification. (Material inspected by Consignee)	Metre	162.00	1321.44	214073.28

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWS2026-27SIG05

Closing Date/Time: 19/06/2026 15:00

15	15	Supply of DC Neutral Line Relay, Non ACI, 60 V DC (Metal to Metal Contact) Spec: IRS:S-46 with Amdt.1, IRS: S 23-88, IRS:S 34-68, STR: SIQ 0420 Ver. 1.0, 4F-4B/5F-3B/6F-2B front and back contacts metal to metal. The relay housing shall contain two miniature identical relays in a mini group housing complete with base plate. Integra make compatible with existing system. Break-up of configuration will be given by railways before supply of material (Material inspected by RDSO)	Numbers	30.00	9586.50	287595.00
16	16	Supply of mini group base plate complete with amphanols, code pin, fixing screw suitable for metal to metal. Integra make compatible with existing system. (Material inspected by Consignee)	Numbers	58.00	805.43	46714.94
17	17	Supply of Relay plug-in-type, Mech. Interlocked Relay, 60V (Metal to Metal) Spec: IRS:S-46 with Amdt.1, IRS:S 23-88 ; IRS:S 34-68, STR: SIQ 0420 Ver. 1.0 as applicable and firm's specification in mini group housing containing two miniature identical relays with contact configuration 4F-4B, 5F-3B, 6F-2B, metal to metal with base plate of same make. Integra make compatible with existing system. Break-up of configuration will be given by railways before supply of material. (Material inspected by RDSO)	Numbers	16.00	8330.28	133284.48
18	18	Supply of Relay 110V AC LED ECR for LED Signal Lamp Metal to Metal as per IRS:S-46 ; Amdt.1 ; STS/E/Relays/AC Lit LED Signal/09-2002 Amdt.- 1, STR: SIQ 0420 Ver.1. (Material inspected by RDSO)	Numbers	12.00	6197.81	74373.72
19	19	Supply of Key Lock Relay AC immunised with different ward combinations (Five extra set of ward plate for Point Machine to be supplied with each relay) working on 24V/60V DC or functional equivalent as per site requirement. (Material inspected by RDSO)	Numbers	4.00	10093.10	40372.40
20	20	Supply of Time Element Relay (Clock work type) AG timer Siemens Make or equivalent with timer range upto 120 seconds.(Material inspected by Consignee)	Numbers	1.00	8600.74	8600.74
21	21	Supply of Relay, Miniature, Plug in Type, M to C, DC Neutral, Track Relay, ACI, Style QTA2, 9 Ohm, 2F-1B Contact front and back contacts metal to carbon complete with plug board, retaining clips & connectors conforming to BRS:939A & 966 (Appx F2) & IRS:S-23, S34 & 60. (Material inspected by RDSO)	Numbers	8.00	8113.89	64911.12
22	22	Supply of Relay, Miniature, Plug in Type, M to C, DC Neutral , Line Relay QSPA1, 24V DC, Slow to Pick up AC Immunized, 8F-4B Contact, front and back contacts metal to carbon complete with plug board, retaining clips & connectors conforming to BRS:933A, IRS S 34, IRS S 23, IRS S 60-78 as applicable. (Material inspected by RDSO)	Numbers	8.00	7651.21	61209.68
23	23	Supply of QNA1 (AC immunised relay), 12F-4B/8F-8B, 24VDC along with plug board (Base plate), retaining clips and connectors conforming to BRS:931A, IRS:S34, IRS:S23 & IRS S 60-78. Break-up of configuration will be given by railways before supply of material. (Material inspected by RDSO)	Numbers	61.00	5369.75	327554.75

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWS2026-27SIG05

Closing Date/Time: 19/06/2026 15:00

24	24	Supply of QN1 Non AC Immunised Relay, Style QN1, 24 V DC, 8F-8B/12F-4B Contact, along with plug board (Base plate), retaining clips and connectors conforming to BRS:930, IRSS 34, IRS S 23. Break up of configuration will be given by railway before supply. (Material inspected by RDSO)	Numbers	57.00	4828.02	275197.14
25	25	Supply of PVC insulated railway signalling indoor single core [tinned jumper wire] 1X 0.6 mm dia as per Spec. No. IRS:S-76/89 with latest amendments of various colours to be decided by Site in-charge. (Material inspected by RDSO)	Kilometre	1.00	3209.88	3209.88
26	26	Supply of PVC Indoor Cable 1x60x0.6mm dia. Colour coding of insulation of inner core shall be in six colour viz Blue, Red, Green, Grey, Brown & Black as per IRS:S-76/89 (Amd. 3 or latest). (Material inspected by RDSO)	Kilometre	0.50	239260.63	119630.32
27	27	Supply of PVC Indoor Cable 1x 40x0.6mm dia. Colour coding of insulation of inner core shall be in four colour viz Yellow, white, pink & violet as per IRS:S-76/89 (Amd. 3 or latest). (Material inspected by RDSO)	Kilometre	0.50	166812.70	83406.35
28	28	Supply of Indication bulb for indication panel (LED Type) 24 Volt Yellow compatible with existing operating panel. (Material inspected by Consignee)	Numbers	20.00	21.50	430.00
29	29	Supply of Indication bulb for indication panel (LED Type) 24 Volt Green compatible with existing operating panel. (Material inspected by Consignee)	Numbers	20.00	21.50	430.00
30	30	Supply of Indication bulb for indication panel (LED Type) 24 Volt White compatible with existing operating panel. (Material inspected by Consignee)	Numbers	20.00	21.50	430.00
31	31	Supply of retro reflective Signal No. plates as per Signal engineering manual Drg. No. 19-D10. (Material inspected by Consignee)	Numbers	20.00	812.22	16244.40
32	32	Supply of Non Metallic (FRP) colour light signal housing multi unit type for railway signaling suitable for RE area TWO Aspects complete without lenses, lamps and signal transformer as per RDSO Drg. No. SA 23001/A/M Adv. Alt- S and as per Spec. No. RDSO/SPN/194/2006 (Ver. 1.0) or latest and FRP material as per RDSO Spec. No. RDSO/SPN/151/1997 or latest. (Material inspected by Consignee)	Numbers	1.00	41074.55	41074.55
33	33	Supply of Non Metallic (FRP) colour light signalhousing multi unit type for railwaysignalling suitable for RE area FOUR Aspects. Complete without lenses,lamps and signal transformer as perRDSO DRG. No. SA 23001/A/M Adv.Alt- S and as per SPEC. No.RDSO /SPN /194/2006 (Ver. 1.0) or latest and FRP material as per RDSOSPEC. No. RDSO/SPN/151/1997 orlatest. (Material inspected by Consignee)	Numbers	1.00	39777.41	39777.41
34	34	Supply of Offset Bracket 3-1/2" for shunt signal. (Material inspected by Consignee)	Numbers	1.00	893.23	893.23
35	35	Supply of position light shunt signal Unit as per RDSO Drg. No. SA23840. (Material inspected by Consignee)	Numbers	4.00	15843.92	63375.68
36	36	Supply of Shunt Signal Post with Base (GI Pipe of 80 mm Dia. Medium class 49 IS Specification IS:1239 Pt-1/1990). (Material inspected by Consignee)	Numbers	4.00	4476.87	17907.48

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWK2026-27SIG05

Closing Date/Time: 19/06/2026 15:00

37	37	Supply of B type choke to spec. No. IRS:S-65/83 with latest amendments. (Material inspected by RDSO)	Numbers	8.00	4798.65	38389.20
38	38	Supply of adjustable Track Feed Resistance 30 ohms as per RDSO Drg. No. SA 20161-66/M with latest amendments (with Phenolic moulded base). (Material inspected by RDSO)	Numbers	8.00	1697.87	13582.96
39	39	Supply of Track feed battery chargers, 110V AC input and 2, 4 to 8 V DC Output, 10 amp to Spec. No. 2013 with amendment or latest amendments. Charger shall be suitable for charging 80 AH battery. (Material inspected by RDSO)	Numbers	8.00	4318.19	34545.52
40	40	Supply of low maintenance lead acid secondary cells 2V, 80 AH as per spec No. IRS:S-88/93 with latest amendments. (Material inspected by RDSO)	Numbers	40.00	2626.33	105053.20
41	41	Supply of track lead junction boxes as per Drg. No. RST-11509 made from fibre glass along with terminal block. (Material inspected by Consignee)	Numbers	24.00	1967.34	47216.16
42	42	Supply of Stop Board as per RDSO Drg. No. 7235/B. (Material inspected by Consignee)	Numbers	2.00	3506.49	7012.98
43	43	Supply of Lamp holder and switches, Two pin (Backelite type) for location boxes (Anchor make or similar). (Material inspected by Consignee)	Numbers	6.00	163.13	978.78
44	44	Supply of domino units with cover plates as per approved panel diagram, each of size 54x34mm completely wired up similar to existing make (Deltron style -electrostar make panel) installed at site. Each domino unit should have all the 15 contact terminals wired up. (Material inspected by Consignee)	Numbers	30.00	949.96	28498.80
45	45	Supply of PVC insulated single core flexibler wire multi-strand 36/0.3 (50/.25) mm Dia 2.5 sq mm copper conductor for voltage grade up to 1100v confirming to IS-694/1990 color Red,Yellow and Greay equal quantity Make- Finolex, Havells, Polycab or similar OEM/Authorized Dealers Guarantee certificate to be submitted at the time of supply Make polycab/Havells or similar. (Material inspected by Consignee)	Metre	500.00	25.39	12695.00
46	46	Supply of Hand Cuff Locks / Godrej Navtal lock with common key. (Material inspected by Consignee)	Numbers	40.00	399.80	15992.00
47	47	Supply of Clamp with deflector plate and hard warefor fixing the Transmitter and Receiver Coil suitable for ELDYNE make single section digital axle counter System OEM/Authorized dealer'sguarantee certificate to be submitted at the time ofsupply. (I(Material inspected by Consignee)	Set	8.00	8681.40	69451.20
48	48	Supply of tool kit for signal maintainer. List of items to be supplied as per attached annexure-I.	Set	2.00	5929.50	11859.00
49	49	Supply of Standard Tools set. Kit will includes all tools measuring instruments as per annexure-II (Material inspected by Consignee)	Set	6.00	45184.83	271108.98
50	50	Supply of Cable Fault locator as per annexure-III attached. (Material inspected by RITES)	Numbers	1.00	628332.70	628332.70
51	51	Supply of Tx-21-25 KHz coil for GG Tronics make SSDAC (Phase reversal type) as per RDSO Specn No. RDSO/SPN/177/2012 version 3.0 or latest. Make/Brand:- GGTronics. (Material inspected by RDSO)	Numbers	5.00	45736.80	228684.00

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWK52026-27SIG05

Closing Date/Time: 19/06/2026 15:00

52	52	Supply of Rx-21-25 KHz coil for GG Tronics make SSDAC (Phase reversal type) as per RDSO Specn No. RDSO/SPN/177/2012 version 3.0 or latest. Make/Brand:- GGTronics. (Material inspected by RDSO)	Numbers	5.00	45736.80	228684.00
53	53	Supply of 'E' type lock complete with keys as per RDSO Drg. No. SA-3473,3377 and specification No. 30/64. Ward to be specified by engineer in-charge. (Material inspected by RDSO)	Numbers	24.00	2218.72	53249.28
54	54	Supply of Relay Testing Jig with thefollowing hardware requirement are required to be adhered to for the Relay Testequipment - Test Equipment for QN1 & QNA1 series of relays covering 12F4B, 8F8B,8F4B, 6F6B, 4F4B relay types.Microcontroller-based Relay Test Equipmentwith an inbuilt database that would store, prepare & print test results. Therequirement also specifies for a HDMI port and a USB communication port. 1) The testequipment should be microcontroller based 2) Should include low noise and highaccuracy/high resolution A/D converter 3)The equipment should be provided with a 7"touch screen display for frontend- graphic user interface (GUI) and an additional LiquidCrystal Display (LCD - 16 x 2) - to displays the relay type being tested and the progressof relay testing cycle 4) Should be equipped with a HDMI port for connecting to anexternal display 5) A Universal Serial Bus (USB) based communication interface toexport test data to IBM PC compatibles. 6) A wireless keyboard and mouse 7) A plugboard to securely place the Relay to be tested 8) Powder coated mild steel cabinet]. (Material inspected by (RITES)	Numbers	2.00	411761.00	823522.00
55	55	Supply of High current Relay Flashing unit which comprises of the following : -The Relay Test equipment should be capable of measuring & reporting on the following parameters - 1) Coil Resistance normalizedto 20 degree 2) Ambient temperature 3)Contact Resistance of each contact 4) FullOperation Voltage (pick-up voltage)5)Release Voltage (drop voltage) . (Material inspected by Consignee)	Numbers	2.00	176469.00	352938.00
					Total	6809555.91

Schedule Schedule 02- Supply portion-II

Item- 02 Total Supply portion-II

S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	01	Supply of main LED signal UNIT 110V/AC as per RDSO specification No. RDSO/SPN/199/2025 Rev. 1.2 or latest. Suitable for existing CLS housing unit. RED Aspect. (Material inspected by RDSO)	Numbers	4.00	9422.98	37691.92
2	02	Supply of main LED signal UNIT 110V/AC as per RDSO specification No. RDSO/SPN/199/2025 Rev.1.2 or latest. Suitable for existing CLS housing unit. YELLOW Aspect. (Material inspected by RDSO)	Numbers	8.00	9946.48	79571.84
3	03	Supply of main LED signal UNIT 110V/AC as per RDSO specification No. RDSO/SPN/199/2025 Rev.1.2 or latest. Suitable for existing CLS housing unit. GREEN Aspect. (Material inspected by RDSO)	Numbers	6.00	11255.23	67531.38

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWS2026-27SIG05

Closing Date/Time: 19/06/2026 15:00

4	04	Supply of Route LED Signal Lighting 110 V AC in existing CLS housing and compatible with AC LED ECR as per RDSO Spec. No. RDSO/SPN/153/2023 Revision: 5.0 or latest. (Material inspected by RDSO)	Numbers	12.00	6216.55	74598.60
5	05	Supply of LED for Shunt Signal Integrated type 110V AC retrofittable in existing signal housing and compatible with ACLED ECR as per RDSO Spec. No.RDSO/SPN/153/2023 Revision 5.0 or latest. (Material inspected by RDSO)	Numbers	20.00	5980.97	119619.40
					Total	379013.14
Schedule Schedule 03-Execution Portion						
Item- 03 Total Execution Portion						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	01	Installation of powder coated Relay Rack Assembly including IDF pillars complete with wall supports,scaffolding, ladders,runway for cables,Relay/Relay group base plates, fixing of Tag blocks etc. The work shall be done as per approved plan, extant practice on W.C. Railways & the instructions of Rly. engineer at site.	Set	1.00	1804.51	1804.51
2	02	Soldering of tag block fixing and wiring of g type fuse bus bar wiring per tag block as per approved plan extant practice of WCR & as per instruction if site engineer (Soldering wire, resin core etc. material to be supplied by contractor.) unit per tag block	Numbers	10.00	239.11	2391.10
3	03	Wiring in Relay Room: Fixing of Q series relay base plate/ Metal to Metal relay mini group and major group base plates, laying, lacing, dressing & packeting of 60/40 core PVC indoor cable/flexible wire and termination of 60/40 core cable/flexible wire on tag block/base plate & soldering. Wiring of circuits to be done as per the approved diagram based on relay interlocking system using metal to metal/metal to carbon type relays and soldering after testing. This also includes fuse wiring, function wiring (interconnection between relay rack & CT rack), material required like jumper wire of 0.6mm, 1.0mm and 16/0.02 multi strand flexible etc. resin core, solder wire, lacing thread, adhesive tapes, resistance, condensers, diodes, lugs etc. of various ratings and capacity as per site requirement will be supplied by the contractor free of cost and will be used after approval of Rly. engineer at site. The tinned jumper wire required for carrying out the indoor work shall be supplied from RDSO approved vendor, if applicable. The quantity of jumper wire should be assessed jointly with the engineer-in-charge at the begining itself. The work shall be done as per approved plan extant practice on W.C. Rly & the instruction of Rly. engineer at site. NOTE: The jumper wire required for carrying out the indoor wiring shall be supplied after RDSO inspection. The quantity required for jumpering shall be assessed jointly with the engineer in charge in the beginning itself. All type of resistances, capacitors etc required for commissioning will be provided by the contractor. (No. - Per Rack)	Rack	1.00	17032.26	17032.26

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWKS2026-27SIG05

Closing Date/Time: 19/06/2026 15:00

4	04	Wiring of Q series relay, Metal to Metal relay/relay groups. Energisation of the system, making the panel through, 1/2 wire testing, functional test as per control table/selection table, square sheet testing with contractor's own mock panel, break test if applicable in presence of Rly. Engineers. This will include wiring alterations required if any at that stage, preparation and submission of wire count detail register etc. The work shall be done as per extant practice on W.C.Rly & the instruction of Rly engineer at site. All type of resistances ,capacitors etc required for commissioning have to be provided by the contractor free of cost. unit=per rack	Rack	1.00	1471.90	1471.90
5	05	Circuit wiring/jumpering as per diagram in relay rack/IDF rack/tag block. This include preparation of jumper sheet duly checked by firm 's site supervisor & wire testing as per wire to wire testing as per wiring diagram. Any wrong jumper done by wire man will be consider & payment for wrong jumper will not be done by railway. Jumper wire will be supplied by railway and other material like solder wire will be supplied by contractor. (Unit is per jumper)	Numbers	2000.00	20.15	40300.00
6	06	Preparation & submission of cable route plan of main & tail cables, cable corage plan and location particulars, CT rack particulars, Track bonding plan among others required in Auto CAD in size as per requirement of drawing /extant practice of WCR as per data/hard copy given by the railway. Each sheet should have a block for signature of Railway Officials as well as block for signature of the firm, where signature shall be put up by the authorized signatory of the firm. The name of the work as given by the Railways shall be written on every sheet under the work column. One complete set of tracings and four sets of copies of complete above detailed particulars/drawings along with one CD to be supplied by the contractor in thick plastic folder. This include one set of paper print for checking after that tracing to be supplied by contractor. Final 4 sets of paper print to be supplied by contractor after approval of tracing. Note: The drawing shall be submitted for complete yard incorporating existing drawings and proposed drawing also at the time of tracing and final Blueprints.unit=per stn	Station	1.00	34747.04	34747.04

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWKS2026-27SIG05

Closing Date/Time: 19/06/2026 15:00

7	07	Design and supply of Detailed Signalling Circuits including panel diagram, SWR (in Hinid), SWRD, Control table, Route section plan, Selection Table, Fuse & Negative Tag Analysis, Contact Analysis, Relay Rack Arrangement and wire countsheet etc. in A3 size, Completion circuit shall be plotted in AutoCAD. The contractor shall initially supply 2 Sets of circuits duly signed by the circuit designer having substantial experience on design side for making such circuits, complete for approval of Railways. Railway will return one set of circuit to the contractor duly approved with alterations/ corrections, if any. The contractor shall incorporate Railway's alterations/corrections in the original tracings & CD without any deviation and submit two copies of the modified circuits. Original tracings so modified & final CD complete in all respects along with 4 sets of final approved circuits (out of which one set shall be supplied in transparent polythene bags. Only two sheets of circuits shall be placed in one polythene bag/cover each) shall be submitted to the Railways in case there are no further alteration suggested by Railways. Note: Complete circuit shall be submitted for complete yard incorporating existing drawings and proposed drawing also at the time of tracing and final Blueprints. unit =per stn	Station	1.00	91989.48	91989.48
8	08	Detailed testing of wiring including continuity testing, functional testing, selection table and locking table testing with simulation panel including making panel through in the presence of Rly officials. The item includes wiring of simulation panels as per standard practice. Erection and wiring of simulation panels shall be with contractors own materials. Signal lamps required for simulation panel will be supplied by contractor. The contractor shall hand over the system for railways testing and shall arrange technical man power, wireman and supervisor to facilitate this testing by railway. UNIT- Per stn	Station	1.00	125909.65	125909.65
9	09	Installation, wiring/Alteration & Testing of Control cum Indication Panel / operating panel / indication panel/Cabinet for housing dual VDU as the case may be, UFSBI, KLR boxes, Group phone, ELD, Fuse indication system & test board etc. This includes laying & termination of cable, if any from Panel Room To Relay Room in GI/HDPE pipe.	Lot	1.00	16272.24	16272.24
10	10	Alteration in Data logger wiring, testing & commissioning of Data logger complete along with accessories with contractor's own material, nThis includes programming of data logger for fault diagnostic in suitable structured language in consultation with Railway. unit=per stn	Station	1.00	13227.41	13227.41

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWKS2026-27SIG05

Closing Date/Time: 19/06/2026 15:00

11	11	Excavation of trench as per cable route plan, 1.2 mtr deep, 300mm wide at the bottom along main line in normal soil. This work includes covering of cable laid in trenches by loose soil for a layer of 50 mm thickness approximately before covering by shahabad stone/bricks, clearing of route, bushes etc and refilling of the trench by excavated soil and ramming after laying of the required quantity of cables as per instructions of Engineer at site. If it is not possible to reach the required depth at any location, then the contractor shall obtain prior approval of Engineer-in-charge before commencement of cable laying process and only then shall the proportionate payment be made to the contractor.	Kilometre	2.20	69174.38	152183.64
12	12	Excavation of cable trench as per cable route plan, 1 mtr. Deep and 300 mm wide along side the track in hard soil, confirming to distances as per cable route plan and refilling after cable laying. This work includes covering of cable laid in trenches by loose soil for a layer of 50 mm thickness approximately before covering by shahbad stone/bricks, clearing of route, bushes etc. The work shall be done as per extant practice on W.C.Rly. & instruction of Rly. engineer at site. In case depth of trench not achievable due to site conditions proportionate payment will be made.	Kilometre	2.40	101971.59	244731.82
13	13	Excavation of cable trench 1 mtr. deep and 300mm wide across the track, for track crossing and refilling after laying of DWC pipes and restore the track to its original condition. The work shall be done as per extant practice on W.C. Rly & instruction of Rly engineer at site.	Metre	90.00	157.95	14215.50
14	14	Preparation of cable duct 150mm x300mm deep for laying of cable in rocky area and refilling the duct(after cable laying) with concrete mixture of proportion 1:3:6 and grouting the ends at either side of the rocky portion using concrete mixture with contractors own cement and other materials.	Metre	100.00	812.83	81283.00
15	15	Cutting of all types of Roads preparatory to trenching & excavation to depth of 1 Mtr X 300 mm wide approximately and refilling after laying of DWC/GI pipes and restore to its original condition as per WCR Drg. no. TS/Cable laying/12/03/04 attached. The work shall be done as per extant practice on W.C.Rly & instruction of Rly engineer at site.	Metre	10.00	312.29	3122.90
16	16	Cutting of all types of Roads preparatory to trenching & excavation to depth of 1 Mtr X 300 mm wide approximately and refilling after laying of DWC/GI pipes and restore to its original condition as per WCR Drg. no. TS/Cable laying/12/03/04 attached. The work shall be done as per extant practice on W.C.Rly & instruction of Rly engineer at site.	Metre	13.00	281.57	3660.41
17	17	Fixing and laying of GI pipe for crossing culvert , stone bridges etc. and concreting the ends with brick masanary at both ends as per instruction of railway engineer at site with contractor materials. Proporation will be done at an interval of 150 mm as per instruction of railway engineer at site.	Metre	12.00	87.58	1050.96

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWS2026-27SIG05

Closing Date/Time: 19/06/2026 15:00

18	18	Laying of signalling/Power/Telecom cable of various cores/sizes in trenches. The work shall be done as per extant practice followed on W.C.Railway and as per the instructions of Railway Engineer at site.	Kilometre	63.00	7319.27	461114.01
19	19	Laying of DWC/GI pipes alongwith collars in trenches at places wherever required as per extant practice on WCR and instruction of engineer at site.	Metre	276.00	45.65	12599.40
20	20	Supply & laying of well burnt bricks of size 225 x 100 x 75mm inside the trench (with the brick length being perpendicular to cable route) after laying of cable in station area from Outermost to Outermost signal or at any other location as per instruction of Site Engineer. Note: - Size of bricks to be got approved by Site Engineer. In case brick size is in variance with the size given in the tender schedule then proportionate payment on volumetric basis shall be paid to contractor subject to a maximum limit of schedule rate.	Numbers	50400.00	4.98	250992.00
21	21	Installation of Thermo-shrinkable jointing kits for making (a) straight through joints without transformer for 6 -quad Jelly filled cable, (b) Derivation joint without transformer for 6-Quad Jelly filled cable, and (c) Straight Through joint without transformer for 10 Pr/20Pr. PIJF cables and construction of Brick Chamber for protection of joints with contractor's all materials as per Drg. No. WCR/TELE/2008/2 /Amendment 1 where VF transformers are not required. All the materials required for the work are to be arranged by the contractor himself at his own cost except Thermo-shrinkable jointing kit which is already covered in Supply portion of the tender. After jointing the cable through test such as insulation test, Continuity cable losses etc. to be carried out jointly with the Railway Engineer. If any defect or any damage observed during jointing, the contractor should redo the joint free of cost.	Numbers	12.00	2783.19	33398.28
22	22	Provision of cement concrete work 1:3:6 with 25 mm graded stone aggregated and curing of same as per above.	cum	16.00	3476.36	55621.76
23	23	Providing brick masonry in ratio of 1:6 cement & sand including plastering 20 mm thick on each side with 1:4 cement and sand mixture with contractor own second class bricks, sand, cement including excavation, curing, grouting bolting etc where required.	cum	1.00	3089.39	3089.39
24	24	Lettering & Numbering of detail and description writing of particulars of terminations & equipments on relay rack, relays, cable termination rack, battery & power equipments, IPS, operating panel, axle counter etc constituting entire system with contractor's own paint and writing material ("Asian" make or similar enamel paints or similar paint only to be used). This includes supply and fixing of teflon strips 3mm thick and 25 mm wide for each row of relays and cable terminations. The work shall be done as per extant practice on W.C.Rly & instruction of Rly engineer at site. unit=per stn	Station	1.00	6708.93	6708.93

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWS2026-27SIG05

Closing Date/Time: 19/06/2026 15:00

25	25	Fixing of ARA /WAGO Terminals/Pheonix terminal in locations with provision of hole in location boxes/CT rack and else where. This includes provision of two additional holes on the hylam board on either side for cable conductor entry. The work shall be done as per instruction of site engineer at site.	Numbers	2500.00	12.29	30725.00
26	26	Termination of cable cores on ARA terminal/Wago/Pheonix terminal and fuse blocks in apparatus cases/ cable termination rack etc.This includes all associated works of pulling out the cable from underground dressing of cable making wiring etc. Both end of cable core shall be counted as per conductor. It includes cable armouring earthing with contractor's own material. Ferruling work to be done in conductors. The work shall be done as per location plan and instruction of Rly. engineer at site.unit=per terminal	Numbers	2500.00	10.53	26325.00
27	27	Excavation, casting and plastering (above ground level) of Apparatus case foundation with contractors own Metal Sheet frame, cement, anchor bolts and other materials. Single case as per Drg No JBP/S&T/C/084A	Numbers	10.00	13391.48	133914.80
28	28	Erection of Apparatus cases with miniature E Type Locks with keys as per spec. No IRS S 30/64 & RDSO Drg. No. SA 3376/M with latest amendments.This includes filling of location foundation with river bed sand and plastering on top of the sand.Apparatus cases will be provided by railway from SSE/Depot. Single case.	Numbers	10.00	1314.23	13142.30
29	29	Fabrication and fixing of phenolic laminated sheet in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated string rods at the back side for cable support with contractor's own material and for fixing equipment and battery as per site requirement. The work shall be done as per drg and arrangement similar to RST/C/11175/A, 11176/A & 007/I&II as per instructions of Rly engineers at site with latest alterations and as per instructions of Rly. Engineer at site. Hylem sheet will be provided by railway from SSE/depot. Single case	Numbers	10.00	1966.69	19666.90
30	30	Installation, of equipment (Relays, resistance, choke, chargers & batteries etc. as applicable wiring with 2.5sq mm flexible copper wire for equip & 16/0.2 for Track relay of same in apparatus case as per location & circuit diagrams with contractor's own wiring material . It also include all wire looping for point,track circuit ,signal etc. The work shall be done as per instruction of RLY engineer at site and approval of wiring material being used and extant practice .It include testing of track circuit as per instruction Single case	Numbers	3.00	1712.06	5136.18
31	31	Provision of bonding with GI wire 4mm dia (8 SWG) for track jumper and fish plate joint bonds. This will include drilling of 7.2 mm dia hole in rails and provision of two jumpers for each bond, clipping of bonds etc with contactors own material and tools as per instruction of Rly engineer at site. Channel pin, bonding wire and PVC sleeve will be supplied by contactors. "Z" bonding will be done using left over cable pices. Two jumpers will constitute one unit of this item.	Numbers	100.00	185.69	18569.00

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWK2026-27SIG05

Closing Date/Time: 19/06/2026 15:00

32	32	Painting two coats of enamel paintover one coat of Red Oxide primer onthe following items after scrappingand cleaning of the surface wherevernecessary. Primer and Paints bothAsian paints / Berger / Shalimar areto be supplied by Contractor. Thework shall be done as per instructionsof Rly engineer at site and extantpractice on W.C Rly on locationboxes. Appratus case full size	Numbers	8.00	628.32	5026.56
33	33	Painting two coats of enamel paint over one coat of Red Oxide primer on the following items after scrapping and cleaning of the surface wherever necessary. Primer and Paints both Asian paints / Berger / Shalimar are to be supplied by Contractor. The work shall be done as per instructions of Rly engineer at site and extant practice on W.C Rly on location boxes, signal posts, TLJB. This includes lettering/Numbering of signals, point machine, TLJB, Block joints, apparatus cases also Termination particulars, equipment names etc. legibly and neatly inside location boxes etc. Shunt Signal post with signal unit, surface base as per W.C. Rly.Standard practice.	Numbers	4.00	281.93	1127.72
34	34	Painting two coats of enamel paint over one coat of Red Oxide primer (inside & outside where ever applicable) on the following items after scrapping and cleaning of the surface wherever necessary. Primer and Paints both ISI paint is to be supplied by Contractor. The work shall be done as per instructions of rly engineer at site and extant practice on W.C Rly on location boxes, signal posts, TLJB. Single case	Numbers	26.00	138.30	3595.80
35	35	Painting two coats of enamel paint over one coat of Red Oxide primer onthe following items after scrapping and cleaning of the surface wherever necessary. Primer and Paints both Asian paints / Berger / Shalimar are to be supplied by Contractor. The work shall be done as per instructions of Rly engineer at site and extant practice on W.C Rly on Point machines. Point machine with ground connection complete. (Point machine with black enamel only out side and ground connection with red oxide)	Numbers	10.00	244.67	2446.70
36	36	Painting two coats of enamel paint over one coat of RedOxide primer on the following items after scrapping and cleaning of the surface wherever necessary. Primer and Paints both Asian paints/ Berger / Shalimar are to be supplied by Contractor. The work shall be done as per instructions of Rly engineer at site and extant practice onWCR on signal posts. Main Signal post with signal unit,surface base and complete fittings as per W.C.Rly.Standard practice.	Numbers	1.00	1180.98	1180.98
37	37	Lettering numbering of signals, point machine, track lead junction boxes, block joint, appratus cases etc (each item to be taken as one unit)	Numbers	45.00	93.91	4225.95
38	38	Lettering numbering termination perticulars equipments names etc legibly and neatly inside location boxes Single case	Numbers	10.00	198.78	1987.80

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWKS2026-27SIG05

Closing Date/Time: 19/06/2026 15:00

39	39	Installation & fixing of earth electrode assembly as per drg. No. CR/SK-753 including earth wire connected through GI wire 8 SWG supported on M.S. flat of size 6mm x 40mm to earth electrode for signaling Equipment such as lever frames, apparatus cases, signals, relay racks, block instruments etc. as per RE manual. The earth value should be less than 10 ohms including the lead wire. It should be documented and painted on earth enclosure made of concrete (only earth electrodes will be supplied by Rly.) Contractor will bring Earth enclosure and all other material required for provision of earthing	Numbers	16.00	2748.46	43975.36
40	40	Excavation, casting and plastering(above ground level) of main signal foundation as per Drg. No.WCR/S&T/SIG/01 with contractor's own materials including cement and galvanised anchor bolts of standard size. The hole for cable entry should be kept as per site requirement and instruction of Rly engineer at site. The required scaffolding, Formwork etc. for casting of foundation will have to be brought by the contractor at his own cost.	Numbers	2.00	12945.40	25890.80
41	41	Excavation, casting and plastering (above ground level) of Shunt Signal foundation as per Drg.No. WCR/S&T/SIG/01 with Contractor's own materials including Cement and galvanised Anchor Bolts of Standard Size. The hole for cable entry should be kept as per site requirement and instruction of Rly engineer at site. The required scaffolding, Formwork etc. for casting of foundation will have to be brought by the Contractor at his own cost.	Numbers	4.00	4261.07	17044.28
42	42	Erection of shunt signal with Surface Base, Post, Signal unit and fixing of No. plates. The work shall be done as per instructions of Rly engineer at site. Wooden white cross-arms (1000x100 mm) to be provided by the contractor till the signals are commissioned with contractor's own material.	Numbers	4.00	686.44	2745.76
43	43	Termination of tail cable on Shunt signal units and wiring with contractor own material, fixing of LED signal unit etc. Flexible Single core copper wire 2.5 sq.mm (50/0.25) conforming to IS-694:1990 copper wire as per Rly. Standard and lugs etc. will be supplied by the contractor. This includes insertion of tail cables from ground to signal unit. The work shall be done as per instruction of Rly engineer at site.	Numbers	4.00	561.19	2244.76
44	44	Charging of Low Maintenance Lead Acid Batteries with contractors own battery grade sulphuric acid and distilled water with minimum two charge - discharge cycles, installation of charged batteries in groups & their connection & wiring. The work shall be done as per extant practice on W.C. Rly & the instruction of site engineer. The sulphuric acid & distilled water to be used for charging shall conform to specification IS 266- 1961 & IS 1070-1960 respectively.	Numbers	40.00	93.83	3753.20

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWS2026-27SIG05

Closing Date/Time: 19/06/2026 15:00

45	45	Erection of CLS Post with Surfacebase and signal unit on top or on OFFset Bracket, fixing of front and backstaging, ladder and guards, signalname plates and A/AG/C/P/G markerboard , protective screen, blanking of ladder (0.6mm MS sheet) if any with contractors own brackets and fixing materials. This also includes erection of auxiliary signals like calling on, shunt signal if any. The work shall be done as per instructions of Rly engineer at site. Wooden white cross-arms (1000x100 mm) to be provided by the contractor till the signals are commissioned with contractor's own material.	Numbers	2.00	4468.95	8937.90
46	46	Patching work in existing location consisting (i) Digging of pit, cleaning of earth from all sides, breaking of seal of location boxes, removal of sand , from location, marking of new cable hole. (ii) Insertion of cable from ground. (iii) making place from cable termination in old location, shifting of ARA, fuse etc after removal of termination, including shifting of ARA. (iv) Termination of cable in old location. (v) Sand filling and plaster	Numbers	12.00	9824.18	117890.16
47	47	Shifting of Existing apparatus case with foundation by crane or by other means upto 2-20 Mtr decided as per site engineer. (During shifting of location boxes signalling gears disconnection will be taken by railway representative). This includes excavation of earth around location box, all type of labours charges and filling of locations foundation with river bed sand and plastering on top of the sand.	Numbers	4.00	9588.65	38354.60
48	48	Dismantling / Releasing of existing Signaling Gears. One Signalling gear will be all parts of one signal (consisting of CLS unit, Signal post along with base) or lever frame (5 levers set), or one point (consisting of all parts of a mechanical point, point machine, ground connections etc.) or one track circuits (consisting of battery box & other parts of DC Track circuit / AFTC /DAC) or one Block instruments etc. This includes the cost of transportation of release materials to store depot or as decided by consignee in charge. This work to be done by contractors with his own vehicle and labour. (Rate to be consider when total gear to be dismantled at a station is more than 10) Note:- Qty unit "Number" is to be considered as "Per Gear"	Numbers	12.00	1251.29	15015.48
49	49	Excavation to railway specification in ordinary soil, black soil or soft murum.	cum	20.00	100.60	2012.00
50	50	Dismantling of Concrete foundations/Demolishing RCC/CC/Stone Work /Cutting Tarpenting/CC Flooring/Precast Concrete slabs etc./Brick work including leading the debris inside Railway limit or outside Railway limit as directed by Engineer in charge.	cum	14.00	648.56	9079.84
51	51	Physical tracing and opening/locating of existing working cables by precession digging for diversion of cables in connection with cable clearance for engineering earth work without interfering the circuits as per the advice of Railway site engineer.	Metre	600.00	366.32	219792.00

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWKS2026-27SIG05

Closing Date/Time: 19/06/2026 15:00

52	52	Preparation & submission of cable route plan of main & tail cables, cable corage plan and location particulars,CT rack particulars,track bonding required in Auto CAD in size as per requirement of drawing /extant practice of WCR as per data/ hard copy given by the railway . Each sheet should have a block for signature of Railway Officials as well as block for signature of the firm, where signature shall deput up by the authorized signatory of the firm. The name of the work as given by the Railways shall be written on every sheet under the work column. One complete set of tracings and four sets of copies of complete above detailed particulars / drawings along with one CD to be supplied by the contractor in thick plastic folder.This include one set of paper print for chaecking after that tracing to be supplied by contractor . Final 3 sets of paper print to be supplied by contractor after approval of tracing.(1 unit= 1 stn/LC gate/IBH)	Lot	2.00	31328.79	62657.58
53	53	Replacement of old signal units of Main signals. This will include releasing of old unit from top of signal post, errection and mounting of new signal unit over the post. This also includes bringing new unit from station/platform to site and bringing back the released unit to station/central cabin.	Numbers	2.00	1830.00	3660.00
54	54	Releasing of complete point machine with ground connection, existing tailcables, insulation sets, bend pipe, etc. from existing point machine. Thisincludes transportattion of release material at cconsignee depot office asper extant practice on W.C. Rly & the instruction of Rly engineer at site.(Unit-No.=Per Point M/C)	Numbers	4.00	3961.79	15847.16
55	55	Fixing of point machine on turnout on Wooden/MBC/Steel sleepers & fixing of ground connections. Adjustment and testing with crank handle operations. This will include: 1) fixing of bend pipes with welded frame for cable entry to machine, 2) necessary adjustment and smithy work, drilling of Holes to tongue rails, gauge plate & steel sleeper, fitting of insulation for tongue	Numbers	8.00	4970.65	39765.20
56	56	Termination of tail cable on main &auxiliary signal units and wiring with contractor own material, fixing of LEDsignal units etc. Flexible Single corecopper wire 2.5 sq.mm (50/0.25)conforming to IS-694:1990 (as peraspect colour) and lugs etc. will besupplied by the contractor. Thisincludes insertion of tail cables fromground to signal unit. The work shallbe done as per instruction of Rlyengineer at site.	Numbers	2.00	1549.23	3098.46

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWKS2026-27SIG05

Closing Date/Time: 19/06/2026 15:00

57	57	Erection, Fitting and Rail connection of Track Lead Junction Box with contractor's fixing material and jacketed wire rope including 7mm single groove galvanized channel pin for track lead connection including angle of size 40 x 40 x 5 mm 1200 mm length. This will include drilling of holes in rails for track lead connections as per instructions of Rly engineer at site. PVC jacketed galvanized steel wire ropes of 6mm dia (7 x 19 strands) sheathed with PVC of 2mm wall thickness and over all thickness of 10mm for connection between the TLJB and the rails are to be used and to be supplied by the contractor. PVC sheath should be made of type 6 compound as per IS 5831 of 1970. Double wire ropes are to be connected between each rail and TLJB.	Numbers	24.00	1618.76	38850.24
58	58	Hiring of JCB Machine (in good working condition) for leveling and dressing ground / dismantling structures including disposal of debris through dumpers etc. with including disposal of debris through dumpers etc. with contractor's labour, JCB machine, machine operator, fuel,etc. The contractor shall arrange road permit for vehicle for all the States of operation, as per instructions of engineer in-charge and vehicle shall not be more than three years old. Payment shall be made for actual working hours at site	Hour	24.00	715.34	17168.16
59	59	Supply and installation of RCCcable route marker engraved and painted on both side along the route every 40 m and route diversion as per latest SEM	Numbers	48.00	618.83	29703.84
60	60	Fixing of cutting in relay base & wiring of relays with contactors own wiring materials in location box.Complete wiring and all other materials required for wiring and fixing of relays will be supplied by the contactor as per instructions of site engineer	Numbers	10.00	653.46	6534.60
61	61	Supply Polyolefin cable channel of size width 240/340 mm, height 155/230 internal/external, length 1 meter produced of polyolefin with fire protection class K-1 in accordance with DIN 53438 Part-II for laying signaling/telecom cables.	Metre	1300.00	1762.09	2290717.00

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWKS2026-27SIG05

Closing Date/Time: 19/06/2026 15:00

62	62	Providing earth Electrode and earthing connections in Rocky area with mechanized drilling of 6 inch (150mm) dia hole, 3 meter deep. All other items for installation of earth electrode assembly shall be followed as per WCR Drg. No. S&T/CON/KOTA/ EARTHING/01 ALT - 01 and connecting through stainless steel wire 8 SWG supported on M.S. flat of size 5mm x 40mm to earth electrode as per drg. No. T/2014/1 for signals and T 2014/5 for location boxes. The earth value should be less than 10 Ohms including the lead wire. The value should be measured in presence of Rly. Supervisors. It should be documented and painted on earth enclosure made of concrete. Only earth electrode will be supplied by Railway. All other material required for provision of earthing will be brought by the contractor. This earth can be provided for DPs, block instruments & ELD etc. also, so as to achieve the desired earth resistance value. Earth enclosure to be manufactured & supplied by contractors own material of ratio 1:3:6, without cover. Additional connection of Earth pipe including parallel connection with other earth pipes with the function shall be done using left over pieces of signalling cable. Laying of cable pieces shall be covered in laying of cable item and cable shall be supplied by Railways.	Numbers	4.00	15792.69	63170.76
63	63	Blowing and drawing of OFC through already buried HDPE duct , taking due care while transporting and sealing both the ends after blowing. The cable should be blown according to the technical instructions of the manufacturer and the instructions of the site in-charge.	Kilometre	1.00	19325.36	19325.36
64	64	Laying of HDPE pipe as per approved cable route plan in the excavated trench, taking due care while transporting and laying the same in the trenches or other protective works. Both the ends of the duct should be sealed with end plugs before laying and should remain sealed till blowing is done.	Kilometre	1.00	7947.50	7947.50
65	65	Splicing of 24 fibre OFC from both sides for straight through joint and testing. This includes excavation of pit & backfilling & supply of all type of material and any other equipment of all types.	Numbers	2.00	6718.19	13436.38

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWKS2026-27SIG05

Closing Date/Time: 19/06/2026 15:00

66	66	Modification/Shifting of existing trackdevice: Installation of track device(double rail contact of digital axlecounter) includes digging of trench,trackcrossing, laying of Double walled antirodent corrugated pipe from trackdevice to location box and making itsterminations. Fixing of deflector plates. (Double walled antirodentcorrugated pipe made up of HighDensity Polyethylene of required diaand all other accessories as persiterequirement to be supplied by thefirm) this also includes supply ofHDPE pipes for laying of transmitterand receiver cables for rail contactsto location box. Casting of foundation for track side housing & erection oftrack side housing if required.Installation & wiring of EJB / Trackside Electronics inside the track sidehousing (this housing will be suppliedand installed on foundation by the contractor with his own material)including supply of wires and other accessories. This also includesreleasing of existing track device & EJB from site, painting and writing on detection points and track sidehousing covers. This also includes OEM pre-commissioning check list.	Numbers	4.00	17061.30	68245.20
					Total	5122851.86

4. ELIGIBILITY CONDITIONS

Standard Financial Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	IR GCC 2022 ACS 1 CLAUSE 10.2 Financial Eligibility Criteria: The tenderer must have minimum average annual contractual turnover of V/N or 'V' whichever is less; where: V= Advertised value of the tender in Crores of Rupees, N= Number of years prescribed for completion of work for which bids have been invited. The average annual contractual turnover shall be calculated as an average of "total contractual payments" in the previous three financial years, as per the audited balance sheet. However, in case balance sheet of the previous year is yet to be prepared/audited, the audited balance sheet of the fourth previous year shall be considered for calculating average annual contractual turnover. The Tenderers shall submit requisite information as per Annexure-VIB, along with copies of Audited Balance Sheets duly certified by the Chartered Accountant/ Certificate from Chartered Accountant duly supported by Audited Balance Sheet.	No	No	Allowed (Mandatory)

Standard Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
-------	-------------	-----------------------	-----------------	---------------------

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWKS2026-27SIG05

Closing Date/Time: 19/06/2026 15:00

1	IR GCC 2022 ACS 1 CLAUSE 10.1 - 1. Technical Eligibility Criteria: (As Per IR GCC Clause 10.1) (a)The tenderer must have successfully completed or substantially completed any one of the following categories of work(s) during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: (i) Three similar works each costing not less than the amount equal to 30% of advertised value of the tender, or (ii) Two similar works each costing not less than the amount equal to 40% of advertised value of the tender, or (iii) One similar work costing not less than the amount equal to 60% of advertised value of the tender. (b) (1) In case of tenders for composite works (e.g. works involving more than one distinct component, such as Civil Engineering works, S&T works, Electrical works, OHE works etc. and in the case of major bridges - substructure, superstructure etc.), tenderer must have successfully completed or substantially completed any one of the following categories of work(s) during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: (i) Three similar works each costing not less than the amount equal to 30% of advertised value of each component of tender, or (ii) Two similar works each costing not less than the amount equal to 40% of advertised value of each component of tender, or (iii) One similar work each costing not less than the amount equal to 60% of advertised value of each component of tender. Note for b(1): Separate completed works of minimum required values shall also be considered for fulfillment of technical eligibility criteria for different components. Note - Works Completion certificate of Similar work along with copy of LOA as per IR GCC 2022 may be submitted (If MEC Applicable), this shall be on bidder's name. NOTE - SUBSTANTIALLY COMPLETED WORKS IS DEFINED IN TENDER DOCUMENT ATTACHED HERewith vide Para 10.5 of GCC April 2022 with latest applicable ACS.Similar nature of the work:- Any Signalling Work of EI/PI/RR/IBH/ABH/LC Gate Interlocking Track circuit works /Axle counter works etc.	No	No	Allowed (Mandatory)
1.1	Work experience certificate from private individual shall not be considered. However, in addition to work experience certificates issued by any Govt. Organisation, work experience certificate issued by Public listed company having average annual turnover of Rs 500 crore and above in last 3 financial years excluding the current financial year, listed on National Stock Exchange or Bombay Stock Exchange, incorporated/registered at least 5 years prior to the date of closing of tender, shall also be considered provided the work experience certificate has been issued by a person authorized by the Public listed company to issue such certificates. In case tenderer submits work experience certificate issued by public listed company, the tenderer shall also submit along with work experience certificate, the relevant copy of work order, bill of quantities, bill wise details of payment received duly certified by Chartered Accountant, TDS certificates for all payments received and copy of final/last bill paid by company in support of above work experience certificate.	No	No	Allowed (Mandatory)
1.2	Any Signalling Work of EI/PI/RR/IBH/ABH/LC Gate Interlocking Track circuit works /Axle counter works etc.	No	No	Allowed (Mandatory)

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.
3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.
5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.
6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWKS2026-27SIG05

Closing Date/Time: 19/06/2026 15:00

7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.
8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.
9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.
10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description
1	Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. (Click here to download the Format of Self Certification)

5. COMPLIANCE

Commercial-Compliance

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The local content requirement for this work is minimum 50% for Make in India compliance. The offer submitted by the firm against this tender shall be in compliance of Order No. P-45021/2/2017-PP (BE-II)-Part(4)Vol.II dated 19.07.2024 of Department of Promotion of Industry and Internal Trade, Ministry of Commerce and Industry attached with this tender as PDF. Non-compliance of this Make in India order in the offer submitted by the firm shall lead to summarily rejection of the offer. The tenderer shall enter local content percentage under Sl. No. 2 of Commercial-Compliance with their offer.	No	No	Not Allowed
2	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)
3	The said suppliers of goods and/or services would be subject to GST Act and rules as applicable from time to time. Tenderers are requested to submit their offers as per GST Tax regime. All the bidders/tenderers should ensure that they are GST compliant and their quoted tax structure/rates are as per GST Law.	No	No	Not Allowed

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWKS2026-27SIG05

Closing Date/Time: 19/06/2026 15:00

4	In case of sole proprietorship Firm: A copy of notarized affidavit on Stamp Paper declaring that his Concern is a proprietary Concern and he is sole proprietor of the Concern OR HUF: A copy of notarized affidavit on Stamp Paper declaring that he who is submitting the tender on behalf of HUF is in the position of 'Karta' of Hindu Undivided Family (HUF) and he has the authority, power and consent given by other members to act on behalf of HUF. OR for Partnership Firms: (i) A notarized copy of the Partnership Deed or a copy of the Partnership deed registered with the Registrar. (ii) A notarized or registered copy of Power of Attorney in favour of the individual to tender for the work, sign the agreement etc. and create liability against the firm. OR For Company registered under the Company's Act: (i) The copies of MOA (Memorandum of Association) / AOA (Articles of Association) of the company. (ii) A copy of Certificate of Incorporation. (iii) A copy of Authorization /Power of Attorney issued by the Company (backed by the resolution of Board of Directors) in favour of the individual to sign the tender on behalf of the company and create liability against the company. OR For Registered Society and Registered Trust: (i) A copy of Certificate of Registration. (ii) A copy of Memorandum of Association of Society/Trust Deed. (iii) A copy of Power of Attorney in favour of the individual to sign the tender documents and create liability against the Society/Trust. (iv) A copy of Rules & Regulations of the Society. OR For Limited Liability Partnership (LLP) Firms: (i) A copy of LLP Agreement. (ii) A copy of Certificate of Incorporation. (iii) A copy of Power of Attorney /Authorization issued by the LLP in favour of the individual to sign the tender on behalf of the LLP and create liability against the LLP. Concealment / wrong information in regard to above shall make the contract liable for determination under Clause 62 of the Standard General Conditions of Contract. In Absence of these documents, offer of the firm will be summarily rejected. For more clarification regarding this, pls refer GCC April 2022 with latest ACS available on railway official website.	No	No	Allowed (Mandatory)
---	--	----	----	------------------------

General Instructions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	I/We agree to carry out all works with use of modern equipments of required capacity for the work without extra payment. The decision of railway engineer shall be final and binding in this regard.	No	No	Not Allowed
2	It is the responsibility of contractor to arrange the payment of the labour employed for the work through bank and to deduct PF as per the provisions of Minimum Wages Act.	No	No	Not Allowed
3	The quantities shown above are approximate and to give a general guideline. Railway reserves a right to increase, decrease or to delete any of the items mentioned in schedule.	No	No	Not Allowed

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWKS2026-27SIG05

Closing Date/Time: 19/06/2026 15:00

4	Special Conditions of Contract for Mandatory Updating of Labor Data or Railway's Shramikkalyan Portal by Contractor as per Railway Board's letter No2018/CE-I /CT/4 dated 17.10.2018: In order to increase in payment of contract labour wages and other payments aweb-based e- application has been developed and hosted on website www.shramikkalyan.indianrailways.gov.in All contractors are required to upload details of their LOAs, engaged workmen, wage payment details, PF/ESI details, bonus details etc., on monthly basis. The details so uploaded shall be available in public domain.. In order to ensure the compliance and fulfillment of these instructions, following action is required to be completed by contractors: A) Contractor is to abide by the provisions of Payment of Wages Act and Minimum wages Act in terms of Clause 54 and 55 or Indian Railways General Conditions of Contract. In order to ensure the same, an application has been developed and hosted on website www.shramikkalyan.indianrailways.gov.in . Contractor shall register his firm/company etc. and upload requisite details of labor and their payment in this portal. These details shall be available in public domain. The Registration/updating of Portal shall be done as under:-a)contractor shall apply for one time registration of his company/firm etc. in the Shramikkalyan portal with requisite details subsequent to issue of Letter of Acceptance Engineer shall approve the contractor's registration on the portal within 7 days of receipt of such request. b)Contractor once approved by any Engineer, can create password with login 1D (PAN No.) for subsequent use of portal for all LoAs issued in his favor. c)The contractor once registered on the portal, shall provide details of his letter of Acceptance (LOA)/Contract Agreements on Shramikkalyan portal within 15 days of issue of any LoA for approval of concerned Engineer. Engineer shall update (if required) and approve the details of LoA filled by contractor within 7 days of receipt of such requested) After approval of LoA by Engineer, contractor shall fill the salient details of contract labours engaged in the contract and ensure updating of each wage payment to them on Shramikkalyan portal on monthly basis. e)It shall be mandatory upon the contractor to ensure correct and prompt uploading of all salient details of engaged contractual labour and payments made thereof after each wage period. B)While processing payment of any On Account bill or Final bill or release of Advances or Performance Guarantee/Security Deposit, Contractor shall submit a certificate to the Engineer or Engineer's representatives that I have uploaded the correct details of contract labours engaged in connection with this contract and payments made to them during the wage period in Railway's Shramikkalyan portal atwww.shramikkalyan.indianrailways.gov.in till..Month... Year.....	No	No	Not Allowed
5	GCC April 2022 with latest ACS has been introduced and published/available on railways website. The provisions of GCC 2022 or latest amendments released till the time of date of publishing of tender will be applicable on this tender. Tenderers are requested to download the same from the railways website and ensure the implementation of the latest provisions made in GCC while execution of work.	No	No	Not Allowed

Undertakings

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	I/we have carefully gone through the IR GCC 2022 with latest ACS, tender documents, specifications, special conditions, Annexures etc. attached with the tender documents.	No	No	Not Allowed
2	I/We undertake to keep this offer valid for a period indicated in tender documents from the date of opening of tender and further not to revoke the same before the expiry of such period.	No	No	Not Allowed
3	I/We have Visited the works site and I We am/ are aware of the site Conditions.	No	No	Not Allowed

Custom

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWKS2026-27SIG05

Closing Date/Time: 19/06/2026 15:00

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Maintenance period for this work will be 12 months from the date of successful completion of work.	No	No	Not Allowed
2	Similar nature of the work:- Any work of EI / PI / RRI / ABS/ IBH/ LC Gate interlocking work which include indoor and outdoor signalling work.	Yes	Yes	Allowed (Mandatory)

6. Documents attached with tender

S.No.	Document Name	Document Description
1	GCCApril2022.pdf	GCC April 2022
2	GCCAPRIL2022ACS1toACS112.pdf	GCC April 2022 ACS01 to ACS11
3	AnnexureVI-B.pdf	Annexure VIB
4	MII_Revision_Order_19July2024.pdf	MI Order
5	TENDERBOOKLETDEPOSITWORK_2.pdf	tender document
6	AnnexureNIT26-2705.pdf	annexure
7	cablecuttingcircular.pdf	JPO CABLE CUT

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

Signed By: SANJEEV KUMAR JAIN

Designation : Sr.DSTE