

**BHUSAWAL DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-N-SNT-06-2026-27

Closing Date/Time: 18/06/2026 15:00

Sr DSTE acting for and on behalf of The President of India invites E-Tenders against Tender No **BSL-N-SNT-06-2026-27** Closing Date/Time 18/06/2026 15:00 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

1. NIT HEADER

Name of Work	Provision of additional stabling lines for handling Kumbh Mela traffic in 2027 at Kherwadi, Kasbe Sukene, Nashik Road and Development of examination and maintenance facilities for NMG/ NMGH/ NMGHS rakes at Devlali Station on Bhusawal Division of Central Railway.		
Bidding type	Normal Tender		
Tender Type	Open	Bidding System	Single Packet System
Tender Closing Date Time	18/06/2026 15:00	Date Time Of Uploading Tender	26/05/2026 11:49
Pre-Bid Conference Required	No	Pre-Bid Conference Date Time	Not Applicable
Advertised Value	58857235.12	Tendering Section	S AND T
Bidding Style	[Decision at Schedule level]	Bidding Unit	
Earnest Money (Rs.)	1177200.00	Validity of Offer (Days)	60
Tender Doc. Cost (Rs.)	0.00	Period of Completion	3 Months
Contract Type	Works - General	Contract Category	Expenditure
Bidding Start Date	04/06/2026		
Are JV allowed to bid	No	Number of JV Member Allowed	0
Are Consortium allowed to bid	No	Number of Consortium Member Allowed	0
Ranking Order For Bids	Lowest to Highest	Expenditure Type	Combined (Revenue + Capital Works)

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A-Provision of additional stabling lines for handling Kumbh Mela traffic in 2027 at Kherwadi, Kasbe Sukene, Nashik Road and Development of examination and maintenance facilities for NMG/NMGH/NMGHS rakes at Devlali Station on Bhusawal Division of Central Railway.							17711132.72	Above/ Below/ Par
1	6A	3.00	Set	35301.04	105903.12	(-) 10.61	94666.80	
	Description:- Supply of Relay Rack Assembly complete with scaffolding, fixtures and accessories including MS Bars for fixing of relay plug board, string rods, fuse strips with bracket, 11 Way Bus Bars with cover and mounting brackets, runway for cable/wires, frame, base assembly etc. Siemens type & as per extant practice on C. Rly. Typical part list and Rack arrangement as per Sketch no SK-727 and Rack plan as approved by Engineer incharge. (Inspection by Consignee)							
2	9A	3.00	Set	30404.00	91212.00	(-) 10.61	81534.41	
	Description:- Supply of Main Cable Termination rack complete with scaffolding, fixtures & accessories including square bars for mounting 8-way terminal blocks, ladder, string rods, frame, base assembly, insulators, J bolt, nut/bolts & fasteners, backelite sheet, etc. Siemens type and as per extant practice on Central Railway. Typical part list and rack arrangement shall be as per sketch No. SK-727 with latest alterations. (Inspection by Consignee)							
3	22A	6.00	Kilometre	8647.71	51886.26	(-) 10.61	46381.13	
	Description:- Supply of Indoor Jumper Wire of various colour as per Railways standard practice of type ATC 1 x 0.6 mm dia.conforming to IRS 76/89 (Amdt 3) or latest.(Inspection by Consignee)							
4	23A	3.00	Kilometre	13093.54	39280.62	(-) 10.61	35112.95	
	Description:- Supply of Indoor Jumper Wire ATC 1 x 1 mm dia. conforming to IRS 76/89 (Amdt 3) or latest. (Inspection by Consignee)							
5	24A	6.00	Kilometre	44575.65	267453.90	(-) 10.61	239077.04	
	Description:- Supply of PVC Flexible Copper Cable, Single core, multi strand 1x2.5 sq mm(50 conductor each dia 0.25 + /- 0.01) as per specn IS 694/2010 with latest amendment. If any with insulation thickness of 0.70 mm nominal conductor resistance 7.98 ohms /km and test parameters are as per IRS (S)76/89 (Amdt .3). (Inspection by RDSO)							

**BHUSAWAL DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-N-SNT-06-2026-27

Closing Date/Time: 18/06/2026 15:00

6	25A	3.00	Kilometre	91617.31	274851.93	(-) 10.61	245690.14	
	Description:- Supply of PVC Flexible Copper Cable, Single core, multi strand 1x6 sq mm(84 conductor each dia 0.30 + /- 0.01) as per specn IS 694/2010 with latest amendment. If any with insulation thickness of 0.80 mm nominal conductor resistance 3.30 ohms /km and test parameters are as per IRS (S)76/89 (Amdt .3). (Inspection by RDSO)							
7	26A	3.00	Kilometre	141059.30	423177.90	(-) 10.61	378278.72	
	Description:- Supply of PVC Flexible Copper Cable, Single core, multi strand 1x10 sq mm(80 conductor each dia 0.40 + /- 0.01) as per specn IS 694/2010 with latest amendment. If any with insulation thickness of 1.00 mm nominal conductor resistance 1.91 ohms /km and test parameters are as per IRS (S)76/89 (Amdt .3). (Inspection by RDSO)							
8	27A	1.80	Kilometre	209928.30	377870.94	(-) 10.61	337778.83	
	Description:- Supply of PVC Flexible Copper Cable, Single core, multi strand 1x16 sq mm(126 conductor each dia 0.40 + /- 0.01) as per specn IS 2465/1984 & IS:694/2010 with latest amendment. If any with insulation thickness of 1.00 mm nominal conductor resistance 1.121 ohms /km and test parameters are as per IRS (S)76/89 (Amdt .3).(Inspection by RDSO)							
9	28A	1.20	Kilometre	326216.47	391459.76	(-) 10.61	349925.88	
	Description:- Supply of PVC Flexible Copper Cable, Single core, multi strand 1x25 sq mm(196 conductor each dia 0.40 + /- 0.01) as per specn IS 2465/1984 & IS:694/2010 with latest amendment. If any with insulation thickness of 1.2 mm nominal conductor resistance 0.780 ohms /km and test parameters are as per IRS (S)76/89 (Amdt .3). (Inspection by RDSO)							
10	29A	6.00	Kilometre	6445.17	38671.02	(-) 10.61	34568.02	
	Description:- Supply of wire 16/0.2(blue,red,gray,yellow,brown,black,white as per site engineer instruction)finolex/polycab/delton make.IRS:S-76/89(Amd.3),BS:4808 Part-2.Wire to be procured from RDSO approved vendor (Inspection by Consignee)							
11	30A	130.00	Numbers	1997.16	259630.80	(-) 10.61	232083.97	
	Description:- Supply of low maintenance Lead Acid Secondary Cells 2V 80 AH. As per specn. IRS 88/2004 with latest amendment (Inspection by RDSO)							
12	52A	310.00	Kg	129.53	40154.30	(-) 10.61	35893.93	
	Description:- Supply of Rubber Mat 5 mm thick for use in signalling installation.(Inspection by Consignee)							
13	73A	26.00	Numbers	9145.93	237794.18	(-) 10.61	212564.22	
	Description:- Supply of Key Lock Relay with different ward combinations (three extra set of ward plate for Point Machine to be supplied with each relay). Siemens Make working on 60V DC/24 DC or functional equivalent without base plates. RDSO/SPN/219/2016 Version 1.0 d 1. (Inspection by RDSO)							
14	83A	15.00	Numbers	3852.35	57785.25	(-) 10.61	51654.23	
	Description:- Supply of QNA1 AC immunized relay 8F-8B,24VDC along with plug board, retaining clip and connectors conforming to BRS:931A,IRS:S60,IRS:S34 & IRS:S23 . (Inspection by RDSO)							
15	87A	38.00	Numbers	4414.93	167767.34	(-) 10.61	149967.23	
	Description:- Supply of QSPA1relay, 24VDC,Slow to pick up, 8F.4B along with plug board, retaining clip and connectors conforming to BRS:933A,IRS:S60,IRS:S34 & IRS:S23.(Inspection by RDSO)							
16	88A	28.00	Numbers	3859.82	108074.96	(-) 10.61	96608.21	
	Description:- Supply of QTA2 AC immunised track relay, 9 Ohm,2F.1B, along with plug board,retaining clip and connectors conforming to BRS:939A, 966, & appendix F2, IRS:S34& IRS:S23(Inspection by RDSO)							
17	89A	10.00	Numbers	6603.79	66037.90	(-) 10.61	59031.28	
	Description:- "Supply of QBAT track Relay, AC immunised, 2F-2B contacts, 9 ohms. complete with plug board, retaining clip & connectors as per RDSO / SPN/84 ver 2.0 or latest. (Inspection by RDSO)"							
18	90A	60.00	Numbers	3724.04	223442.40	(-) 10.61	199735.16	
	Description:- "Supply of Universal LED Lamp proving relay QECX61 relay, 4F-4B,AC conforming to BRS:941A STS/E/RELAYS/AC LIT LED SIGNAL/09-2002 ,Amdt.-1 (FOR ALL ASPECT ECR FOR AC LED SIGNAL) (Inspection by RDSO)"							
19	92A	29.00	Numbers	4736.76	137366.04	(-) 10.61	122791.50	
	Description:- "Supply of QBCA1 AC immunised relay, 2FHD 4F-4B,24VDC along with plug board,retaining clip and connectors conforming to BRS:943 POINT CONTACTOR RELAY. And IRS S46. & firms specification. (Inspection by RDSO)"							
20	93A	29.00	Numbers	4736.76	137366.04	(-) 10.61	122791.50	
	Description:- Supply of QL 1 LATCH relay, 11 F-4B or 8F-6B along with plug board , retaining clip and connectors conforming to BRS:935A (Inspection by RDSO)							
21	98A	135.00	Numbers	4147.94	559971.90	(-) 10.61	500558.88	

**BHUSAWAL DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-N-SNT-06-2026-27

Closing Date/Time: 18/06/2026 15:00

	Description:- Supply of QNA1K relay 1000 ohm,6F/6B 24V DC as per BRS :931A, IRS:S60, IRS:S34 & IRS:S23 and RDSO spec. STS/ E/ Relays/UEA (PI) dtd.30.05.1997 (Inspection by RDSO)						
22	101A	3.00	Numbers	17965.19	53895.57	(-) 10.61	48177.25
	Description:- "Supply of Fail Safe Electronic Flasher Device 24V DC or 60V DC as per RDSO spec No.RDSO spec No.RDSO/SPN/173/2002 amendment 2 or latest." (Inspection by RDSO)						
23	124A	60.00	Numbers	8.56	513.60	(-) 10.61	459.11
	Description:- Supply of PPTC Fuse GP 30-100 (24V/1.4A)TPR Circuit. Make: LITTLE FUSE,FUZETEC,TYCO,BOURN,RAYCHEM etc (Inspection by RDSO)						
24	125A	60.00	Numbers	8.56	513.60	(-) 10.61	459.11
	Description:- Supply of PPTC Fuse GP 250-185UL-94 Certifcaion (24V/4A)TPR Circuit) .Make:LITTLEFUSE,FUZETEC,TYCO,BOURN,RAYCHEM etc(Inspection by RDSO)						
25	127A	6.00	Kg	1252.58	7515.48	(-) 10.61	6718.09
	Description:- Resin cored wire as per specification No. IS:1921-1975 with Alloying element percentage as 63% SN (Tin) and / 37% Pb (Lead) with percentage of various impurities not exceeding the values Sb (Antimony) 0.2% maximum , Cu (Copper) 0.1% maximum, As (Arsenic) 0.05% maximum, Fe (Iron) 0.02% maximum & other impurities mainly Al, Zn & Cd shall be limited. The flux shall be free from corrosive action as per clause 5.2 & flux percentage may be used as per requirement. (Inspection by Consignee)						
26	128A	60.00	Numbers	66.15	3969.00	(-) 10.61	3547.89
	Description:- Lacing thread rolls, black, wax coated (100 mtrs) (Inspection by Consignee)						
27	130A	12.00	Numbers	26760.23	321122.76	(-) 10.61	287051.64
	Description:- Design,fabrication and supply of fuse Auto changeover system for 32 Nos of external non detorating Type fuses of G type fuses from 0.6 A Amp to 4A Amp capacities used in signalling circuits.System shall have 8 cards with monitoring arrangement of 4 fuses in one card.As per RDSO spec.RDSO/SPN/209/2012 Ver.2.0 or latest amendment if any. (NO. OF MODULES=NUMBER) (Inspection by RDSO)						
28	131A	5.00	Numbers	40513.38	202566.90	(-) 10.61	181074.55
	Description:- Design,fabrication and supply of fuse Auto changeover system for 24 Nos of external non detorating Type fuses of G type fuses from 4 A to 10 Amp capacities generally used for point operation circuits.System shall have 6 cards with monitoring of 4 fuses in one card.As per RDSO spec.RDSO/SPN/209/2012 Ver.2.0 or latest amendment if any. (NO. OF MODULES=NUMBER) (Inspection by RDSO)						
29	134A	19.00	Numbers	6948.50	132021.50	(-) 10.61	118014.02
	Description:- Supply of Main Signal Post 140 mm outer dia 4.6 Mtr Length as per spec No IRS S 6/81 with latest amendments. (Inspection by RITES)						
30	136A	16.00	Numbers	2711.85	43389.60	(-) 10.61	38785.96
	Description:- Supply of Shunt Signal Post with Base (GI Pipe of 80 mm Dia of min. 1 meter length.). (Inspection by RITES)						
31	137A	19.00	Numbers	9034.12	171648.28	(-) 10.61	153436.40
	Description:- Supply of Cast Iron Main signal surface base140 mm as per spec No IRS S-10 and Drg No 2011/M with latest amendments, with CLS ladder assembly complete for CLS signal 5.5/4.5/3.5 mtrs long as per R. No SA-23156(Adv),SA 23153(Adv) & SA 23150 (Adv) Alt. 1 respectively with latest Amendment as the case may be for CLS unit & signal back staging as per extant C.Rly practice . (Inspection by RITES)						
32	138A	20.00	Numbers	2071.84	41436.80	(-) 10.61	37040.36
	Description:- Supply of Cast Iron Shunt signal surface base 80 mm as per spec.No IRS S 10 and Drg No 2011/M with latest amendment,as per RDSO Drg.No SA-23156/Drg.No RST/11413 as per extent C.Rly practice. (Inspection by RITES)						
33	139A	39.00	Numbers	521.69	20345.91	(-) 10.61	18187.21
	Description:- Supply of Signal No.plates. as per Drg No RST-11393/SK 842 (Inspection by Consignee)						
34	140A	1.00	Numbers	999.74	999.74	(-) 10.61	893.67
	Description:- OFF set bracket 5-1/2 " to suit 140 mm dia CLS post with two nos. of "U" Bolts with nuts and washer complete as per RDSO Drg No SA-23080 for Signals & Routes (Inspection by Consignee)						
35	142A	15.00	Numbers	561.74	8426.10	(-) 10.61	7532.09
	Description:- Supply of A/AG/C/P/G/IB Board as per Drg RST-11444/1(A), RDSO Drg No SA 23460(AG), SA 23461(C) , RST-11445 , SA 23456(P), SA 23477(G) & SA 234476-77(IB) as applicable respectively with latest Amendment. (Inspection by Consignee)						
36	145A	30.00	Numbers	286.20	8586.00	(-) 10.61	7675.03
	Description:- Supply of Hand Cuff Locks/ Godrej Navtal lock with three common key (Inspection by Consignee)						

**BHUSAWAL DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-N-SNT-06-2026-27

Closing Date/Time: 18/06/2026 15:00

37	146A	14.00	Numbers	30939.41	433151.74	(-) 10.61	387194.34	
	Description:- Supply of 2 aspect signal unit in FRP body without lenses and transformers as per RDSO Specification RDSO/SPN/194/2006/Rev 2.0 or latest complete to suit LED signals lamps and suitable for 140 mm dia post saves pigment finish on the back side of the and inside . White pigment finish inside the 2 aspect unit to avoid any extra paint cost. (Inspection by RITES)							
38	147A	5.00	Numbers	31708.99	158544.95	(-) 10.61	141723.33	
	Description:- Supply of 3 aspect signal unit in FRP body without lenses and transformers as per RDSO Specification RDSO/SPN/194/2006/Rev 2.0 or latest complete to suit LED signals lamps and suitable for 140 mm dia post saves pigment finish on the back side of the and inside . White pigment finish inside the 4 aspect unit to avoid any extra paint cost. (Inspection by RITES)							
39	149A	20.00	Numbers	13950.27	279005.40	(-) 10.61	249402.93	
	Description:- Supply of Shunt signal position light type FRP complete as per RDSO spn no RDSO/SPN/194/2006/Rev 2.0 or latest with off set bracket 3-1/2" to be fitted on 140 mm post drawing No. SA 23840 (Adv) Alt-2 for dependent type complete with signal unit bracket, terminals etc without lenses,lamp, lamp holder, and to suit LED signal lamp. (Inspection by RITES)							
40	150A	2.00	Numbers	35033.30	70066.60	(-) 10.61	62632.53	
	Description:- Supply of One way Junction route indicator in FRP body without lenses and transformers as per RDSO spn RDSO/SPN/194/2006/Rev.2 .0 or latest complete and to suit LED signal lamp. (Inspection by RITES)							
41	151A	1.00	Numbers	44432.00	44432.00	(-) 10.61	39717.76	
	Description:- Supply of two way Junction route indicator in FRP body without lenses and transformers as per RDSO spn RDSO/SPN/194/2006/Rev.2 .0 or latest complete and to suit LED signal lamp.(Inspection by RITES)							
42	154A	2.00	Numbers	8669.75	17339.50	(-) 10.61	15499.78	
	Description:- Supply of "Calling ON" signal unit in FRP body without lenses and transformers as per RDSO Specification RDSO/SPN/194/2006/Rev.2 .0 or latest complete and to suit LED signal lamp. (Inspection by RITES)							
43	156A	60.00	Numbers	5250.48	315028.80	(-) 10.61	281604.24	
	Description:- Supply of Phenolic 10mm thick sheet, grade P3 in standard size of 1.22X1.22 Mtr as per spec. No IS 2036 of 1995. (Inspection by RITES)							
44	157A	60.00	Numbers	5300.00	318000.00	(-) 10.61	284260.20	
	Description:- Supply of FIBRE GLASS INSULATING FIRE RETARDENT SHEET of 10 mm THICKNESS AS PER ISO:10192-1982,Dielectric strength -25KV/mm with glass content 25 to 34%, in standard size of 1.10x1.10Mtr.as per spec.No.IS:10192-1982 (Inspection by RITES)							
45	158A	25250.00	Numbers	72.61	1833402.50	(-) 10.61	1638878.49	
	Description:- Supply of ARA Terminal blocks with links made of PBT Specn No.IRS/75/2006(Rev - 2) with latest amendments and RDSO Drg.No.SA-23741 Alt.4., SA-23745 Alt 5, SA-23746, SA-23748 Alt -4 & SA-23756 Alt-3. (Inspection by RDSO)							
46	159A	280.00	Numbers	162.94	45623.20	(-) 10.61	40782.58	
	Description:- Supply of cartridge fuse block made of PBT as per RDSO Drg No SA-23748 Alt 4,SA-23749 & Spec No IRS S 75/2006 with latest amendment. Fuse block shall be suitable for round head type voltage fuses.(Inspection by RDSO)							
47	160A	280.00	Numbers	70.13	19636.40	(-) 10.61	17552.98	
	Description:- Supply of round head type non deteriorating type low voltage cartridge fuse as per Specn No IRS/S/78/92 with latest amendments 2A/4A/6A capacity(Inspection by RDSO)							
48	161A	115.00	Numbers	33.41	3842.15	(-) 10.61	3434.50	
	Description:- Supply of Tik-tak, piano type switches,5 A (As per IS specification).(Inspection by Consignee)							
49	164Aa	63.00	Numbers	16020.05	1009263.15	(-) 10.61	902180.33	
	Description:- Supply of Apparatus Case with godown locks with deattachable handle on both the doors. i) Single Case as per Drg No SK 783-1&2. with latest alteration. (Inspection by RITES)							
50	164Ab	57.00	Numbers	12853.94	732674.58	(-) 10.61	654937.81	
	Description:- Supply of Apparatus Case with godown locks with deattachable handle on both the doors. ii) Half Case as per Drg No SK 783-1&2. with latest alteration. (Inspection by RITES)							
51	165A	134.00	Numbers	1078.08	144462.72	(-) 10.61	129135.23	
	Description:- Supply of earth electrode assembly as per Drg.No.CR/S&T/SK/815 (Inspection by Consignee)							
52	174A	47.00	Set	17786.33	835957.51	(-) 10.61	747262.42	

**BHUSAWAL DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-N-SNT-06-2026-27

Closing Date/Time: 18/06/2026 15:00

	Description:- Maintenance Free Earth As per RDSO/SPN/197/2008 or latest consisting of :1) Copper bond steel electrode 3 Mtr long 17 mm dia with copper bonding thickness of min.250 micron & UL listed & marked -01 No 2) Earth enhancement compound RDSO Approved in sealed bag of 10Kgs-03 No 3) Copper strip 150x25x6 mm -02 No 4) Copper strip 300x25x6 mm -01 No 5)35 Sqmm Copper Cable to connect earth electrode to MEEB-15 Mtr Approx. (Inspection by RDSO)						
53	175A	60.00	Metre	406.33	24379.80	(-) 10.61	21793.10
	Description:- Supply of 35 Sq. mm. multistrand single core PVC insulated copper for connecting earth bus bar to earth electrode. (Inspection by RDSO)						
54	178A	3.00	Numbers	145626.55	436879.65	(-) 10.61	390526.72
	Description:- Supply of Microprocessor based universal earth resistance sensing unit 12 channel AC/DC. as per RDSO/SPN/256/2002 with latest amendments. (Inspection by RDSO)						
55	179A	114.00	Numbers	1047.98	119469.72	(-) 10.61	106793.98
	Description:- Supply of Track Lead Junction Boxes as per C.Rly Drg. No.RST 11509 made from fiber glass alongwith terminal blocks. (Inspection by Consignee)						
56	180A	38.00	Numbers	3666.35	139321.30	(-) 10.61	124539.31
	Description:- Supply of B type choke to specn.No.IRS.S.65/83 (Amdt -3) with latest amendments. (Inspection by RDSO)						
57	181A	38.00	Numbers	1288.14	48949.32	(-) 10.61	43755.80
	Description:- Supply of adjustable Track Feed Resistance disc type 7.5/15/30 ohms as per RDSO Drg. No. SA 20161-66/M (Adv) with latest amendments (with Phenolic moulded base). (Inspection by Consignee)						
58	182A	38.00	Numbers	2430.30	92351.40	(-) 10.61	82552.92
	Description:- Supply of Track feed battery chargers, 110V AC input 2, 4 to 6 V DC Output to Specn.No.IRS.89/2013/Ver 1.0 with latest amendments. Charger shall be suitable for charging 80 AH battery. (Inspection by RDSO)						
59	183A	2500.00	Numbers	2.01	5025.00	(-) 10.61	4491.85
	Description:- Supply of Channel Pins single groove, galvanised, 7 mm suitable for 4mm dia bonding wire as per spec No IRS S 17-75 Revision 3 . (Inspection by Consignee)						
60	185A	225.00	Kg	86.82	19534.50	(-) 10.61	17461.89
	Description:- Supply of 8 SWG GI wire (4mm dia) suitable for track circuit rail bonding .As per IRS specification S:13-62 (Inspection by Consignee)						
61	186A	30.00	Numbers	283.64	8509.20	(-) 10.61	7606.37
	Description:- Supply of Hydrometer, Exide make or similar for measuring specific gravity of Battery Graded acid with mounting stand in location Boxes.Consignee inspection under manufacturer certificate. (Inspection by Consignee)						
62	204A	102.00	Set	531.87	54250.74	(-) 10.61	48494.74
	Description:- Supply of William stretcher nylon insulation set suitable for ground connection as per RDSO drg No T-10367, T-10368, T-10384 as applicable and to the spec IRS S 23 & 40/84 with latest amendements .(Inspection by Consignee)						
63	205A	68.00	Set	338.30	23004.40	(-) 10.61	20563.63
	Description:- Supply of Tongue attachment nylon insulation set consisting of one insulating plate as per Drg no: RST-106961 & 3 nos of Ferrules with collars to suite rodding supplied as per RDSO spec & Drg.no: RST-10692 (Inspection by Consignee)						
64	206A	108.00	Set	244.11	26363.88	(-) 10.61	23566.67
	Description:- Supply Gauge Tie plate nylon insulation as per RDSO drg No: T- 10372Alt2, T-10368, T- 10371Alt2, T-15083/88/Alt2 & T-11690/Alt2 and to the spec IRS S 23 & 40 with latest amendements 01 or latest amandments .(Inspection by Consignee)						
65	207A	8.00	Set	8171.32	65370.56	(-) 10.61	58434.74
	Description:- Supply of Ground connections, complete set suitable for IRS type/appd. point Machine for ordinary turnout with tounge attachment insulation and other insulation as per RDSO Drg. S /3361 /62 /63(for IRS type point machine) or RDSO Drg No. SA-9151 /52 (for Siemens point machine) with latest amendements . However the ground connection shall be procured only after confirmation from Railway engineer as per site condition /type of machine/turnout.(Inspection by Consignee)						
66	211A	150.00	Metre	1029.32	154398.00	(-) 10.61	138016.37
	Description:- Supply of GI pipe, inner dia. 100mm dia. B-class as per spec. No.IS 1239 PT.1/2004 or latest with sockets and fittings.TATA/ JINDAL/ ZENITH BIRLA Make. (Inspection by Consignee)						
67	212A	228.00	Metre	321.43	73286.04	(-) 10.61	65510.39
	Description:- Supply of DWC HDPE Pipe with one snap fit coupler and 'O' ring fire resistant, anti rodent,in 6mtr length of size 120 mm outer dia as per RDSO /SPN /204/2011/Ver 1.1 with Amdt 1 or latest. (Inspection by Consignee)						
68	216A	13000.00	Numbers	206.14	2679820.00	(-) 10.61	2395491.10

**BHUSAWAL DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-N-SNT-06-2026-27

Closing Date/Time: 18/06/2026 15:00

69	217A	5200.00	Numbers	422.25	2195700.00	(-) 10.61	1962736.23	
	Description:- Supply of RCC pipe half round of size 150mm dia outer and 100 mm dia internal 1 mtr long matching to IS No.458/2003 amendment-1 with Rev.4. (Inspection by RITES)							
70	219A	3720.00	Numbers	117.12	435686.40	(-) 10.61	389460.07	
	Description:- Supply of RCC pipe half round of size 300mm dia outer and 250 mm dia internal 1 mtr long. matching to IS No.458/2003 amendment-1 with Rev.4.(Inspection by RITES)							
71	220A	110.00	Numbers	216.73	23840.30	(-) 10.61	21310.84	
	Description:- Supply of DIN channel for the terminals 1 Mtr each (Inspection by RDSO)							
72	221A	340.00	Numbers	23.39	7952.60	(-) 10.61	7108.83	
	Description:- Supply of End plates for modular terminal block (Inspection by RDSO)							
73	222A	340.00	Numbers	16.81	5715.40	(-) 10.61	5109.00	
	Description:- Supply of End clamp for modular terminal block (Inspection by RDSO)							
74	223A	160.00	Numbers	83.81	13409.60	(-) 10.61	11986.84	
	Description:- Supply of marker card as per customer spec(10x10) (Inspection by RDSO)							
75	226A	150.00	Numbers	43.14	6471.00	(-) 10.61	5784.43	
	Description:- Fuse links of (400mA,630mA,1 A,1.6 A,2A,4A,6.3A & 10A) (Inspection by Consignee)							
76	233A	22.00	Numbers	2991.97	65823.34	(-) 10.61	58839.48	
	Description:- Supply of thermo shrink jointing kit (Reinforced) TSF-2 type generally conforming to RDSO Specification No.RDSO/SPN/TC/57/2015 Rev 1 with modified kit contents as per CSTE Specification No.CR/SPN/TC/57 (A)/2015 dtd 06.01.2015(Table -A) to be suitable for jointing both 10/20/50 pair PIJF and 4/6 Quad cables alongwith sub-kit(Table-B) for armour continuity. (Inspection by RDSO)							
77	276A	24.00	Kilometre	73053.08	1753273.92	(-) 10.61	1567251.56	
	Description:- "Supply of Permanently Lubricated HDPE Telecom duct of size 50/42 mm and accessories as per latest Specification TEC GR No. GR/TX/CDS-008/03/March 11 with latest amendment" for OFC cable of size 24 fibre armoured in length of 1000 mtrs/roll. Duct to be supplied from TEC approved sources." (Inspection by RITES)							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () B-Provision of additional stabling lines for handling Kumbh Mela traffic in 2027 at Kherwadi, Kasbe Sukene, Nashik Road and Development of examination and maintenance facilities for NMG/NMGH/NMGHS rakes at Devlali Station on Bhusawal Division of Central Railway.							12157328.88	Above/ Below/Par
1	4B	3.00	Numbers	1534.73	4604.19	(-) 10.61	4115.69	
	Description:- Installation of relay rack assembly including IDF pillars if any complete with wall support, scaffolding, ladders, runway for cables,Relay/Relay group base plates, fixing of Tag block etc.The work shall be done as per approved plan, extant practice on C. Railway & instruction of Rly. Engineer at site.							
2	5B	3.00	Numbers	1306.63	3919.89	(-) 10.61	3503.99	
	Description:- Installation of Cable Termination Racks Assembly complete including wall supports, scaffolding, Disconnecting links/ARA terminal, 96 way tag block with tagblock cover & other necessary accessories etc. The work shall be done as per approved plan, extant practice on C. Railways & the instruction of Rly engineer at site.							
3	9B	208.00	Numbers	75.87	15780.96	(-) 10.61	14106.60	
	Description:- Charging of 2V Lead Acid Batteries with contractors own battery grade sulphuric acid and distilled water with minimum two charge - discharge cycles, installation of charged batteries in groups & their connection & wiring. The work shall be done as per extant practice of C.Rly & instruction of Engineer-in-charge.Detailed measurements of initial charging shall be recorded jointly by contractor & Rly's site-in-charge. PER 100 VAH= NUMBERS							
4	25B	12.00	Numbers	646.87	7762.44	(-) 10.61	6938.85	
	Description:- Wiring,Fixing & commissionig of modules of fuse 0.6 to 4 Amp rating alarm system having change over arrangement and potential free contact witing at Datalogger IDF Etc as per instruction of Railway Engineer (Module of 32 nos fuses) NO OF MODULES= NUMBERS							
5	26B	5.00	Numbers	645.83	3229.15	(-) 10.61	2886.54	
	Description:- Wiring,Fixing & commissionig of modules of fuse 4 to 10 Amp rating alarm system having change over arrangement and potential free contact witing at Datalogger IDF Etc as per instruction of Railway Engineer (Module of 24 nos fuses) NO OF MODULES= NUMBERS							
	27B	6.00	Rack	368.47	2210.82	(-) 10.61	1976.25	

**BHUSAWAL DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-N-SNT-06-2026-27

Closing Date/Time: 18/06/2026 15:00

6				Description:- "Lettering & Numbering of detail and description writing of particulars of terminations & equipments on relay rack, relays, cable termination rack, battery & power equipments, IPS, operating panel, axle counter etc constituting entire system with contractor's own paint and writing material ("Asian/Dulux" make enamel paints to be used). The work shall be done as per extant practice on C.Rly & instruction of Rly engineer at site. "			
7	30B	19.00	Numbers	9149.34	173837.46	(-) 10.61	155393.31
				Description:- Excavation and Casting of main signal foundation as per Drg No SK 801 with contractor's own materials including cement and anchor bolts of standard size. The required scaffolding Ferma etc for Casting of foundation will have to be brought by the contractor at his own cost.			
8	31B	20.00	Numbers	2649.22	52984.40	(-) 10.61	47362.76
				Description:- Excavation and Casting of Shunt Signal foundation as per Drg.No.SK 802 with Contractor 's own materials including Cement and Anchor Bolts of Standard Size. The required scaffolding, Ferma etc for Casting of foundation will have to be brought by the Contractor at his own cost.			
9	32B	19.00	Numbers	3490.22	66314.18	(-) 10.61	59278.25
				Description:- Erection of CLS Post with Surface base and signal unit on top or on OFF set Bracket, fixing of front and back staging, ladder and guards, signal name plates/boards if any with contractors own brackets and fixing materials. This also includes erection of auxiliary signals like calling on, shunt signal if any. The work shall be done as per instructions of Rly engineer at site.			
10	33B	20.00	Numbers	481.44	9628.80	(-) 10.61	8607.18
				Description:- Erection of shunt signal with Surface Base, Post, Signal unit and fixing of No.plates. The work shall be done as per instructions of Rly engineer at site.			
11	34B	3.00	Numbers	763.70	2291.10	(-) 10.61	2048.01
				Description:- Fixing of Jn.Route Indication 1-Way/2-Way/3-Way on the top of the signal post.			
12	36B	19.00	Numbers	1096.27	20829.13	(-) 10.61	18619.16
				Description:- "Termination of tail cable on Main signal units and wiring with contractor own material, etc. The work shall be done as per instruction of Rly engineer at site."			
13	37B	20.00	Numbers	356.23	7124.60	(-) 10.61	6368.68
				Description:- "Termination of tail cable on Shunt signal units and wiring with contractor own material, fixing of lenses etc. The work shall be done as per instruction of Rly engineer at site."			
14	42B	60.00	Numbers	2251.73	135103.80	(-) 10.61	120769.29
				Description:- Fabrication and fixing of phenolic laminated/Fibre glass sheet in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated/with PVC pipe covered string rods at the back side for cable support with contractor's own materials. The work shall be done as per drg and arrangement similar to SK 783-1/2. with latest alterations & as per instructions of Rly engineer at site. a) Single Case			
15	42Bb	55.00	Numbers	1984.78	109162.90	(-) 10.61	97580.72
				Description:- Fabrication and fixing of phenolic laminated/Fibre glass sheet in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated/with PVC pipe covered string rods at the back side for cable support with contractor's own materials. The work shall be done as per drg and arrangement similar to SK 783-1/2. with latest alterations & as per instructions of Rly engineer at site. b) Half Case			
16	44B	25250.00	Numbers	14.05	354762.50	(-) 10.61	317122.20
				Description:- Fixing of ARA Terminals and fuse blocks on phenolic laminated sheets and fixing by stainless steel/brass nuts & bolts.This includes provision of two additional holes on the board on either side for cable conductor entry.			
17	46Ba	63.00	Numbers	9887.02	622882.26	(-) 10.61	556794.45
				Description:- Excavation and Casting of Apparatus Case foundation with contractors Anchor bolts, cement, ballast and other materials.The required Scaffolding Ferma etc for Casting of foundation will have to be brought by the contractor at his own cost a) Single Case as per Drg No SK 803			
18	46Bb	57.00	Numbers	9693.93	552554.01	(-) 10.61	493928.03
				Description:- Excavation and Casting of Apparatus Case foundation with contractors Anchor bolts, cement, ballast and other materials.The required Scaffolding Ferma etc for Casting of foundation will have to be brought by the contractor at his own cost b) Half Case as per Drg No SK 804			
19	47Ba	63.00	Numbers	1098.04	69176.52	(-) 10.61	61836.89
				Description:- Erection of Apparatus Cases. This includes filling of location foundations and plastering A) Single Case			
20	47Bb	57.00	Numbers	842.40	48016.80	(-) 10.61	42922.22
				Description:- Erection of Apparatus Cases. This includes filling of location foundations and plastering B) Half Case			
	48Ba	63.00	Numbers	1497.72	94356.36	(-) 10.61	84345.15

**BHUSAWAL DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-N-SNT-06-2026-27

Closing Date/Time: 18/06/2026 15:00

21	Description:- Installation of Eqpt. (Relays, resistance, chargers batteries etc.as applicable) & wiring of the same in apparatus Cases as per location diagrams & circuit diagrams, as per Instruction of site incharge and practice. A) Single Case						
22	48Bb	57.00	Numbers	1017.78	58013.46	(-) 10.61	51858.23
	Description:- Installation of Eqpt. (Relays, resistance, chargers batteries etc.as applicable) & wiring of the same in apparatus Cases as per location diagrams & circuit diagrams, as per Instruction of site incharge and practice. B) Half Case						
23	49B	134.00	Numbers	2528.14	338770.76	(-) 10.61	302827.18
	Description:- Installation of earth electrode assenbly as per Drg.No.RE/S&T/SIG/Tender/SK726/85 including earth wire connected through GI wire 8 SWG supported on M.S. flat of size 6mm x 40 mm to earth electrode as per drg. No.CR/S&T/SK-815 for sigg. Equipment such as lever frames, apparatus case, signals, relay racks,block insruments, and etc. as per RE manual. The earth value should be less than 10 Ohms including the lead wire. The value should be measured in presence of Rly. supervisor. It should be documented and painted on earth enclosure made of concrete.(only earth electrode will be supplied by Railway). All other material required for provision of earthing will be brought by the contractor.						
24	53B	47.00	Set	5290.34	248645.98	(-) 10.61	222264.64
	Description:- Installation of unit earth as per RDSO/SPN/197/ver I or latest, to construct earthing of < /= 1 Ohm consisting of a. digging the earth to required depth, insertion of electrode, filling of earth enhancing compound & construction of chamber, measurement of earth value and all other work of earthing as per code of practice. All the consumables for mounting the copper tape inside the relay room, Exothermic weld materials and tools & fixtures for the welding Copper tapes andElectrodes etc shall be arranged by the contractor.						
25	57B	3.00	Numbers	7411.03	22233.09	(-) 10.61	19874.16
	Description:- Installation, wiring,testing & commissioning of Microprocessor based universal earth leakage detector unit 12 channel AC/DC						
26	58B	114.00	Numbers	1305.34	148808.76	(-) 10.61	133020.15
	Description:- Erection, Fitting and Rail connection of Track Lead Juntion Box on two supports(M.S.angle) with contractor's fixing material and PVC jacketed wire for track lead connection including angles of size 40 x 40 x 5 mm 1200 mm length. This will include drilling of holes for track lead/side connections on rail. The work shall be done as per Drg. No.SK-845 or/ & instructions of Rly engineer at site.						
27	59B	760.00	Numbers	169.65	128934.00	(-) 10.61	115254.10
	Description:- Provision of bonding with contractor's PVC jacketed wire rope for Track Lead connections.PVC jacketed wire rope should be of Galvanised steel wire rope 6mm dia (6 x 19 stranded wire with steel core of 6 mm dia) sheathed with PVC 2mm wall thickness, overall thickness being 10mm PVC sheath should be made of type 6 compound as per IS 5831 of 1984 Reaffirmed 2001 and steel wire rope as per IS:2266:2019.Reclaimed or recycled material should not be used .This will include drilling of 7.1mm dia holes in rails (4 Nos) and provision of two jumpers for each bond, clipping of bonds etc. with contractors own materials and tools as per instruction of Rly engineer at site.						
28	60B	225.00	Numbers	160.48	36108.00	(-) 10.61	32276.94
	Description:- Provision of bonding with GI wire 4mm dia (8 SWG) for track jumper & fish plate joints bonds. This will include drilling of 7.1mm dia holes in rails (4 Nos) and provision of two jumpers for each bond, clipping of bonds etc. with contractors own tools as per instruction of Rly engineer at site.						
29	71B	47.00	Per Detection Point (DP)	2890.19	135838.93	(-) 10.61	121426.42
	Description:- "Installation, wiring & Testing/commissioning of Multi Section Digital Axle counters's Central Unit/Evaluator/Processor for the section/at station including its associated all indoor equipments, Indication Panel, monitoring console/interface computer and wiring the same to integrate with the relay circuits including Supply of required power cable of multi- strand 10 sq.mm or more from power room to central evaluator, 2 core shielded cable of required size copper conductor as per as per IRS (S)76/89(Amd. 3). or IS 694/2010. with latest amendment as applicable with other accessories as per the instruction of Rly engineer at site and earthing as per OEM's technical requirement and specifications. This also includes laying & termination of cable, if any from Panel Room to Axle couter room/Relay room in DWC pipe with contractor's material/existing ladder."						
30	74B	47.00	Per Track Circuit	12066.56	567128.32	(-) 10.61	506956.01

**BHUSAWAL DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-N-SNT-06-2026-27

Closing Date/Time: 18/06/2026 15:00

	Description:- "Installation of complete assembly of track device/double rail contact unit for entry or exit with conductors all material including drilling of required sizes holes on rails for fixing these, taking the cable lead through anti-rodent, anti-oxidant & non-flame propagating type Double walled corrugated (DWC) pipe as per RDSO/SPN/204/2011 Ver 1.1 with Amd.1 or latest from track device to location box and terminating it on terminals including digging of trench under track and up to location/Track side unit and all other accessories as per site requirement for laying of transmitter and receiver cable with suitable wire embeded rubber pipe with clamp for protecting these cables at DP end."						
31	79B	28.00	Turn-out	3526.79	98750.12	(-) 10.61	88272.73
	Description:- Fixing of point machine on newly laid turnout on Wooden/MBC sleepers , fixing of ground connections, adjustment and testing with crank handle operations,Removal of ground connection & point machines duly numbered. This will include fixing of bend pipes with welded frame for cable entry to machine. This will also includes necessary adjustment and smithy work, drilling of holes to tounge rails, fitting of insulation for tounge attachment, gauge plate & stretcher bars, cable termination & wiring if required. The work shall be done as per extant practice on C. Rly & the instruction of Rly engineer at site.						
32	80B	26.00	Numbers	3119.39	81104.14	(-) 10.61	72498.99
	Description:- Installation,fixing and wiring of Boxes for Key Lock Relays with contractors wiring & fixing material.The work shall be done as per extent practice on C.Rly & the instruction of site engineer.						
33	81B	5480.00	cum	350.00	1918000.00	(-) 10.61	1714500.20
	Description:- Excavation of cable trench as per cable route plan,1.0 mt. deep and 300mm wide along side the track in normal soil/strata, conforming to distances as per cable route plan and refilling after cable laying. This work includes covering of cable laid in trench by loose soil for a layer of 50mm thickness after clearing of route,bushes etc.It shall be ensured that top of the cables laid is at a depth of 0.8 m or more If it is less,then the width and depth shall be suitably increased and accordingly proportionate payment shall be made .In case depth of trench is not achievable due to site conditions,Proportionate payment will be made as per procedure.The work shall be done as per the extant practice on Central Railway and instructions of Railway Engineer at site.Drg No.SK 805						
34	82B	1700.00	cum	583.33	991661.00	(-) 10.61	886445.77
	Description:- Excavation of cable trench as per cable route plan,1.0 mt. deep and 300mm wide along side the track in hard soil, conforming to distances as per cable route plan and refilling after cable laying. This work includes covering of cable laid in trench by loose soil for a layer of 50mm thickness after clearing of route,bushes etc.It shall be ensured that top of the cables laid is at a depth of 0.8 m or more If it is less,then the width and depth shall be suitably increased and accordingly proportionate payment shall be made .In case depth of trench is not achievable due to site conditions,Proportionate payment will be made as per procedure.The work shall be done as per the extant practice on Central Railway and instructions of Railway Engineer at site.Drg No.SK 805						
35	83B	15.00	cum	2916.67	43750.05	(-) 10.61	39108.17
	Description:- Cutting of all types of Roads/ platforms (except concrete type) for trenching and excavation to depth of 300mmx300mm wide approx. and refilling after laying of RCC/GI/DWC pipe & to restore them to original condition. The work shall be done as per extant practice on C.Rly & instructions of Rly engineer at site.SK-807						
36	84B	150.00	Metre	69.97	10495.50	(-) 10.61	9381.93
	Description:- Fixing of GI pipes for crossing the culverts, bridges etc. and concreting of ends with brick masonry at both ends as per the instruction of Rly engineer at site.						
37	85B	65.00	cum	583.33	37916.45	(-) 10.61	33893.51
	Description:- Digging of trench 1.0M deep from rail flange/road level (for LC) and 0.3 mtrs to 0.6 Mtrs wide and back filling after placing of DWC/RCC/GI pipe (Placing of DWC/RCC/GI pipe covered separately) The ballast disturbed be screened and dressed as required by Engineerin-charge or his representatives and road tarred immediately.Drg No.SK 806						
38	86B	228.00	Metre	56.85	12961.80	(-) 10.61	11586.55
	Description:- Laying of DWC/RCC pipes alongwith collars/RCCHalf round pipe in trenches at places of track and road crossings, platform cuttings etc.						
39	87B	359.00	Kilometre	5197.42	1865873.78	(-) 10.61	1667904.57
	Description:- Laying of signalling/Power/Telecom cable of various cores/sizes in trenches.						
40	89B	290.00	Numbers	12.53	3633.70	(-) 10.61	3248.16
	Description:- Placing and securing of cable route markers in trenches at the specified interval and at diversions, joints etc along the cable route. The work shall be done as per extant practice on C Railways & the instruction of Rly engineer at site.						
41	90B	22.00	Numbers	3562.19	78368.18	(-) 10.61	70053.32
	Description:- Jointing of 4 / 6 quad cable with Heat Shrinkable straight through Jointing Kit for 4 / 6 quad cable.						
	91B	15.00	Metre	2034.85	30522.75	(-) 10.61	27284.29

**BHUSAWAL DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-N-SNT-06-2026-27

Closing Date/Time: 18/06/2026 15:00

42	Description:- Provision of brick masonry duct as per Rly.Drg.No. PA/N/CN/STD/19(modified) after cutting of platform/excavating the earth for the duct with contractor's own materials and restoring the excavated earth to its original condition.							
43	92B	17.00	cum	5329.55	90602.35	(-) 10.61	80989.44	
	Description:- Wherever depth of 0.5 m cable trench is not feasible cable shall be protected as under :- Preparation of cement mixture 1:3:6 with contractor's own materials and spreading cement concrete mixture layer of 100 mm thick over the already laid cables in the excavated trench.							
44	93B	3720.00	Numbers	19.05	70866.00	(-) 10.61	63347.12	
	Description:- "Fixing of modular terminal/fuse blocks alongwith all accessories with provision of fixing holes on hylam sheets/side angles of Loc Box and fixing by galvanised nuts & bolts. This includes fixing of DIN channel alongwith PVC Comb type 'C' channel (size 2 inch x 2 inch) for cable termination on modular terminal. The PVC channel with cover to be supplied by firm as required. The work shall be done as per the instruction "							
45	94B	43220.00	Per Conductor	7.10	306862.00	(-) 10.61	274303.94	
	Description:- Termination of cable cores on ARA terminal/Disconnecting link/fuse blocks, in the apparatus Cases/ cable termination rack. This includes all associated works of pulling out the cable from underground. The work shall be done as per location plans and instructions of Rly engineer at site.							
46	103B	1040.00	Metre	2610.46	2714878.40	(-) 10.61	2426829.80	
	Description:- Horizontal boring of cable duct of minimum 2.0 mtr depth along with laying of 120 mm HDPE pipe for track crossing with minimum depth reckoned from bottom of the rail/Road crossing with minimum depth reckoned from ground level. The work shall be done as per extent practice & instruction of site engineer.Preparation of site for Horizontal boring shall be carried out in presence of Railway Representative.HDPE will be supplied by Railway. Note:- Contractor shall provide all material required for boring and adequate nos.of labours for proper laying of cable into the bore.Cable shall be laid cautiously so that it should not get damage due to rough handling & pressure on cable.							
47	112B	18200.00	Metre	36.45	663390.00	(-) 10.61	593004.32	
	Description:- Laying of RCC half round cement pipe of approximate size (150/300 mm dia X 2 Meter length) inside the trench after laying of cable. Pipes shall be placed as per directives of engineer							
48	134B	24.00	Kilometre	6137.97	147311.28	(-) 10.61	131681.55	
	Description:- "Laying of HDPE duct in trench and its protective work as per direction of site engineer."							
49	135B	24.00	Kilometre	13042.17	313012.08	(-) 10.61	279801.50	
	Description:- Blowing/Drawing of OFC cable in HDPE/DWC duct and protective work, as per direction of site engineer.							
50	45B	7500.00	Per Conductor	10.58	79350.00	(-) 10.61	70930.97	
	Description:- "Termination of cable cores on ARA terminal/ fuse blocks,in the apparatus Cases/ cable termination rack.This includes all associated works of pulling out the cable from underground. The work shall be done as per location plans and instructions of Rly engineer at site."							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () C-Provision of additional stabling lines for handling Kumbh Mela traffic in 2027 at Kherwadi, Kasbe Sukene, Nashik Road and Development of examination and maintenance facilities for NMG/NMGH/NMGHS rakes at Devlali Station on Bhusawal Division of Central Railway.(Non-SOR Items)							15311773.52	
1	1	290.00	Numbers	339.79	98539.10	AT Par	98539.10	Rs.
	Description:- Supply of cable route marker as per RST/C/203 of FRP. (Inspection by Consignee)							
2	2	8.00	Numbers	6059.19	48473.52	AT Par	48473.52	Rs.
	Description:- Supply, transportation and provision of optical Fibre splice (Joint) Enclosure (24F) for loose tube complete with all accessories as per TEC specifications no. TEC/GR/OJC-02/02 Sept 2003 or latest with the following (Inspection by Consignee)							
3	3	8.00	Numbers	6059.19	48473.52	AT Par	48473.52	Rs.
	Description:- Supply, transportation and provision of optical Fibre splice (Joint) Enclosure (48F) for loose tube complete with all accessories as per TEC specifications no. TEC/GR/OJC-02/02 Sept 2003 or latest with the following (Inspection by Consignee)							
4	4	16.00	Numbers	20323.82	325181.12	AT Par	325181.12	Rs.
	Description:- Splicing and termination of 48 Fiber OFC (2x48 Fibers) and testing. This include excavation of pitand its back filling & all relevent type of materials for splicing (Splice enclose supplied under item 27). (Inspection by Consignee)							

**BHUSAWAL DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-N-SNT-06-2026-27

Closing Date/Time: 18/06/2026 15:00

5	5	11.00	Numbers	53090.03	583990.33	AT Par	583990.33	Rs.
	Description:- Supply of 48F FDMS E2000/APC with pigtails Rack Mountable (Inspection by Consignee)							
6	6	11.00	Numbers	8082.94	88912.34	AT Par	88912.34	Rs.
	Description:- Splicing and termination of OFC & FDMS (48Fibers) as per specifications and testing. This include all relevent type of materials for splicing. (Inspection by Consignee)							
7	7	6.00	Numbers	74955.00	449730.00	AT Par	449730.00	Rs.
	Description:- Supply of True RMS Multimeter Fluke Make model 289/Kyoritsu KEW 1061/Stanone SMM 180 (Inspection by RITES)							
8	8	5.00	Numbers	18488.90	92444.50	AT Par	92444.50	Rs.
	Description:- Supply of Insulation resistance tester with3-3/4 digital display make Rishabh RISH MIT30 /Stanone/SIT500, (Stanone CET500/Metravi CET-03B (Inspection by Consignee)							
9	9	8.00	Numbers	93000.00	744000.00	AT Par	744000.00	Rs.
	Description:- "Supply of Electric Point Machine IRS type, 110V DC, Non-trail able, 143 mm stroke as per DRG. no. RDSO/S-10800 complete as per specification no. IRS: S-24/2002 with latest amendment with complete accessories viz. slides for lock & detector, cable termination box, telescopic pipes, tool kit with every 8 point machine". (Inspection by RDSO)							
10	10	26.00	Numbers	113000.00	2938000.00	AT Par	2938000.00	Rs.
	Description:- "Electric Point Machine Non-Trailable type confirming to RDSO Specification No. IRS: S-24/2002 amendment No. 1 or latest with following further information. A) 220MM throw with Interlocking for operation of point in Railway yard as per RDSO Drg. No.S- 11000. B) Type of Ground connection with Nylon insulation confirming RDSO Drg. No. S- 3454 & clamp point lock confirming to RDSO Drg. No. 3395 for 60 Kg Thick web switch. C) AC immunitylevel of Motor for Electric Point Machine should be of 400V (r.m.s) 50HZ. The external colour of Electric motor shall be painted with Red colour. (Inspection by RDSO)							
11	11	26.00	Set	32450.00	843700.00	AT Par	843700.00	Rs.
	Description:- Supply Set of Assembly parts of-60kg TWS Clamp point lock as per RDSO Drg. No. RDSO/S-3395 A, Alt-1. along with Ground Connection for EPM-220 MM as per RDSO Drg. No. RDSO/S-3454 Alt-B or latest up to the date of tender Opening. Further details of description is as per Attached document No. 3 Accepted Make: SMS (Inspection by RITES)							
12	12	6.00	Numbers	47867.89	287207.34	AT Par	287207.34	Rs.
	Description:- "Supply, installation, wiring, testing&commissioning of Bumpless Power Supply Autochangeover device complete along with accessories using Contractor's own wiring & fixing material as per following configuration - (i) Power Supply - AC/DC. (ii) Voltage 24V to 150V. (iii) Current Up to - 45Amp. Note: The work shall be done as per instructions of Railway's Engineer in-charge. " (Inspection by RITES)							
13	13	6.00	Numbers	54967.00	329802.00	AT Par	329802.00	Rs.
	Description:- Bumpless Automatic power source changeover device DC-20-150V, 45A(2 input sources) Model no. PT-RSA-HL-DC-03.(Inspection by RITES)							
14	14	6.00	Numbers	3997.60	23985.60	AT Par	23985.60	Rs.
	Description:- "Installation of item Automatic changeover unit of signal/ Track /Point supply of 32A, DC consisting of 3TC44 contactors or similar , LED Lamp, Push button terminals, VSR, polarity switches. "							
15	15	1040.00	Metre	374.77	389760.80	AT Par	389760.80	Rs.
	Description:- Supply of 110 mm Diameter PE 100 HDPE Pipe (Detailed Description/Specification as per Product # 1 of GeM Contract No. GEMC-511687786912153 dt.08/12/2023) Make: GANGA KAVERI or Similar. (Inspection by RITES)							
16	16	3.00	Numbers	600000.00	1800000.00	AT Par	1800000.00	Rs.
	Description:- "Supply of GPS tagging featured cable route locator/tracer set suitable for detecting under groung armoured optic fiber cable(OFC) and signaling cables with LCD Graphic Display active/passive modes and depth range 3M-10M model no .RD8200G clause or Equivalent." (Inspection by RITES)							
17	17	3.00	Numbers	11540.00	34620.00	AT Par	34620.00	Rs.
	Description:- OFFSET BRACKET 5 1/2". (Inspection by Consignee)							
18	18	142.00	Numbers	46.02	6534.84	AT Par	6534.84	Rs.
	Description:- "7 WATT LED LAMPS MINIMUM 560/700 LUMENS FOR OFFICE & SERVICE BUILDING AS PER WESTERN RAILWAY TECHNICAL SPECIFICATION NO.WR/CCG/SPECIFICATION/P/001(REV -'1')-2018"" FOR ENERGY EFFICIENT LED BASED LUMINAIRE FOR OUTDOOR & INDOOR APPLICATION" (Inspection by Consignee)							
19	19	760.00	Numbers	35.99	27352.40	AT Par	27352.40	Rs.
	Description:- "PVC SHEATHED STAINLESS STEEL WIREROPE 4 MM DIA. DETAIL DESCRIPTION AS PER SIGNAL WORKSHOP, SABARMATI'S DRAWING NO.SW/927. FIRM WILLBE REQUIRED TO FURNISH MANUFACTURER'S GUARANTEE CERTIFICATE. " (Inspection by Consignee)							

**BHUSAWAL DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-N-SNT-06-2026-27

Closing Date/Time: 18/06/2026 15:00

20	20	6.00	Numbers	65000.00	390000.00	AT Par	390000.00	Rs.
	Description:- "Supply & installation of smart video display unit (VDU) 55" LED panel" (Inspection by Consignee)							
21	21	6.00	Numbers	265500.00	1593000.00	AT Par	1593000.00	Rs.
	Description:- "Industrial Grade Imbedded fanless operator console PC Model Aventech make MOXA V Box, 10th generation intel i7 latest processor or better as per RDSO's TAN No. STS/E/TAN/3007, dated: 02.11.2012 (Annexure attached). Accepted Make/Brand:- Vecow ECX-2210MX with i7 10 generation processor."(Inspection by RITES)							
22	22	6.00	Set	163135.00	978810.00	AT Par	978810.00	Rs.
	Description:- "Supply of modular power supply arrangement for VDU (42"" to 85""") and embedded PC (As specified in NWR HQ Policy letter No. SG/184/1-Vol.VII dtd 01.03.24) with input and output redundancy arrangement and hot plugable modules having voltage & load current digital display on each module. Each set consisting of: - 1.Isolated inverters (master/slave with auto changeover) -2 Nos. input: 110VDC, output: 110 VAC, 500VA (as per RDSO TAN No. STS/E/TAN/3012 Version 3.0 Dated.03.11.22) 2.Isolated DC-DC converters - 02 Nos. connected in parallel with built in O-ring diode, active current sharing as per RDSO/SPN/165/2023 version 4.0 or latest (input: 110VDC, output:24 VDC/10A) 3.Input (redundancy) O-ring diode module with two input sources and one output supply along with potential free contacts, alarm and acknowledgment switch. 4. 3U stainless steel rack with back panel mother board and front panel power connectors, power cord for VDU panel. Technical detail is mentioned in Annexure-TS-1(B). MakeGallant/Phoenix/APC or better. Inspection: RITES, Inspection charges:Borne by Railways, Paymentterms:100% after supply(Item is also planned to be use at midsection LC gates (where IPS is not provided) to produce the 110V AC for road user signal and 24 V for gate circuits from common 110 V DC input extended from nearest IPS.)" (Inspection by RITES)							
23	23	329.00	Numbers	349.79	115080.91	AT Par	115080.91	Rs.
	Description:- Chase cutting 500mm deep in hard rocky area as per DRG Ni-CORE/S&T/ALD/SK/579/04 per meter							
24	24	1.00	Numbers	6200.00	6200.00	AT Par	6200.00	Rs.
	Description:- Bracket for a marker /Calling on signal (Inspection by Consignee)							
25	25	15.00	Numbers	6500.00	97500.00	AT Par	97500.00	Rs.
	Description:- Supply of Light Weight Rail Drilling Machine Drill Bit Tungsten Carbide Tipped Size- 22 MM Dia X 50 MM Long with Ejector pin. Accepted offer Make/ BrandBDS Make (Inspection by Consignee)							
26	26	200.00	Numbers	109.93	21986.00	AT Par	21986.00	Rs.
	Description:- Supply of Drill bit 7.2mm make JK/ ITI (Inspection by Consignee)							
27	27	10.00	Numbers	1798.92	17989.20	AT Par	17989.20	Rs.
	Description:- "Supply of High speed ratchet type drill bit. Size- 13 mm dia. Full length 145 mm flute Excise Duty -length 90 mm as per IS specn. IS: 503 DIN 345 square shank. Make - IT/MIRANDA/ JK, HSN code - 8207" (Inspection by Consignee)							
28	28	2.00	Numbers	249850.00	499700.00	AT Par	499700.00	Rs.
	Description:- "Battery operated rail core drill along with additional 18 mm TCT rail core drill. Maximum core cutting capacity 36mm, rated speed 250/450ZRPm, Battery type Lion, Battery voltage 50V,Battery pack capacity 4AH,Number of battery supplied - 2No. Charger-1No. Special design pressurized internal spindle cooling to give maximum life of core cutter by avoiding heating.3 sets of 22,13,16,7.2 gauge drills adapters to be provided along with the machine,weight of machine with battery18.5Kg Make :Eibenstok, Bosch, KPT" (Inspection by RITES)							
29	29	500.00	Numbers	507.40	253700.00	AT Par	253700.00	Above/ Below/P ar
	Description:- Supply of Cable lug 25 sqmm. (Safe 6080) (Inspection by Consignee)							
30	30	500.00	Numbers	731.60	365800.00	AT Par	365800.00	Rs.
	Description:- "Safetrack Sweden pin brazing material for various track connections :- a) Brazing Pin (safe 10011) b) Ferrules (Safe 2003)" (Inspection by Consignee)							
31	31	1.00	Numbers	177000.00	177000.00	AT Par	177000.00	Rs.
	Description:- Supply of Crimping Tool (Safe 7520N) (Inspection by Consignee)							
32	32	1.00	Numbers	1634300.00	1634300.00	AT Par	1634300.00	Rs.
	Description:- Supply of Safetrack Sweden Digitized Pin Brazing Unit ECONECT (HSN Code : 85158090) as per annexure (Inspection by RITES)							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit

**BHUSAWAL DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-N-SNT-06-2026-27

Closing Date/Time: 18/06/2026 15:00

Schedule () D-Provision of additional stabling lines for handling Kumbh Mela traffic in 2027 at Kherwadi, Kasbe Sukene, Nashik Road and Development of examination and maintenance facilities for NMG/NMGH/NMGHS rakes at Devlali Station on Bhusawal Division of Central Railway.							13677000.00	
1	1	47.00	Per Detection Point (DP)	291000.00	13677000.00	AT Par	13677000.00	Rs.
	Description:- "Supply of Digital Axle Counter Multi section type complete system alongwith supply of MSDAC toolkit. as per annexure. Digital Axle Counter Multi section type complete system includes the Central Evaluator and final track clearance relay for each section, Reset boxes, LV boxes All Track side units with detection point complete assembly & fixing arrangement for each detection point, clamps deflector for either side of each detection points, monitoring console for monitoring all the DPs at a time installed at a station/RH/IBH etc. with all other accessories fully wired and fully equipped as per RDSO specification No. RDSO/SPN/176/ 2013 (ver.3) or latest and manufacturers specification. The equipment must also include the following : a) System must have remote monitoring and health diagnostics feature as per RDSO specification. b) Surge protection device, c) 20% spare slots for the both detection heads and track section in the evaluator for future and emergency provision. Each set also consisting of a) Double rail contact of standard length of cable as per site requirement and mounting accessories - Equal to no. of DP. b) Deflectors to safe guard Rail Contact will be TWICE the no. of DPs. c) Protecting tube from DP to railhead as per requirement. d) Diagnostic PC as per specification and other accessories (as per Annexure-VI) one PC for every 10 DP. e) Pre-wired cabinet/rack -No. as per site requirement. f) 6 nos. Electrostatic Discharge Wrist Band for cards/ modules protection. g) Toolkit as per RDSO checklist & recommended by OEM For KBSN, KW, NK Station." (Inspection by RDSO)							

3. ITEM BREAKUP

No item break up added

4. ELIGIBILITY CONDITIONS

Standard Financial Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer must have minimum average annual contractual turnover of V/N or 'V' whichever is less; where V= Advertised value of the tender in crores of Rupees N= Number of years prescribed for completion of work for which bids have been invited. The average annual contractual turnover shall be calculated as an average of "total contractual payments" in the previous three financial years, as per the audited balance sheet. However, in case balance sheet of the previous year is yet to be prepared/ audited, the audited balance sheet of the fourth previous year shall be considered for calculating average annual contractual turnover. The tenderers shall submit requisite information as per Annexure-VIB of SGCC, along with copies of Audited Balance Sheets duly certified by the Chartered Accountant/ Certificate from Chartered Accountant duly supported by Audited Balance Sheet.	No	No	Allowed (Mandatory)

Standard Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
-------	-------------	-----------------------	-----------------	---------------------

**BHUSAWAL DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-N-SNT-06-2026-27

Closing Date/Time: 18/06/2026 15:00

1	(a)The tenderer must have successfully completed or substantially completed any one of the following categories of work(s) during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: Three similar works each costing not less than the amount equal to 30% of advertised value of the tender, or Two similar works each costing not less than the amount equal to 40% of advertised value of the tender, or One similar work costing not less than the amount equal to 60% of advertised value of the tender. (b) (1)In case of tenders for composite works (e.g. works involving more than one distinct component, such as Civil Engineering works, S&T works, Electrical works, OHE works etc. and in the case of major bridges - substructure, superstructure etc.), tenderer must have successfully completed or substantially completed any one of the following categories of work(s) during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: Three similar works each costing not less than the amount equal to 30% of advertised value of each component of tender, or Two similar works each costing not less than the amount equal to 40% of advertised value of each component of tender, or One similar work each costing not less than the amount equal to 60% of advertised value of each component of tender. Note for b(1): Separate completed works of minimum required values shall also be considered for fulfillment of technical eligibility criteria for different components. (b)(2)In such cases, what constitutes a component in a composite work shall be clearly pre-defined with estimated tender cost of it, as part of the tender documents without any ambiguity. (b) (3) To evaluate the technical eligibility of tenderer, only components of work as stipulated in tender documents for evaluation of technical eligibility, shall be considered. The scope of work covered in other remaining components shall be either executed by tenderer himself if he has work experience as mentioned in clause 7 of the Standard General Conditions of Contractor through subcontractor fulfilling the requirements as per clause 7 of the Standard General Conditions of Contract or jointly i.e., partly himself and remaining through subcontractor, with prior approval of Chief Engineer in writing.	No	No	Allowed (Mandatory)
1.1	Defination of Similar Work :- "Trenching cable laying location and signal foundation/erection/termination/wiring in connection with any signaling work." OR "Any indoor or combined Indoor/ Outdoor Signaling work including Supply, Installation, Testing and commissioning of Relay Interlocking (RRI/PI) system for passenger carrying lines".	No	No	Not Allowed

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.
3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.
5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.
6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.
7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.
8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.
9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.

**BHUSAWAL DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-N-SNT-06-2026-27

Closing Date/Time: 18/06/2026 15:00

10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)
----	---

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description
1	Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. (Click here to download the Format of Self Certification)

5. COMPLIANCE

Commercial-Compliance

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)

Technical-Compliances

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The bid must comply technical conditions of tender.	Yes	Yes	Allowed (Optional)

Custom

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer shall clearly specify whether the tender is submitted on his own (Proprietary Firm) or on behalf of a Partnership Firm / Company / Joint Venture (JV) / Registered Society / Registered Trust / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. The tenderer(s) shall enclose the attested copies of the constitution of their concern, and copy of PAN Card along with their tender. Tender Documents in such cases are to be signed by such persons as may be legally competent to sign them on behalf of the firm, company, association, trust or society, as the case may be. Tenderer should upload all necessary documents as specified in Clause no 14 of GCC-April, 2022 of Indian Railway.	Yes	Yes	Allowed (Mandatory)
2	Contractor shall employ following Qualified Engineers during execution of the allotted work- a] One Qualified Graduate Engineer when cost of work to be executed is Rs. 200 Lakh and above, b] One Qualified Diploma Holder Engineer when cost of work to be executed is more than Rs. 25 Lakh, but less than Rs. 200 Lakh. C] If the total cost of the tenderer's offer is Rs.25 Lakh or more, the tenderer(s) shall also give a declaration along with his/their tender to the effect that he/they shall engage and continue in service for the period of the contract, one Engineering Degree holder/one Engineering Diploma holder in line with above sub clause (a) and (b).	No	No	Allowed (Mandatory)
3	Mandate form dully signed by Bank Authority with seal to be attached.	No	No	Allowed (Mandatory)
4	GST Registration certificate of the tenderer to be uploaded alogwith tender document.	No	No	Allowed (Mandatory)

6. Documents attached with tender

S.No.	Document Name	Document Description
-------	---------------	----------------------

**BHUSAWAL DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-N-SNT-06-2026-27

Closing Date/Time: 18/06/2026 15:00

1	KWSIPREVISED.pdf	KW SIP REV
2	KBSNSIPREVISED.pdf	KBSN SIP REV
3	NASIKROADSIPNo.2106-03DT-22.07.2025FOREI.pdf	NK SIP REV
4	InspectionofSafety-CriticalSignalingItemsbyRDSORSDte26.09.2025.1.pdf	Annexure A Critical list
5	DEVLALISIPNO-2105-04-REV--_compressed.pdf	DEVLALI SIP REV
6	CorrectionSlips1-11.pdf	GCC APR 2022 Correction Slip
7	MSDACANNX.pdf	MSDAC Annexure
8	TenderDocumentsAdditionalStabling_1.pdf	Tender documents
9	C.RLYDRAWINGANNEXURES-SORST-20211_compressed.pdf	Drawing SOR
10	GCC_April-2022_2022__POLICY_27_04_22.pdf	GCC APR 2022

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

Signed By: PRAMOD DESHRAJ SINGH

Designation : DSTE WKS BSL