

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

Sr.DSTE/BKN acting for and on behalf of The President of India invites E-Tenders against Tender No **SnT-BKN-2026-27-08** Closing Date/Time 08/06/2026 15:00 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

1. NIT HEADER

Name of Work	S&T associated indoor and outdoor work for provision of Interlocking of 02 Nos. of manned LC Gate No. LC-14, 34-I in HMH-SDLP section over Bikaner Division.		
Bidding type	Normal Tender		
Tender Type	Open	Bidding System	Single Packet System
Tender Closing Date Time	08/06/2026 15:00	Date Time Of Uploading Tender	15/05/2026 12:59
Pre-Bid Conference Required	No	Pre-Bid Conference Date Time	Not Applicable
Advertised Value	10989248.84	Tendering Section	TECH SIG
Bidding Style	Single Rate for Tender	Bidding Unit	Above/Below/Par
Earnest Money (Rs.)	219800.00	Validity of Offer (Days)	60
Tender Doc. Cost (Rs.)	0.00	Period of Completion	9 Months
Contract Type	Works - General	Contract Category	Expenditure
Bidding Start Date	25/05/2026		
Are JV allowed to bid	No	Number of JV Member Allowed	0
Are Consortium allowed to bid	No	Number of Consortium Member Allowed	0
Ranking Order For Bids	Lowest to Highest	Expenditure Type	Capital (Works)

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A-SOR Items							10681783.74	
1	Please see Item Breakup for details.				99928.74	AT Par	99928.74	
	Description:- Chapter-1: Electronic interlocking, Design of circuits and drawings							
2	Please see Item Breakup for details.				633476.52	AT Par	633476.52	
	Description:- Chapter-2: Data Logger, RTU, FEP, CMU, FAS and Networking Accessories							
3	Please see Item Breakup for details.				1018790.66	AT Par	1018790.66	
	Description:- Chapter-3: Indoor Relays, Timers, Flasher, KLCR							
4	Please see Item Breakup for details.				566056.67	AT Par	566056.67	
	Description:- Chapter-4: Relay Racks, CT Racks, Tag Blocks, Terminal, Fuses, Indoor Cables and Jumper Wires							
5	Please see Item Breakup for details.				358196.92	AT Par	358196.92	
	Description:- Chapter-5: Power Supply Equipments, Batteries, Surge protection, Program Switches, DG sets							
6	Please see Item Breakup for details.				1238.20	AT Par	1238.20	
	Description:- Chapter-7: Track Circuit Equipments, HASSDAC, MSDAC, Block Instruments etc.							
7	Please see Item Breakup for details.				822823.88	AT Par	822823.88	
	Description:- Chapter-8: LED Main & Subsidiary signals, CLS units, Route Indicators & foundation etc.							
8	Please see Item Breakup for details.				1920551.42	AT Par	1920551.42	
	Description:- Chapter-9: Level Crossing Gates, Interlocking of LC gates, ELBs, Accessories etc.							
9	Please see Item Breakup for details.				1252892.00	AT Par	1252892.00	
	Description:- Chapter-10: Panel room Equipments, VDUs (Video Display Units), Fire alarm Equipments, Furniture							
10	Please see Item Breakup for details.				451564.34	AT Par	451564.34	
	Description:- Chapter-11: Apparatus case, outdoor installation, Fuses, ARA Terminal, Hylam Sheet, Phenolic Laminated sheets							
	Please see Item Breakup for details.				2101674.74	AT Par	2101674.74	

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

11	Description:- Chapter-12: Cable laying material, Cable protection, Cable execution, Jointing Kits items etc.							
12	Please see Item Breakup for details.			1220276.34	AT Par	1220276.34		
	Description:- Chapter-13: Earthing, Measuring Instruments, Multi-meter, Earth Tester, Clamp meters, Fault Locators, ELD (Earth Leakage Detector) etc.							
13	Please see Item Breakup for details.			95643.09	AT Par	95643.09		
	Description:- Chapter-14: Miscellaneous Signalling items, Painting, Lettering							
15	Please see Item Breakup for details.			138670.22	AT Par	138670.22		
	Description:- Chapter-15: Telecom items (IPIS, OFC equipments, Control equipments, LC gate phones and Network equipment etc.)							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () B-Non-SOR Items							307465.10	
1	NS1	40.00	Numbers	736.21	29448.40	AT Par	29448.40	
	Description:- Fixing and wiring of outdoor relays as per instruction of site engineer. It also includes supply of all the necessary material like PVC wire, thread required for wiring of outdoor relays. It also includes to arrange all the necessary material like solder wire, solder iron, thread, wire fastener as per requirement for wiring of outdoor relays. This also includes proper dressing of wire as per instruction of site engineer. Wiring is to be done by PVC insulated multi strand, single core copper conductor of size 16/0.2 mm (0.5sqmm) as per IS 694:2010 and RDSO Specn. No. IRS:S-76/89 (Amnd-3) or latest. Note : Only Relay will be supplied by railways and colour of wire will be decided by consignee of the work or site incharge. Inspection: Consignee Inspection Charges: None Payment Terms: 100% on execution.							
2	NS2	10.00	Numbers	3134.91	31349.10	AT Par	31349.10	
	Description:- Supply of magneto Telephone Desk Type (pish button) spec No. TC-79/2000 with Amendment No. 3 or latest. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs or as per extant policy. (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs or as per extant policy Inspection Charges: (i) Borne by Railways (ii) None Payment Terms: 100% after Supply.							
3	NS3	6.00	Kilometre	679.00	4074.00	AT Par	4074.00	
	Description:- Provision of Cable route tracing with Man power as per instruction of railway representative. This includes the tracing of the S&T cables with provision adequate Man power equipped with Cable route tracer to identify the location/route of laid cable(s) and after tracing of S&T cable. The same is to be updated in cable route plan for that particular patch of section and copy of updated route plan will be submitted by the contractor in 2 copies of print and soft copy for approval by Railway for specified patch of section as per instruction of SSE Work In charge. Man power and Cable fault locator/tracer required to execute the above item will be provided by the contractor. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after submission of updated and approved "Integrated cable route plans".							
4	NS4	20.00	Hour	1851.98	37039.60	AT Par	37039.60	
	Description:- Hiring of Hydra/Fork lift machine for lifting and moving of miscellaneous S&T materials like apparatus case foundations, shifting of point machines, heavy signal materials from/to the store/Station yard of SSE/Signal, uplifting and relocating of signals, apparatus cases,cable drums, and other miscellaneous items as directed by consignee incharge of the work. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after execution.							
5	NS5	500.00	Metre	161.32	80660.00	AT Par	80660.00	
	Description:- Installation of Linear Heat sensing (LHS) cable as per RDSO Specification No. RDSO/ SPN/ 217/2025 ver-3.1 or latest. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after execution.							
6	NS6	2.00	Numbers	27123.16	54246.32	AT Par	54246.32	
	Description:- Supply of LHS interface module as per RDSO Specification No. RDSO/ SPN/ 217/2025 ver-3.1 or latest. Inspection: RDSO Inspection Charges:Borne by Railways Payment Terms: 100% after Supply.							
7	NS7	2.00	Numbers	6780.79	13561.58	AT Par	13561.58	
	Description:- Installation of LHS interface module as per RDSO Specification No. RDSO/ SPN/ 217/2025 ver-3.1 or latest. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after execution.							
8	NS8	10.00	Numbers	5708.61	57086.10	AT Par	57086.10	
	Description:- Supply of CO2 type fire extinguisher capacity 4.5 Kg capacity ISI Mark IS: 15683 operating temperature (-30) ° to (50) ° for class 13 B type of fire with 1 mtr. Hose pipe fitted with PVC bend horn complete in all respect. Inspection: (i) RITES if value of item in work more than 5 lakhs or as per extant policy (ii) Consignee if value of whole item in work less than 5 lakhs or as per extant policy Inspection Charges:(i) Borne by Railways (ii) None Payment Terms: 100% after Supply.							

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

3. ITEM BREAKUP

Schedule A-SOR Items						
Chapter-1: Electronic interlocking, Design of circuits and drawings						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	01011800	Preparation of SWR literature in English along with associated mid-section interlocked gate with all corrections as per approved SWRD & approved SIP. For these all-technical corrections, editing, grammatical correction etc. are to be carried out and one rough print to be given to railways for approval before printing, as required for final processing of CRS sanction. This also includes preparation of maintenance cards in format provided by Rly. Inspection: Consignee Inspection charges: None Payment terms:100% after execution.	Station	2.00	4330.94	8661.88
2	01011900	Translation of Station Working Rules from English to Hindi and framing out in DIGLOT form (or similar software) as per extant Rly practice. The required SWR in English will be provided by the contractor and has been covered separately in item no. 01011800 of Chapter 1 of SOR. Inspection: Consignee Inspection charges: None Payment terms:100% after execution.	Station	2.00	5389.49	10778.98
3	01012000	Making photocopies & binding of the SWR literature in English/Hindi/Diglot form as per Railway practice. Inspection: Consignee Inspection charges: None Payment terms:100% after execution.	Set	12.00	214.85	2578.20

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

4	01012300	Design of circuits and plans to suit layout given in the signalling plan of IBS/ABS/LC GATE. All plans and wiring diagram shall be prepared on Auto cad Drawing and supplied with CD. This will include supply of Control cum Indication panel diagram, Route section plan, square sheet, wiring diagrams, Relay rack/Relay arrangements, Bus bar details, Fuse analysis, contact analysis, Relay room tag block analysis, panel tag block analysis, Power panel diagram, IPS wiring diagram, Auto change over diagram, Power equipment arrangement with program switch, Block circuit wiring diagram, Digital Axle counter wiring diagram and all other relevant drawings. NOTE: The contactor shall initially supply 2 sets of documents (Paper Prints) for approval of Railways. Railway will return one set to the contactor duly approved with alterations/corrections, if any. The contactor shall incorporate Railways' alterations/ corrections/ comments, if any, in the tracing & CD without any deviation and submit all the tracings and Final CD complete with all respect for Approval of Railways. After Approval of Railways on the tracings, the contractor shall submit 3 sets of final approved diagrams to the Railways within 15 days. He shall ensure each sheet has a block for signature of railway official as well as a block for signature of firm, duly signed by the authorized signatory of the firm. The name of the work as given by Railways shall be written on every sheet under the work column. All the drawing shall be supplied in a good quality folder for each IBS/ABS/LC Gate. Inspection: Consignee Inspection charges: None Payment terms:100% after execution.	Lot	2.00	17305.01	34610.02
5	01012600	Preparation and supply of laminated one set of all the completion plans including circuit diagrams and indoor as well as outdoor completion documents on standard 75-micron polyester film for Mid-Section Interlocked LC Gate (OSL) on Auto CAD. 6 (Six) sets xerox copies will be provided for each of the documents mentioned below: Cable Route Plan, Cable Core Chart, Location details plan for all the locations, Cable termination details, Signalling Plan, SWR Diagram, Wiring Diagrams, Contact Analysis, Fuse and Tag Block Analysis of Relay Rack and CT Rack, Control Cum Indication Panel/VDU Diagram, Power Panel Diagram, Track Circuit Plan, Rack Erection Plan and Junction Box details etc. Inspection: Consignee Inspection charges: None Payment terms:100% after execution.	LC Gate	2.00	10071.65	20143.30

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

6	01012800	Complete Indoor wiring at Mid-Section Interlocked LC Gate (OSL). It includes supply of PVC insulated indoor Railway signalling cable @40<45@Core/40-Core) of (1 / 0.6) sqmm as per RDSO Spec. No. IRS/S-76/89 (Amnd.2 or latest) for wiring between relay room and SM's/Panel room & Relay room to DP in SM office for block working. This also includes supply of PVC insulated jumper wires of multi strand 16/.2 mm, tinned in all colours as per RDSO Spec.No.IRS-S-76/89 (Amnd. 2 or latest). This item will include bringing all the power supplies from power room to respective bus bars on relay racks by using 10/6 sqmm copper flexible wire as per instructions of engineer incharge. This will also include wiring between control panel and relay room if required. All wiring will be done as per standard practice of North Western Railway with neat dressing & threading. The item includes supply & wiring of tag block, fuse with bases (G-Type and ND-Type) and all other related material required for complete indoor relay room wiring at mid-section interlocked LC Gate. Inspection: Consignee Inspection charges: None Payment terms:100% after execution.	Per Gate	2.00	11578.18	23156.36
					Total	99928.74
Item- 2	Chapter-2: Data Logger, RTU, FEP, CMU, FAS and Networking Accessories					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	02010400	Supply of Micro Processor based Remote Terminal Unit (RTU) with 128 digital input & 16 analog input as per RDSO Spec. No. IRS (S) 99/2006 or latest with laser printer 22 ppm (Only branded HP/Brother/Canon). It includes supply of all the items required for complete indoor relay room wiring from RTU to relay rack tag blocks, drawing/extension of power supply upto RTU. It includes supply of relay room door lock checking arrangement, commercial power supply monitoring arrangement & monitoring of DG sets, ELD (if installed), IPS, interlinking and networking of RTU. It also includes supply of leased line MODEM, suitable online UPS (minimum 6 hours backup) and other interfacing cards, if required for networking of RTU. Note: Total numbers of relays and other signalling functions/gears required to be wired as per list circulated vide RDSO Letter No. STS/E/Data logger dtd.12.09.2011 or latest guidelines. Inspection: RDSO Inspection charges: Borne by Railways Payment terms:100% after supply	Numbers	2.00	224050.47	448100.94

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

2	02010500	Installation, wiring, testing & commissioning of Micro Processor based Remote Terminal Unit (RTU) with 128 digital input & 16 analog input as per RDSO Spec. No. IRS (S) 99/2006 or latest. It covers complete indoor relay room wiring from RTU to relay rack tag blocks, drawing/extension of power supply upto RTU. It includes relay room door lock checking arrangement, commercial power supply monitoring arrangement & DG sets, ELD (if installed), IPS, interlinking and networking of RTU. All material required for wiring, networking, power supply monitoring, door-locking arrangement etc will be supplied by contractor. Note: Total numbers of relays and other signalling functions/gears required to be wired as per list circulated vide RDSO Letter No. STS/E/Data logger dtd.12.09.2011 or latest guidelines. Networking of RTU includes extraction of data report from test room. For networking, required communication channel (Quad/ OFC cable) will be arranged/provided by Rly in SM/ASM's room or in OFC Porta Cabin and it will be extended by contractor upto location of RTU by using CAT-5/6 telecom cable with proper casing and capping. The contractor will supply all the material like CAT-5/6 telecom cable, casing & capping, nuts, bolts etc. The final commissioning will be done after filling up of Pre- Commissioning checklist (circulated by RDSO) with the OEM representative. Inspection: Consignee, Inspection charges: None Payment terms:100% after commissioning	Numbers	2.00	56012.62	112025.24
3	02011600	Supply of T-Networking equipments suitable for Networking to the existing Data Logger equipments. This includes supply of all equipment / accessories required for the purpose e.g. modems and network accessories. Inspection: Consignee, Inspection charges: None Payment terms:100% after supply	Set	2.00	29340.14	58680.28
4	02011700	Commissioning of T-Networking suitable for Networking to the existing Data Logger equipments. This includes supply of all equipment / accessories required for the purpose. Inspection: Consignee, Inspection charges: None Payment terms:100% after commissioning	Set	2.00	7335.03	14670.06
Total					633476.52	
Item- 3	Chapter-3: Indoor Relays, Timers, Flasher, KLCR					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	03010100	Relay fail safe electronic time delay device with fixed timing (0 -120) seconds and conforming to RDSO Specn.No.IRS:S-61/2000 with Amnd.1 or latest mounted on Q-series relay base & covered complete with connectors, retaining clip etc. The interlocking code for this unit shall be "AFGKY". Inspection: - RDSO Inspection charges: - Borne by Railways Payment Terms: - 100% after supply.	Numbers	10.00	2210.43	22104.30

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

2	03010200	Relay fail safe electronic time delay device with fixed timing (0 @45<41@ seconds and conforming to RDSO Specn.No.IRS:S-61/2000 with Amnd.1 or latest mounted on Q-series relay base & covered complete with connectors, retaining clip etc. The interlocking code for this unit shall be "AFHKY". Inspection: - RDSO Inspection charges: - Borne by Railways Payment Terms: - 100% after supply.	Numbers	10.00	2520.02	25200.20
3	03010400	Q-Series Neutral Line Relay (QN1 Type), 12F/4B, 24V DC complete with plug board (base plate), connectors and retaining clips etc and conforming to BRS- 930 and RDSO Specn.No.IRS:S-34 & S-23 or latest. The interlocking code for this unit shall be "ABCDE". Inspection: - RDSO Inspection charges: - Borne by Railways Payment Terms: - 100% after supply.	Numbers	25.00	4746.07	118651.75
4	03010500	Q-Series Neutral Line Relay (QN1 Type), 8F/8B, 24V DC complete with plug board (base plate), connectors and retaining clips etc and conforming to BRS- 930 and RDSO Specn.No.IRS:S-34 & S-23 or latest. The interlocking code for this unit shall be "ABCDF". Inspection: - RDSO Inspection charges: - Borne by Railways Payment Terms: - 100% after supply.	Numbers	25.00	4560.51	114012.75
5	03010800	Q-Series Magnetically Latched Neutral Line Relay (QL1 Type), 11F/4B,24V DC complete with plug board (base plate), connectors and retaining clips and conforming to BRS-935A and RDSO Specn.No.IRS:S-34 & S-23 or latest. The interlocking code for this unit shall be "ABDEG". Inspection: - RDSO Inspection charges: - Borne by Railways Payment Terms: - 100% after supply.	Numbers	30.00	6861.70	205851.00
6	03011100	Q-Series LED ECR (Universal Type i.e. QECX-61), 4F/4B complete with plug board (base plate), connectors, retaining clips etc and conforming to BRS:941A STS/E/RELAYS/AC LIT LED SIGNAL/09-2002, Amdt.-1 and RDSO Specn.No.IRS:S-34 & S-23 or latest. The interlocking code for this unit shall be "ABDHK". Inspection: - RDSO Inspection charges: - Borne by Railways Payment Terms: - 100% after supply.	Numbers	25.00	5997.68	149942.00
7	03011200	Sealing wire used for sealing of signalling relays & equipments. Inspection: - RDSO Inspection charges: - Borne by Railways Payment Terms: - 100% after supply.	Kg	2.00	210.93	421.86
8	03011600	Q-Series Line Relay (QNA1 Type), AC immunized, 8F/8B, 24V DC along with plug board (base plate), connectors, retaining clips etc and conforming to BRS-931A and RDSO Specn.No.IRS:S@45"44@ S-23 and S-60 or latest. The interlocking code for this unit shall be "ABDGH". Inspection: - RDSO Inspection charges: - Borne by Railways Payment Terms: - 100% after supply.	Numbers	40.00	4710.10	188404.00

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

9	03011700	Q-Series Line Relay (QNA1 Type), AC immunized, 12F/4B, 24V DC along with plug board (base plate), connectors, retaining clips etc and conforming to BRS-931A and RDSO Specn.No.IRS:S@45"44@ S-23 and S-60 or latest. The interlocking code for this unit shall be "ABDFH". Inspection: - RDSO Inspection charges: - Borne by Railways Payment Terms: - 100% after supply.	Numbers	30.00	4579.92	137397.60
10	03012400	Key Lock Checking Relay (KLCR) working on 24V DC, AC Immunized with different ward combinations and contact configuration 4F/4B with 2 extra ward plates and with case, RDSO spec no. RDSO/SPN/219/2016 ver 1.0 or latest, confirming to IRS S-23, S-34 & S@45<44@ IRS S:46. Inspection: - Consignee. Inspection charges: - None. Payment Terms: - 100% after supply.	Numbers	5.00	11361.04	56805.20
Total					1018790.66	
Item- 4	Chapter-4: Relay Racks, CT Racks, Tag Blocks, Terminal, Fuses, Indoor Cables and Jumper Wires					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	04010100	Supply of PVC insulated multi strand, single core copper conductor of size 16/0.2 mm (0.5sqmm) as per IS 694:2010 and RDSO Specn.No.IRS:S-76/89 (Amnd-3) or latest. Each coil should be of 100/200/500 meters length. Colour of the wire which is required will be specified by the Engineer incharge. Inspection: (i) RDSO/RITES if value of item in work more than 10 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 10 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply	Kilometre	1.00	6996.26	6996.26
2	04011100	Supply of Powder Coated Relay Racks as per Drg. No. CSTE/ S&T/SOR/01 with scaffolding and suitable grouting arrangements. The relay racks shall be supplied & completed with scaffolding, bus bars, fuse strips, fuses (G/NDT), fuse bases, resistors, capacitors, insulators and 200-Way tag blocks with poly carbonate covers, grouting bolts, tripods etc. It includes supply of Tag Blocks as per RDSO Specn.No.IRS:S-77/2006 (Rev.1) or latest and RDSO Drg.No.SA-24751. The top of relay racks will be supported through an angle iron with one side fixed on supporting wall. Inspection: (i) RITES if value of item in work more than 10 lakhs (ii) Consignee Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply	Numbers	2.00	55835.23	111670.46

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

3	04011200	Erection of Powder Coated Relay Racks as per Drg. No. CSTE/ S&T/SOR/01 with scaffolding and suitable grouting arrangements. The relay racks shall be completed with scaffolding, bus bars, fuse strips, fuses (G/NDT), fuse bases, resistors, capacitors, insulators and 200-Way tag blocks with poly carbonate covers, grouting bolts, tripods etc. It includes fixing of Tag Blocks as per RDSO Specn.No.IRS:S-77/2006 (Rev.1) or latest and RDSO Drg.No.SA-24751. The top of relay racks will be supported through an angle iron with one side fixed on supporting wall. After installation of relay racks, one coat of paint will be done by contractor before fixing the fuses. Scaffolding should include 1 relay rack position as spare at every Station/ Level Crossing Gate for future expansion. Inspection: Consignee Inspection Charges: None Payment Terms: 100% on execution	Numbers	2.00	13958.81	27917.62
4	04011300	Supply of Cable Termination (CT) racks as per Drg. No. CSTE/S&T/SOR/02 complete along with fitting arrangements and also with arrangement for fixing four 8-way terminal strips/ Screw less terminals/ ARA terminals on each row having 16 such rows. Supply of 8 way terminal strips/ Screw less terminals / ARA terminals not covered under this item. Cable termination rack shall be Powder Coated. Inspection: (i) RITES if value of item in work more than 10 lakhs (ii) Consignee if value of whole item in work less than 10 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply	Numbers	2.00	27358.46	54716.92
5	04011400	Installation of Cable Termination Racks assembly complete including wall supports, scaffolding and suitable grouting arrangements with installation of 8 way/ARA terminals /Screw less connectors, Tag blocks & other necessary accessories etc. The work shall be done as per approved plan, extant practice on NWR & the instruction of Rly engineer at site. Inspection: Consignee Inspection Charges: None Payment Terms: 100% on Commissioning.	Numbers	2.00	10454.95	20909.90
6	04011500	Supply of ARA Terminal Block (M-6) made of PBT/Poly Carbonate as per RDSO Specn.No.IRS:S-75/2006 (Rev.2) or latest and RDSO Drg. No. SA-23741A (Alt. 4) or latest. Inspection: RDSO. Inspection Charges: Borne by Railways. Payment Terms: 100% on supply.	Numbers	600.00	105.20	63120.00
7	04011600	Supply of Cartridge Fuse Block made of PBT and as per RDSO Drg. No. SA-23748 (Alt. 4) or latest and RDSO Specn.No.IRS:S-75/2006 (Rev.2) or latest. Inspection: RDSO. Inspection Charges: Borne by Railways. Payment Terms: 100% on supply.	Numbers	100.00	184.11	18411.00

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

		Supply of indicating type fuse inserts with holder (material will be supplied only from approved vendors of RDSO). Inspection: Consignee Inspection Charges: Borne by Railways. Payment Terms: 100% on supply.				
8	04011701	0.6 A	Numbers	50.00	73.55	3677.50
9	04011702	1.6 A	Numbers	50.00	77.52	3876.00
		Supply of indicating type fuse inserts without holder (material will be supplied only from approved vendors of RDSO). Inspection: Consignee Inspection Charges: Borne by Railways. Payment Terms: 100% on supply.				
10	04011801	0.6 A	Numbers	20.00	24.35	487.00
11	04011802	1.6 A	Numbers	20.00	21.93	438.60
12	04011900	Supply of round head type non-deteriorating type low voltage cartridge fuse as per RDSO Specn.No.IRS:S-78/92 or latest and Capacity - 2/4/6/10A/16A/20A Amp. (material will be supplied only from approved vendors of RDSO). Inspection: Consignee Inspection Charges: Borne by Railways. Payment Terms: 100% on supply.	Numbers	300.00	65.76	19728.00
13	04012200	Supply of PVC insulated Railway Signalling multi-core Indoor Cable 60core (0.6mm Dia) conforming to IRS:76/89(Amd3) or latest. Inspection: (i) RDSO/RITES if value of item in work more than 10 lakhs(ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 10 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply	Kilometre	0.25	185872.85	46468.21
14	04012300	Termination of Outdoor Cables (Main Cables /tail cables) at both ends in location boxes, cable termination rack in relay room, station building, generator room etc. The item includes dressing of cables and wires with dressing threads as per standard practice. All material required for this item will be supplied by contractor. The outdoor cable shall be terminated in Relay Room, DG Room, ASM Room etc under supervision and instructions issued by Engr. incharge of the work. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after execution	Per Conductor	600.00	10.18	6108.00
		Supply of Disconnect Terminal Block, Screw less type, as per RDSO Spec. No. RDSO/SPN/189/2004(Modular Terminal Blocks, Fuse Terminal Blocks &Miniature fuse link of international standard for Railway signaling) With latest amendments. Inspection: (i) RDSO/RITES if value of item in work more than 10 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 10 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply				

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

15	04012601	Supply of Disconnect Terminal Block, Screw less type, 4-wire front entry (Two in-put & Two out-put) The colour will be decided by Engineer - in - Charge. (Preferably In Blue, Red & Grey Colors in the ratio of 1:2:3)	Numbers	500.00	65.75	32875.00
16	04012602	Supply of End plate for above item (04012601) 2.5mm/0.091 in thick as per site requirement.	Numbers	20.00	12.32	246.40
17	04012603	Supply of End Stopper for above item (04012601) 10mm/0.0394 in width as per site requirement.	Numbers	20.00	12.32	246.40
18	04012604	Supply of Carrier Rails for above item (04012601) 35mm x 7.5mm, 1mm/0.039 in thickness un-slotted type as per site requirement.	Metre	20.00	128.75	2575.00
19	04012605	Supply of Markers strip for above item (04012601)	Numbers	20.00	19.17	383.40
20	04013200	Supply of Fuse auto changeover system for used in Railway Signalling System as per RDSO/SPN/209/2012 rev.1 with latest amendments. One Automatic changeover Unit comprise 32 nos. of external Non-Deteriorating Type or 'G' type fuses from 0.6 Amp to 4 Amp capacities which are in signalling circuits. System shall have 8 cards with monitoring arrangement of 4 fuses in one card. Inspection:(i) RDSO/RITES: if value of item in work more than 10 lakhs (ii) Consignee: subject to procurement from RDSO approved vendors if value of whole item in work less than 10 lakhs or as per extant policy. Inspection charges:(i) Borne by Railways (ii) None Payment Terms: 100% after supply.	Each Module	4.00	35235.62	140942.48
21	04013400	Installation wiring testing and commissioning of Fuse change over system (FACS). This includes provision of common Buzzer & indication at ASM Room & ESM Duty Room and painting of fuse details. This also includes fabrication of frame for installation of FACS at Station/ LC gate where installation of relay racks not feasible. Inspection: Consignee Inspection charges: None Payment Terms: 100% on commissioning	Each Module	4.00	1065.63	4262.52
					Total	566056.67
Item- 5	Chapter-5: Power Supply Equipments, Batteries, Surge protection, Program Switches, DG sets					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

		Installation, Wiring and testing of Integrated Power Supply System. This includes power distribution connection to bus bars and relay racks in the room with contractor's own wiring materials and fabrication and fixing of AC/DC power distribution board made on 10mm thick Phenolic hylam sheets or any standard make with connections suitable for 32 A. Wiring to be done considering site requirement, depending upon the load with suitable wires, lugs & glands as per instructions of Engineer-in-charge. The work includes installation of Thermo flasher relay, ELD's, fixing & wiring of change over switch (program switch) for selection of DG set supply (DG1 & DG2) and wiring of change over switch (program switch) for selection of mains or DG supply. This item also includes supply & fixing of ladder along the wall for carrying power supply wires/cables from IPS room to Relay room/power room etc. Any masonry work required will be carried out by contactors own material. It includes transportation of IPS from consignee depot to work site/station/ LC gate. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after execution				
1	05011102	For LC gate/IBS/ ALH Hut/ Portacabin	Numbers	2.00	44038.70	88077.40
		Charging of Lead Acid Batteries with contractors own battery grade sulphuric acid and distilled water with minimum two charge - discharge cycles, installation of charged batteries in groups & their connection & wiring. The work shall be done as per extant practice of N.W.Rly & instruction of Engineer-in-charge. Detailed measurements of initial charging shall be recorded jointly by contractor & Rly's site-in-charge. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after Execution.				
2	05012302	2V, 200AH	Numbers	120.00	1186.16	142339.20

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

3	05013300	Installation, wiring, testing and commissioning of Diesel Generator Set 5 KVA, Single Phase, 240V, 1500 RPM, 50 Hz, 8 BHP (minimum) mounted with air cooled double cylinder diesel engine with acoustic enclosure complete silent type DG sets confirming to RDSO Specn.No.IRS:S-69/86 or latest (CPCB Noise & Emission Complaint) Kirloskar make engine/alternator. This also includes supply of standard AMF control panel, supply of 12V/80 AH battery set along with battery charger of suitable rating for charging the batteries to ensure self-starting arrangement of DG sets. It also includes supply of start/stop buttons, Volt/Ampere/Frequency meters and 63 AMP MCB. Note: DG set will be procured from OEM or authorized dealer of OEMs with the warranty certificate of minimum 1 year. All masonry work required for installation of DG set will be done by contractor under supervision/instructions issued by site engineer incharge. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after Commissioning	Numbers	2.00	59773.26	119546.52
4	05013800	Supply of Insulation Rubber Mat for electrical purpose 2.5mm thick size 2m*1m suitable for 3.3KV to 11KV (Class B) conforming to IS 15652-2006 Inspection: Consignee Inspection Charges: None Payment Terms: 100% after Supply.	Kg	25.00	106.98	2674.50
5	05014500	Supply laying & fixing of Anti-Static vinyl Flooring with black conductive layer sandwiched between two antistatic layer thickness of 2mm ± 01mm self-fire extinguishing as approved by engineer incharge. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after execution.	Square Foot	290.00	19.17	5559.30
					Total	358196.92
Item- 6	Chapter-7: Track Circuit Equipments, HASSDAC, MSDAC, Block Instruments etc.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	07011500	Supply of Hydrometer, Exide make or similar for measuring specific gravity of Battery Graded acid with mounting stand in location Boxes. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after Supply.	Numbers	4.00	309.55	1238.20
					Total	1238.20
Item- 7	Chapter-8: LED Main & Subsidiary signals, CLS units, Route Indicators & foundation etc.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	08010300	Installation and wiring of LED signals lamps for auxiliary/subsidiary signals/main signals (i.e. route, shunt, calling on, Red, Yellow, Green) as per instructions given by engineer incharge. Complete wiring inside the signal unit with 2.5 sq. mm multi strand wire of different colour according to signal aspect with copper lug as per standard practice. The contractor will supply all materials required for installation. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after execution.	Numbers	24.00	215.29	5166.96

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

2	08010400	Supply of Colour Light Signal Complete. This includes: - (1) Post Tubular 140 mm Dia, as per IRS: S-6/81 or Latest & RDSO Drg. No. SA-24625 (Advance). (2) CI Base (As per IRS S-10 & RDSO Drg. No. 2011/M with latest assembly). (3) Number plate to Drawing No. S 23149 Alt.1 =1 No, Number plate clamps to Drawing No. S 23148 Alt.1 =2 no (4) Ladder Assembly, as per RDSO Drg. No. SA-23156, with Base, Ladder Guard rail (complete) to Drawing No. SA 23138 Alt.1(1No), Platform to Drawing No. SA 23134 Alt.1(1 No), Front Maintenance Platform, MS Supporting bracket to Support Ladder. Ladder stay (small) to Drawing No. S 23159 Alt. 1 (2 Nos.) , Ladder stay (large) to Drawing No. S 23160 Alt. 1 (2 Nos.) , Ladder section to Drawing No. SA 23157 Alt. 1(1 Nos.) Stay clamp to Drawing No. SA 2062/M (2 no), Rail Clamp to Drawing No. S 2066/M (1 No.) (5) Signal Front Staging Complete Assembly for CLS Unit. (6) Signal back staging as per extent NWR Practice. Note: Height of the Post shall be 5.5 Long. Inspection: (i) RDSO/RITES if value of item in work more than 10 lakhs (ii) Consignee- if value of whole item in work less than 10 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply	Numbers	12.00	12987.53	155850.36
		Erection of CLS Post with base and signal unit on top or on OFFset Bracket, fixing of front and back staging, ladder and guards, signal name plates / boards if any with contractor's own brackets and fixing materials. This also includes erection of auxiliary signals like calling on, shunt signal if any. The work shall be done as per instructions of Rly engineer at site. It also includes provision & fixing of maintenance platform as per design given by Engineer -In-Charge at site. The Item includes cutting of Signal post if required by Site In charge. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after installation.				
3	08010702	2/3/4 aspect signal unit mounted directly on signal post.	Numbers	12.00	2632.57	31590.84
4	08010800	Supply of Non-Metallic (FRP) colour light signal housing multi-unit type for railway signalling suitable for RE area TWO Aspects. Complete without lenses, lamps and signal transformer as per RDSO DRG. No. SA 23001/A/M Adv. Alt- S and as per SPEC. No. RDSO/SPN/194/2006 (Rev 2.0) or latest and FRP material as per RDSO SPEC. No. RDSO/SPN/151/1997 or latest. Inspection: (i) RDSO/RITES if value of item in work more than 10 lakhs (ii) Consignee- if value of whole item in work less than 10 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply	Numbers	8.00	32215.42	257723.36

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

5	08010900	Supply of Non-Metallic (FRP) colour light signal housing multi-unit type for railway signalling suitable for RE area THREE Aspects. Complete without lenses, lamps and signal transformer as per RDSO DRG. No. SA 23001/A/M Adv. Alt- S and as per SPEC. No. RDSO/SPN/194/2006 (Rev 2.0) or latest and FRP material as per RDSO SPEC. No. RDSO/SPN/151/1997 or latest. Inspection: (i) RDSO/RITES if value of item in work more than 10 lakhs (ii) Consignee- if value of whole item in work less than 10 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply	Numbers	4.00	33749.49	134997.96
6	08012600	Supply of Stop Board as per RDSO Drg No 7235/B / Block Section Limit Board/Shunting Limit Board as per RDSO Drg. No. SA2375 (Adv.). This includes Painting and retro reflective arrangement should be as per SEM. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after installation.	Numbers	6.00	2580.52	15483.12
7	08012700	Supply of Different warning Boards / Calling on Board used for Railway Signalling system as per latest specification. This includes Painting and retro reflective arrangement should be as per IRSEM. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after installation.	Numbers	10.00	5581.54	55815.40
8	08012800	Fixing of Stop Board, Block section limit Board, Shunting Limit Board, goods warning board, Calling on Board with contractors own material. This excludes supply of Stop Board / Block section limit Board / Goods warning board/Calling on board. The work shall be done as per instruction of Rly Engineer at site. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after installation.	Numbers	10.00	402.69	4026.90
9	08012900	Supply, Fabrication and fixing of Signal Number Plate 'A' Marker, 'AG' Marker, 'P' Marker, Arrow Marker, 'G' Marker, 'C' Marker as per IRSEM drawings. All material required for this work shall be supplied by Contractor. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after installation.	Numbers	10.00	1472.43	14724.30
10	08013000	Supply and fixing of protective screen of expanded metal 12 SWG of size 1200 x 1500 mm on signals as per std. practice in RE Area. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after installation.	Numbers	2.00	6122.98	12245.96

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

11	08013100	Casting of CC Foundation for Signal Post in the ratio of 1:3:6 as per Drg. No. CSTE/NWR/SOR/21/A using standard size of foundation/galvanized holding down bolts required for erection of colour light signal post. Item includes excavation, ramming of CC using vibrator, curing and plastering with 1:4 cement-sand mixture (aggregate will not exceed 3.8 cm). Aggregate, cement, sand and holding down bolts will be supplied by contractor. Any machines & tools, if required for execution of this item, will be arranged/provided by contractor. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after installation.	Numbers	12.00	11266.56	135198.72
					Total	822823.88
Item- 8	Chapter-9: Level Crossing Gates, Interlocking of LC gates, ELBs, Accessories etc.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	09010100	Supply of Electrically Operated Lifting Barrier complete set suitable for 110VDC/24V DC (option to be specified in tender specifically of either 110 V DC or 24V DC) supply without hand generator back up & motorized boom locking arrangements as per RDSO Spec. SPN/208/2012, Ver 2.0 with latest amendment. One set consisting 02 Nos of Barriers of length 09.76 Mtrs. along with Spares & tool kit mentioned in RDSO Spec. SPN/208/2012 clause 10.1 & 10.2 as below 10.1 Following spares shall be supplied alongwith each set (02 nos.) of Electric lifting barrier as per requirement of the purchaser i) GI boom - 1 no. complete. ii) Belt - 1 no. iii) Crank handle - 1 no. iv) Motor Contactor - 1 no. v) Motor protection MCB- 1 no. vi) Push button complete- 2 nos. vii) Limit switch - 3 nos. (1 lever type and 2 top roller type) viii) Fuses used - 2 sets 10.2 Tool kit consisting of standard sizes of wrench/ spanner and Allen keys should also be supplied with each set (02 nos.) of Electric Lifting barrier. Inspection: RDSO Inspection Charges: Borne by Railways. Payment Terms: 100% after Supply.	Set	2.00	521717.26	1043434.52
2	09010200	Installation, testing and commissioning of electrically operated lifting barrier, complete with Casting of cement concrete foundation for pedestal and boom rest post, cabling, power supply connection & wiring with complete outdoor work as per approved drawing, wiring etc. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Commissioning	LC Gate	2.00	56250.98	112501.96
3	09010300	Supply of Yellow Retro reflective sheet for LC Boom prismatic grade reflective sheets of size 305 x 290 mm one set consist 18 pieces. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% on Supply	Set	25.00	2054.56	51364.00
4	09010400	Supply of Dual Tone Bell /Buzzer with Flasher arrangement and 20Watt horn working on 24 V DC/ 110 V AC for warning road users at LC gates. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply	Set	6.00	6244.87	37469.22

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

5	09010500	Supply of (02) nos. electrical lifting barrier booms of 9.76 meter each as per DRG RDSO/S 11600. The material will be as per RDSO Spec. No. RDSO/SPN/208/2012/Ver.2.0 and Amendment 1 or latest. Inspection: Consignee subject to procurement from RDSO approved supplier. Inspection Charges: None. Payment Terms: 100% after Supply	Set	2.00	30242.67	60485.34
6	09010600	Supply of Sliding type mechanical Boom barrier assembly 11 to 12 Meter Long, movement drive mechanism, resetting & supporting stand suitable for Mechanical/Electrical level crossing gate as an emergency arrangement as per Drg. mentioned in the tender document. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after supply	Set	2.00	164601.36	329202.72
7	09010700	Installation & commissioning of Sliding booms with E type lock and KLCR. This includes wiring of KLCR, running of cables, necessary painting & transportation of materials from store to site. All material required to commissioning of slide booms on gate will be supplied by the contactor. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after Commissioning	LC Gate	2.00	18423.88	36847.76
8	09010800	Casting of CC foundations in the ratio of 1:3:6 for sliding boom as per Drg. Minimum 10 Nos of foundation per set shall be cast using standard size holding down bolts & nuts for erection. Item include excavation, ramming, curing and plastering 1:4 cement and sand mixture. Aggregate, cement, sand and holding down bolts & nuts to be supplied by the c o n t a c t o r . Inspection: Consignee Inspection Charges: None Payment Terms: 100% after installation	LC Gate	2.00	35368.48	70736.96
9	09010900	Supply of LED type control-cum indication panel complete with prewired Tag- Blocks, Wires MS angles etc. for LC gate, depicting the yard layout Signal, Point, Track circuit, Operating / emergency Push Button, counter with sealing arrangements, house in a Steel metal cabinet. This shall be consisting 15 x 10 exchangeable Domino Unit as per Spec. SPN/186/2004 ver. 1 or latest amendment. Inspection: RDSO Inspection Charges: Borne by Railway. Payment Terms: 100% after Supply	Set	2.00	70127.44	140254.88

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

10	09011000	Installation and complete wiring of operating cum indication panel for LC gate as per technical specification and site requirement. The indoor wiring inside panel shall be terminated on tag block as per instructions of Engineer-in-charge. The wiring on panel tag blocks shall be repeated on tag blocks located in relay room. This includes laying & termination of cable, if any from Panel Room to Relay Room in HDPE pipe. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after installation	Numbers	2.00	8462.03	16924.06
11	09011200	Releasing of all the S & T gadgets at LC gates like SM slide instruments, illuminated diagram board, block counter, termination box, telephones, emergency key box, dismantling of ground lever frame along with all connected lever locks, 'E' type locks, HP locks, breaking and removal of concrete foundation, lock rods with rod roller trestles, complete assembly, cranks, compensators, 'A' type concrete foundation on the rod run, transmission wires single wire/double wire accounting and stocking them neatly at a place as instructed by Railway representative at site. After releasing any holes on the walls/ floor are to be filled with cement mortar and plastered.	LC Gate	2.00	10665.00	21330.00
					Total	1920551.42
Item- 9	Chapter-10: Panel room Equipments, VDUs (Video Display Units), Fire alarm Equipments, Furniture					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	10011000	Supply, installation testing and commissioning of Heat and smoke multi sensor as per RDSO/SPN/217/2025 ver-3.1 or latest. along with its base, back-box and all accessories in compliance with IS:2175 and IS:11360 standard and Under writers Laboratory (UL) listed. Inspection: RDSO Inspection Charges: Borne by Railways Payment Terms: 100% after execution.	Numbers	16.00	6276.00	100416.00
2	10011200	Supply of Analogue linear heat sensing (LHS) cable as per RDSO/SPN/217/2025 ver-3.1 or latest Inspection: RDSO Inspection Charges: Borne by Railways Payment Terms: 100% after Supply.	Metre	400.00	1420.00	568000.00
3	10011400	Supply of Fire survival cable 2x1.5 sq.mm unarmoured as per RDSO/SPN/217/2025 ver-3.1 or latest Inspection: RDSO Inspection Charges: Borne by Railways Payment Terms: 100% after Supply.	Metre	300.00	161.00	48300.00

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

4	10011500	Supply, installation, testing and commissioning of Networkable single loop addressable Fire alarm Control panel expandable up to 4 loops with GSM interface as per RDSO/SPN/217/2025 ver-3.1 or latest. This work involves supply, fixing, installation and testing of control panel. The control panel shall be networkable to Zonal/Divisional headquarters preferably over TCP/IP and shall have clock synchronization facility. This includes Networking module (TCP/IP) for control panel along with power supply unit and battery set of required capacity for 24 hours backup as per RDSO specification. The panel should support degrade mode operation in compliance with IS : 2189, EN54 standards and Underwriters Laboratory (UL) listed. Inspection: RDSO Inspection Charges: Borne by Railways Payment Terms: 100% after execution.	Numbers	2.00	210156.00	420312.00
5	10011700	Supply, installation, testing and commissioning of Manual call point (resettable) with backbox and all other accessories as per RDSO/SPN/217/2025 ver-3.1 or latest. Inspection: RDSO Inspection Charges: Borne by Railways Payment Terms: 100% after execution.	Numbers	4.00	8009.00	32036.00
6	10011900	Supply, installation, testing and commissioning of Hooter and Visual strobe alarm units with backbox and all other accessories as per RDSO/SPN/217/2025 ver-3.1 or latest along with its power supply unit. Inspection: RDSO Inspection Charges: Borne by Railways Payment Terms: 100% after execution.	Numbers	4.00	14607.00	58428.00
7	10012400	Supply of Fire survival cable 2x 1.5 sq.mm armoured as per RDSO/SPN/217/2025 ver-3.1 or latest. Inspection: RDSO Inspection Charges: Borne by Railways Payment Terms: 100% after Supply.	Metre	200.00	127.00	25400.00
					Total	1252892.00

Item- 10	Chapter-11: Apparatus case, outdoor installation, Fuses, ARA Terminal, Hylam Sheet, Phenolic Laminated sheets					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	11010100	Supply of Apparatus Case Single (Large) NE Rly Type as per Drg. No. CSTE/6088 fitted with two nos of E Type lock (ward No will be specified by Engineer-in Charge) as per RDSO Drg. No. SA 3376 and Key to Drg. No. 3377 as per RDSO drawing No. RDSO/S-11500. Note: This item includes the supply of 2 Nos E Type Lock fitted on both doors, along with two Keys. Inspection: (i) RITES if value of item in work more than 10 lakhs or as per extant instructions by Railway Board. (ii) Consignee if value of whole item in work less than 10 lakhs or as per extant instructions by Railway Board. Inspection Charges:(i) Borne by Railways (ii) None Payment Terms: 100% after Supply.	Numbers	6.00	17986.94	107921.64

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

2	11010200	Installation of Apparatus Cases Single (Large) with 'E' type lock on CC foundation. This includes filling of location foundations with river bed sand and plastering on top of the sand. Supply of 'E' Type lock has been covered in supply of Apparatus case separately. It covers fixing of lamp holder, switch and lamp etc. in Apparatus Case. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after installation.	Numbers	6.00	1250.54	7503.24
3	11010300	Supply of Apparatus Case half (Medium) NE Rly Type as per Drg. No. CSTE/6088 fitted with two nos of E Type lock (ward No will be specified by Engineer-in-Charge) as per RDSO Drg. No. SA 3376 and Key to Drg. No. 3377 as per RDSO drawing No. RDSO/S-11507. Note: This item includes the supply of 2 Nos E Type Lock fitted on both doors, along with two Keys. Inspection: (i) RITES if value of item in work more than 10 lakhs or as per extant instructions by Railway Board. (ii) Consignee if value of whole item in work less than 10 lakhs or as per extant instructions by Railway Board. Inspection Charges:(i) Borne by Railways (ii) None Payment Terms: 100% after Supply.	Numbers	8.00	11360.32	90882.56
4	11010400	Installation of Apparatus Cases Half (Medium) with 'E' type lock on CC foundation. This includes filling of location foundations with river bed sand and plastering on top of the sand. Supply of 'E' Type lock has been covered in supply of Apparatus case separately. It covers fixing of Location lamp holder, switch and lamp etc. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after installation.	Numbers	8.00	761.56	6092.48
		Excavation and Casting of Apparatus Case foundation in ratio 1:3:6 with contractor's own materials including cement and galvanized anchor bolts of standard size. The required scaffolding Ferma etc for Casting of foundation will have to be brought by the contractor at his own cost. The item also includes additional masonry work as well as earthwork if required on bank where there will be possibilities of foundation sinked, fallen or tilted. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after installation.				
5	11010801	Single (Large) Case Apparatus case / SS location box as per Drg No. CSTE/5074	Numbers	6.00	8290.81	49744.86
6	11010802	Half (Medium) Case Apparatus case / SS location box as per Drg No. CSTE/5074	Numbers	8.00	6329.40	50635.20
7	11011200	Supply of Phenolic laminated Sheet, grade P3 in standard size of 1220 X 1220 x 20 mm as per spec. No IS 2036 of 1995 or latest. Test report of manufacture to be supplied. Inspection: (i) RITES if value of item in work more than 10 lakhs or as per extant instructions by Railway Board. (ii) Consignee Inspection Charges:(i) Borne by Railways(ii) None Payment Terms: 100% after Supply.	Numbers	4.00	11509.62	46038.48

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

8	11011300	Supply of Phenolic laminated Sheet, grade P3 in standard size of 1220 X 1220 x 12 mm as per spec. No IS 2036 of 1995 or latest. Test report of manufacture to be supplied. Inspection: (i) RITES if value of item in work more than 10 lakhs or as per extant instructions by Railway Board. (ii) Consignee Inspection Charges:(i) Borne by Railways (ii) None Payment Terms: 100% after Supply.	Numbers	8.00	5843.15	46745.20
		Fabrication and fixing of phenolic laminated sheet of size 10/12/20 mm thick in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated string rods at the back side for cable support with contractor's own materials. The work shall be done as per instructions of Rly engineer at site. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after installation.				
9	11011501	Single Case (Large Case)	Numbers	6.00	2821.59	16929.54
10	11011502	Half Case (Medium Case)	Numbers	8.00	823.19	6585.52
11	11011600	Fixing of ARA(M-6) Terminals /Screw less connectors / modular disconnect terminal blocks and fuse blocks on phenolic laminated sheets and fixing by stainless steel/brass nuts & bolts. This includes provision of two additional holes on the board on either side for cable conductor entry. (Supply of all above terminals have been covered separately in Chapter 4 of SOR) Inspection: Consignee Inspection Charges: None Payment Terms: 100% after installation.	Numbers	600.00	15.07	9042.00
12	11012000	Supply of Tic-tac Piano type Switches, 5A (ISI mark of reputed make) Inspection: Consignee Inspection Charges: None Payment Terms: 100% after supply	Numbers	14.00	35.61	498.54
13	11012100	Supply of two pin Lamp holder Bakelite type for Apparatus Cases. (ISI mark of reputed make) Inspection: Consignee Inspection Charges: None Payment Terms: 100% after supply	Numbers	14.00	53.42	747.88
14	11012200	Supply of Miniature 'E' type lock complete with keys as per RDSO Drg. No. SA 3473, 3373 & spec. IRS(S) 30/64. Ward to be specified by Engineer - in - charge. Inspection: Consignee. Inspection Charges: None. Payment Terms: 100% after supply.	Numbers	5.00	2439.44	12197.20
					Total	451564.34
Item- 11	Chapter-12: Cable laying material, Cable protection, Cable execution, Jointing Kits items etc.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	12010200	Supply of Medium class GI pipes 100 mm Dia (4.5 mm thickness) as per IS 1239 (Part 1): 2004 with coupling on culverts bridges as per Drg. No. CSTE/NWR/SOR/06 to 12 or at any other locations as decided by Site Engineer. It includes supply of all material required for fixing arrangement. Contractor will also supply flexible/corrugated HDPE pipe at the end of GI pipe to protect the cables from sharp edges and sudden bends. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply.	Metre	90.00	915.45	82390.50

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

2	12010300	Fixing of Medium class GI pipes 100 mm dia(4.5 mm thickness) as per IS 1239 (Part 1): 2004 with coupling on culverts bridges as per Drg. No. CSTE/NWR/SOR/06 to 12 or at any other locations as decided by Site Engineer. It includes installation of all material required for fixing arrangement. Contractor will install flexible/corrugated HDPE pipe at the end of GI pipe along with any masonry work (if required) to protect the cables from sharp edges and sudden bends. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after installation.	Metre	30.00	228.87	6866.10
		Supplying and placing of one layer of standard size of 'B' grade quality bricks of the local make spreading on cables laid. (minimum size of brick 200mm X 100mm X 70mm) Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Installation.				
3	12010601	Length wise (up to 2 cables).	Running Metre	500.00	17.81	8905.00
4	12010602	Width wise (more than 2 cables)	Running Metre	4000.00	38.36	153440.00
5	12010700	Supply of Double Walled Corrugated (DWC) HDPE Pipe/duct with associated collars etc. as per RDSO Specification No. RDSO/SPN/204/2011 or latest anti-rodent & anti-oxidant and non-flame propagating type in 6 meters straight length and of size 120 mm outer Dia & 103.5 mm inner dia. (The manufacturers, suppliers must produce valid IS license and should be certified under ISO 9000 and shall submit copy of certificate). One of the following coupling arrangements should also be supplied with each pipe as per the site requirement.1) Suitable snap fit coupler with rubber O-Ring 2) Spacers3) Tees4) Bend,5) End-cap(The total quantity of above items is equal to no. of pipes supplied.)DWC pipe shall be marked at every 1 mtr length in such a way that manufacturer's name, vendor name and year of manufacture can be easily identified. Inspection: (i) RDSO/RITES if value of item in work more than 10 lakhs or as per extant policy (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 10 lakhs or as per extant policy Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% after Supply	Numbers	100.00	2164.13	216413.00

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

6	12010800	Supply of Double Walled Corrugated (DWC) HDPE Pipe/duct with associated collars etc. as per RDSO Specification No. RDSO/SPN/204/2011 or latest anti-rodent & anti-oxidant and non-flame propagating type in 6 meters straight length and of size 50 mm outer Dia, & 38 mm inner dia. (The manufacturers, suppliers must produce valid IS license and should be certified under ISO 9000 and shall submit copy of certificate). One of the following coupling arrangements should also be supplied with each pipe as per the site requirement.1) Suitable snap fit coupler with rubber 'O-Ring 2) Spacers3) Tees4) Bend,5) End-cap(The total quantity of above items is equal to no. of pipes supplied.)DWC pipe shall be marked at every 1 mtr length in such a way that manufacturer's name, vender name and year of manufacture can be easily identified. Inspection: (i) RDSO/RITES if value of item in work more than 10 lakhs or as per extant policy (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 10 lakhs or as per extant policy Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% after Supply	Numbers	100.00	434.20	43420.00
7	12011600	Placing of DWC HDPE/RCC/GI pipes along with collars in trenches at places near track and road, crossings, platform cuttings etc. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution	Running Metre	1200.00	35.61	42732.00
8	12012100	Supply of High-Density Polyethylene Pipes (HDPE) of 110 mm Outer Dia, 10 mm Wall Thickness, along with one coupler for every 6 Meters as per latest specification No. IS 4984: 2016 with latest amendments and Material Grade: PE 80. Inspection: (i) RDSO/RITES if value of item in work more than 10 lakhs or as per extant policy (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 10 lakhs or as per extant policy Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% after Supply	Metre	300.00	763.00	228900.00
9	12012500	Supply of Thermo shrink Universal Jointing kit for Quad Cable (for straight joints) as per RDSO spec IRS/TC-77/2012 revision 3 With latest Amd. Inspection: RDSO Inspection Charges: Borne by Railways Payment Terms: 100% after Supply	Numbers	15.00	2586.00	38790.00

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

10	12012600	Joining of 4 / 6 quad /Signalling cable with Heat Shrinkable straight through Joining Kit. All the material required for the work are to be arranged by contractor himself at his own cost except Thermo shrinkable Joint Kit/Rapid Joint kit. After joining the cable through test such as insulation test, continuity cable losses etc. to be carried out jointly with Railway Engineer. If any defect or any damage is observed during joining, the contractor has to redo the joint free of cost. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution	Numbers	10.00	1392.99	13929.90
11	12012700	Horizontal direction drilling/boring without damage of surface road /track using Auger Machine (HDD machine) or by Closed trench Method. The bore shall be upto 200 mm Dia & shall be done at the depth of minimum 1200 mm from the ground level. The ground level shall be considered ignoring the bank height of the bank of the road. The length of the bore shall be minimum 4 Mtrs long. This includes insertion of different Dia DWC-HDPE pipe/ GI pipes coupling etc. as per direction of Engineer In charge. Note: - Pipe Supply is not covered under this item. Contractor shall provide all material required for boring and adequate nos. of labours for proper laying of cables into the bore. Cable shall be laid cautiously so that it should not get damage due to rough handling & pressure on cable. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution	Metre	300.00	1447.77	434331.00
12	12012900	Supply of RCC cable route marker engraved and painted on both side along the route at every 50 meter and route diversion as per Drg. No 4014/00/CC4 or latest/ Stone marker. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply	Numbers	80.00	395.57	31645.60
13	12013000	Transportation at site and Installation of RCC cable route marker engraved and painted on both side along the route at every 50 meter and route diversion as per Drg. No 4014/00/CC4 or latest/ Stone marker. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution	Numbers	80.00	98.89	7911.20

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

14	12014200	Excavation of cable trench as per cable route plan, 1.2 Mtr. deep and of 0.3 Mtr. to 0.6 Mtr. wide at bottom as per RDSO sketch No. SDO/CABLE LAYING/003 or latest alongside the track in normal (all type) soil/strata, conforming to distances as per cable route plan and refilling. This work includes clearing of route from bushes etc, covering of cable laid in trench by loose soil for a layer of 50mm thickness approximately before covering by bricks. The work shall be done as per the extant practice on North Western Railway and instructions of Railway Engineer at site. In case 1.2m depth of trench is not achievable due to site conditions, specific approval of JA grade officer will be required for each site where trench depth of 1.2m is not possible. Without the approval of JA Grade officer, no payment for trenching will be made for trench depth less than 1.2m. (cum is Cubic Meter) Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution	cum	1500.00	330.10	495150.00
15	12014500	Digging of cable pit (min 2x2x1m) as per instruction of Site Engineer, supplying and filling of sand before and after coiling the cables, covering top of the cable pit with stones and providing brick masonry on all four sides of the cable pit and plastering thereafter. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after Execution	Numbers	2.00	15051.67	30103.34
16	12014600	Laying of S&T Cables of various cores/ pairs/ quads in trenches/ GI pipes/ RCC pipes/ DWC pipes/ Trunking. This also includes laying of cables in track crossings & road crossings. Item includes provision of labels of coloured plastic adhesive tapes or any other identifiable material on each cable to give the cable number at each Gantry Post/hectometer post. (Cables will be meggered before and after its laying by contractor under supervision of Railway Representative and he will submit the meggering report of each testing). Length of the cable laid includes the length of the cable coiled for termination purposes. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution	Running Metre	20000.00	10.95	219000.00
17	12014700	Cement concrete work for miscellaneous items in the ratio 1: 3: 6. Item includes excavation, ramming, curing and plastering with cement & sand mixture (aggregate not exceeding 3.8 cm.) (Aggregate cement & sand to be supplied by the contractor)(cum is Cubic Meter). Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution	cum	5.00	4366.61	21833.05

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

18	12014800	Providing brick masonry in ratio 1:6 cement and mortar including plastering with 1:4 cement and sand mixture both sides, 20 mm thick each with contractor's owned class II bricks, including excavation, curing, grouting, bolting etc. wherever required. Bricks sand and cement to be supplied by the contractor. (cum is Cubic Meter) Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution	cum	5.00	2395.61	11978.05
19	12014900	Video recording of cable trench using minimum 720P and above HD camera and submit one copy in New removable hard disks (With capacity as per requirement). Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution	Kilometre	4.00	3484.00	13936.00
					Total	2101674.74
Item- 12	Chapter-13: Earthing, Measuring Instruments, Multi-meter, Earth Tester, Clamp meters, Fault Locators, ELD (Earth Leakage Detector) etc.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
		Supply of Earth Leakage Detector (ELD), LEVEL-3, as per RDSO Spec. RDSO/SPN/256/2025 or latest., with Earth Fault Localization system. The engineer-in-charge to specify the distribution of number of channels of DC or AC voltage on the bus bar/ conductor for which earth leakage detector is required. Inspection: RDSO Inspection Charges: Borne by Railways Payment Terms: 100% after Supply				
1	13010101	12 Channel Earth Leakage Detector	Numbers	2.00	190686.42	381372.84
2	13010200	Wiring, installation, testing and commissioning of Earth Leakage Detector (ELD), 12/16 Channels as per RDSO Spec. RDSO/SPN/256/2025 or latest. This includes supply of fuse terminal strip for incoming power supply wires. On job training at site will be given by OEM engineer for installation and maintenance of ELD. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after commissioning.	Numbers	2.00	47671.61	95343.22

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

3	13010300	Supply of basic material to construct unit maintenance free earth as per RDSO Specs. No. RDSO/SPN/197 Version 1.0 dtd. 04.07.2016 or latest and conforming to RDSO Drg. No. SDO/ RDSO/E&B/001. It consist of following: (a) Copper bonded steel electrode of 3.0 m long, 17 mm Dia with copper bonding thickness of minimum macrons and UL listed and marked = 1 no. (b) Earth enhancement material supplied in sealed bags of minimum 10 kg = 3 nos. (c) Copper strip of 150x25x6 mm, to terminate earth rod = 1 no. (d) Copper strip of 300x25x6 mm (MEEB) = 1 no. (e) Copper strip of 150x25x6mm (SEEB) = 1 no. (ii) Supply of 35 sq. mm multi strand single core PVC insulated copper cable as per IS: 694 for connecting main earth electrode to MEEB in the equipment room in duplicate. (minimum 10 meter) (iii) Supply of 16 sq. mm multi strand single core PVC insulated copper cable as per IS: 694 for connecting MEEB to SEEB and SPD to MEEB (minimum 10 meter) (iv) Supply of 10 sq. mm multi strand single core PVC insulated copper cable as per IS: 694 for connecting various equipments to SEEB (v) Supply of copper lug sleeve for 3/16 cable Inspection: RDSO Inspection Charges: Borne by Railways Payment Terms: 100% after Supply	Lot	4.00	21098.23	84392.92
---	----------	--	-----	------	----------	----------

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

4	13010400	Installation of Unit Maintenance Free Earth as supplied under item no. 13010300 above It includes: (i) Digging the earth to the required depth. (ii) Insertion of electrode. (iii) Filling of earth enhancing compound (Approx.30 Kg) (iv) Provision of exothermic weld connections to copper tape of 25 mm x 6 mm x 150 mm to the earth electrodes. All material tools and features required for weld will be arranged by contractor. (v) This also includes CC cover 1.5 ft x 1.5 ft. 1 ft wall thickness 2 inch with cover 3-inch thickness. Cables 35 Sq mm/ 16 Sq mm/10 sq mm for connecting earth to busbar, busbar to busbar and busbars to various equipments. Earth electrode of 17.20 mm Dia and 3.00 meter long high tensile low carbon steel circular rods molecularly bonded with copper and outer surface (minimum copper bonding thickness of 250 microns to made requirement of under writer's laboratories (UL) 467-2007 or latest. Copper strips of 150 mm x 25 mm x 6 mm to be welded with each earth electrode, copper strips of 300 mm x 25 mm x 6 mm for main equip- potential busbar, copper strips of 150 mm x 25 mm x 6 mm sub equip-potential busbar in relay room, power room and panel room. GI strip 25 mm x 2 mm for ring formation of earth pits Earth enhancement material in bags for each Earth Electrode. Inspection chamber of size 300 mm x 300 mm x 300 mm (Inside dimension) of approximate 50 mm thick with pulling hooks to cover the earth pits. Note: The installation of this item shall be carried out by the contractor as per RDSO/SPN/197 Version 1.0 dtd. 04.07.2016 or latest and conforming to RDSO Drg. No. S DO/RDSO/E&B/001 or latest. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after execution and testing.	Set	4.00	9461.53	37846.12
5	13010700	Supply and Installation of earth electrode including MS flat for signalling equipments on lever frame, apparatus cases, signal, relay racks, cable termination rack, block instrument etc. (supply & installation of earth electrode as per drawing no. RE/S&T/DRG/Tender/SK/398/94 for apparatus cases, signal post & other equipments as per instruction on earthing of S&T equipment. Laying of earth lead mild steel flat of size 35mmx6mm and fixing of lead MS flat to earth electrode and lever frame, signal post & apparatus cases as per Drg. No. CORE/S&T/ALD/SK/591/2008, 592/2008 and 593/2008 respectively and instructions on earthing at S&T equipment and providing cement enclosure for earth electrode as per drawing no. RE/S&T/Sig./Tender/SK/13/85 Alt. A) Note: This item requires for earthing of all the A/Cases & Signal as per RE standard. Inspection: Consignee Inspection charges: None Payment terms: 70% after supply, 20% after installation & 10% after commissioning	Numbers	75.00	8199.86	614989.50

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

6	13011900	Standard Tool kit for signal maintenance (suitable for RE area working) with following items (with small size canvas log) (i) Insulated combination plier of 8" = 1no. (ii) Insulated long nose plier of (road wise) 6" =1 no. (iii) Insulated wise stroper plier of 6"=1 no (iv) Insulated screw driver set(5 piece) =1 set (v) Side cutting plier 6" =1 no (vi) Hex with frawise 12"= 1 no (vii) Double end spanner set (6 to 32mm) = 1 set (viii) Adjustable spanner set 8" =1 no (ix) Ball pin hammer 200 gm =1 no (x)Soldering iron 25 watt =1 no (xi)Torch cell LED (3 cell) Eveready/jeep = 1no (xii) Auto ranging digital multi-meter (Branded) =1 no (xiii) Crow bar steel/ tommy bar =1 no Inspection: Consignee Inspection charges: None Payment terms: 100% after supply	Set	1.00	6331.74	6331.74
					Total	1220276.34
Item- 13	Chapter-14: Miscellaneous Signalling items, Painting, Lettering					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	14010200	Supply of seal plier as per sample got approved from site engineer incharge. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after Supply	Numbers	4.00	1267.08	5068.32
2	14010400	Supply of Safety lock Godrej or Navtal make size as approved by site engineer. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after Supply	Numbers	10.00	134.72	1347.20
3	14010500	Supply of hand cuff lock Godrej or Navtal make size as approved by site engineer. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after Supply	Numbers	25.00	414.41	10360.25
		Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor's own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy paint will be supplied by Railways. Note: - The paint and primer should be from Asian Paints/ Nerolac/ Dulux / Berger. The primer / enamel paints (Aluminium synthetic, black enamel, brilliant white and yellow) will be as per (IS 5660 of 1970) / (IS 2932 of 1974). Inspection: Consignee Inspection Charges: None Payment Terms: 100% after Execution				
4	14010801	Apparatus Case Full Size. (Outside & inside)	Numbers	6.00	305.45	1832.70
5	14010802	Apparatus case Half Size. (Outside & inside)	Numbers	8.00	276.68	2213.44
6	14010804	Main Signal Post with Signal Units, Surface base and complete fittings as per North Western Railways standard practice.	Numbers	12.00	421.86	5062.32
7	14010809	Painting & Lettering of power operated lifting barriers (ELB) includes Operating console, Aluminium Lifting barriers of 24 fit long, 2 pedestal driving & driven mechanism, 2 Electric motors, 2 stop boards, 2 Nos Boom light, 2 Nos of Boom rest & Boom locking arrangements etc. (All Items at one LC gate to be taken as one LOT)	Numbers	2.00	3896.80	7793.60

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

		Lettering / Numbering Termination particulars, equipments names etc., legibly and neatly inside location boxes. This includes supply of paints of Asian Paints/ Nerolac / Dulux / Berger make. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after Execution				
8	14011001	Full Case	Numbers	6.00	143.82	862.92
9	14011002	Half Case	Numbers	8.00	98.61	788.88
10	14011100	Dismantling of existing interlocked mid-section LC gate (OSL) and other associated S&T gears. All the released material will be transported to the place/location as decided by site engineer. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after Execution	Numbers	2.00	6192.28	12384.56
11	14011900	Hiring of JCB machine (in good condition) for levelling and dressing ground/ dismantling structures including disposal of debris through dumpers etc with contractor's labour, JCB machine, machine operator, fuel etc. The contractor shall arrange for road permit for all the states for operation as per instructions of engineer incharge and vehicle shall not be more than 3 years old. Payment shall be made for actual working hrs at site. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after Execution	Hour	30.00	1312.53	39375.90
12	14012600	Supply & fixing of Crank Handle Box & SM's key box of size 450 mm x 250 mm x150 mm and made of 12 mm thick teakwood with a glass front, lock and sealing arrangement. All material like lock, teakwood, handles, hinges, glass sheet of 3 mm thick will be supplied by the contractor. Box will be polished and description will be written as per instructions of Engineer in charge. Inspection: Consignee Inspection Charges: None Payment Terms: 100 % after Execution	Numbers	2.00	2203.51	4407.02
13	14012700	Supply & fixing of KLCR boxes & fixing of KLCR Relays in ASM office. It includes supply of any minor bracket, nuts, bolts, teakwood, sun mica, lock, drilling hole etc as directed by engineer at site. It also includes supply and wiring of push buttons along with LEDs for KLCR circuit. Rly will supply only KLCR relays and contractor has to wire KLCR relays. It includes supply of all the related wiring material. Inspection: Consignee Inspection Charges: None Payment Terms: 100 % after Execution	Numbers	2.00	2072.99	4145.98
					Total	95643.09
Item- 15	Chapter-15: Telecom items (IPIS, OFC equipments, Control equipments, LC gate phones and Network equipment etc.)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
		Supply of various DP boxes				
1	15011101	Supply of 10 Pairs Krone type D.P. box as per Tech spec, make Hensel or superior. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply.	Numbers	2.00	1483.52	2967.04

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

2	15011102	Fixing and wiring of 10 Pairs Krone type D.P. box as per Tech spec, make Hensel or superior. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after execution.	Numbers	2.00	370.88	741.76
3	15011103	Supply of 20 Pairs Krone type D.P. box as per Tech spec, make Hensel or superior. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply.	Numbers	2.00	2362.57	4725.14
4	15011104	Fixing and wiring of 20 Pairs Krone type D.P. box as per Tech spec, make Hensel or superior. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after execution.	Numbers	2.00	590.64	1181.28
Electronic LC Gate Telephone system						
5	15014903	Supply of Electronic Station telephone (master telephone) for LC gate telephone system with Voice Logger facility as per RDSO Spec No. RDSO/SPN/TC/51/2021 (Rev 1.0) or latest. This Master telephone is compatible/suitable for existing slave Telephones installed in section. Inspection:(i) RDSO if value of item in work more than 10 lakhs or as per extant policy (ii) Consignee if value of whole item in work less than 10 lakhs or as per extant policy Inspection Charges: (i)Borne by Railways Payment Terms: 100% after Supply	Numbers	2.00	47757.00	95514.00
6	15014904	Supply of LC Gate Telephone (Slave Telephone) of Electronic LC gate telephone system as per RDSO specification No. RDSO/SPN/TC/51/2021 (Rev 1.0) or latest. This slave telephones are compatible/suitable for existing Master Telephones installed in section. Inspection:(i) RDSO if value of item in work more than 10 lakhs or as per extant policy (ii) Consignee if value of whole item in work less than 10 lakhs or as per extant policy Inspection Charges: (i)Borne by Railways (ii)Payment Terms: 100% after Supply	Numbers	2.00	5851.00	11702.00
7	15014905	Supply of Centralized power supply system 24V DC power pack with 7AH MF batteries for electronic LC gate Telephone as per RDSO specification No. RDSO/SPN/TC/51/2021 (Rev 1.0) or latest. Inspection:(i) RDSO if value of item in work more than 10 lakhs or as per extant policy (ii) Consignee if value of whole item in work less than 10 lakhs or as per extant policy Inspection Charges: (i)Borne by Railways Payment Terms: 100% after Supply	Numbers	2.00	8227.00	16454.00
8	15015300	Supply of VF Transformer (1120:470/1120:1120/ 470:470/470:600/ 1200:600 Ohm) as per Specification No. IRS-TC-76/2021 Ver 1.0 or latest (Cylindrical type) or IRS/TC/22/ 2021 Ver 1.1 or latest (Rectangular type). Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply.	Numbers	5.00	1077.00	5385.00
					Total	138670.22

4. ELIGIBILITY CONDITIONS

Standard Financial Criteria

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	: The tenderer must have minimum average annual contractual turnover of V/N or 'V' whichever is less, where V= Advertised value of the tender in crores of Rupees N= Number of years prescribed for completion of work for which bids have been invited. The average annual contractual turnover shall be calculated as an average of "total contractual payments" in the previous three financial years, as per the audited balance sheet. However, in case balance sheet of the previous year is yet to be prepared/ audited, the audited balance sheet of the fourth previous year shall be considered for calculating average annual contractual turnover. The tenderer shall submit requisite information as per Annexure-VIII given in tender document, along with copies of Audited Balance Sheets duly certified by the Chartered Accountant/ Certificate from Chartered Accountant duly supported by Audited Balance Sheet. As per Clause No. 10.2 of Tender Form (second Sheet) of Annex. I of Part-I of GCC-2022, with up to date correction slip.	No	No	Allowed (Mandatory)
1.1	If the tenderer submits/ upload Audited Balance sheet duly certified by a chartered accountant to fulfill the Standard Financial Criteria, the tenderer may also submit/ upload Form No. 26AS /16A along with the tender offer to certify the amount of contractual receipt.	No	No	Allowed (Optional)

Standard Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	(a) The tenderer must have successfully completed or substantially completed any of the following categories of work(s) during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: (i) Three similar works each costing not less than the amount equal to 30% of advertised value of the tender, or (ii) Two similar works each costing not less than the amount equal to 40% of advertised value of the tender, or (iii) One similar work each costing not less than the amount equal to 60% of advertised value of the tender. (b) (1) In case of tenders for composite works (e.g. works involving more than one distinct component, such as Civil Engineering works, S&T works, Electrical works, OHE works etc. and in the case of major bridges - substructure, superstructure etc.), tenderer must have successfully completed or substantially completed any of the following categories of work(s) during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: (i) Three similar works each costing not less than the amount equal to 30% of advertised value of each component of tender, or (ii) Two similar works each costing not less than the amount equal to 40% of advertised value of each component of tender, or (iii) One similar work each costing not less than the amount equal to 60% of advertised value of each component of tender.	No	No	Allowed (Mandatory)

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

1.1	Note for b(1): Separate completed works of minimum required values shall also be considered for fulfillment of technical eligibility criteria for different components. (b) (2) In such cases, what constitutes a component in a composite work shall be clearly pre-defined with estimated tender cost of it, as part of the tender documents without any ambiguity. (b) (3) To evaluate the technical eligibility of tenderer, only components of work as stipulated in tender documents for evaluation of technical eligibility, shall be considered. The scope of work covered in other remaining components shall be either executed by tenderer himself if he has work experience as mentioned in clause 7 of the Standard General Conditions of Contractor through subcontractor fulfilling the requirements as per clause 7 of the Standard General Conditions of Contract or jointly i.e., partly himself and remaining through subcontractor, with prior approval of Chief Signal & Telecom Engineer in writing. However, if required in tender documents by way of Special Conditions, a formal agreement duly notarised, legally enforceable in the court of law, shall be executed by the main contractor with the subcontractor for the component(s) of work proposed to be executed by the subcontractor(s), and shall be submitted along with the offer for considering subletting of that scope of work towards fulfillment of technical eligibility. Such subcontractor must fulfill technical eligibility criteria as follows: The subcontractor shall have successfully completed at least one work similar to work proposed for subcontract, costing not less than 35% value of work to be subletted, in last 5 years, ending last day of month previous to the one in which tender is invited through a works contract. Note: for subletting of work costing up to Rs 50 lakh, no previous work experience of subcontractor shall be asked for by the Railway. In case after award of contract or during execution of work it becomes necessary for contractor to change subcontractor, the same shall be done with subcontractor(s) fulfilling the requirements as per clause 7 of the Standard General Conditions of Contract, with prior approval of Chief Signal & Telecom Engineer in writing.	No	No	Not Allowed
1.2	Note: A work experience certificate from a private individual shall not be considered. However, in addition to work experience certificates issued by any Govt. Organization, work experience certificate issued by Public listed company having average annual turnover of Rs 500 crore and above in last 3 financial years excluding the current financial year, listed on National Stock Exchange or Bombay Stock Exchange, incorporated/registered at least 5 years prior to the date of closing of tender, shall also be considered provided the work experience certificate has been issued by a person authorized by the Public listed company to issue such certificates. In case tenderer submits work experience certificate issued by public listed company, the tenderer shall also submit along with work experience certificate, the relevant copy of work order, bill of quantities, bill wise details of payment received duly certified by Chartered Accountant, TDS certificates for all payments received and copy of final/last bill paid by company in support of above work experience certificate. As per Clause No. 10.1 of Tender Form (second Sheet) of Annex.I of Part-I of GCC-2022, with up to date correction slip	No	No	Not Allowed
1.3	Defination of Similar Work :- "Any Signaling Work"	No	No	Not Allowed

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.
3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.
5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.
6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.
8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.
9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.
10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description
1	Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. (Click here to download the Format of Self Certification)

5. COMPLIANCE

Commercial-Compliance

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer must opt for payment by letter of credit (LC) as per the Railway Board's letter no. 2018/CE-I/CT/9 dated 04.06.18.	Yes	Yes	Allowed (Optional)
2	Tenderers are required to quote their Permanent Account Number in the tender document.	Yes	Yes	Allowed (Mandatory)
3	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)
4	The tenderer must opt for payment by letter of credit (LC) as per the Railway Board's letter no. 2018/CE-I/CT/9 dated 04.06.18.	Yes	Yes	Allowed (Optional)
5	Tenderers are required to quote their Permanent Account Number in the tender document.	Yes	Yes	Allowed (Mandatory)
6	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)

General Instructions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
-------	-------------	-----------------------	-----------------	---------------------

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

1	No garbage, dry leaves, paper, grass, bushes, or any other items shall be burnt. They shall only be disposed of at the nominated disposal point by prescribed methods, duly observing the Municipal Solid Wastes (Management and Handling) Rules, 2000 indicates under Schedule II- Management of Municipal Solid Wastes: Para I.I vii that Waste(garbage, dry leaves) shall not be burnt. Any violation of the provisions of the MSW rules,2000, attracts the penal provisions of the Environment(Protection) ACT,1986.CPCB and SPCBs have also issued various guidelines/orders against the practice of such open burning. If the contractor or anybody deployed by him for this work is found guilty of unregulated open burning of plastic, rubber, waste, and similar substances, a fine of Rs. 5000/- on each occasion shall be imposed in addition to the other rights and remedies available in the contract. The decision of the Engineerin-Charge shall be final and binding in this regard.	No	No	Not Allowed
---	--	----	----	-------------

Technical-Compliances

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	1) In case of a partnership deed, please submit copies of all previous/old/amended partnership deeds, also, if any. 2) In case of a company, please submit a copy of the certificate of incorporation issued by the Registrar of Companies. 3) In case of a company, please submit a copy of the MOA and AOA. 4) In case of a company, please submit a copy of the Resolution of the Board of Directors passed for Power of Attorney, along with a copy of the stamped and notarized POA (backed by the above Board Resolution). Please submit copies of the PAN and GSTIN.	Yes	Yes	Allowed (Optional)

Undertakings

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	I/We have submitted full information in the prescribed format regarding membership/ employment of retired Gazetted officer and family members working in gazetted capacity in the Engineering or any other department of the railways. If no information is provided in this regard or if Annexure-XXIII is not submitted with the original offer, then I hereby certify that the information is nil as on the date of opening of tender. If it is found in the future, after award of LOA, that information in this regard, as required as per clause 16 a), b), c) of GCC-2022 has been deliberately concealed, the contract is liable to be dealt in accordance with the provisions of clause 62 of the Standard General Conditions of contract.	No	No	Not Allowed
2	I/ We have visited the worksite and I / We am/are aware of the site conditions.	No	No	Not Allowed
3	I/We have submitted full information in the prescribed format regarding membership/ employment of retired Gazetted officer and family members working in gazetted capacity in the Engineering or any other department of the railways. If no information is provided in this regard or if Annexure-XXIII is not submitted with the original offer, then I hereby certify that the information is nil as on the date of opening of tender. If it is found in the future, after award of LOA, that information in this regard, as required as per clause 16 a), b), c) of GCC-2022 has been deliberately concealed, the contract is liable to be dealt in accordance with the provisions of clause 62 of the Standard General Conditions of contract.	No	No	Not Allowed
4	I/ We have visited the worksite and I / We am/are aware of the site conditions.	No	No	Not Allowed

Custom

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Certificate to be submitted by tenderer along with the tender documents as per Annexure-II attached in tender Document.	Yes	Yes	Allowed (Mandatory)

**BIKANER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-BKN-2026-27-08

Closing Date/Time: 08/06/2026 15:00

1.1	The certificate to be submitted by the tenderer along with the tender documents as per Annexure-IIA is attached to the tender Document. (This certificate is to be given by the attorney/ authorized signatory/ each member of the Partnership firm/ Joint Venture (JV)/ Hindu Undivided Family (HUF)/ Limited Liability Partnership (LLP) etc.) The certificate to be submitted by the tenderer along with the tender documents as per Annexure-IIA is attached to the tender Document. (This certificate is to be given by the attorney/ authorized signatory/ each member of the Partnership firm/ Joint Venture (JV)/ Hindu Undivided Family (HUF)/ Limited Liability Partnership (LLP) etc.)	Yes	Yes	Allowed (Optional)
2	Declaration regarding constitution of firm & Bank Details as per Annexure-I attached in tender Document.	Yes	Yes	Allowed (Mandatory)
3	Mandatory undertaking Regarding Employment/ Partnership of Retired Railway Employees as per Annexure - XXIII attached in Tender Document.	Yes	Yes	Allowed (Mandatory)
4	Relevant Annexure is to be submitted in connection with status of their firms. i. e. Either for Sole Proprietorship/Partnership/Company registered under companies Act 2013/LLP (Limited Liability Partnership) Registered under LLP Act 2008/Registered Society and Registered Trust/HUF (Hindu undivided Family) Firm's. Prescribed Format (Relevant Annexure) as per Firm's status is attached in tender document as per clause 16.2	Yes	Yes	Allowed (Mandatory)

6. Documents attached with tender

S.No.	Document Name	Document Description
1	SnT-BKN-2026-27-08.pdf	Tender Booklet
2	GCCCS1.pdf	GCC CS
3	IRGCCApril2022.pdf	GCC, 2022
4	GCCCS2.pdf	GCC CS
5	GCCCS11.pdf	GCC CS
6	GCCCS7.pdf	GCC CS
7	GCCCS9.pdf	GCC CS
8	GCCCS4.pdf	GCC CS
9	GCCCS5.pdf	GCC CS
10	GCCCS8.pdf	GCC CS
11	GCCCS10.pdf	GCC CS
12	GCCCS3.pdf	GCC CS
13	GCCCS6.pdf	GCC CS

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

Signed By: RAN SINGH GODARA

Designation : Sr.DSTEBKN