

**RATLAM DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT_RTM_26_07_R_Signal

Closing Date/Time: 08/06/2026 15:00

SrDSTE-Co-Ratlam acting for and on behalf of The President of India invites E-Tenders against Tender No **SnT_RTM_26_07_R_Signal** Closing Date/Time 08/06/2026 15:00 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

1. NIT HEADER

Name of Work	Supply, Installation, Testing and Commissioning of S&T material in connection with:- Leftover work for Provision of intermediate block signaling (IBS) between Shambhupura - Gambhiri Road stations on the Nimach- Chittaurgarh double line section.		
Bidding type	Normal Tender		
Tender Type	Open	Bidding System	Single Packet System
Tender Closing Date Time	08/06/2026 15:00	Date Time Of Uploading Tender	15/05/2026 17:58
Pre-Bid Conference Required	No	Pre-Bid Conference Date Time	Not Applicable
Advertised Value	10485790.32	Tendering Section	SIGNAL
Bidding Style	Single Rate for Each Schedule	Bidding Unit	
Earnest Money (Rs.)	209700.00	Validity of Offer (Days)	60
Tender Doc. Cost (Rs.)	0.00	Period of Completion	9 Months
Contract Type	Works - General	Contract Category	Expenditure
Bidding Start Date	25/05/2026		
Are JV allowed to bid	No	Number of JV Member Allowed	0
Are Consortium allowed to bid	No	Number of Consortium Member Allowed	0
Ranking Order For Bids	Lowest to Highest	Expenditure Type	Capital (Works)

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () XS1-NS Schedule							4670190.32	Above/ Below/Par
1	Please see Item Breakup for details.				1703089.00	AT Par	1703089.00	
	Description:- A-1 Signal Supply Items							
2	Please see Item Breakup for details.				2838977.45	AT Par	2838977.45	
	Description:- B-1 Signal Execution Items							
3	Please see Item Breakup for details.				40269.46	AT Par	40269.46	
	Description:- A-2 Telecom Supply Items							
4	Please see Item Breakup for details.				87854.41	AT Par	87854.41	
	Description:- B-2 Telecom Execution Items							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () XS2-EI alteration items icw IBS at SMP & GRF station							5815600.00	Above/ Below/Par
1	Please see Item Breakup for details.				5815600.00	AT Par	5815600.00	
	Description:- EI alteration items icw IBS at SMP & GRF station							

3. ITEM BREAKUP

Schedule	Schedule XS1-NS Schedule					
Item- 1	A-1 Signal Supply Items					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Indicative type Fuse base/ holder withcap,suitable to G type fuse of capacity0.63A -3.0A. (System, Rapid, Malnador RBCO make or similar)	Numbers	50.00	55.34	2767.00

**RATLAM DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT_RTM_26_07_R_Signal

Closing Date/Time: 08/06/2026 15:00

2	2	Indicative type Fuse suitable to G type fuse base/holder of capacity 0.63 A -3.0 A (System, Rapid, Malnad or RBC make or similar)	Numbers	50.00	20.12	1006.00
3	3	Time Element Relay (Clock work type) AG timer Siemens Make (No RSSK30/0052)	Numbers	4.00	5631.17	22524.68
4	4	PVC insulated Railway Signaling multi core Indoor Cable 1 x 60 x 0.6mm dia conforming to IRS:76/89(Amd3) or latest	Metre	500.00	171.06	85530.00
5	5	PVC insulated Railway Signaling multi core Indoor Cable 1 x 40 x 0.6 mm dia conforming to IRS:76/89(Amd3) or latest.	Metre	500.00	110.69	55345.00
6	6	PVC insulated Railway Signaling multicore Indoor Cable 1 x 24 x 1 mm dia conforming to IRS:76/89(Amd3) or latest	Metre	300.00	176.09	52827.00
7	7	PVC insulated Railway Signaling Indoor Single core wire conforming to IRS 76/89(Amd3) or latest. Note: - Wire Colours shall be decided by engineer - in - Charge." (i) 1 x 0.6 mm	Kilometre	4.00	2797.35	11189.40
8	8	PVC insulated Railway Signaling Indoor Single core wire conforming to IRS 76/89 (Amd3) or latest. Note: - Wire Colours shall be decided by engineer - in - Charge (ii) 1 x 1 mm	Kilometre	4.00	6527.98	26111.92
9	9	Single core multi-strand wire 0.5sq.mm. (16 conductor each dia. 0.2mm), as per IRS 76/89 (Amd3)	Kilometre	10.00	5802.23	58022.30
10	10	Flexible cable (Power wire), multi strand copper conductors cross section 1x6 Sq.mm.(85 conductor each diameter 0.30 +/- 0.01) as per IS 694/1990 with insulation thickness of 0.80 mm nominal conductor resistance 3.30 ohms/km and test parameters are as per IRS(S) 76/89.	Metre	100.00	42.77	4277.00
11	11	Flexible cable (Power wire), multi strand copper conductors cross section (1x16 Sq.mm). 101 Conductor each diameter 0.45 + 0.01 as per IS 694/2010 with insulation thickness of 1.2mm nominal conductor resistance 1.127 Ohms/Km and test parameters as per IRS(S) 76/89	Metre	100.00	138.36	13836.00
12	12	Desk type Electronic Magneto Telephone as per spec No IRS/TC-79/2000 or with latest amendments.	Numbers	4.00	3406.12	13624.48
13	13	Medium Class G.I. Pipes to IS :1239(Pt.I)-2004 or latest ; 100mm dia.(int. dia) 3.65 mm +/- 10% thick with coupling. G.I.pipes shall have ISI mark on it and contractor should submit manufacturer's test certificate of G.I.pipes.	Metre	2.30	631.42	1452.27
14	14	Thermo shrink Universal Jointing kit for Quad Cable (for straight joints) as per RDSO spec IRS/TC-77/2012 revision 3 With latest Amd.	Numbers	5.00	2374.73	11873.65
15	15	Automatic Media changeover of Modems working on redundant channels for data transmission on OFC/Quad/ microwave radio.	Numbers	2.00	33769.41	67538.82
16	16	Modem for UFSBI (for used with secondary media OFC/Quad)	Numbers	2.00	57970.74	115941.48
17	17	ARA Terminal blocks with links made of PBT Spec No. IRS/75/2006 (Rev - 2) with latest amendments and RDSO Drg.No.SA-23741A Alt.4.	Numbers	2500.00	75.47	188675.00
18	18	Cartridge fuse block made of PBT as per RDSO Drg No SA-23748 Alt 4 & Spec No IRSS 75/2006 with latest amendment. Fuse block shall be suitable for round head type voltage fuses. This also includes supply of equivalent no of ND type Fuses of 2A capacity as per specification IRS S-78/92.	Numbers	50.00	135.84	6792.00
19	19	Special type Neutral lines magnetically latched relay QL1, 24VDC, 11F/4B. complete with plug board, finger contact and connectors conforming to BRS 935 A.	Numbers	10.00	5307.00	53070.00
20	20	10 Pair x 0.63 mm dia Polythene Insulated Polythene Sheathed Jelly Filled Telephone Cable with Poly-AL Moisture Barrier; Spec.No. IRS : TC41/97 Amdt No.1 to 3.	Metre	100.00	103.00	10300.00

**RATLAM DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT_RTM_26_07_R_Signal

Closing Date/Time: 08/06/2026 15:00

21	21	Supply of DC-DC convertor modules24-40V5A RDSO/SPN/165/2012 (Ver3) with latest amendment.For carrying out alterations inExisting IPS.	Numbers	5.00	26433.00	132165.00
22	22	Supply of DC-DC convertor modules24-32V5A RDSO/SPN/165/2012 (Ver3) with latest amendment.For carryingout alterations in Existing IPS.	Numbers	5.00	20805.00	104025.00
23	23	Supply of Fiber glass reinforcedplastic Plates of size 530x960x10 mmas per instruction of Engineer incharge.	Numbers	16.00	1630.00	26080.00
24	24	Supply of 19" 9U Rack as per technical specification and instructions of engineering incharge	Numbers	3.00	6495.00	19485.00
25	25	Supply of Permanently Lubricated (PLB) Highdensity polyethylene(HDPE) Telecom duct foruse as underground cable conduits-40/33 mmas per RDSO specification No.RDSO/SPN/TC/45/2013Rev.2.0amnd 1& 2 or latest.	Metre	12000.00	39.00	468000.00
26	26	Supply of optical Patch cord cable(3Meterlong with connectors) as per RDSO specs no.RDSO/SPN/TC/69/2007or latest.	Numbers	10.00	313.00	3130.00
27	27	Supply of optical branching card for STM-1(XA14ET)with SFP modules compatible with existing network and instruction of engineering incharge	Numbers	2.00	73750.00	147500.00
					Total	1703089.00
Item- 2	B-1 Signal Execution Items					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Preparation of following completion plan on standard 75 micron polyester film all drawing will be prepared on CAD & one DVD/CD willbe providedfor the finally corrected versionofdrawing & documents after it ischecked &approved by Rlys.Completion documents willalsosupplied for ST/LT, WD etc. 6 copieswillalso be provided for each of thedocumentsmention below cable Routeplan includingdepth of cable , cablecore chart, location details, plan for allocation and 20 copies of SWR plans,SWR literature and other literature required for commissioning.	Per Route	60.00	1677.91	100674.60
2	2	Installation of Relay Rack AssemblyincludingIDF pillars if any completewith wall supports,scaffolding,ladders, runway for cables, fixingofRelay / Relay group base plates, fixing of Tag blocks etc. The work shall bedone as perapproved plan, extant practice on WR & the instructions of Rly engineer at site.	Numbers	2.00	9600.79	19201.58
3	3	Installation of Cable TerminationRacksAssembly complete includingwall supports,scaffolding, 8 way/ARAtterminals /Screw lessconnectors, Tagblocks & other necessary accessoriesetc. The work shall be done as pe rapproved plan, extant practice onWR & the instruction of Rly engineer atsite.	Numbers	2.00	9600.79	19201.58
4	4	Installation wiring testing andcommissioning of Fuse change oversystem (FACS). This includes provisionof common Buzzer &indication at ASMRoom & ESM Duty Roomand paintingof fuse details. This also includesfabrication of frame for installation of FACS at Station/ LC gate where installation of relay racks not feasible.	Per Unit	4.00	978.57	3914.28
5	5	Supply & installation of Test board(LED, Pintool type) for relay Room asper as per DrgNo RST/C/105 A & B	Numbers	1.00	12144.06	12144.06

**RATLAM DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT_RTM_26_07_R_Signal

Closing Date/Time: 08/06/2026 15:00

6	6	Circuit wiring/jumpering as per circuit diagrams in the relay racks/ID Frack tag blocks. This includes preparation of Jumper sheets by wireman duly checked by firm's site supervisor & wire to wire testing as per circuit diagram. Any wrong jumper done by wireman will not be paid & correction shall be done free of cost. Jumper wires will be issued by Railways. Good quality solder resin core to be supplied by contractor for soldering of jumper wires. Soldering of jumper wires to be done after completion of testing by Railways.	Numbers	5000.00	13.84	69200.00
7	7	Installations, wiring, testing and commissioning of Remote Terminal Unit complete along with accessories using Contractor's own wiring & fixing materials. (It includes loading of NETWORKING software and networking with data logger. The requisite communication cable/channel for networking will be arranged by Railway.	Set	1.00	8570.65	8570.65
8	8	Installation, Wiring and testing of Integrated Power Supply System. This includes power distribution connection to bus bars and relay racks in the room with contractor's own wiring materials and fabrication and fixing of AC/DC power distribution board made on 10mm thick Phenolic laminate sheets or any standard make with connections suitable for 32A. Wiring to be done considering site requirement, depending upon the load with suitable wires, lugs & glands as per instructions of Engineer-in-charge. The work includes installation of Thermo flasher relay, ELD's, fixing & wiring of change over switch (program switch) for selection of DG set supply (DG1 & DG2) and wiring of change over switch (program switch) for selection of mains or DG supply. This item also includes supply & fixing of ladder along the wall for carrying power supply wires/cables from IPS room to Relay room/power room etc. Any masonry work required will be carried out by contractor's own material." (ii) For LC gate/IBS	Numbers	1.00	40440.79	40440.79
9	9	Supply laying & fixing of Anti Static vinyl Flooring with black conductive layers sandwiched between two anti static layer thickness of 2mm ± 0.1mm self fire extinguishing as approved by engineer in charge	Sqm	200.00	17.61	3522.00
10	10	Excavation and Casting of foundation for main signal post as per CSTE/3122(WR) with contractor's own materials including cement and anchor bolts of standard size. There required scaffolding, Form etc for Casting of foundation will have to be brought by the contractor at his own cost.	Numbers	1.00	8146.77	8146.77
11	11	Erection of CLS Post with base and signal unit on top or on OFF set Bracket, fixing of front and back staging, ladder and guards, signal name plates / boards if any with contractor's own brackets and fixing materials. This also includes erection of auxiliary signals like calling on, shunt signal if any. The work shall be done as per instructions of Rly engineer at site. It also includes provision & fixing of maintenance platform as per design given by Engineer -In-Charge at site. The item includes cutting of Signal post if required by Site In charge. (ii) 2/3/4 aspect signal unit mounted directly on signal post.	Numbers	4.00	2417.49	9669.96
12	12	Fabrication and fixing of Signal Number Plate (CSTE Drg No CSTE/6186), 'A' Marker (Drg No. CSTE/6180), 'AG' Marker (Drg No. CSTE/6181), 'P' Marker (Drg No. CSTE/6182), Arrow Marker (Drg No. CSTE/6183), 'G' Marker (Drg No. CSTE/6184), 'C' Marker (Drg No. CSTE/6185). marker disk on signals as per standard practice. All material required for this work shall be supplied by Contractor.	Numbers	4.00	1352.14	5408.56

**RATLAM DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT_RTM_26_07_R_Signal

Closing Date/Time: 08/06/2026 15:00

13	13	Supply & Fixing of Protective screen of expanded metal 12 SWG of Size 1200 X 1500mm on Signaling as per standard practice for protecting against voltage in AC Traction area as per instruction of Engineer In Charge.	Numbers	4.00	4452.61	17810.44
14	14	Excavation and Casting of Apparatus Case foundation with contractor's own materials including cement and anchor bolts of standard size. The required scaffolding, Formwork etc for Casting of foundation will have to be brought by the contractor at his own cost. (i) Single Case as per Drg No SK 748 or CSTE/5074	Numbers	2.00	7613.46	15226.92
15	15	Excavation and Casting of Apparatus Case foundation with contractor's own materials including cement and anchor bolts of standard size. The required scaffolding, Formwork etc for Casting of foundation will have to be brought by the contractor at his own cost. (ii) Half Case as per Drg No SK 747 or CSTE/5074 or SS Location	Numbers	6.00	5812.29	34873.74
16	16	Installation of Apparatus Cases with miniature 'E' type lock on CC foundation. This includes filling of location foundations with riverbed sand and plastering on top of the sand. 'E' Type lock will be provided by Railway. (i) Single Case	Numbers	2.00	1148.37	2296.74
17	17	Installation of Apparatus Cases with miniature 'E' type lock on CC foundation. This includes filling of location foundations with riverbed sand and plastering on top of the sand. 'E' Type lock will be provided by Railway. (ii) Half Case	Numbers	6.00	699.34	4196.04
18	18	Excavation of cable trench as per cable route plan, 1 Mtr. deep and of 0.3 Mtr. to 0.6 Mtr. wide as advised by Engineer-in-charge along side the track in normal (all type) soil/strata, conforming to distances as per cable route plan and refilling. This work includes clearing of route from bushes etc, covering of cable laid in trench by loose soil for a layer of 50mm thickness approximately before covering by bricks. The work shall be done as per the extant practice on Western Railway and instructions of Railway Engineer at site. In case 1m depth of trench is not achievable due to site conditions, specific approval of JAGrade officer will be required for each site where trench depth of 1m is not possible. Without the approval of JAGrade officer, no payment for trenching will be made for trench depth less than 1m.	cum	689.70	303.13	209068.76
19	19	Digging of cable trench 0.3 Mtrs. Deep and 0.3 Mtrs. Wide on Asphalted Platform / Road / Hard rocky area. Refilling with earth leveling of trenches & restoring the original surface of trenches.	cum	150.00	555.95	83392.50
20	20	Placing of DWC/RCC/GI pipes along with collars in trenches at places of track and road crossings, platform cuttings etc.	Metre	100.00	32.70	3270.00
21	21	Fixing of GI pipes for crossing the culverts, bridges etc. and concreting of ends with brick masonry at both ends as per the instruction of Rly engineer at site.	Metre	76.00	216.34	16441.84
22	22	Supply & fixing of GI troughing & Channel on girder bridges for carrying cables. Fixing of channel with Girder to be done with hook/ 'J' bolts of suitable size to hold the load of the troughing as per Drg. No. CSTE/3004 and CSTE/3006. This item also includes the filling of one layer of Bitumen compound as per extant practice. (ii) Supply and fixing of GI troughing of size 150mm x 200 mm x 2000mm	Metre	130.00	1309.37	170218.10

**RATLAM DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT_RTM_26_07_R_Signal

Closing Date/Time: 08/06/2026 15:00

23	23	Laying of S&T Cables of various cores/pairs/quads in trenches/ GI pipes/ RCCpipes/ DWCPipes/ Trunking. This alsoincludes laying ofcables in trackcrossings & road crossings.Itemincludes provision of labels ofcolouredplastic adhesive tapes or anyotheridentifiable material on eachcable to give thecable number ateach G.P.(Cables will bemaggeredbefore and after its layingbycontractor under supervision ofRailwayRepresentative and he willsubmit themaggering report of eachtesting). Length ofthe cable laidincludes the length of the cable coiled for termination purposes.	Metre	9928.00	10.06	99875.68
24	24	Supply and installation of RCC cableroutemarker engraved and painted onboth sidealong the route every 50 Mand routediversion as per Drg. No4014/00/CC4 or latest/ Stone marker.	Numbers	110.00	454.07	49947.70
25	25	Digging of cable pit (min 2x2x1m) asperinstruction of Site Engineer,supplying andfilling of sand beforeand after coiling thecables, coveringtop of the cable pit withstones andproviding brick masonry on all foursides of the cable pit and plastering thereafter.	Numbers	1.00	13821.96	13821.96
26	26	Providing brick masonry in ratio 1:6cementand mortar includingplastering with 1:4cement and sandmixture both sides, 20 mmthick eachwith contractor's owned class II bricks,including excavation, curing,grouting,bolting etc. wherever required. Bricks sand and cement tobe supplied by the contractor.	cum	10.00	2199.89	21998.90
27	27	Earthwork in filling in embankment,guidebunds, around typeabutments, bridge gaps, trolleyrefuges, rain bunds ifprovided,platforms etc. with earthexcavated fromoutside railwayboundary entirely arranged bythecontractor at his own cost as perRDSO'slatest guidelines andspecifications and specialcondition ofcontract including all leads,royalty,lifts, ascents, descents, crossingofnallahs or any other obstructions.The ratesshall include all dressing ofbank to finalprofile, demarcation andsetting out of profile,site clearance,removing of shrubs, rootsofvegetations growth, heavy grass,benching ofexisting slope of old bank,all handling/re-handling. Taxes, Octroiand royalty etc. as acomplete job. Cuttrees shall be property of railways andto be deposited in the railway godown unless specified otherwise in theSpecial conditions of contract.	cum	6.00	162.70	976.20
28	28	Painting of two coats of syntheticeenamelpaint over one coat of primeron the followingafter scraping &cleaning surface wherevernecessarywith contractor's own supply ofpaints.Wherever required contractorshallapply coating of epoxy paint alsoas perinstructions of site-in-charge.Epoxy paint willbe supplied byRailways. NOTE:- The paintand primersshould be from Asian Paints/Nerolac /Dulux / Berger. The primer /enamelpaints (Aluminum synthetic,black enamel,brilliant white and yellow) will be as per (IS5660 of1970) / (IS 2932 of 1974)."(i)Apparatus Case Full Size. (Outside& inside)	Numbers	10.00	280.49	2804.90
29	29	Painting of two coats of syntheticeenamelpaint over one coat of primeron the followingafter scraping &cleaning surface wherevernecessarywith contractor's own supply ofpaints.Wherever required contractorshallapply coating of epoxy paint alsoas perinstructions of site-in-charge.Epoxy paint willbe supplied byRailways. NOTE:- The paintand primersshould be from Asian Paints/Nerolac /Dulux / Berger. The primer /enamelpaints (Aluminum synthetic,black enamel,brilliant white andyellow) will be as per (IS5660 of1970) / (IS 2932 of 1974)."(ii)Apparatus case Half Size. (Outside&inside)	Numbers	6.00	254.08	1524.48

**RATLAM DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT_RTM_26_07_R_Signal

Closing Date/Time: 08/06/2026 15:00

30	30	Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor's own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy paint will be supplied by Railways. NOTE:- The paint Nerolac /Dulux / Berger. The primer /enamel paints (Aluminum synthetic, black enamel, brilliant white and yellow) will be as per (IS 5660 of 1970) / (IS 2932 of 1974)." (iv) Main Signal Post with Signal Units, Surface base and complete fittings as per Western Railways standard practice.	Numbers	15.00	387.40	5811.00
31	31	Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor's own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy paint will be supplied by Railways. NOTE:- The paint and primers should be from Asian Paints/Nerolac /Dulux / Berger. The primer /enamel paints (Aluminum synthetic, black enamel, brilliant white and yellow) will be as per (IS 5660 of 1970) / (IS 2932 of 1974)." (vi) Track Lead Junction Box. (Black enamel outside only)	Numbers	20.00	66.66	1333.20
32	32	Lettering / Numbering Termination particulars, equipments names etc., legibly and neatly inside location boxes. This includes supply of paints of Asian Paints/ Nerolac /Dulux/ Berger make. (i) Full Case.	Numbers	10.00	132.07	1320.70
33	33	Lettering / Numbering Termination particulars, equipments names etc., legibly and neatly inside location boxes. This includes supply of paints of Asian Paints/ Nerolac /Dulux/ Berger make. (ii) Half Case	Numbers	6.00	90.56	543.36
34	34	Dismantling of Concrete foundation/ Demolishing RCC/CC/ Stonework /Cutting Tar carpenting/ CCFlooring/ Precast concrete slab/ Brickwork including leading the debris inside Railway limit or outside Railway limit as directed by site in charge. This work to be done by contractors with his own vehicle and labour.	cum	10.00	646.51	6465.10
35	35	Dismantling & releasing of all type of Apparatus case including foundation complete and other accessories and transporting them to consignee's depot or DS-8 depot as per the instruction of Engineer In-charge by contractors own vehicle & labour	Lumpsum	9.00	5729.28	51563.52
36	36	Dismantling of all signals complete with signal unit, route indicator, signal foundation and other accessories complete with transporting them to consignee's depot or DS-8 depot as per the instruction of Engineer In-charge by contractors own vehicle & labour.	Numbers	6.00	4658.89	27953.34
37	37	Dismantling of Track circuit equipments including track circuit charger, battery choke, resistance, bonding wires, bootlegs and other accessories with transporting them to consignee's depot or DS-8 depot as per the instruction of Engineer In-charge by contractors own vehicle & labour.	Numbers	8.00	935.80	7486.40
38	38	Installation of Maintenance free Earth Electrode for Maintenance free earth spec of RDSO/SPN/197 ver 1.0	Numbers	30.00	1583.57	47507.10
39	39	Installation of media change over as per instruction of engineering in charge.	Pair	2.00	2600.00	5200.00

**RATLAM DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT_RTM_26_07_R_Signal

Closing Date/Time: 08/06/2026 15:00

40	40	Installation testing & commissioning of Axle counter 4DP/3TS type system or as provided and decided by railways complete with track devices and other associated accessories. This includes fixing of device, relays, wiring, lacing/dressing, cable termination with lug eyelet, drilling holes in rails, installation of track devices and make it functional along with existing UFSBI/block instrument. Material required other than supply item of DAC shall be arranged by contractor to make it functional.	Set	8.00	83708.00	669664.00
41	41	Fixing of Q series relay baseplate/metal to metal relay mini group and major group baseplate, laying, bunching, lacing, dressing & packeting of @10<47@40 core PVC indoor cable/flexible wire and termination of core of cable/flexible wire on tag block/base plate & base plates & soldering. This includes fuse wiring, busbar looping etc. required for keeping installation ready for circuit wiring work & panel throughing work. The work shall be done as per approved plan, extant practice on WR & the instruction of Rly. Engineer at site	Numbers	144.00	418.00	60192.00
42	42	Supply and installation of two wire talk back system consisting of one master unit and one slave unit suitable for IBS, working voltage 110 VAC as per site in charge's instructions.	System	6.00	8838.00	53028.00
43	43	Detailed testing of wiring as per approved wiring diagram (W.D.) at stations, including one and two wire check, functional testing, section table & locking table testing with simulation panel including making panel through, in the presence of railway officials. A copy of tested selection table, locking table and cross sheet duly signed by contractor to be submitted to field office for record. This item includes wiring of simulation panel for testing as per standard practice, with contractor's own materials. Contractor will put sufficient staff to carry out the testing round the clock and will ensure that any alternations which may become necessary during testing are carried out and testing is repeated wherever required. This includes supply of lamps for simulation panel for testing. This also includes extending various supplies up to bus bars in relay room, and up to battery room, providing manual bypass arrangement for automatic changeover arrangement and stabilizers, provision of Test Board for monitoring supplies as per instruction of Engg. In charge. All materials like nuts, bolts, fixtures etc required shall be supplied by Contractor.	Station	2.00	21770.00	43540.00
44	44	Installation, fixing and wiring of LED signal lighting unit inside all types of Signal units. It also includes complete wiring in signal unit and location boxes/hut as per approved drawing and as per instruction of Engineer in charge. Note: LED Signal Unit will be supplied by Railways.	Numbers	30.00	601.00	18030.00

**RATLAM DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT_RTM_26_07_R_Signal

Closing Date/Time: 08/06/2026 15:00

45	45	Supply, Fabrication & fixing of hylamsheet of size 10mm thick (other dimension i.e. length and breadth will be decided by Engg in-charge) for A/case NE type by providing all fixtures including fixing of PVC coated String Rods at the back side for cable support with contractor own materials. The item includes fixing of M6 terminals or screw less /fuse blocks /HRC fuses ND type on each strip. Two extra holes on both sides of M6 terminals or screw less/fuse blocks/HRC fuse and two extra holes for fixing the sheet. Note: (i) The complete hylam sheet to be covered with either M6 terminals or screw less/fuse blocks/ND type HRC fuses as per instructions of engineer at site. (ii) Hylam sheet to be of grade P2. (iii) M6 terminals or screwless, HRC fuses will be supplied by Railway. The above item also includes fixing of Q series (GPR) relays.	Sqm	4.00	5203.00	20812.00
46	46	Supply, fabrication and fixing of commercially available Compact water resistance Laminated Sheet 12mm thick for keeping S&T equipments as per the Instruction of Engineer in charge. This item includes supply and fabrication/ fixing of all materials like laminated sheet, Nuts and bolts, fixing arrangements along with fabrication of tables for keeping equipments like reset box, Block panel and fabrication of Key box and/ or any type of box/ table box for keeping equipment setc. can also be got fabricated under this item as per the design given by engineer in charge.	Sqm	5.00	1050.00	5250.00
47	47	Termination of cable cores on AR terminal/fuse blocks, 8 way terminals block/Screw-less connectors in the apparatus cases/cable termination rack at both ends. Both ends of a cable core terminated shall be counted as one terminal. This includes all associated works of pulling out the cable from underground. The item includes dressing of cables, making wiring tree etc. The work shall be done as per Location plans and as per the instruction of Engineer in- charge.	Numbers	5000.00	1.00	5000.00
48	48	Provision of Earth connection to Location Boxes and signals with MS flat strip as per instruction of engineering in-charge. Supply of MS flat of size 40X6mm at site which includes loading, unloading, transportation and fixing.	Metre	600.00	206.00	123600.00
49	49	Installation of 9U rack with complete accessories as per instructions of Engineering in charge	Numbers	3.00	400.00	1200.00
50	50	Splicing of OFC cable and making the splice joint in dust free environment with contractor's own equipment and labour. All required materials tools plants shall be arranged by the contractor. Splicing shall be started from one end and each splicing shall be monitored after splicing and after closing the enclosure for all the fibers from one central location by contractor engineer with his own OTDR and optic talk set with railway engineer trace for the fibers shall be taken and signed jointly, if any fiber splice shows high loss/lossy event the same shall be redone before completion of splicing work. The splice loss shall be as per the policy/technical circular issued by the Railways from time to time.	Numbers	8.00	287.00	2296.00
51	51	Blowing of OFC through HDPE duct & protective work where it is not feasible to blow OFC due to curve road/track crossing bridges or for any other reason, OFC shall be draw/laid manually as per standard procedure. All the equipments and machinery required shall be arranged by the contractor at his own cost. In case OFC is to be laid adopting direct in trench method.	Metre	13850.00	10.00	138500.00

**RATLAM DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT_RTM_26_07_R_Signal

Closing Date/Time: 08/06/2026 15:00

52	52	Laying of HDPE Pipe of size 40 mmwith protective workas per instruction of Engineer in charge.	Metre	14000.00	2.00	28000.00
53	53	Installation of Axle counter cable conductor's Earth Resistance sensing unit	Numbers	4.00	5841.00	23364.00
54	54	Supply, installation andcommissioning of Microprocessorbased Networkable AnalogueAddressable upto 64 nodes 1Loop FireAlarmControl panel with LCD display,the panel should be equipped withsufficient nos.of loop as per RDSOSpecification No.RDSO/SPN/217/2025ver 3.1 or latest.Each loop shall havecapacity of 127 analogue addressabledevices in1loop,the panel shall have sufficient nos. of programmable relaycontrol for controlling AHU's,pressurisation fans,ventilation fans atfire pump room,monitoring of firesprinkler & sealed lead acid batteriessufficient for 24 Hours normal working& then capable of operating thesystem for 24 Hours duringEmergency conditions as required.The panel shall have provision ofconnectivity ofBACNET/MODBUS/LONWOK/TCP-IP.The panel shall have dedicated RS232serial port for direct PC or MODEMconnection,optional remote printer asper RDSO SpecificationNo.RDSO/SPN/217/2025 ver 3.1 orlatest.	Numbers	1.00	73368.00	73368.00
55	55	Supply, installation andcommissioning of intelligent AnalogueAddressable Multi-Sensor type smokedetector with inbuilt fault isolator andintegral response indicator with 360degree viewing angle.Detector shallcommunicate 3 danger levels fordifferentiated alarm activation andhigh tolerance todust,dirt,temperature fluctuations andair current.Detector should haveunique address for communicationand assigned through panel withmounting base as required with theprotection category of IP40. All itemsas per RDSO Specification No.RDSO/SPN/ 217/ 2025 ver 3.1 or lates	Numbers	6.00	4003.00	24018.00
56	56	Supply installation commissioning ofAnalogue Addressable Manual CallPoint with integral short circuitisolator, Analogue addressableprotocol having status LED foralarms & standbymode,Electronically addressed) asperRDSO Specification No.RDSO/SPN/217/2025 ver 3.1 or latest	Numbers	1.00	4190.00	4190.00
57	57	Supply, installation, testing andcommissioning of Linear Heat Sensing (LHS)cable as per RDSO Specification No.RDSO/ SPN/ 217/2025 ver 3.1 or latest	Metre	10.00	876.00	8760.00
58	58	Supply, installation, testing and commissioning of LHS interface module as per RDSO Specification No.RDSO/SPN/217/2025 ver 3.1 orlatest.	Numbers	1.00	36840.00	36840.00
59	59	Supply, installation, testing andcommissioning of FRLSunarmoured/armouredcable(2Cx1.5sq.mm)with all accessories for connection of all Fire Alarm devices as per RDSOSpecification No. RDSO/SPN/217/2025 ver 3.1 or latest	Lot	1.00	39961.00	39961.00
60	60	Supply installation commissioning ofUV/IRType Flame detector withrequired module to communicateonmain fire alarm panel as perRDSOSpecification No. RDSO/SPN/217/2025 ver 3.1 or latest.	Numbers	1.00	78397.00	78397.00
61	61	Supply, installation, testingand commissioning of Supply of AirSampling Type detector shall useLASER type. This type ofdetector shalluse piping or tubingdistributionnetwork thatshallrunfromthe detector to theareaas tobeprotected. Itshouldbesuppliedwithrequired module&Powersupplyunitcomplete as asystem with all accessories like pipes,Sampling point set as per RDSO Specification No.RDSO/SPN/217/2025 ver 3.1 or latest.	Numbers	1.00	168532.00	168532.00

**RATLAM DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT_RTM_26_07_R_Signal

Closing Date/Time: 08/06/2026 15:00

62	62	Supply, installation, testing and commissioning of Supply of intelligent Addressable Loop Powered Sounder cum beacon with base in built fault isolator with protection category of IP42 and duly approved as per RDSO Specification No.RDSO/SPN/217/ 2025 ver 3.1 or latest.	Numbers	1.00	9412.00	9412.00
					Total	2838977.45
Item- 3 A-2 Telecom Supply Items						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Thermo shrink Universal Jointing kit for Quad Cable (for straight joints) as per RDSO spec IRS/TC-77/2012 revision 3 With latest Amd.	Numbers	2.00	2374.73	4749.46
2	2	Supply of one inch diameter PVC pipe with medium mechanical stress conforming to IS 9537 Part-III.	Metre	200.00	19.00	3800.00
3	3	Supply of 30 MBPS 2W/4W LAN Extender supporting short and long distance (upto 10Kms or more) Dual power supply AC/DC from a single socket plug in module in the stand alone unit. Make MROTEK, TEAMLINK, Cygnus, ANDA.	Pair	1.00	19114.00	19114.00
4	4	Supply of 24 Port LIU Rack Mountable loaded with suitable connectors of Dlink, Molex, Raychem or Amp make. The Contractor should supply all miscellaneous items like connector patch cord for complete installation of Fixed optical fiber inter connection unit.	Numbers	2.00	6303.00	12606.00
					Total	40269.46
Item- 4 B-2 Telecom Execution Items						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Excavation of cable trench as per cable route plan, 1 Mtr. deep and of 0.3 Mtr. to 0.6 Mtr. wide as advised by Engineer-in-charge along side the track in normal (all type) soil/strata, conforming to distances as per cable route plan and refilling. This work includes clearing of route from bushes etc, covering of cable laid in trench by loose soil for a layer of 50mm thickness approximately before covering by bricks. The work shall be done as per the extant practice on Western Railway and instructions of Railway Engineer at site. In case 1m depth of trench is not achievable due to site conditions, specific approval of JAGrade officer will be required for each site where trench depth of 1m is not possible. Without the approval of JAGrade officer, no payment for trenching will be made for trench depth less than 1m.	cum	150.00	303.13	45469.50
2	2	Laying of S&T Cables of various cores/pairs/quads in trenches/ GI pipes/ RCC pipes/ DWCP pipes/ Trunking. This also includes laying of cables in track crossings & road crossings. Item includes provision of labels of coloured plastic adhesive tapes or any other identifiable material on each cable to give the cable number at each G.P. (Cables will be tagged before and after its laying by contractor under supervision of Railway Representative and he will submit the tagging report of each testing). Length of the cable laid includes the length of the cable coiled for termination purposes.	Metre	150.00	10.06	1509.00
3	3	Supply and installation of RCC cable route marker engraved and painted on both side along the route every 50 M and route diversion as per Drg. No 4014/00/CC4 or latest/ Stone marker.	Numbers	13.00	454.07	5902.91
4	4	Laying of Telecom cable in PVC Pipe, Casing Capping & conduit Pipe as per Instruction of Engineer Incharge.	Metre	100.00	2.99	299.00

**RATLAM DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT_RTM_26_07_R_Signal

Closing Date/Time: 08/06/2026 15:00

5	5	Labour assistance for SSE/JE in day to day works i.e., checking the curves/straight alignment of formation levels etc., Carrying the tools & equipments etc., Watch & ward during the course of execution of work as per the instructions of concerned SE/JE.	Man-Days	60.00	577.90	34674.00
					Total	87854.41
Schedule Schedule XS2-EI alteration items icw IBS at SMP & GRF station						
Item- 1 EI alteration items icw IBS at SMP & GRF station						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Design and modification in existing Elas per approved Signalling plan. This work includes all indoor and outdoor work necessary software and hardware to carrying out alteration/modification and also carry out FAT and SAT test (If required). This also includes modification to all existing drawings provided with Electronic interlocking and preparation/alteration of Logic diagram, Interfacediagram, VDU diagram. Square sheet, I/F wiring chart and selection table etc. and other inter connection drawings with Relay room, equipment room etc. on the basis of approved signalling plan like typical circuit diagram, fuse analysis chart, terminal analysis and contact analysis chart etc. as per Railway practice and obtaining approval of competent authority for EI. Design and supply for additional alteration and modification in Electronic interlocking system of Ansal do make at Gambhiri Road station and Medha make at Shambupura station. Existing EI is Ansal do make at Gambhiri Road station and Medha make at Shambupura station.	Numbers	1.00	5815600.00	5815600.00
					Total	5815600.00

4. ELIGIBILITY CONDITIONS

Special Financial Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer must have minimum average annual contractual turnover of V/N or 'V' whichever is less; where V= Advertised value of the tender in crores of Rupees N=Number of years prescribed for completion of work for which bids have been invited. The average annual contractual turnover shall be calculated as an average of "total contractual payments" in the previous three financial years, as per the audited balance sheet. However, in case balance sheet of the previous year is yet to be prepared/ audited, the audited balance sheet of the fourth previous year shall be considered for calculating average annual contractual turnover. The tenderers shall submit requisite information as per Annexure-VIB, along with copies of Audited Balance Sheets duly certified by the Chartered Accountant/ Certificate from Chartered Accountant duly supported by Audited Balance Sheet.	No	No	Allowed (Mandatory)
1.1	Audited Balance sheet as per above description along with information as per Annexure-VIB (of GCC) to be enclosed.	No	No	Allowed (Mandatory)

Special Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
-------	-------------	-----------------------	-----------------	---------------------

**RATLAM DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT_RTM_26_07_R_Signal

Closing Date/Time: 08/06/2026 15:00

1	(a) The tenderer must have successfully completed or substantially completed any of the following during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: Three similar works costing not less than the amount equal to 30% of advertised value of the tender, or Two similar works costing not less than the amount equal to 40% of advertised value of the tender, or One similar work costing not less than the amount equal to 60% of advertised value of the tender. (b) (i) In case of composite works (e.g. works involving more than one distinct component, such as Civil Engineering works, S&T works, Electrical works, OHE works etc. and in the case of major bridges substructure, superstructure etc.), tenderer must have successfully completed any of the following during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: Three similar works costing not less than the amount equal to 30% of advertised value of each component of tender, or Two similar works costing not less than the amount equal to 40% of advertised value of each component of tender, or One similar work costing not less than the amount equal to 60% of advertised value of each component of tender. Note: Separate completed works of minimum required values shall also be considered for fulfillment of technical eligibility criteria for different components.	No	No	Allowed (Mandatory)
1.1	The similar nature of the work is defined as: "Any work in connection with signaling installation. The work shall include indoor wiring component if the tendered work includes indoor work and laying & termination of cables if the tendered work includes outdoor work"	No	No	Allowed (Mandatory)

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.
3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.
5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.
6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.
7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.
8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.
9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.
10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description
1	Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. (Click here to download the Format of Self Certification)

5. COMPLIANCE

Commercial-Compliance

**RATLAM DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT_RTM_26_07_R_Signal

Closing Date/Time: 08/06/2026 15:00

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)

Technical-Compliances

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer whether sole proprietor / a company or a partnership firm / joint venture (JV) / registered society / registered trust / HUF / LLP etc if they want to act through agent or individual partner(s), should submit along with the tender, a copy of power of attorney duly stamped and authenticated by a Notary Public or by Magistrate in favour of the specific person whether he/they be partner(s) of the firm or any other person, specifically authorizing him/them to sign the tender, submit the tender and further to deal with the Tender/ Contract up to the stage of signing the agreement except in case where such specific person is authorized for above purposes through a provision made in the partnership deed / Memorandum of Understanding / Article of Association /Board resolution, failing which tender shall be summarily rejected. Note:- Power of attorney on non-judicial stamp paper as per MP state stamp duty.	No	No	Allowed (Mandatory)
2	The tenderer shall clearly specify whether the tender is submitted on his own (Proprietary Firm) or on behalf of a Partnership Firm / Company / Joint Venture (JV) / Registered Society / Registered Trust / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. The tenderer(s) shall enclose the attested copies of the constitution of their concern, and copy of PAN Card along with their tender. Tender Documents in such cases are to be signed by such persons as may be legally competent to sign them on behalf of the firm, company, association, trust or society, as the case may be as follows	Yes	Yes	Allowed (Mandatory)
2.1	(a) Sole Proprietorship Firm: (i) All documents in terms of Para 10 of the Tender Form (Second Sheet) of GCC.	Yes	Yes	Allowed (Optional)
2.1.1	The tenderer(s) shall enclose the attested copies of the constitution of Firm.	Yes	Yes	Allowed (Optional)
2.1.2	Copy of PAN Card along with their tender.	Yes	Yes	Allowed (Optional)
2.2	(b) HUF: (i) A copy of notarized affidavit on Stamp Paper declaring that he who is submitting the tender on behalf of HUF is in the position of 'Karta' of Hindu Undivided Family (HUF) and he has the authority, power and consent given by other members to act on behalf of HUF. (ii) All other documents in terms of Para 10 of the Tender Form (Second Sheet).	Yes	Yes	Allowed (Optional)
2.2.1	The tenderer(s) shall enclose the attested copies of the constitution of Firm.	Yes	Yes	Allowed (Optional)
2.2.2	Copy of PAN Card along with their tender.	Yes	Yes	Allowed (Optional)
2.3	(c) Partnership Firm: (i) All documents as mentioned in para 18 of the Tender Form (Second Sheet).	Yes	Yes	Allowed (Optional)
2.3.1	The tenderer(s) shall enclose the A notarized copy of the Partnership Deed or a copy of the Partnership deed/partnership firm agreement registered with the Registrar.	Yes	Yes	Allowed (Optional)
2.3.2	Copy of PAN Card of partnership firm along with their tender.	Yes	Yes	Allowed (Optional)
2.3.3	A notarized or registered copy of Power of Attorney in favour of the individual to tender for the work, sign the agreement etc. and create liability against the firm.	Yes	Yes	Allowed (Optional)
2.3.4	An undertaking by all partners of the partnership firm that they are not blacklisted or debarred by Railways or any other Ministry/ Department of the Govt. of India from participation in tenders / contracts as on the date of submission of bids, either in their individual capacity or in any firm/LLP in which they were / are partners/members.	Yes	Yes	Allowed (Optional)

**RATLAM DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT_RTM_26_07_R_Signal

Closing Date/Time: 08/06/2026 15:00

2.4	(d)Company registered under Companies Act2013: (i)The copiesof MOA (Memorandum of Association) / AOA (Articles ofAssociation) of the company.	Yes	Yes	Allowed (Optional)
2.4.1	(ii)A copy of Certificate of Incorporation .	Yes	Yes	Allowed (Optional)
2.4.2	(iii)A copy of Authorization/Power of Attorney issued by theCompany (backed by the resolution of Board of Directors) infavour of the individual to sign the tender on behalf of thecompany and create liability against the company.	Yes	Yes	Allowed (Optional)
2.5	(e)LLP (Limited Liability Partnership): (i)A copy of LLP Agreement	Yes	Yes	Allowed (Optional)
2.5.1	(ii)A copy of Certificate of Incorporation.	Yes	Yes	Allowed (Optional)
2.5.2	(iii)A copy of Power of Attorney/Authorization issued by the LLPin favour of the individual to sign the tender on behalf of the LLPand create liability against the LLP.	Yes	Yes	Allowed (Optional)
2.5.3	(iv)An undertaking by all partners of the LLP that they are notblacklisted or debarred by Railways or any other Ministry /Department of the Govt. of India from participation in tenders /contracts as on the date of submission of bids, either in theirindividual capacity or in any firm/LLP or JV in which they were /are partners/members. Concealment / wrong information inregard to above shall make the contract liable for determinationunder Clause 62 of the Standard General Conditions of Contract.	Yes	Yes	Allowed (Optional)
2.6	(f)Registered Society & Registered Trust: (i)A copy of Certificateof Registration	Yes	Yes	Allowed (Optional)
2.6.1	(ii)A copy of Memorandum of Association of Society/Trust Deed	Yes	Yes	Allowed (Optional)
2.6.2	(iii)A copy of Power of Attorney in favour of the individual to signthe tender documents and create liability against theSociety/Trust.	Yes	Yes	Allowed (Optional)
2.6.3	(iv)A copy of Rules & Regulations of the Society .	Yes	Yes	Allowed (Optional)
3	Please submit a certificate in the prescribed format {As perAppendix 1- Annexure C & Appendix 1- Annexure H (if applicable)of Tender Documents} for verification / confirmation of thedocuments submitted for compliance of eligibility / qualifyingcriteria. Non submission of the certificate, or submission ofcertificate either not properly filled in, or in a format other thanthe prescribed format shall lead to summary rejection of youroffer.	Yes	Yes	Allowed (Mandatory)
4	Information as per Para 16 of GCC Part (1)(Tender form secondsheet AnnexI) related to Employment/Partnership Etc. of RetiredRailway Employees and clauses 59 (9) & 62 (1)(xv) to GCCregarding employment etc. Of retired government officers byrailway contractors"	Yes	Yes	Allowed (Mandatory)
4.1	Certificate of Information regarding EMPLOYMENT/PARTNERSHIPetc. of Retired Railway Employees with the tender as per theattached proforma, Appendix1, Annexure L2 of tender document	Yes	Yes	Allowed (Optional)
4.2	Document :- Certificate of NO RELATIVE being an employee ofWestern Railway as per attached Performa Appendix1, AnnexureL1 of Tender document.	Yes	Yes	Allowed (Optional)

6. Documents attached with tender

S.No.	Document Name	Document Description
1	GCC_April-2022_1.pdf	GCC 2022
2	GCCACS.pdf	GCC ACS
3	revisedTANearthingHQletter040725_compressed.pdf	Latest Earth TAN
4	TenderdocumentGRF-SMPIBS1.pdf	Tender Document
5	AppendixGRF-SMPIBS2.pdf	Appendix
6	ACS-2toGCC-2022.pdf	GCC 2022 ACS2
7	GCCApril2022ACSNo_3_1.pdf	GCCACS3
8	GCCApril2022ACSNo_4.pdf	GCCACS4
9	GCCApril2022ACSNo_5.pdf	GCCACS5
10	GCCApril2022ACSNo_6.pdf	GCCACS6
11	GCCApril2022ACSNo_8.pdf	GGC correction slip 8
12	GCCApril2022ACSNo_9.pdf	GGC correction slip 9

**RATLAM DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT_RTM_26_07_R_Signal

Closing Date/Time: 08/06/2026 15:00

13	GCCApril2022ACSNo_10.pdf	GGC correction slip 10
14	GCCApril2022ACSNo_7.pdf	GGC correction slip 7
15	GCCApril2022ACSNo_11.pdf	GGC correction slip 11
16	ApprovedSIPofGRFicwSMP-GRFIBS.pdf	Approved SIP of GRF icw SMPGRF IBS
17	ApprovedSIPofSMPicwSMP-GRFIBS.pdf	Approved SIP of SMP icw SMPGRF IBS

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

Signed By: ASHOK KUMAR JOSHI

Designation : Sr.DSTE SOUTH RTM