

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-49R

Closing Date/Time: 09/06/2026 15:00

Sr.DSTE acting for and on behalf of The President of India invites E-Tenders against Tender No **KOTA-SNT-SIG-2025-49R** Closing Date/Time 09/06/2026 15:00 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

1. NIT HEADER

Name of Work	Estimate: Enhancing safety by replacing defective/ worn-out TLJBs, Track leads, point insulations, ground connections, Location boxes & foundations, Signal assemblies & foundations including trenching, laying of cables, terminations etc. in the section of DSTE/ SWM on Kota Division		
Bidding type	Normal Tender		
Tender Type	Open	Bidding System	Single Packet System
Tender Closing Date Time	09/06/2026 15:00	Date Time Of Uploading Tender	15/05/2026 18:19
Pre-Bid Conference Required	No	Pre-Bid Conference Date Time	Not Applicable
Advertised Value	14476907.58	Tendering Section	SIGNAL
Bidding Style	Single Rate for Tender	Bidding Unit	Above/Below/Par
Earnest Money (Rs.)	289600.00	Validity of Offer (Days)	60
Tender Doc. Cost (Rs.)	0.00	Period of Completion	12 Months
Contract Type	Works - General	Contract Category	Expenditure
Bidding Start Date	26/05/2026		
Are JV allowed to bid	No	Number of JV Member Allowed	0
Are Consortium allowed to bid	No	Number of Consortium Member Allowed	0
Ranking Order For Bids	Lowest to Highest	Expenditure Type	Capital (Works)

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () sch-schedule							14476907.58	
1	Please see Item Breakup for details.				6464704.42	AT Par	6464704.42	
	Description:- SCHEDULE-A							
2	Please see Item Breakup for details.				8012203.16	AT Par	8012203.16	
	Description:- SCHEDULE-B							

3. ITEM BREAKUP

Schedule	Schedule sch-schedule					
Item- 1	SHEDULE-A					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	(i) Supply of 4 conductor disconnect terminal block with test & measurement facility, with screw less, spring cage clamp connections suitable for 0.08 to 2.5 Sq.mm conductor with current capacity of 16 Amps as per RDSO Spcn. No. RDSO/SPN/189/2004 Ver. 3.0 or latest.	Numbers	400.00	66.79	26716.00
2	2	ii) Supply of End Stop 10mm for above Din 35 Rail.	Numbers	200.00	11.37	2274.00
3	3	Supply of PD1 (21KHz) card for GG Tronic make HASSDAC as per RDSO specification No.RDSO/SPN/177/2012 withversion 3.0 or latest with RDSO inspection Make/Brand:- GG Tronics. Make / Brand: G.G. TRONICS INDIA PRIVATE LIMITED	Numbers	12.00	39530.00	474360.00

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-49R

Closing Date/Time: 09/06/2026 15:00

4	4	Supply of PD2 25 KHZ Card suitable for GG Tronic make SSDAC/HASSDAC as per RDSO Spec. no. RDSO/SPN/177/2012 Ver 3.0 or latest make/brand:-GG Tronics Make / Brand: G.G. TRONICS INDIA PRIVATE LIMITED	Numbers	12.00	39530.00	474360.00
5	5	Supply of 21 KHZ/25 KHZ Transmitter coil assembly for HASSDAC Systems RDSO Specn. No. RDSO/SPN/177/2012 (Ver.3) Make-G.G.Tronics. Make/Brand:- GG Tronics ,HSN Code: 85309000	Numbers	9.00	44861.24	403751.16
6	6	Supply of 21 KHZ/25 KHZ Receiver coil assembly for HASSDAC Systems RDSO Specn. No. RDSO/SPN/177/2012 (Ver.3) Make-G.G.Tronics. Make/Brand:- GG Tronics , HSN Code:- 85309000HSN	Numbers	9.00	44861.24	403751.16
7	7	21/25 KHZ TX Coil Assembly - 15 meter cable length Base clamp split-G36-T212505 for HASSDAC system suitable for G.G. Tronics India Pvt. Ltd. specification no. RDSO/SPN/177/2012 Version3, Make G.G.Tronics or similar	Numbers	2.00	43660.00	87320.00
8	8	21/25 KHZ RX Coil Assembly - 15 meter cable length Base clamp split-G36-R212505 for HASSDAC system suitable for G.G. Tronics India Pvt. Ltd. specification no. RDSO/SPN/177/2012 Version3, Make G.G.Tronics or similar	Numbers	2.00	43660.00	87320.00
9	9	Supply of Digital Cards for SSDAC as per site requirement as per RDSO Specn. No. RDSO/SPN /177/ 2012 (Ver. 3) or latest.	Numbers	4.00	172870.00	691480.00
10	10	Supply of Analog Cards for SSDAC as per site requirement as per RDSO Specn. No. RDSO/SPN/177/ 2012 (Ver. 3) or latest.	Numbers	4.00	106200.00	424800.00
11	11	"Supply of High power main signal with LED aspect integrated type, current Regulator as per RDSO Specn. No RDSO/SPN/199/2025 (Rev. 1.2) or latest. Red"	Numbers	45.00	8243.51	370957.95
12	12	"Supply of High power main signal with LED aspect integrated type, current Regulator as per RDSO Specn. No RDSO/SPN/199/2025 (Rev. 1.2) or latest. Yellow"	Numbers	45.00	8243.51	370957.95
13	13	Supply of High power main signal with LED aspect integrated type, current Regulator as per RDSO Specn. No RDSO/SPN/199/2025 (Rev. 1.2) or latest. Green	Numbers	45.00	9351.57	420820.65
14	14	Supply of calling ON Unit LED integrated type as per RDSO Specn. No RDSO/SPN/153/2023 Rev.5.0. or latest.	Numbers	45.00	6176.82	277956.90
15	15	Supply of LED for shunt signal integrated type as per RDSO Specn. No RDSO/SPN/153/2023 Rev.5.0. or latest.	Numbers	45.00	5070.97	228193.65
16	16	Supply of Thermo shrink Jointing Kit for jointing underground 0.9 mm dia. cond. 4/6 quad cables as per specn No. IRS: TC-77/2012 (Rev.3.0) with Amend. 1, 2 & 3 or latest.	Numbers	15.00	3402.91	51043.65
17	17	Supply of Earth Electrode assembly as per Drg. No. S&T/CON/KOTA/EARTHING/01 ALT - 01. All nut, Bolts & Lugs to be of stainless steel. The earth electrode pipe shall be 'B' Class/ Medium Grade as per Specification No. IS: 1239 Pt. 1/ 2004 of Nominal Inner Dia 50mm, Outside dia (Max 60.8 mm, Min 59.7 mm), Thickness (3.6mm), Tolerance in Thickness ('+' not limited, '-' 12.5 percent).	Numbers	53.00	1313.36	69608.08

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-49R

Closing Date/Time: 09/06/2026 15:00

18	18	Supply of Electromagnetic boom holding / locking system with +VE boom locking operated on 110VDC as per drawing attached	Pair	45.00	25283.43	1137754.35
19	19	Supply of Timing Belt for locking in ELB. confirming to RDSO/SPN/208/2012 ver. 2.0.or latest amendment.	Numbers	45.00	460.20	20709.00
20	20	"Supply of Chlorinated rubber Paint as per IS 13467 : 1992 suitable for applying on insulated rail joint. Colour:- Grey (Warranty Period : Upto 30 months from the date of supply)"	Litre	300.00	271.40	81420.00
21	21	"SUPPLY OF MAPLE 4C , INTEGRATE MULTIPLEXER (TDM) FOR CONVERSION OF E ONE TO 64 KBPS, 19"" RACK MOUNTABLE OF 1 U HEIGHT, 4*E 1 UPLINK, 4 SERVICE SLOTS. ONE SERVICE SLOT POPULATED WITH 2w/4w E&M CARD SUPPORTING UP TO 8 INTERFACE, BALANCE 2 SLOT EMPTY, UNIT UP LINK E ONE 1+1 PRODUCTION, SHOULD SUPPORT UP TO 4 DIRECTION, POWERSUPPLY SUITABLE FOR AC & DC WORKING. MAKE : MRO TEK (MAPLE 4C/4E1/AC(V4) OR FABIO 4C OR SIMILAR"	Numbers	4.00	44250.00	177000.00
22	22	Supply of 108 Mbps TDM over Ethernet Access Multiplexer with provision of 4 DTE E1 channel over fibre port, fibre port supporting single mode with driving distance upto 15 Kms plus one Ethernet port 10/100 Mbps, power supply AC / DC option from a single socket. Mrotek model ECAT-01L as per specification.	Numbers	4.00	21611.01	86444.04
23	23	Supply of Hydrometer Exide make or similar for measuring specific gravity of Battery Graded acid with mounting stand in location Boxes. (Material inspected by Consignee)	Numbers	17.00	289.54	4922.18
24	24	Supply of Reflective Tape Yellow :- Highlighter grade retro reflective tape is made of non metelised polycarbonate micro primatice visible from 1000 meters highly durable ASI 90 specified reflection value will not detroinate as sure clean application and endures protection against seepage and dirt are to confirm compliance to ASI 90 size per four feet width in roll .Inspection by Consignee.	Sqm	300.00	131.91	39573.00
25	25	Supply of Reflective Tape Black :- Highlighter grade retro reflective tape is made of non metelised polycarbonate micro primatice visible from 1000 meters highly durable ASI 90 specified reflection value will not detroinate as sure clean application and endures protection against seepage and dirt are to confirm compliance to ASI 90 size per four feet width in roll .Inspection by Consignee.	Sqm	150.00	131.91	19786.50
26	26	Supply of 48 Fiber OFC JointClosure similar to Specification No.RDSO/SPN/TC/68/2014 Rev 1.0 or latest.	Numbers	20.00	1571.21	31424.20
					Total	6464704.42
Item- 2	SCHEDULE-B					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-49R

Closing Date/Time: 09/06/2026 15:00

1	01	"Carrying out relay alteration to the existing relay wiring at relay rack/location box as per the approved circuit diagram. These work includes the releasing of existing unused wires and wiring the relays using 16/0.2 mm copper wire as per RDSO Spec. Wire to be procured from RDSO's approved source	Per Relay	1500.00	248.13	372195.00
2	02	Lettering & Numbering of detail and description writing of particular relays, battery & power equipments, IPS, operating panel, axle counter etc. constituting entire system with contractor's own paint and writing material ("Asian" make or similar enamel paints or similar paint only to be used). The work shall be done as per extant practice on W.C. Railway & instruction of Railway Engineer at site. Per Unit = 1 No. of Relay OR 1 No. of Battery OR 1 Nos. of Power equipment.	Per Unit	1500.00	74.77	112155.00
3	03	Excavation of trench 1.2 mtr deep, 300mm wide at the bottom along main line in normal soil, including clearing of bushes, trees etc and refilling of the trench by excavated soil and ramming after laying of the required quantity of cables as per instructions of Engineer at site. The work also includes excavation of trenches in the beds of culverts. Whenever the dimensions of cable Trenches as mentioned in the Tender Schedule are not easily achievable due to terrain conditions, then payments will be made on a pro-rata basis, for the dimensions achieved.The specific approval of the Engineer in charge of the work (not below the rank of Sr. Scale officer), will be required for such dispensation.	Kilometre	8.00	113517.63	908141.04
4	04	Excavation of cable trench 300mm wide at the bottom and 1.2 meter deep in hard soil mixed with bolders / hard murum soil including clearing of trees, bushes and refilling of cable trench by excavated soil, murum, bolders etc. Care should be taken while refilling the cable trench such that the murum / bolders etc. does not damage the cable. Ramming after laying of cable (a) 6-quad (b) jelly filled & power cables etc. Whenever the dimensions of cable Trenches as mentioned in the Tender Schedule are not easily achievable due to terrain conditions, then payments will be made on a pro-rata basis, for the dimensions achieved.The specific approval of the Engineer in charge of the work (not below the rank of Sr. Scale officer), will be required for such dispensation.	Kilometre	2.00	194423.97	388847.94

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-49R

Closing Date/Time: 09/06/2026 15:00

5	05	Excavation of cable trench 1.0m deep from the rail flange and 300mm wide across the track, for track crossing and refilling after laying of RCC/ GI/ DWC pipes and restoring the track to its original condition. Generally there shall be no proportionate payment for cable at depth lesser than that specified in the tender schedule. If it is not possible to reach the required depth at any location, then the contractor shall obtain approval of Railway Site Engineer, who shall get the dispensation, from JAG vide Rly. Board's letter No. 2013/Sig/SEM Pt.-II/Misc., dated 12.06.2014 before commencement of cable laying process and only then shall the proportionate payment be made to the contractor. The work shall be done as per extant practice on W.C. Railway & instruction of Railway Engineer at site. Cable trench as per Drg. No. TS/Cable laying/12/03/03 Alt.-1. For achieving 1.0 Mtr depth for the bottom most cable, the contractor shall dig the trenches to a depth, slightly more than 1.0m to take care of practical problems. Laying of RCC/GI/DWC pipe and cables is covered in separate item	Metre	750.00	233.59	175192.50
6	06	"Blowing / drawing of OFC through HDPE duct & protective work already provided in the excavated trench. All the equipment and machinery required shall be arranged by the contractor at his own cost. Cable should be laid according to the technical conditions and instructions of the site in charge. Note: OFC will be supplied by Railway."	Kilometre	2.00	15426.15	30852.30
7	07	Transportation & laying of HDPE Duct in the trenches and in the protective works (i.e. GI pipes/DWC pipe/ boring etc.) and supply as well as pulling of nylon rope through it at different places as per direction of Engineer-in-charge. This also includes laying of Duct in track crossings & road crossings etc. Note-HDPE pipes along with all accessories such as couplers, plugs, end-plugs etc., which are required for proper laying & fixing of HDPE duct, shall be supplied by Railways.	Kilometre	2.00	4511.16	9022.32
8	08	Supply & laying of well burnt bricks of size 200mm x 90mm x 65mm inside the trench (with the brick length being perpendicular to cable route) after laying of cable & covering of cables laid in trenches by loose excavated soil for a layer of 50mm thickness approximately, in station area from Outermost to Outermost signal or at any other location as per instruction of Site Engineer. Note:- Size of bricks to be got approved by Railway Site Engineer. In case brick size is in variance with the size given in the tender schedule then proportionate payment on volumetric basis shall be paid to contractor subject to a maximum limit of schedule rate.	Numbers	100000.00	3.89	389000.00
9	09	Laying of All types of Signal/ Telecom/ Power Cable of various cores/ sizes in excavated trenches. The work shall be done as per extant practice followed on W.C. Railway and as per the instructions of Railway Engineer at site.	Kilometre	30.00	13375.32	401259.60

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-49R

Closing Date/Time: 09/06/2026 15:00

10	010	Transportation & Laying of GI/DWC/RCC pipes along with collars in trenches at places wherever required as per the instruction of the engineer at site.	Metre	300.00	75.29	22587.00
11	011	Cutting of all types of Roads (1 Mtr X300 mm)/ platforms (300mm X 300mm) preparatory to trenching, excavation and refilling after laying of RCC/ GI/ DWC pipe & restoring them to original condition. Generally there shall be no proportionate payment for cable at depth lesser than that specified in the tender schedule. If it is not possible to reach the required depth at any location, then the contractor shall obtain prior approval of Railway Site Engineer, who shall get the dispensation, from JAG vide Rly. Board's letter No. 2013/Sig/SEM Pt.-II/Misc., dated 12.06.2014 before commencement of cable laying process and only then shall the proportionate payment be made to the contractor. This also includes laying of any No. of DWC/RCC/GI pipes, as per requirement. The work shall be done as per extant practice on W.C. Rly & instructions of Railway Engineer at site. The DWC/RCC/GI pipes will be supplied by Railway. Laying of RCC/GI/DWC pipe is covered in separate item.	Metre	300.00	248.64	74592.00
12	012	Installation of Thermo-shrinkable jointing kits for making (a) straight through joints without transformer for 6 -quad Jelly filled cable, (b)Derivation joint without transformer for 6-Quad Jelly filled cable, and (c)Straight Through joint without transformer for10 Pr/20Pr. PIJFcables and construction of BrickChamber for protection of joints withcontractor's all materials as per Drg.No. given by Railway where VF transformers are notrequired. All the materials required for the work are to be arranged bythe contractor himself at his own cost except Thermo-shrinkable jointing kitwhich is already covered in Supplyportion of the tender. After jointingthe cable through test such asinsulation test, Continuity cablelosses etc. to be carried out jointlywith the Railway Engineer. If anydefect or any damage observedduring jointing, the contractor shouldredo the joint free of cost.	Numbers	15.00	2959.14	44387.10
13	013	Supply, fixing, painting and installation of RCC/Stone cable route markers as per drawing No. DRM/KOTA/MISC-87 or WCR/Sig/ST.RT.MARKER/201401. Placing and securing of cable route markers in trenches at the specified interval and diversions, joints etc along the cable route. The work shall be done as per extant practice on W. C. Rly & the instructions of Rly engineer at site. Sample to be approved by engineer in-charge of the Railways before supply, after the testing prescribed in drawing. This includes supply of Paints of different colours as per drawing. The paint shall be either from Asian or Shalimar / Apcolite / Berger having ISI mark.	Numbers	334.00	229.23	76562.82

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-49R

Closing Date/Time: 09/06/2026 15:00

14	014	Fixing of ARA/cage type disconnect terminals and fuse blocks with provision of holes on Phenolic Laminated Sheets and fixing with galvanised nuts & bolts in Location Boxes and elsewhere. This includes provision of additional holes on the Phenolic Laminated Board on either side for cable conductor entry. The work shall be done as per the instructions of Railway Engineer at site.	Numbers	2000.00	30.07	60140.00
15	015	Termination of cable cores on ARA Terminals/cage type disconnect terminals, fuse blocks, 8-way terminals blocks, telecom terminals in new/existing apparatus cases, existing MCTB/existing telecom cable termination racks. This includes all associated works of pulling out the cable from underground, dressing of cable, making wiring tree with contractor lacing & threading material etc. Both ends of a cable core shall be counted as per conductor. This includes soldering of armour tree/ring of cables and connecting to copper plate through GI wire bus bar in location boxes. The work shall be done as per instructions of Railway Engineer at site.	Per Conductor	2000.00	22.56	45120.00
16	016	Excavation, casting (1:3:6) and plastering (1:4, with fine sand) of main signal foundation as per Drg. No. Dy.CSTE/C/Kota/1 ALT 'A' with contractor's own material including ballast, cement, local available sand, PVC pipe & galvanised anchor bolts with nuts & washers, etc. The hole for cable entry should be kept as per site requirement and instruction of Railway Engineer at site. The required Ferma of the size mentioned in the drawing for casting of foundation will have to be brought by the contractor at his own cost. All nuts, bolts and washers etc. should be galvanised iron.	Numbers	20.00	11430.80	228616.00
17	017	Erection of Main Signal (CLS) Post with Surface base and signal unit complete on top or on Off-set Bracket, fixing of front and back staging, ladder, guard, signal name plates/board, protective screen, blanking of ladder (0.6mm MS sheet), if any with contractor's own brackets, nuts & bolts & other fixing materials. This also includes erection of auxiliary signals like Calling-ON, Shunt Signal. Wooden white cross-arms (1000mm x 100 mm) to be provided by the contractor till the signals are commissioned with contractor's own material. If the ladder/front/back staging is infringing the SOD, then suitable arrangement of fixing steps for climbing up to signal unit and reducing the size of front/back staging as per instructions of site engineer shall be done. The work shall be done as per instructions of Railway Engineer at site. All nuts, bolts and washers etc. should be galvanised iron.	Numbers	20.00	3946.08	78921.60

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-49R

Closing Date/Time: 09/06/2026 15:00

18	018	Termination of tail cable on Main & Auxiliary Signal units and wiring with contractor own material, fixing of LED signal units etc. Flexible Single core copper wire 2.5 sq.mm (50/0.25) conforming to IS-694:1990 (as per aspect colour) and lugs etc. will be supplied by the contractor. This includes insertion of tail cables from ground to signal unit, thereafter sealing the opening and testing the signal as per instructions of Railway Engineer at site.	Numbers	20.00	1367.97	27359.40
19	019	Excavation, casting (1:3:6) and plastering (1:4, fine sand) of shunt signal foundation as per Drg. No. Dy.CSTE/C/Kota/1 ALT 'A' with contractor's own material including ballast, cement, local available sand, PVC pipe & galvanised anchor bolts with nuts & washers, etc. The hole for cable entry should be kept as per site requirement and instruction of Rly engineer at site. The required Ferma of the size mentioned in the drawing, for casting of foundation will have to be brought by the contractor at his own cost. All nuts, bolts and washers etc. should be galvanised iron.	Numbers	10.00	3392.40	33924.00
20	020	Erection of Shunt Signal Post with surface base, unit, number plate complete. Wooden white cross-arms (1000mm x 100 mm) to be provided by the contractor till the signals are commissioned with contractor's own material. The work shall be done as per instructions of Railway Engineer at site. All nuts, bolts and washers etc. should be galvanised iron.	Numbers	10.00	546.51	5465.10
21	021	Termination of tail cable on Shunt Signal units and wiring with Contractor's own material, fixing of LED Signal unit etc. Flexible Single core copper wire 2.5 sq.mm (50/0.25) conforming to IS: 694:1990 copper wire as per Railway standard and lugs etc. will be supplied by the contractor. This includes insertion of tail cables from ground to signal unit, thereafter sealing the opening and testing the signal as per instructions of Rly engineer at site.	Numbers	10.00	446.80	4468.00
22	022	"Excavation and Casting of Apparatus Case Foundation with mixture of Cement:Sand:Stone aggregate/Chip in 1:3:6 ratio and plastering with mixture of Cement:Sand in 1:4 ratio, with contractors own Metal Sheet ferma of the size mentioned in the drawing, cement, anchor bolts, with nuts & washers and other materials. The items also include additional earth work if required as per instruction of Rly. Engineer at site. All nuts, bolts and washers etc. should be galvanised iron. Single Case as per Drg. No. SK 783-1/2 with latest alterations"	Numbers	17.00	11824.68	201019.56
23	023	"Excavation and Casting of Apparatus Case Foundation with mixture of Cement:Sand:Stone aggregate/Chip in 1:3:6 ratio and plastering with mixture of Cement:Sand in 1:4 ratio, with contractors own Metal Sheet ferma of the size mentioned in the drawing, cement, anchor bolts, with nuts & washers and other materials. The items also include additional earth work if required as per instruction of Rly. Engineer at site. All nuts, bolts and washers etc. should be galvanised iron. Half Case as per Drg. No. SK 783-1/2 with latest alterations"	Numbers	7.00	11396.98	79778.86

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-49R

Closing Date/Time: 09/06/2026 15:00

24	024	"Erection of Apparatus cases. This includes filling of Location Foundations with the sieved sand being used for making the foundation of location boxes and plastering on top of the sand. All nuts, bolts and washers etc. should be galvanised iron. Single Case"	Numbers	17.00	1240.69	21091.73
25	025	"Erection of Apparatus cases. This includes filling of Location Foundations with the sieved sand being used for making the foundation of location boxes and plastering on top of the sand. All nuts, bolts and washers etc. should be galvanised iron. Half Case"	Numbers	7.00	948.76	6641.32
26	026	"Supply, fabrication and fixing of Phenolic Laminated Sheet Board in Location Box by providing all fixtures, double ended insulators (06 Nos.), PVC coated string rods at the back side for cable support with contractor's own material. The work shall be done as per Drg. No. SK 783-1/2 with latest alterations & as per instructions of Railway Engineer at site. The Phenolic Laminated Sheets should be of 10mm thick, grade P3 as per specification No. IS: 2036 of 1995 or latest. The size of the Phenolic Laminated Sheet for Full Case terminal board should be 800mm x 950mm and for half case it should be 800mm x 450mm. In case board size is in variation with the size mentioned as per location details, then proportionate payment on area basis shall be made. This also include, the work to be done in existing Location Boxes (if required) as per instructions of Railway Site Engineer. Single Case"	Numbers	17.00	4877.16	82911.72
27	027	"Supply, fabrication and fixing of Phenolic Laminated Sheet Board in Location Box by providing all fixtures, double ended insulators (06 Nos.), PVC coated string rods at the back side for cable support with contractor's own material. The work shall be done as per Drg. No. SK 783-1/2 with latest alterations & as per instructions of Railway Engineer at site. The Phenolic Laminated Sheets should be of 10mm thick, grade P3 as per specification No. IS: 2036 of 1995 or latest. The size of the Phenolic Laminated Sheet for Full Case terminal board should be 800mm x 950mm and for half case it should be 800mm x 450mm. In case board size is in variation with the size mentioned as per location details, then proportionate payment on area basis shall be made. This also include, the work to be done in existing Location Boxes (if required) as per instructions of Railway Site Engineer. Half Case"	Numbers	7.00	2999.11	20993.77

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-49R

Closing Date/Time: 09/06/2026 15:00

28	028	"Supply, fabrication and fixing of Phenolic Laminated Sheet for Shelf of equipments/batteries with contractor's own fixing material, angle frames, additional in-between supporting angle for the Shelf, etc. The work shall be done as per Drg. No. SK 783-1/2 with latest alterations & as per instructions of Railway Engineer at site. The Phenolic Laminated Sheets should be 10mm thick, grade P3 as per specification No. IS: 2036 of 1995 or latest. The size of Shelf for Single Case Apparatus/Location Box shall be 500mm x 950mm and for Half Case Location Box it shall be 500mm x 450mm. In case board size is in variation with the size mentioned as per Location details, then proportionate payment on area basis shall be made. Galvanised nut & bolts to be used for fixing of Phenolic Laminated Sheets. Single Case"	Numbers	17.00	3105.23	52788.91
29	029	"Supply, fabrication and fixing of Phenolic Laminated Sheet for Shelf of equipments/batteries with contractor's own fixing material, angle frames, additional in-between supporting angle for the Shelf, etc. The work shall be done as per Drg. No. SK 783-1/2 with latest alterations & as per instructions of Railway Engineer at site. The Phenolic Laminated Sheets should be 10mm thick, grade P3 as per specification No. IS: 2036 of 1995 or latest. The size of Shelf for Single Case Apparatus/Location Box shall be 500mm x 950mm and for Half Case Location Box it shall be 500mm x 450mm. In case board size is in variation with the size mentioned as per Location details, then proportionate payment on area basis shall be made. Galvanised nut & bolts to be used for fixing of Phenolic Laminated Sheets. Half Case"	Numbers	7.00	1934.94	13544.58
30	030	"Installation of Equipments (Relays, Resistance, chargers, Choke, batteries, LV box, KLCR, PPTC fuses & track feed charger alarm unit, etc. as applicable) with contractor's own wiring material, MS frame, copper lugs etc. & wiring of the same in Apparatus Cases as per Location Diagrams, paralleling of spare contacts of Metal to Carbon Relays and wiring of potential free contact of track feed charger and testing of track circuits as per instruction of Railway's Site Incharge and standard practice. This also includes supply of Multi-strand Flexible Single Core Copper Wire 2.5 sq.mm (50/0.25) except for relay wiring which will be done with 16/0.2 mm flexible multi-strand wire conforming to IS: 694:1990 with suitable lugs. All wires to be duly manufactured by RDSO approved firms (16/0.2 mm flexible multi-strand wire inspected by RDSO). Note: PPTC fuses shall be provided as per fixing arrangement of PPTC as advised by HQ's policy guideline issued vide letter no. WCR/N-HQ/110/Signal Policy/Sig-32 Pt-VII, dtd. 07.11.2013 i.e. PPTC fuse are to be connected with crimped ring type lugs and crimped area is also to be filled with solder. PPTC lead to be provided with ferrules for volt & current rating of PPTC. Single Case"	Numbers	17.00	2083.19	35414.23

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-49R

Closing Date/Time: 09/06/2026 15:00

31	031	"Installation of Equipments (Relays, Resistance, chargers, Choke, batteries, LV box, KLCR, PPTC fuses & track feed charger alarm unit, etc. as applicable) with contractor's own wiring material, MS frame, copper lugs etc. & wiring of the same in Apparatus Cases as per Location Diagrams, paralleling of spare contacts of Metal to Carbon Relays and wiring of potential free contact of track feed charger and testing of track circuits as per instruction of Railway's Site Incharge and standard practice. This also includes supply of Multi-strand Flexible Single Core Copper Wire 2.5 sq.mm (50/0.25) except for relay wiring which will be done with 16/0.2 mm flexible multi-strand wire conforming to IS: 694:1990 with suitable lugs. All wires to be duly manufactured by RDSO approved firms (16/0.2 mm flexible multi-strand wire inspected by RDSO). Note: PPTC fuses shall be provided as per fixing arrangement of PPTC as advised by HQ's policy guideline issued vide letter no. WCR/N-HQ/110/Signal Policy/Sig-32 Pt-VII, dtd. 07.11.2013 i.e. PPTC fuse are to be connected with crimped ring type lugs and crimped area is also to be filled with solder. PPTC lead to be provided with ferrules for volt & current rating of PPTC. Half Case"	Numbers	7.00	1449.44	10146.08
32	032	Supply & Fixing of lamp holders (two pin) with switches (ISI mark) of reputed make for location boxes. This also includes supply of bulb of reputed make.	Numbers	17.00	119.77	2036.09
33	033	Installation of earth electrode assembly as per Drg. No. S&T/CON/Kota/Earthing/01 ALT-1 and connecting through stainless steel wire 8 SWG supported on MS flat of size 5mm x 40mm to earth electrode as per Drg. No. T/2014/1 for signals and T 2014/5 for Location Boxes/Apparatus Cases. The earth value should be less than 10 Ohms including the lead wire. The value should be measured in presence of Railway Supervisors. It should be documented and painted on earth enclosure made of concrete. Only earth electrode will be supplied by Railway. All other material required for provision of earthing will be brought by the contractor. This earth can be provided for DPs, block instruments & ELD etc. also, so as to achieve the desired earth resistance value. Earth enclosure to be manufactured & supplied by contractors own material of ratio 1:3:6, without cover. Additional connection of Earth pipe including parallel connection with other earth pipes with the function shall be done using left over pieces of signalling cable. Laying of cable pieces shall be covered in laying of cable item and cable shall be supplied by Railways.	Numbers	53.00	2426.89	128625.17

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-49R

Closing Date/Time: 09/06/2026 15:00

34	034	"Erection, Fitting and Rail connection of Track Lead Junction Box (TLJB) on two vertical support (M.S. angle) with contractor's own fixing material including 7mm single groove galvanized channel pins for track lead connections as per Drg. No. JBP/S&T/C/106/II. This include drilling of holes (04 Nos., 8.2 mm dia) in rails for track connections as per instructions of Railway Engineer at site. Note: Jacketted galvanized steel wire rope of 6mm dia., PVC sheathed of 2mm thickness for connection between the TLJB and the rails to be used and to be supplied by the contractor. Double wire ropes to be connected between each rail and TLJB (using lugs) i.e. with each TLJB, 04 Nos. of wire ropes to be fixed, at locations having positive & negative connections and at other TLJBs i.e. for jumpering only 02 wire ropes are required to be fixed (jacketted galvanised steel wire rope of 6mm dia, PVC sheathed of 2mm thickness inspected by consignee)."	Numbers	150.00	1905.29	285793.50
35	035	Provision of bonding with GI wire 4mm dia (8 SWG) for fish plate joints bonds, crossing bond etc. This will include drilling of 7.2 mm dia. holes in rails (4 Nos.) and provision of two jumpers for each bond, etc. with contractor's own tools as per instruction of Railway Engineer at site. (Channel pin, bonding wire (8 SWG) will be supplied by contractor). Z-bonding will be done using left over cable pieces (two pieces per bond) with 08 holes per bond, these cables will be supplied by the railways (GI wire 4mm dia, 8SWG for bonding inspected by consignee). NOTE: Two jumpers will constitute one unit of this item.	Numbers	1500.00	219.08	328620.00
36	036	Charging of 2V lead Acid Batteries with contractors own battery grade sulphuric acid and distilled water with minimum two charge - discharge cycles, installation of charged batteries in group & their connection & wiring. The work shall be done as per extant practice of W.C. Railway & instruction of Engineer in-charge. The item unit will be per 100 VAH	Per Unit	960.00	100.73	96700.80
37	037	Excavation of pit in and around the existing location boxes very carefully without damaging the working cables and shifting and turning the location boxes to clear of the infringement as instructed by the Railway representative at site. The work includes ensuring the safety of the signalling system, releasing the cable coils to give access for shifting/turning the location boxes. Necessary masonry work and earth work in and around the location boxes to the required level shall be done as instructed by the Railway representative at site. If the existing earth connections to the location boxes are disturbed, the earth wires shall be properly re-connected. [All materials required for the work shall be supplied by the Contractor].(a)Shifting of apparatus case (full)	Numbers	10.00	3893.05	38930.50

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-49R

Closing Date/Time: 09/06/2026 15:00

38	038	Excavation of pit in and around the existing location boxes very carefully without damaging the working cables and shifting and turning the location boxes to clear of the infringement as instructed by the Railway representative at site. The work includes ensuring the safety of the signalling system, releasing the cable coils to give access for shifting/turning the location boxes. Necessary masonry work and earth work in and around the location boxes to the required level shall be done as instructed by the Railway representative at site. If the existing earth connections to the location boxes are disturbed, the earth wires shall be properly re-connected. [All materials required for the work shall be supplied by the Contractor]. (b) Shifting of apparatus case (half)	Numbers	5.00	2576.88	12884.40
39	039	"Fixing/ Refixing of electrical point machine on existing layout, ground connection during phase working (NI/ Pre-NI) after removing the electrical point detector, FPL assembly and mechanical or any other fittings including existing Point Machine fitting if any, adjustment if necessary, wiring of point machine testing and commissioning of electrically operated point, fixing and connecting point indicator on derail switch if necessary. This will include fabrication and fixing of GI bend pipes as per Drg. No. Dy.CSTE(Con)/Kota/5 of S-shape of 1.2 meter length & 50mm dia with welded frame for cable entry to the point machine and termination of tail cable in point machine and wiring servicing of point machine & supply and filling of SAE-30 lubrication oil . This also includes installation of William stretcher nylon insulation set (complete), Tongue attachment nylon insulation set and Guage Tie plate nylon insulation set as per RDSO specification. The work shall be done as per extant practice on W.C. Railway and the instructions of Railway Engineer at site. Internal wiring of Point machine & cable termination suitable for EI/PI/RR1 installation, 2.5 sq.mm (50/0.25) conforming to IS: 694:1990 flexible copper wire of different colours & lug will be supplied by contractor. Point Machine, ground connection, insulation sets will be supplied by Railways. This includes drilling of holes in tounge rail, provision of high di-electric varnish on contact assembly and wiring during NI period. This also include rewiring of point machine if required as per type of point machine & circuit (independent detection) & as per instruction of site engineer. To reduce the no. of days of NI, the existing point machines may be replaced with new point machines and operated from existing panel. During pre-NI / NI, rewiring at MCTB/location box/point machine shall be carried out as per the requirement without any additional cost."The item unt will be Per point	Per Unit	10.00	8952.48	89524.80

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-49R

Closing Date/Time: 09/06/2026 15:00

40	040	"Supply and fixing of Insulating Components for Ground Connections of 143mm stroke Point Machine in set. One set consists of :- 1. Insulating Bush for Leading Stretcher Bar to Drg.No. S-8813 : 02 Nos. 2. Insulating Bush for Switch Extension Bracket to drg.no. S-23199: 04 Nos. 3. Insulating Plate RH to Drg.No. S 3265 Alt-1 : 01 No. 4. Insulating Plate LH to Drg.No. S-3266Alt-1 : 01 No. 5. Insulating Washer to drg.No. S-8640 : 06 Nos. 6. Insulating Plate to drg.No. S-8804 : 01No. 7. Crank Bush 'B' to Drg.No. S 8912 Alt-2 : 4 Nos, 8. Insulation Plate for Gauge Tie Plate to Drg.No. CWM 09723 : 02 Nos 9. Insulating Washer for Gauge Tie Plate/Stretcher Bar to Drg.No. CWM 09623 : 28 Nos. 10. Insulating Plate for Insulated Stretcher Bars to Drg.No. CWM 09823 : 04 Nos. 11. Insulation Bush for Gauge Tie Plate/Stretcher Bar to Drg.No. CWM 09923 : 14 Nos."	Set	600.00	754.02	452412.00
41	041	"Supply and fixing of Insulating Components for Ground Connections of 220mm stroke Point Machine in set One set consists of :- 1. Insulating Bush for Switch Extension Bracket to drg.no. S-23199 : 04 Nos. 2. Bush for Drive Rod Lug to Drg.No. RDSO S 3463 : 1 No. 3. Insulating Plate RH to Drg.No. S 3592 : 01 No 4. Insulating Plate LH to Drg.No. S-3593 : 01 No 5. Insulating Washer to drg.No. S-8640 : 04 Nos. 6. Drive Rod Insulation Washer to Drg.No. CWM 10323 : 2 Nos. 7. Insulating Plate for Locking Bar Assembly to Drg.No. S 3404 Alt-PTJ/2 : 02 Nos. 8. Crank Bush to Drg.No. S 8912 Alt-2 : 6 Nos 9. Insulation Plate for Gauge Tie Plate to Drg.No. CWM 09723 : 03 Nos 10. Insulating Washer for Gauge Tie Plate and Stretcher Bar to Drg.No. CWM 09623 : 22 Nos. 11. SSD Insulation Plate to drg.No. CWM 10023 : 01 No. 12. Insulation Bush to Drg.No. CWM 09923 : 11 Nos. Firm's offer:-As Above."	Set	330.00	998.28	329432.40
42	042	All work pertaining to Horizontal Dirctional Drilling (HDD)/Boring and trenchless cabling. It includes supply, transportation and insertion of self lubricated HDPE Pipe and laying of cables in boring under the track/road/platform/circulating area by using different sizes of pipes depending on total number of cables will be crossed. The depth of horizontal boring should be minimum 1 mtr upto 3 mtr, from rail flange/ road level/ground level as per site requirement and as per instructions of Railway Engineer incharge. This item will be used for track crossing of running lines, road crossing & circulating area. By using self lubricated HDPE Pipe of 120mm outer dia and 103.5mm inner dia in the bore and laying of cables in the bore under the track/road/circulating area.	Metre	150.00	1001.39	150208.50
43	043	Preparation of cable duct 150mm x 300mm deep for laying of cables in rocky area and refilling the duct (after cable laying) with concrete mixture of proportion 1:3:6 and grouting the ends at either side of the rocky portion using concrete mixture with contractors own cement and other materials. Cable trench shall be as per Drg. No. Dy.CSTE/C/Kota/07/A. Laying of cables is covered in separate item.	Metre	150.00	358.00	53700.00

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-49R

Closing Date/Time: 09/06/2026 15:00

44	044	"Painting two coats of Enamel Paint over one coat of Red Oxide primer on the following items after scrapping and cleaning of the surface wherever necessary. Primer and Paints with ISI mark is to be supplied by the Contractor. The work shall be done as per instructions of Railway Engineer at site and extant practice on W.C. Railway. Note: Second coat shall be made after completely drying up of first coat of paint, to give good smooth & lasting finish. Apparatus case full size"	Numbers	150.00	554.81	83221.50
45	045	"Painting two coats of Enamel Paint over one coat of Red Oxide primer on the following items after scrapping and cleaning of the surface wherever necessary. Primer and Paints with ISI mark is to be supplied by the Contractor. The work shall be done as per instructions of Railway Engineer at site and extant practice on W.C. Railway. Note: Second coat shall be made after completely drying up of first coat of paint, to give good smooth & lasting finish. Apparatus case Half size"	Numbers	75.00	415.05	31128.75
46	046	"Painting two coats of Enamel Paint over one coat of Red Oxide primer on the following items after scrapping and cleaning of the surface wherever necessary. Primer and Paints with ISI mark is to be supplied by the Contractor. The work shall be done as per instructions of Railway Engineer at site and extant practice on W.C. Railway. Note: Second coat shall be made after completely drying up of first coat of paint, to give good smooth & lasting finish. Point machine with ground connection complete. (Point machine with black enamel only outside and ground connection with Red Oxide)"	Numbers	150.00	194.81	29221.50
47	047	"Painting two coats of Enamel Paint over one coat of Red Oxide primer on the following items after scrapping and cleaning of the surface wherever necessary. Primer and Paints with ISI mark is to be supplied by the Contractor. The work shall be done as per instructions of Railway Engineer at site and extant practice on W.C. Railway. Note: Second coat shall be made after completely drying up of first coat of paint, to give good smooth & lasting finish. Main Signal post with main & auxilliary signal unit, surface base and complete fittings as per W.C. Railway's Standard practice."	Numbers	150.00	940.23	141034.50
48	048	"Painting two coats of Enamel Paint over one coat of Red Oxide primer on the following items after scrapping and cleaning of the surface wherever necessary. Primer and Paints with ISI mark is to be supplied by the Contractor. The work shall be done as per instructions of Railway Engineer at site and extant practice on W.C. Railway. Note: Second coat shall be made after completely drying up of first coat of paint, to give good smooth & lasting finish. Shunt Signal post with signal unit, surface base as per W.C. Railway's Standard practice."	Numbers	150.00	224.46	33669.00

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-49R

Closing Date/Time: 09/06/2026 15:00

49	049	"Painting two coats of Enamel Paint over one coat of Red Oxide primer on the following items after scrapping and cleaning of the surface wherever necessary. Primer and Paints with ISI mark is to be supplied by the Contractor. The work shall be done as per instructions of Railway Engineer at site and extant practice on W.C. Railway. Note: Second coat shall be made after completely drying up of first coat of paint, to give good smooth & lasting finish. Track lead junction box"	Numbers	300.00	140.72	42216.00
50	050	Lettering, numbering of point machine, track lead junction boxes, block joint, glued joints, , batteries, apparatus cases etc. (outside) (each item to be taken as one unit)	Numbers	75.00	74.77	5607.75
51	051	"Lettering & numbering of termination particulars, equipments names etc. legibly and neatly inside Location Boxes as per standard practice of W.C. Railway & instructions of Railway Engineer at Site. Single case"	Numbers	150.00	336.70	50505.00
52	052	"Lettering & numbering of termination particulars, equipments names etc. legibly and neatly inside Location Boxes as per standard practice of W.C. Railway & instructions of Railway Engineer at Site. Half Case"	Numbers	75.00	190.60	14295.00
53	053	Cement concrete 1:3:6 in foundations with upto 25mm graded stone aggregate as per instructions of Railway Engineer at Site of size 0.15*0.3 Meter	cum	472.50	2900.59	1370528.78
54	054	Hiring of Hydra or similar tyre mounted Pick-n Carry crane of 12T capacity for misc. works of handling of material for minor miscellaneous works for short duration including operator / driver, fuel, lubricants and consumable. The contractor shall arrange all statutory permits as required by rules and regulations prevailing in the area of work. Payment shall be made for actual working hours at site.	Hour	60.00	899.71	53982.60
55	055	Replication and Supply of safety related documents in A-4 Size.The item unit will be per page	Per Page	3000.00	1.25	3750.00
56	056	Replication and Supply of safety related documents in A-3 Size.The item unit will be Per page	Per Page	18000.00	2.30	41400.00
57	057	Fixing of EC socket assembly complete with termination of 6-Quad , PIJF derivation cable on the strip of 6pin EC socket box on a good quality laminated board/existing pole at SM building, wherever necessary as per instruction of site incharge at site. The work include metallic of the socket assembly using black enamel paint. Checked by site Engineer.	Numbers	26.00	1077.29	28009.54
58	058	Splicing of Optical Fiber Core and routing in joint closure/FDMS as per instruction of site Engineer.	Numbers	960.00	105.86	101625.60
					Total	8012203.16

4. ELIGIBILITY CONDITIONS

Special Financial Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
-------	-------------	-----------------------	-----------------	---------------------

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-49R

Closing Date/Time: 09/06/2026 15:00

1	Financial Eligibility Criteria: The tenderer must have minimum average annual contractual turnover of V/N or 'V' whichever is less; where: V= Advertised value of the tender in Crores of Rupees. N= Number of years prescribed for completion of work for which bids have been invited. The average annual contractual turnover shall be calculated as an average of "total contractual payments" in the previous three financial years, as per the audited balance sheet. However, in case balance sheet of the previous year is yet to be prepared/ audited, the audited balance sheet of the fourth previous year shall be considered for calculating average annual contractual turnover.	No	No	Allowed (Mandatory)
1.1	The Tenderers shall submit requisite information as per Annexure-VIB, along with copies of Audited Balance Sheets duly certified by the Chartered Accountant/ Certificate from Chartered Accountant duly supported by Audited Balance Sheet.	No	No	Allowed (Mandatory)

Special Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer must have successfully completed or substantially completed any one of the following categories of work(s) during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: 1Three similar works each costing not less than the amount equal to 30% of advertised value of the tender OR 2Two similar works each costing not less than the amount equal to 40% of advertised value of the tender OR 3One similar work costing not less than the amount equal to 60% of advertised value of the tender	No	No	Allowed (Mandatory)
1.1	UPLOADING OF THE CERTIFICATE:-The tenderers shall submit a copy of certificate stating that all their statements/documents submitted along with bid are true and factual. Standard format of certificate to be submitted by the bidder is enclosed as Annexure-V. In addition to Annexure-V, in case of other than Company/Proprietary firm. Annexure-V(A) shall also be submitted by the each member of a Partnership Firm/ Joint Venture (JV) / Hindu Undivided Family (HUF / Limited Liability Partnership (LLP)etc., as the case may be. Non submission of above certificate(s) by the bidder shall result in summarily rejection of his/their bid. It shall be mandatorily incumbent upon the tenderer to identify, state and submit the supporting documents duly self-attested/digitally signed by which they/he is qualifying the Qualifying Criteria mentioned in the Tender Document.	No	No	Allowed (Mandatory)
1.1.1	DEFINATION OF SIMILIAR NATURE OF WORK:-Any Signaling Work of EI/PI/RR/IBH/ABH/LC Gate Interlocking Track circuit works /Axle counter works etc.	No	No	Allowed (Optional)

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.
3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.
5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.
6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.
7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.
8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-49R

Closing Date/Time: 09/06/2026 15:00

9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.
10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description
1	Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. (Click here to download the Format of Self Certification)

5. COMPLIANCE

Commercial-Compliance

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)

General Instructions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	All payment and other conditions are attached with tender document.	No	No	Not Allowed
1.1	Although year of specification is given in the schedule, last amendment, if any, shall apply.	No	No	Not Allowed
1.2	All tenderer must have valid GSTN number and rates must be inclusive of GST Act and its amendment.	No	No	Not Allowed
1.3	Compliance of GST act/rules & correction/modification issue by railway board with regard to GST act shall be binding on contractor & railway.	No	No	Not Allowed

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-49R

Closing Date/Time: 09/06/2026 15:00

1.4	Genral instruction :- 1 The offer will be evaluated based on certificates enclosed with the original offer only. The Railways will not enter into any correspondence to get these certificates subsequently and the offer shall be evaluated based on the documents submitted along with the offer. 2 Tenderer may please note that meeting of eligibility criteria is strictly based on completion certificates issued by the executive in charge of work and not linked with mere list of works claimed to have been executed by the tenderer or a copy of work order from Railways. 3 Tenderer may please note that fulfilling of eligibility clause shall be ascertained only from the completion certificates issued by the executive-in-charge of work and mere list of works claimed to have been executed by the tenderer or a copy of work order from Railways shall not be enough. It may also be noted that cognizance of those works, which are nearing completion or have been almost completed, shall not be taken only those completion certificates, wherein successful commissioning satisfactory performance of work have been clearly unambiguously acknowledged by Executive-in-charge of any Railway Unit or any Govt. Dept./Undertaking for any similar work shall be considered for this purpose. 4 Any variation to quantities in any item and its associated wiring material account of supply and installation will have to be born by the tenderer. Railway Engineer's decision in this regard shall be final. 5 All drawings related with the work can be obtained from the office of DRM Kota on any working day during office hours.	No	No	Not Allowed
-----	---	----	----	-------------

Custom

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenders whether being submitted on behalf of Sole Proprietorship Firm /HUF / Partnership Firm / Joint Venture (JV) / Companies Registered Under Companies Act, 2013/LLP (Limited Liability Partnership) / Registered Society or Registered Trust are required to UPLOAD an UNDERTAKING that - They are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of opening of bids, either in individual capacity or as a member of the partnership firm or JV in which the tenderer was / is a partner/member. Concealment / wrong information in regard to above shall make the contract liable for determination under Clause 62 of the General Conditions of Contract.	No	No	Allowed (Mandatory)

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-49R

Closing Date/Time: 09/06/2026 15:00

1.1	The tenderers shall UPLOAD VALID DOCUMENTS pertaining to prove the constitution of their firm - 1.In case tenderer is Sole proprietorship firm The tenderer shall submit Valid documents or Notarized Affidavit (As per prevailing law) (Annexure E) of Tender document. 2. In case of HUF: A copy of notarized affidavit on Stamp Paper declaring that he who is submitting the tender on behalf of HUF is in the position of 'Karta' of Hindu Undivided Family(HUF) and he has the authority, power and consent given by other members to act on behalf of HUF. 3.In case of Partnership Firm: The tenderer shall submit :(i) A copy of Partnership Deed and (ii) a copy of Power of Attorney)(Annexure D) of Tender document (duly registered /Notarized as perprevailing law) in favour of an individual to sign the tender documents and create liability against the Firm. 4.Joint Venture (JV): The tenderer shall submit documents as mentioned in Clause 17 of the Tender document (Second Sheet). 5.Company registered under Companies Act-2013: The tenderer shall submit (i) the copies of MOA (Memorandum of Association) / AOA (Articles of Association) of the company; and (ii) A copy of Authorization/Power of Attorney issued by the Company (backed by the resolution of Board of Directors) in favour of the individual to sign the tender on behalf of the company and create liability against the company. 6.LLP (Limited Liability Partnership) Firm: If the tender is submitted on behalf of a LLP Firm registered under LLP Act-2008,the tenderer shall submit alongwith the tender- (i) a copy of LLP Agreement,(ii) a copy of Certificate of Incorporation; and (iii) a copy of Power of Attorney/Authorisation issued by the LLP Firm in favour of the individual to sign the tender on behalf of the LLP Firm and create liability against the Firm.7.Registered Society & Registered Trust: The tenderer shall submit (i) a copy of the Certificate of Registration, (ii) Deed of Formation; and (iii) a copy of Power of Attorney in favour of the individual to sign the tender documents and create liability against the Society/Trust. If the above required documents are not uploaded along with the tender, to prove the STATUS of firm that thetender was submitted on behalf of a Sole Proprietorship firm /HUF/ Partnership firm / Joint Venture / Company registered under Companies Act-2013/ LLP(Limited Liability Partnership) Firm: / Registered Society & Registered Trust: etc., then the tender shall be treated as having been submitted by the individual who has signed the tender and the offer will be dealt accordingly.	No	No	Allowed (Mandatory)
-----	--	----	----	------------------------

6. Documents attached with tender

S.No.	Document Name	Document Description
1	TD202549R_compressed1.pdf	TD 2049 R

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

Signed By: VARSHA . SHARMA

Designation : DSTE SIG N WORKs