

**DYCSTE-C-BRC-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-BRC-155-2025-26Tele

Closing Date/Time: 16/06/2026 15:00

DY CSTE C BRC acting for and on behalf of The President of India invites E-Tenders against Tender No **SnT-C-BRC-155-2025-26Tele** Closing Date/Time 16/06/2026 15:00 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

1. NIT HEADER

Name of Work	Supply , installation ,testing and commissioning ,of telecom equipment- including , Trenching, Laying , blowing, splicing, jointing, termination, testing of OFC & Quad cable-in connection of various work of Dy.CSTE /const/ Vadodara jurisdiction - Chhayapuri-Bajwa multitracking ,Sevaliya -WKB interlocking, MYG-LKD Flyover GC project , Karchiya Augmentation maintenance infrastructure, CPM building, and Pratapnager work shop expansion phase-II work- Vadodara Division of Western Railway		
Bidding type	Normal Tender		
Tender Type	Open	Bidding System	Single Packet System
Tender Closing Date Time	16/06/2026 15:00	Date Time Of Uploading Tender	21/05/2026 18:32
Pre-Bid Conference Required	No	Pre-Bid Conference Date Time	Not Applicable
Advertised Value	46086352.64	Tendering Section	BARODA DIV
Bidding Style	Single Rate for Tender	Bidding Unit	Above/Below/Par
Earnest Money (Rs.)	921700.00	Validity of Offer (Days)	60
Tender Doc. Cost (Rs.)	0.00	Period of Completion	12 Months
Contract Type	Works - General	Contract Category	Expenditure
Bidding Start Date	02/06/2026		
Are JV allowed to bid	No	Number of JV Member Allowed	0
Are Consortium allowed to bid	No	Number of Consortium Member Allowed	0
Ranking Order For Bids	Lowest to Highest	Expenditure Type	Capital (Works)

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A1-Supply portion							4662862.83	
1	A1	12.00	Numbers	44152.40	529828.80	AT Par	529828.80	
	Description:- Supply of 2MP day/night vision Full HD P/T/Z (Pan/Tilt/Zoom) IP Colour Camera along with all accessories required including bracket/ fixture/ angle for fixing camera with ceiling mounting kit and built in features of audio recording and as per RDSO Specification No. RDSO/SPN/TC/65/2021 Version 6.0 or latest.							
2	A1	76.00	Numbers	13698.31	1041071.56	AT Par	1041071.56	
	Description:- "Supply of 2MP day/night vision Full HD Bullet/Dome type IP Colour Camera along with all accessories required including bracket/ fixture /angle for fixing camera with ceiling mounting kit and built in features of audio recording and as per RDSO Specification No. RDSO/SPN/TC/65/2021 Version 6.0 or latest."							
3	A1	1.00	Numbers	227026.47	227026.47	AT Par	227026.47	
	Description:- Supply, Installation, Testing & Commissioning of 64-Channel Network Video Recorder and 64TB storage after RAID 5/6 configuration with HDD (8 Nos of HDD capacity 8TB each), 2 nos Ethernet port complete with all other accessories as per RDSO Spec No. RDSO/SPN/TC/65/2021 Rev 6.0 or latest.							
4	A1	2.00	Numbers	183792.92	367585.84	AT Par	367585.84	
	Description:- Supply, Installation, Testing & Commissioning of 32-Channel Network Video Recorder with 40TB storage as per Clause No. 10.2 of RDSO Spec No. RDSO/SPN/TC/65/2021 Rev 6.0 or latest.							
5	A1	4.00	Numbers	18744.79	74979.16	AT Par	74979.16	
	Description:- Supply of 8TB Surveillance Hard Disk & its standard installation as per specification.							
6	A1	88.00	Numbers	1247.50	109780.00	AT Par	109780.00	
	Description:- Supply of Class10 Micro SDXC Memory Card 128GB storage AS PER SPECIFICATION.							
	A1	8.00	Numbers	7986.13	63889.04	AT Par	63889.04	

**DYCSTE-C-BRC-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-BRC-155-2025-26Tele

Closing Date/Time: 16/06/2026 15:00

7	Description:- Supply and Fixing on wall with the help of false nut of 12U Networking Rack 19 inch with Front Glass Door, 06 Socket Power DB, 02 Fan-Fan Tray, Cable Manager, Hardware Packet, Earthing etc. Make: APW-President or similar of reputed make.						
8	A1	8.00	Numbers	3682.19	29457.52	AT Par	29457.52
	Description:- Supply, installation, testing and commissioning of CAT6 24 Port fully populated Patch Panel 19" Rack Mounted as per Technical Specifications.						
9	A1	2.00	Numbers	70699.70	141399.40	AT Par	141399.40
	Description:- Supply and installation of On-line 3 KVA UPS with batteries backup for 60 Minutes, input power single phase 160V - 260V sine wave 50 HZ; output power single phase 230 Volt, +/-1% sine wave 50 Hz, Onsite OEM warranty 3 Years (Battery & UPS Both) or any higher specification. Make - Microtek, Luminous, Artis, V-guard or Similar.						
10	A1	3.00	Numbers	65005.73	195017.19	AT Par	195017.19
	Description:- Supply of Remote Craft Terminal as per specification.						
11	A1	2.00	Numbers	25704.72	51409.44	AT Par	51409.44
	Description:- Supply of Network Cable Tester Similar to Fluke Networks - MS2-100 - MICROSCANNER2 CABLE VERIFIER as per Technical Specification.						
12	A1	2.00	Numbers	14595.80	29191.60	AT Par	29191.60
	Description:- Supply of Optical Laser Torch as per specification.						
13	A1	3.00	Numbers	74999.68	224999.04	AT Par	224999.04
	Description:- Supply, Installation, Testing & Commissioning 65 inch UHD (3840 x 2160) LED TV with HDMI Cable of 5 meter and other accessories; Suitable for 24 x 7 working conditions and 03 Years on-site Warranty and as per Technical Specification. Make -LG/Sony/Samsung.						
14	A1	20.00	Numbers	178.22	3564.40	AT Par	3564.40
	Description:- Supply of HDMI Cable 3Meter compatible withHDMI video source devices.)						
15	A1	20.00	Numbers	964.71	19294.20	AT Par	19294.20
	Description:- Supply of 10 Mtr length HDMI cable (supporting2.0 and above).						
16	A1	2.00	Numbers	16000.00	32000.00	AT Par	32000.00
	Description:- Supply of 14 Feet Telescopic Ladder as per specification.						
17	A1	500.00	Metre	141.89	70945.00	AT Par	70945.00
	Description:- Cutting of wall/floor for insertion of 1" dia PVC conduit/pipes ,fixing hardware for fixing the conduit/pipes along with its supply and then replaster it with contractor's own cement mixture, sand, water and other required materials and restoration of wall/floor as original with tiles/marvel/Granite etc. This also includes painting with matching colour as per existing colour of the wall. Proper joints in pipes, bends/ elbows/ junction are to be provided as per site requirements.						
18	A1	4.00	Pair	11977.00	47908.00	AT Par	47908.00
	Description:- Supply of 5GHz Wireless Access Point. Make: TP-Link; Model: CPE710 or better.						
19	A1	1500.00	Metre	26.79	40185.00	AT Par	40185.00
	Description:- Supply of Armoured Optical Fiber Cable, 6 Core Single Mode as per specification. Molex/AMP/Plexonics/Systemax.						
20	A1	12.00	Numbers	1768.82	21225.84	AT Par	21225.84
	Description:- Supply of Wall Mount 6 core OFC Termination Box complete with base housing, base mounting with fixing arrangement, etc. & as per specification.						
21	A1	915.00	Metre	75.80	69357.00	AT Par	69357.00
	Description:- Supply of Anti-Rodent CAT6 Cables as per specification.						
22	A1	20.00	Set	253.70	5074.00	AT Par	5074.00
	Description:- Supply of Shielded RJ-45 CAT6/CAT6A Connectors - Pass through connectors Gold Plated 3 Prong 8P8C Modular Plugs (10 nos. per pack) for FTP/STP Stranded Ethernet Cable and Solid Wire 23AWG of D-Link/ Digisol/ Spectra/ DAX or any high standard material.						
23	A1	4.00	Numbers	36449.09	145796.36	AT Par	145796.36
	Description:- Supply, testing and commissioning of 24 port, Gigabit Ethernet switch, Layer-2, along with cable and all accessories as per RDSO specification no. RDSO/SPN/TC/83/2020 Rev.-2.1 or latest.						
24	A1	6.00	Numbers	3579.78	21478.68	AT Par	21478.68
	Description:- Supply of 10G SFP+ Module as per specification and compatible with supplied switches. Make: TP-Link/Netgear						
25	A1	22.00	Numbers	1575.00	34650.00	AT Par	34650.00
	Description:- Supply of 1G SFP+ Module as per specification and compatible with supplied switches. Make: TP-Link/Netgear						
26	A1	600.00	Metre	102.66	61596.00	AT Par	61596.00
	Description:- Supply of 45mm X 25mm trunking as per specification.						

**DYCSTE-C-BRC-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-BRC-155-2025-26Tele

Closing Date/Time: 16/06/2026 15:00

27	A1	4.00	Set	10337.23	41348.92	AT Par	41348.92	
	Description:- Supply of Maintenance Free Earth Electrode of length 3m, including supply of 3 bags of Earth enhancement material for earthling (20KGs /bag) for each electrode & other accessories as per Drg. No. SDO / RDSO/ E&B/001 and RDSO Spec No. RDSO / SPN/197/2008 with latest Amd.							
28	A1	2000.00	Metre	33.23	66460.00	AT Par	66460.00	
	Description:- Supply of PVC insulated flexible 3 core x 2.5 sq.mm multi strand power cable as per specification no. IS: 694:1990 reaffirmed 1995 or latest.make-Polycab/finolex,/Anchor/Delton							
29	A1	2.00	Numbers	31598.41	63196.82	AT Par	63196.82	
	Description:- Supply of Optical Power Meter suitable for of testing 1550/1310 As per Spec. with Lithium Battery ,adopter and other accessories .Make /& model OLP-35 Power Meter JDSU or similar. before supply model make approved by Rly.							
30	A1	1000.00	Metre	13.29	13290.00	AT Par	13290.00	
	Description:- Supply & PVC rigid pipe 25mm dia conforming to ISI spec. No. ISI/9537.							
31	A1	1.00	Numbers	95309.93	95309.93	AT Par	95309.93	
	Description:- Supply of Local/Remote service Terminal (Portable) with software for managing both STM1/STM4/IPMPLS ADMs and primary Digital Drop Insert Muxes as per technical specification. in tender document.							
32	A1	4575.00	Metre	35.44	162138.00	AT Par	162138.00	
	Description:- Supply of STP (Shielded Twisted Pair) CAT-6 cable compliant with latest EIA/TIA-568-B. 2-1 standard of make D-Link/DAX/Lucent/Crone/Amp. or similar							
33	A1	1.00	Numbers	1933.45	1933.45	AT Par	1933.45	
	Description:- Supply of Krone tool with test jack.							
34	A1	236.00	Numbers	472.13	111422.68	AT Par	111422.68	
	Description:- LC/SC/Euro OFC patch cord 1.5 to 10 mtr log. As per requirement.							
35	A1	2.00	Numbers	1049.24	2098.48	AT Par	2098.48	
	Description:- Supply of crimping tool suitable for 0.5mm and 0.63 mm dia telecom cable. Make-krone or similar							
36	A1	8.00	Numbers	21568.98	172551.84	AT Par	172551.84	
	Description:- UPS 1 KVA online having one hours backup.Make -APC/Numeric/Microtek or similar							
37	A1	18.00	Numbers	14613.18	263037.24	AT Par	263037.24	
	Description:- Supply of 8 port gigabit managed POE layer 2 switch supports 8 nos 10/100/1000 base-T port along with 2 gigabit SFP ports and modules with green-saving technologies.Make-DG-GS1510 Digisol/cisco/juniper/D-link or similar.							
38	A1	1.00	Pair	8300.93	8300.93	AT Par	8300.93	
	Description:- Supply of Single Mode Single fiber Managed Media Converter (Ethernet & E1 to Optical vice versa) Pair and all the accessories required for their installation as per RDSO Spec NoRDSO/SPN/TC/103/2013 Rev.2 or latest.make like Andra, Cygnus, AE Connect, track route.							
39	A1	250.00	Metre	12.26	3065.00	AT Par	3065.00	
	Description:- Supply and fixing of PVC FLEXIBLE PIPE 1" Dia .(Inspection agency :-Consignee							
S.No. Item Code Item Qty Qty Unit Unit Rate Basic Value Escl.(%) Amount Bidding Unit								
Schedule () A2-Supply portion							1720340.89	
1	A2	2.00	Set	10337.23	20674.46	AT Par	20674.46	
	Description:- Supply of Maintenance Free Earth Electrode of length 3m, including supply of 3 bags of Earth enhancement material for earthling (20KGs /bag) for each electrode & other accessories as per Drg. No. SDO / RDSO/ E&B/001 and RDSO Spec No. RDSO / SPN/197/2008 with latest Amd.							
2	A2	60.00	Running Metre	1170.00	70200.00	AT Par	70200.00	
	Description:- Supply of G.I. Pipes 100 mm dia medium grade engraved on pipe as per spec. no. IS 1239 part I of 2004 with latest amnd. with sockets and fittings. (other dia. Pipes shall be supplied by Railway) (Surya, Jindal, Tata,Apollo or Asian make) -							
3	A2	50.00	Numbers	1260.19	63009.50	AT Par	63009.50	
	Description:- Double Walled Corrugated (DWC) HDPE Pipe with associated collars etc. as per RDSO Specification No. RDSO/SPN/204/2011 or latest anti-rodent & anti-oxidant and non flame propagating type in 6 meters straight length and of size 120 mm outer dia,& 103.5 mm inner dia. (The manufacturers, suppliers must produce valid IS license and should be certified under ISO 9000 and shall submit copy of certificate). One of the following coupling arrangements should also be supplied with each pipe as per the site requirement.							
	A2	4.00	Numbers	16886.51	67546.04	AT Par	67546.04	

**DYCSTE-C-BRC-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-BRC-155-2025-26Tele

Closing Date/Time: 16/06/2026 15:00

4	Description:- Supply of Fiber Distribution management System rack mountable LIU along with all accessories suitable for mono mode 48 fiber armoured cable size 1 U -2 U size for termination of 2x24 Fibers.supplied shuld be slider type .48 fiber complete loaded Euro adoptor,pigtail, etc,as per instruction of site engineer.3M/RAYCHEM/ or Make/model to be approved before supply by railway.							
5	A2	26.00	Kilometre	39269.16	1020998.16	AT Par	1020998.16	
	Description:- Supply of HDPE duct 40/33 mm as per RDSO Spec No RDSO/SPN/TC/45/2013 Rev 2 with latest amendments or TEC GR No. G/CDS 08/02 NOV-2004 OR with latest amendments as available. (suply as per railway). For each Km of HDPE duct following items are to be supplied a) End Plugs- 2no b) Cable sealing plugs -2 no. (c) Plastic couplers slip fit/push fit type - 2no d) End plugs to be provided along with drum -2 nos NOTE-Supply of duct in deferent color as per latest laying policy by HQ.and requirment.							
6	A2	1.00	Numbers	26928.87	26928.87	AT Par	26928.87	
	Description:- Supply of 19" covered racks, Vero President /Rittel or similar make having size of approximately 2.2 mtr.(42U) height X 600mm width x 800mm depth and duly approved by the engineer in charge of the work. The rack shall be suitable for all fittings for housing SDH equipment, primary Muxes, DDF, MDF using krone module and other equipment like runway ladders etc. completely wired and equipped with integrated protection modules for all channels as per technical specifications and other stipulations of tender document. It should be possible to lock all the equipment with only order wire telephone remaining outside the rack. as per railway requirement errection of rach including transportation should be done by contractor. with ladder up to 10 mtr.as specification .Before supply approved by railway.							
7	A2	100.00	Metre	33.23	3323.00	AT Par	3323.00	
	Description:- Supply of PVC insulated flexible 3 core x 2.5 sq.mm multi strand power cable as per specification no. IS: 694:1990 reaffirmed 1995 or latest.make-Polycab/finolex,/Anchor/Delton							
8	A2	2.00	Numbers	120078.42	240156.84	AT Par	240156.84	
	Description:- "PCM TDM Integrated access device 1U heigt /19"" rack mountable; Optical module integrated in the unit supporting dual core OFC and 2E1 one 100Mbps Ethernet Port; optical distance support to be 20 KM; unit consist one E&M module supporting eight 2W/4W (each port configurable); another one slot populated with FSX or FXO for hot line connection .Model : Make : MAPLE-4CS or similar."							
9	A2	2.00	Numbers	20236.32	40472.64	AT Par	40472.64	
	Description:- Optical Module Card having SFP port for connectivity with suitable SFP module or EKT or optical to 4xE1 cinvertor suitable for 4E1.as per requirment of multiplxer MAPPLE -4 C or similar equipmet .which supply item above.							
10	A2	1.00	Numbers	31598.41	31598.41	AT Par	31598.41	
	Description:- Supply of Optical Power Meter suitable for of testing 1550/1310 As per Spec. with Lithium Battery ,adopter and other accessories .Make /& model OLP-35 Power Meter JDSU or similar. before supply model make approved by Rly.							
11	A2	4.00	Numbers	574.05	2296.20	AT Par	2296.20	
	Description:- Supply of push button telephone having DTMF signalling							
12	A2	1.00	Set	53237.27	53237.27	AT Par	53237.27	
	Description:- Supply of 48V , 50 amps battery charger for telecom use as per No RDSO/ SPCN/ TC/ 23/ 99 (ver. 4) or latest in N+1 configuration i.e. using 3 modules of 25 amps with automatic switching between the modules for two sets of 200 AH battery for charging with SMF VRLA. it shall be equipped with surge and lightening protection of class 'B' and 'C' the configuration shall be decided as per site requirement.							
13	A2	1.00	Set	47654.64	47654.64	AT Par	47654.64	
	Description:- supply of full charged VRLA 200 AH Batteries.as per IRS.93/96 amd.1 or latest.							
14	A2	1.00	Numbers	1933.45	1933.45	AT Par	1933.45	
	Description:- Supply of Krone tool with test jack.							
15	A2	20.00	Numbers	472.13	9442.60	AT Par	9442.60	
	Description:- LC/SC/Euro OFC patch cord 1.5 to 10 mtr log. As per requirement.							
16	A2	305.00	Metre	13.99	4266.95	AT Par	4266.95	
	Description:- Supply of UTP CAT-6 CABLE MAKE:- D LINK,Avaya, CP plus, Finolex,Havells, L&T.							
17	A2	2.00	Pair	8300.93	16601.86	AT Par	16601.86	
	Description:- Supply of Single Mode Single fiber Managed Media Converter (Ethernet & E1 to Optical vice versa) Pair and all the accessories required for their installation as per RDSO Spec NoRDSO/SPN/TC/103/2013 Rev.2 or latest.make like Andra, Cygnus, AE Connect, track route.							
	S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount
	Schedule	() A3-Supply portion						Bidding Unit
	A3	4.00	Set	10337.23	41348.92	AT Par	41348.92	3407969.70

**DYCSTE-C-BRC-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-BRC-155-2025-26Tele

Closing Date/Time: 16/06/2026 15:00

1	Description:- Supply of Maintenance Free Earth Electrode of length 3m, including supply of 3 bags of Earth enhancement material for earthling (20KGs /bag) for each electrode & other accessories as per Drg. No. SDO / RDSO/ E&B/001 and RDSO Spec No. RDSO / SPN/197/2008 with latest Amd.						
2	A3	120.00	Running Metre	1170.00	140400.00	AT Par	140400.00
	Description:- Supply of G.I. Pipes 100 mm dia medium grade engraved on pipe as per spec. no. IS 1239 part I of 2004 with latest amnd. with sockets and fittings. (other dia. Pipes shall be supplied by Railway) (Surya, Jindal, Tata,Apollo or Asian make) -						
3	A3	20.00	Numbers	1260.19	25203.80	AT Par	25203.80
	Description:- Double Walled Corrugated (DWC) HDPE Pipe with associated collars etc. as per RDSO Specification No. RDSO/SPN/204/2011 or latest anti-rodent & anti-oxidant and non flame propagating type in 6 meters straight length and of size 120 mm outer dia, & 103.5 mm inner dia. (The manufacturers, suppliers must produce valid IS license and should be certified under ISO 9000 and shall submit copy of certificate). One of the following coupling arrangements should also be supplied with each pipe as per the site requirement.						
4	A3	10.00	Numbers	2318.48	23184.80	AT Par	23184.80
	Description:- Supply of Thermo shrinkable joint kit as per RDSO spec no. IRS TC 77/2010 Rev-2 or latest suitable for 2T joint RTSF3 suitable to 6-quad cable of spec no. IRS TC-30/2005, Ver-1, Amd-4 with latest AMD..						
5	A3	18.00	Running Metre	394.65	7103.70	AT Par	7103.70
	Description:- Supply of G.I. Pipes 80 mm dia medium grade engraved on pipe as per spec. no. IS 1239 of 204 with latest amnd.with sockets and fittings. (other dia. Pipes shall be supplied by Railway) (Surya, Jindal, Tata, Apollo or Asian make).						
6	A3	2.00	Numbers	16886.51	33773.02	AT Par	33773.02
	Description:- Supply of Fiber Distribution management System rack mountable LIU along with all accessories suitable for mono mode 48 fiber armoured cable size 1 U -2 U size for termination of 2x24 Fibers.suitable should be slider type .48 fiber complete loaded Euro adaptor,pigtail, etc,as per instruction of site engineer.3M/RAYCHEM/ or Make/model to be approved before supply by railway.						
7	A3	5.00	Kilometre	39269.16	196345.80	AT Par	196345.80
	Description:- Supply of HDPE duct 40/33 mm as per RDSO Spec No RDSO/SPN/TC/45/2013 Rev 2 with latest amendments or TEC GR No. G/CDS 08/02 NOV-2004 OR with latest amendments as available. (supply as per railway). For each Km of HDPE duct following items are to be supplied a) End Plugs- 2no b) Cable sealing plugs -2 no. (c) Plastic couplers slip fit/push fit type - 2no d) End plugs to be provided along with drum -2 nos NOTE-Supply of duct in deferent color as per latest laying policy by HQ.and requirment.						
8	A3	12.00	Numbers	13342.67	160112.04	AT Par	160112.04
	Description:- Supply and installation of straight joint enclosures (SJC) complete with all accessories with latest amendments or Raychems RPG make FOSC-400-B4-A-BJL-4-H -48 or similar make only. (For 48 fiber OFC) and splicing of 2X48 F laid OFC. Insp. By Consignee.						
9	A3	0.60	Kilometre	29484.32	17690.59	AT Par	17690.59
	Description:- Supply of PVC switch board cable, 10 pair twisted, conductor of size 0.63mm dia annealed copper conforming to TEC spe. No. GR-WIR-06/03 Mar'02 or latest.make-Delton/Birla similar.						
10	A3	500.00	Metre	33.23	16615.00	AT Par	16615.00
	Description:- Supply of PVC insulated flexible 3 core x 2.5 sq.mm multi strand power cable as per specification no. IS: 694:1990 reaffirmed 1995 or latest.make-Polycab/finolex,/Anchor/Delton						
11	A3	2.00	Numbers	20797.40	41594.80	AT Par	41594.80
	Description:- Supply of Digital transmission measurement setas per SPN - IRS TC: 43/87.with latest Amnd. APLAB make - Model 2031 / 2031A/or similar.						
12	A3	2.00	Numbers	120078.42	240156.84	AT Par	240156.84
	Description:- "PCM TDM Integrated access device 1U height /19"" rack mountable; Optical module integrated in the unit supporting dual core OFC and 2E1 one 100Mbps Ethernet Port; optical distance support to be 20 KM; unit consist one E&M module supporting eight 2W/4W (each port configurable); another one slot populated with FSX or FXO for hot line connection .Model : Make : MAPLE-4CS or similar."						
13	A3	1.00	Numbers	6152.98	6152.98	AT Par	6152.98
	Description:- Supply of Digital insulation Tester 100V/250V/500V range Model: Rish insu 20 Make: RISHABH or MECO or similar.						
14	A3	1.00	Numbers	13356.64	13356.64	AT Par	13356.64
	Description:- Supply of digital Earth Resistance tester three terminal type with LED display ,199 count KOICO Model 5600 or any reputed make approved by engineer in-charge.						
	A3	2.00	Numbers	44774.52	89549.04	AT Par	89549.04

**DYCSTE-C-BRC-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-BRC-155-2025-26Tele

Closing Date/Time: 16/06/2026 15:00

15	Description:- Digital Multimeter of Fluke 287 Industrial,true RMS with temperature ,Analog bar graph,Digital display ,Backlight 1000V AC/DC measure up to 10A,20 A for up to 30 seconds or superior.							
16	A3	2.00	Numbers	31598.41	63196.82	AT Par	63196.82	
	Description:- Supply of Optical Power Meter suitable for of testing 1550/1310 As per Spec. with Lithium Battery ,adppter and other accessories .Make /& model OLP-35 Power Meter JDSU or similar. before supply model make approved by Rly.							
17	A3	1.00	Numbers	310355.27	310355.27	AT Par	310355.27	
	Description:- Supply Fusion splicing Machine with all accessories. Make fujikura model no.88S or similar as per tech.specification TEC.GR/TX/OSM-001/04 Sep-2012 with latest amendment. : before supply model / make approved by Rly. Inspection Authority RITES.(OEM/Aauthorised dealer certificate required along with equipment) Not -Model should be listed in TEC list..							
18	A3	1.00	Numbers	271501.92	271501.92	AT Par	271501.92	
	Description:- Supply Optical time domain Reflecto meter make YOKOGAVA model AQ0121A or similar as per tech.specification No. G/OTD-02/02 Jan-2005 with latest amendment all accessories.as per spec. before supply model approved by Rly Engineer .Inspection Authority -RITES.(OEM /Authorised dealer certificate required along with equipment).Not -Model should be listed in TEC list..							
19	A3	300.00	Metre	13.29	3987.00	AT Par	3987.00	
	Description:- Supply & PVC rigid pipe 25mm dia conforming to ISI spec. No. ISI/9537.							
20	A3	2.00	Numbers	562475.91	1124951.82	AT Par	1124951.82	
	Description:- "Supply of Standard 19"" Rack Mountable LER (Label Edge Router) with all necessary accessories & Software, Perpetual Licenses as per RDSO Document No.STT/TAN/IP-MPLS/2020 Version 2.0 as per specification. of Tender document. {supply of E1 cards is not included in this item and is catered in separate item}. "							
21	A3	2.00	Numbers	22480.08	44960.16	AT Par	44960.16	
	Description:- Supply of 8 port x 1GbE (4 nos.of optical ports and 4 nos. of electrical ports) module card suitable for the IP-MPLS routerin S.No.1 and should support all the software features, environmental standards and security features as mentioned in RDSO technical document no STT/TAN/IP-MPLS/2020 Ver2.0 or latest							
22	A3	2.00	Numbers	18728.07	37456.14	AT Par	37456.14	
	Description:- " Supply of 4 port x10G SFP module card (2 x 10G two modules) suitable for the IPMPLS router in S.No.1. and should support all the software features, environmental standards and security features as mentioned in RDSO technical document no STT/TAN/IP MPLS/2020 Ver2.0 or latest. "							
23	A3	4.00	Numbers	2504.82	10019.28	AT Par	10019.28	
	Description:- Supply of DDF (120 Ohms) for terminating 16 E1s of wrapping type and mountable on 19" rack. (Maximum width 2U size). (Inspection by Consignee).							
24	A3	2.00	Numbers	80501.41	161002.82	AT Par	161002.82	
	Description:- " Supply of Gateway for Emergency communication at HQ as per RDSO specification No. RDSO/SPN/TC/99/2023 Ver 3 or latest ."							
25	A3	1.00	Numbers	95309.93	95309.93	AT Par	95309.93	
	Description:- Supply of Local/Remote service Terminal (Portable) with software for managing both STM1/STM4/IPMPLS ADMs and primary Digital Drop Insert Muxes as per technical specification. in tender document.							
26	A3	2.00	Set	53237.27	106474.54	AT Par	106474.54	
	Description:- Supply of 48V , 50 amps battery charger for telecom use as per No RDSO/ SPCN/ TC/ 23/ 99 (ver. 4) or latest in N+1 configuration i.e. using 3 modules of 25 amps with automatic switching between the modules for two sets of 200 AH battery for charging with SMF VRLA. it shall be equipped with surge and lightening protection of class 'B' and 'C' the configuration shall be decided as per site requirement.							
27	A3	2.00	Set	47654.64	95309.28	AT Par	95309.28	
	Description:- supply of full charged VRLA 200 AH Batteries.as per IRS.93/96 amd.1 or latest.							
28	A3	2.00	Numbers	3130.53	6261.06	AT Par	6261.06	
	Description:- Supply of DC Power distribution panel to cater DC power requirements of IPMPLS/STM Multiplexers/PD Mux's / EOW / FANS to be fixed in 19" rack vide item 4 above. (Minimum 8 No's of DC distribution arrangement with MCB's of suitable rating) for -ve . Connecting copper strip for +ve.							
29	A3	1.00	Numbers	1933.45	1933.45	AT Par	1933.45	
	Description:- Supply of Krone tool with test jack.							
30	A3	48.00	Numbers	472.13	22662.24	AT Par	22662.24	
	Description:- LC/SC/Euro OFC patch cord 1.5 to 10 mtr log. As per requirement.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit

**DYCSTE-C-BRC-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-BRC-155-2025-26Tele

Closing Date/Time: 16/06/2026 15:00

Schedule () A4-Supply portion							3450511.10	
1	A4	8.00	Numbers	16886.51	135092.08	AT Par	135092.08	
	Description:- Supply of Fiber Distribution management System rack mountable LIU along with all accessories suitable for mono mode 48 fiber armoured cable size 1 U -2 U size for termination of 2x24 Fibers.supplied should be slider type .48 fiber complete loaded Euro adaptor,pigtaial, etc,as per instruction of site engineer.3M/RAYCHEM/ or Make/model to be approved before supply by railway.							
2	A4	4.00	Kilometre	39269.16	157076.64	AT Par	157076.64	
	Description:- Supply of HDPE duct 40/33 mm as per RDSO Spec No RDSO/SPN/TC/45/2013 Rev 2 with latest amendments or TEC GR No. G/CDS 08/02 NOV-2004 OR with latest amendments as available. (supply as per railway). For each Km of HDPE duct following items are to be supplied a) End Plugs- 2no b) Cable sealing plugs -2 no. (c) Plastic couplers slip fit/push fit type - 2no d) End plugs to be provided along with drum -2 nos NOTE-Supply of duct in deferent color as per latest laying policy by HQ.and requirment.							
3	A4	6.00	Numbers	22480.08	134880.48	AT Par	134880.48	
	Description:- Supply of 8 port x 1GbE (4 nos.of optical ports and 4 nos. of electrical ports) module card suitable for the IP-MPLS routerin S.No.1 and should support all the software features, environmental standards and security features as mentioned in RDSO technical document no STT/TAN/IP-MPLS/2020 Ver2.0 or latest							
4	A4	30.00	Numbers	472.13	14163.90	AT Par	14163.90	
	Description:- LC/SC/Euro OFC patch cord 1.5 to 10 mtr log. As per requirement.							
5	A4	2.00	Numbers	1049.24	2098.48	AT Par	2098.48	
	Description:- Supply of crimping tool suitable for 0.5mm and 0.63 mm dia telecom cable. Make-krone or similar							
6	A4	10.00	Numbers	21568.98	215689.80	AT Par	215689.80	
	Description:- UPS 1 KVA online having one hours backup.Make -APC/Numeric/Microtek or similar							
7	A4	1525.00	Metre	13.99	21334.75	AT Par	21334.75	
	Description:- Supply of UTP CAT-6 CABLE MAKE:- D LINK,Avaya, CP plus, Finolex,Havells, L&T.							
8	A4	1500.00	Metre	74.26	111390.00	AT Par	111390.00	
	Description:- Supply of PVC casing & capping of size 25mm x 25/32mm x 1mm thickness of Precision or Garwareor Presto or similar make.							
9	A4	36.00	Numbers	144.80	5212.80	AT Par	5212.80	
	Description:- Supply of factory crimped CAT 6 UTP Patch Cord 3 Mtrs. as per specification no. of Tender document.							
10	A4	36.00	Numbers	74.19	2670.84	AT Par	2670.84	
	Description:- Supply of factory crimped CAT 6 UTP Patch Cord 1 Mtrs. as per specification no. of Tender document.							
11	A4	2.00	Numbers	5924.86	11849.72	AT Par	11849.72	
	Description:- Supply & Installtion of CAT 6 Patch Panel 24 port loaded.							
12	A4	6.00	Numbers	53682.00	322092.00	AT Par	322092.00	
	Description:- Supply of manageable layer 2 Powering Data 24 Port with 4 SFP Trance receiver Module as per RDSO Specification No. RDSO/SPN/TC/83/2014, rev1.0 Amd 1.0 or latest (Power 370 watt as per RDSO specification) with Installation and commissioning with existing Railnet network at BRC.							
13	A4	1.00	Numbers	17412.50	17412.50	AT Par	17412.50	
	Description:- Supply, installation, testing & commissioning of Integrated Wireless LAN Controller & Firewall Functionality Compatible with above switching and Routing components. as per detailed specification.(with 3 Years Subscription)							
14	A4	36.00	Numbers	28782.46	1036168.56	AT Par	1036168.56	
	Description:- Supply, installation, testing and commissioning of indoor WiFi Access Point (802.11 ac Wave 2 Wi-Fi access point) 2.4 & 5 GHz (Dual Band) as per technical specification.							
15	A4	6.00	Numbers	42423.50	254541.00	AT Par	254541.00	
	Description:- Supply & Installation of OUT DOOR Pole Mount Access Point, Wireless LAN 802.11 b/g/n/AC compliant, 450/1300 Mbps (3T3R), Advanced MIMO technology, Support power adapter & PoE, high power Antenna Gain, as per technical specification.. This include Installtion on Wall, Pole etc. along with its antenna (supplied below) complete as per instruction of Engineer In Charge.							
16	A4	9.00	Numbers	22595.13	203356.17	AT Par	203356.17	
	Description:- 2.4 Ghz Sector / Omni directional Antenna as per technical specification.							
17	A4	9.00	Numbers	17983.88	161854.92	AT Par	161854.92	
	Description:- 5 Ghz Omni directional Antenna (dual Band) as per technical specifcation							
18	A4	6.00	Numbers	8500.00	51000.00	AT Par	51000.00	

**DYCSTE-C-BRC-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-BRC-155-2025-26Tele

Closing Date/Time: 16/06/2026 15:00

18	Description:- Supply & Installtion of Wall Mount Type FDMS, Weather Proof(outdoor), suitable for termination of 6/12/24 Fibers with all required accessories & making Splice joint with contractor's own plicing machine and tools and consumables, as per instruction of Engineer in Charge							
19	A4	6.00	Numbers	70504.41	423026.46	AT Par	423026.46	
	Description:- Supply of Maintenance Terminal with PC & Printer for printing reports as per Technical Specifications.							
20	A4	1.00	Numbers	86000.00	86000.00	AT Par	86000.00	
	Description:- Cloud based Network Management Software to centrally manage & maintain Enter Campus Wi-Fi network, allocation of resources, bandwith etc.							
21	A4	6.00	Numbers	12500.00	75000.00	AT Par	75000.00	
	Description:- Supply & Installtion of Galvenized Pole for of suitable hight for Mounting of Outdoor Access Point, this include its irrection in suitable location using contractors own material, as per instruction of Engineer In Charge							
22	A4	100.00	Numbers	86.00	8600.00	AT Par	8600.00	
	Description:- Supply of 32 mm Steel Wire Reinforced (SWR) PVC Flexible Duct Hoses Pipe, High Tensile, Gray Colour suitable for outdoor useage, with necessary fittings.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A5-Supply portion							6117419.63	
1	A5	2.00	Numbers	134454.59	268909.18	AT Par	268909.18	
	Description:- "Supply, Installation and commissioning of 8 PON port OLT with 4 port SFP +(10G), 4 port SFP (Giga Fibre) & 4 Port Giga TX/SFP Combo, ITU-TG.984/G .998, L2 switching functionality, 4096 VLAN, QoS, SNMP, IGMP as per technical specification."							
2	A5	60.00	Numbers	7519.30	451158.00	AT Par	451158.00	
	Description:- Supply, installation, testing and commissioning of ONT unit with 1 PON port & 4 RJ45 Giga Ethernet, 802. each, 1 x POTS (RJ 11) Ports, 300 Mbps Wi-Fi , VLAN, IGMP, VoIP, QoS, autodiscovery/ Link detection, Dual Band including FTTH termination Box and fiber patch cord as per technical specification.							
3	A5	20.00	Numbers	7195.71	143914.20	AT Par	143914.20	
	Description:- Supply, Installation and commissioning of 2.5 Gig PON Port SFP Module for OLT as per technical specification.							
4	A5	12.00	Numbers	7702.24	92426.88	AT Par	92426.88	
	Description:- Supply, installation, testing and commissioning of wall mount Outdoor 1:8 Optical splitter for PON with fusion Splicing termination as per technical specification/site requirement.							
5	A5	3500.00	Metre	10.31	36085.00	AT Par	36085.00	
	Description:- Supply of 2 core OFC cable suitable for single mode data communication (un-armoured/arial type). Make: Finolex, Beltel or equivalent.							
6	A5	1.00	Numbers	228496.90	228496.90	AT Par	228496.90	
	Description:- Supply and installation of NMS for the GPON system with licence along with supply of high end Desktop for installation of NMS as per Technical Specifications.							
7	A5	14.00	Numbers	65541.51	917581.14	AT Par	917581.14	
	Description:- Supply, installation, testing and commissioning of Professional Large Format LED Video Display Unit, 55" (inches)-4K ultra HD or larger, including wall/table mounting kit .Make LG/Sony/Samsung/Philips as per Spec.							
8	A5	2.00	Numbers	55728.50	111457.00	AT Par	111457.00	
	Description:- Supply & Installtion of Mixture Amplifier Complete with Wiring Material Make: Arpat Audio/Bosch/Bose/Biamp.As per spec.							
9	A5	4.00	Pair	24589.57	98358.28	AT Par	98358.28	
	Description:- Supply & Installtion of Speakers Complete with Wiring Material Make: Arpat Audio/Bosch/Bose/Biamp. As per spec.							
10	Please see Item Breakup for details.				966783.92	AT Par	966783.92	
	Description:- Supply, Installation, Testing & Commissioning of Conference System for meeting Room Make: Sennheiser/Bosch/QSC/Biamp as per spec.							
12	A5	1.00	Lot	74287.30	74287.30	AT Par	74287.30	
	Description:- Supply of Installation Accessories & Cables all type cables with suitable connectors as per requirment for complete conference system as above supply.							
13	A5	1.00	Job	39478.67	39478.67	AT Par	39478.67	
	Description:- Installation and commissioned of above Conference system							
	A5	1.00	Numbers	562000.00	562000.00	AT Par	562000.00	

**DYCSTE-C-BRC-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-BRC-155-2025-26Tele

Closing Date/Time: 16/06/2026 15:00

14				Description:- Short Throw (0.41 to 0.9) Multimedia Projector (MMP) With 1920 x 1080 (Full HD) Resolution, In built Computer, Dual Camera, Mic Speakers etc.(On Site OEM Warranty for Light Source Time or Life in Hours whichever is earlier)-3 year or 15000 hrs.As per Technical Specification.				
15	A5	1.00	Numbers	19386.22	19386.22	AT Par	19386.22	
				Description:- Supply & Installation of motorized screen with remote of 10' x8' size as per spec . Make Dalite/Draper/Liberty or similar.				
16	A5	1.00	Numbers	4672.41	4672.41	AT Par	4672.41	
				Description:- Supply of projector mounting kit . As per spec.				
17	A5	4.00	Numbers	75671.58	302686.32	AT Par	302686.32	
				Description:- Supply of 24 Port FXS Gateway 19" Rack Mountable along with Patch Panel/ krone module for termination (DC or AC based as per site requirement) and Dual input ports (Fiber/Ethernet) including mounting kit and all the accessories and as per specification.				
18	A5	20.00	Numbers	178.22	3564.40	AT Par	3564.40	
				Description:- Supply of HDMI Cable 3Meter compatible withHDMI video source devices.)				
19	A5	20.00	Numbers	964.71	19294.20	AT Par	19294.20	
				Description:- Supply of 10 Mtr length HDMI cable (supporting2.0 and above).				
20	A5	1.00	Numbers	60890.49	60890.49	AT Par	60890.49	
				Description:- Supply of Ethernet Tester of Stanlay/ Fluck make or equivalent.				
21	A5	10.00	Numbers	6320.61	63206.10	AT Par	63206.10	
				Description:- Supply of Cat 6 patch panel 24 port loaded.				
22	A5	4.00	Numbers	5929.32	23717.28	AT Par	23717.28	
				Description:- Supply of HDMI Splitter (1X4) 4K HD as per thefollowing minimum specification: Number ofInputs : 1 Type of Inputs : HDMI Input Resolution : 4K Number of Outputs : 4 Output Resolution : 4K Data Rate : 10.5 Gbps with on Site OEM Warranty of three year.				
23	A5	20.00	Numbers	15760.72	315214.40	AT Par	315214.40	
				Description:- Supply of HDMI to fiber converter and fiber toHDMI converter in pair should have 20km range with one Year warranty. Product should have following minimum Speciation: 1. Full HD 1080P HDMI Optical Converter/Extender 2. Supports up to 1920x1080@ 60Hz 3. Distance - 20KM over Single Mode fiber 4. Video Input Port - HDMI 5. Video Output Port - HDMI 6. HDCP Supported - Yes 7. HDMI Resolution -Up to 1920x1080@ 60Hz 8. Wavelength - 1310nm/1550nm 10.Power - Input: AC110V- 220V,50/60HZ, Output: DC5V/2A.				
24	A5	10.00	Numbers	6715.06	67150.60	AT Par	67150.60	
				Description:- Supply of HDMI to cat 6 cable extender				
25	A5	2000.00	Metre	14.14	28280.00	AT Par	28280.00	
				Description:- 3 Pair switch board cable 0.5 mm dia, annealed tinned, copper conductor PVC insulated, colour coated, Twisted Pair, PVC sheathed with Nylon rip TECSPECN-NO-GR/WIR-06/03-March 2002.				
26	A5	2.00	Numbers	93583.33	187166.66	AT Par	187166.66	
				Description:- "Digital Standee for Portrait Advertisement Size: 55" 4K UHD with Three years Warranty warranty (6 feet height and 3 feet width) Specification: - 55" 4K resolution display, with Offline Android Media Player MS sheet metal Floor Stand Enclosure Box with glass on front side & classic finish power coated paint. Display Make: LG/Samsung "				
27	A5	2.00	Numbers	14083.33	28166.66	AT Par	28166.66	
				Description:- "Online Content Management Software Time scheduling, Group creation, screen split-up, Different Logins, Cloud Based, add / edit / delete / modify the content, Remote Management 1 Yr. Subscription Per Display per your choice) you can do at any time anywhere by remotely per display per year charges."				
28	A5	1.00	Numbers	183796.80	183796.80	AT Par	183796.80	
				Description:- 12 X PTZ Function Video Conferencing Camera (High Precision Motorized-PTZ) Resolution (Maximum) Full HD (1920 x 1080 Pixel) as per technical spec. with all required accessories as per site requirment.				
29	A5	2.00	Set	10337.23	20674.46	AT Par	20674.46	
				Description:- Supply of Maintenance Free Earth Electrode of length 3m, including supply of 3 bags of Earth enhancement material for earthing (20KGs /bag) for each electrode & other accessories as per Drg. No. SDO / RDSO/ E&B/001 and RDSO Spec No. RDSO / SPN/197/2008 with latest Amd.				
30	A5	12.00	Running Metre	1170.00	14040.00	AT Par	14040.00	
				Description:- Supply of G.I. Pipes 100 mm dia medium grade engraved on pipe as per spec. no. IS 1239 part I of 2004 wirh latest amnd. with sockets and fittings. (other dia. Pipes shall be supplied by Railway) (Surya, Jindal, Tata,Apollo or Asian make) -				
	A5	10.00	Numbers	1260.19	12601.90	AT Par	12601.90	

**DYCSTE-C-BRC-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-BRC-155-2025-26Tele

Closing Date/Time: 16/06/2026 15:00

31	Description:- Double Walled Corrugated (DWC) HDPE Pipe with associated collars etc. as per RDSO Specification No. RDSO/SPN/204/2011 or latest anti-rodent & anti-oxidant and non flame propagating type in 6 meters straight length and of size 120 mm outer dia, & 103.5 mm inner dia. (The manufacturers, suppliers must produce valid IS license and should be certified under ISO 9000 and shall submit copy of certificate). One of the following coupling arrangements should also be supplied with each pipe as per the site requirement.						
32	A5	0.50	Kilometre	39269.16	19634.58	AT Par	19634.58
	Description:- Supply of HDPE duct 40/33 mm as per RDSO Spec No RDSO/SPN/TC/45/2013 Rev 2 with latest amendments or TEC GR No. G/CDS 08/02 NOV-2004 OR with latest amendments as available. (supply as per railway). For each Km of HDPE duct following items are to be supplied a) End Plugs- 2no b) Cable sealing plugs -2 no. (c) Plastic couplers slip fit/push fit type - 2no d) End plugs to be provided along with drum -2 nos NOTE-Supply of duct in deferent color as per latest laying policy by HQ.and requirment.						
33	A5	5.00	Numbers	9619.51	48097.55	AT Par	48097.55
	Description:- Supply and installation of Connectors/Pig Tail/Patch cords/ MC/ LIU/ Patch Panels, necessary accessories 24 fiber with termination/ splicing of OFC cable make R&M, 3M or Raychem, Systemax ,.Model make approved before supply.						
34	A5	200.00	Metre	33.23	6646.00	AT Par	6646.00
	Description:- Supply of PVC insulated flexible 3 core x 2.5 sq.mm multi strand power cable as per specification no. IS: 694:1990 reaffirmed 1995 or latest.make-Polycab/finolex,Anchor/Delton						
35	A5	4.00	Numbers	2940.72	11762.88	AT Par	11762.88
	Description:- Supply of 100 pair Cable termination krone type box .Krone module suitable for 0.5 and 0.63 mm conductor for cable termination with locking facility.. as per Sepc.						
36	A5	6.00	Numbers	792.01	4752.06	AT Par	4752.06
	Description:- Supply of 50 Pair Krone box with krone terminal .Krone module suitable for 0.5 and 0.63 mm conductor for cable termination with locking facility.As per Spec.						
37	A5	1.00	Numbers	115452.85	115452.85	AT Par	115452.85
	Description:- Supply of maintenance OFC tools kit as per TEC specification no. GR/OFT-01/03 APR 2005 or latest , one set consisting of following:1-Digital multi meter 4 1/2 digit with Liquid crystal Display 1 No. of Phillips/Motwane /fluke/stanlay Make.2-Utility Knife - 1 Nos 3-Cable Slitter -1 Nos.4-Tubing cutter for cable armour-1Nos.5-Bare Fiber adaptor.6-Miller Height precision stripper for fiber buffer .7-Cleaver Fujkura make or similar.-1 Nos.8-FC/PC Adopter with DB loss-2 Nos.9-Earth resistance measuring instrument with all accessories suitable for measuring earth resistance in range of 0.1 Ohms to 10 Ohms.10-Megger-100v -1 Nos.500 v-1 Nos.11-Loose tube stripper-1 Nos.12Cord stripping pliers.13-Supply of Krone tool-2 nos.14-duct cutter -2 Nos						
38	A5	2.00	Numbers	31598.41	63196.82	AT Par	63196.82
	Description:- Supply of Optical Power Meter suitable for of testing 1550/1310 As per Spec. with Lithium Battery ,adopter and other accessories .Make /& model OLP-35 Power Meter JDSU or similar. before supply model make approved by Rly.						
39	A5	13.29	Metre	13.29	176.62	AT Par	176.62
	Description:- Supply & PVC rigid pipe 25mm dia conforming to ISI spec. No. ISI/9537.						
40	A5	2.00	Numbers	38848.63	77697.26	AT Par	77697.26
	Description:- 19" 24 U Cabinet for Housing the operating console, UPS Amplifier and other interfacing unit.or other requirment.						
41	A5	2.00	Numbers	1933.45	3866.90	AT Par	3866.90
	Description:- Supply of Krone tool with test jack.						
42	A5	250.00	Numbers	472.13	118032.50	AT Par	118032.50
	Description:- LC/SC/Euro OFC patch cord 1.5 to 10 mtr log. As per requirement.						
43	A5	4.00	Numbers	1049.24	4196.96	AT Par	4196.96
	Description:- Supply of crimping tool suitable for 0.5mm and 0.63 mm dia telecom cable. Make-krone or similar						
44	A5	4.00	Numbers	21568.98	86275.92	AT Par	86275.92
	Description:- UPS 1 KVA online having one hours backup.Make -APC/Numeric/Microtek or similar						
45	A5	2.00	Numbers	14613.18	29226.36	AT Par	29226.36
	Description:- Supply of 8 port gigabit managed POE layer 2 switch supports 8 nos 10/100/1000 base-T port along with 2 gigabit SFP ports and modules with green-saving technologies.Make-DG-GS1510 Digisol/cisco/juniper/D-link or similar.						
46	A5	1000.00	Metre	13.99	13990.00	AT Par	13990.00
	Description:- Supply of UTP CAT-6 CABLE MAKE:- D LINK,Avaya, CP plus, Finolex,Havells, L&T.						
47	A5	50.00	Numbers	858.86	42943.00	AT Par	42943.00

**DYCSTE-C-BRC-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-BRC-155-2025-26Tele

Closing Date/Time: 16/06/2026 15:00

	Description:- Supply of single line caller ID hand free telephone with speaker of make beetel M53 or latest with RJ 11 rosettes and 3 nos pen torch cell Eveready or navino to be supply with each telephone and warranty upt 01 year							
48	A5	50.00	Numbers	8.94	447.00	AT Par	447.00	
	Description:- Supply of telephone roset for single line auto telephone with RJ-11 types socket and line termination screw.							
49	A5	200.00	Metre	74.26	14852.00	AT Par	14852.00	
	Description:- Supply of PVC casing & capping of size 25mm x 25/32mm x 1mm thickness of Precision or Garware or Presto or similar make.							
50	A5	100.00	Metre	12.26	1226.00	AT Par	1226.00	
	Description:- Supply and fixing of PVC FLEXIBLE PIPE 1" Dia .(Inspection agency :-Consignee							
51	A5	600.00	Metre	121.87	73122.00	AT Par	73122.00	
	Description:- Supply of PVC channel of size 50x50 mm with all accessories like joint, bends etc. of precision, Garware make or similar standard make							
52	A5	200.00	Numbers	144.80	28960.00	AT Par	28960.00	
	Description:- Supply of factory crimped CAT 6 UTP Patch Cord 3 Mtrs. as per specification no. of Tender document.							
53	A5	100.00	Numbers	74.19	7419.00	AT Par	7419.00	
	Description:- Supply of factory crimped CAT 6 UTP Patch Cord 1 Mtrs. as per specification no. of Tender document.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A6-Supply portion							1033384.25	
1	A6	60.00	Running Metre	1170.00	70200.00	AT Par	70200.00	
	Description:- Supply of G.I. Pipes 100 mm dia medium grade engraved on pipe as per spec. no. IS 1239 part I of 2004 with latest amend. with sockets and fittings. (other dia. Pipes shall be supplied by Railway) (Surya, Jindal, Tata, Apollo or Asian make) -							
2	A6	10.00	Numbers	1260.19	12601.90	AT Par	12601.90	
	Description:- Double Walled Corrugated (DWC) HDPE Pipe with associated collars etc. as per RDSO Specification No. RDSO/SPN/204/2011 or latest anti-rodent & anti-oxidant and non flame propagating type in 6 meters straight length and of size 120 mm outer dia, & 103.5 mm inner dia. (The manufacturers, suppliers must produce valid IS license and should be certified under ISO 9000 and shall submit copy of certificate). One of the following coupling arrangements should also be supplied with each pipe as per the site requirement.							
3	A6	20.00	Numbers	2318.48	46369.60	AT Par	46369.60	
	Description:- Supply of Thermo shrinkable joint kit as per RDSO spec no. IRS TC 77/2010 Rev-2 or latest suitable for 2T joint RTSF3 suitable to 6-quad cable of spec no. IRS TC-30/2005, Ver-1, Amd-4 with latest AMD..							
4	A6	40.00	Running Metre	394.65	15786.00	AT Par	15786.00	
	Description:- Supply of G.I. Pipes 80 mm dia medium grade engraved on pipe as per spec. no. IS 1239 of 204 with latest amend. with sockets and fittings. (other dia. Pipes shall be supplied by Railway) (Surya, Jindal, Tata, Apollo or Asian make).							
5	A6	6.00	Numbers	1691.04	10146.24	AT Par	10146.24	
	Description:- " EMERGENCY 6 PIN SOCKET AND BOX IRS:TC:42/87 (Amendment Slip No.1) BOX - Conforming to RDSO DRG. NO. TCA-20060 (ADV) make-Epsilon /SARASWAT ENTERPRISES or before approved by Railway."							
6	A6	6.00	Numbers	377.32	2263.92	AT Par	2263.92	
	Description:- Supply of 6 Pin EC Socket Plug & Socket flat type as per IRS TC-42-87 ver-2, Amd-1 or latest. Make -Epsilon/SARASWAT ENTERPRISES or approved by Railway.							
7	A6	8.00	Kilometre	39269.16	314153.28	AT Par	314153.28	
	Description:- Supply of HDPE duct 40/33 mm as per RDSO Spec No RDSO/SPN/TC/45/2013 Rev 2 with latest amendments or TEC GR No. G/CDS 08/02 NOV-2004 OR with latest amendments as available. (supply as per railway). For each Km of HDPE duct following items are to be supplied a) End Plugs- 2 no b) Cable sealing plugs -2 no. (c) Plastic couplers slip fit/push fit type - 2 no d) End plugs to be provided along with drum -2 nos NOTE-Supply of duct in deferent color as per latest laying policy by HQ. and requirement.							
8	A6	50.00	Numbers	33.97	1698.50	AT Par	1698.50	
	Description:- HDPE duct coupler of size 40/33 mm dia. compatible to supplied duct. Inspection							
	A6	2.00	Numbers	9619.51	19239.02	AT Par	19239.02	

**DYCSTE-C-BRC-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-BRC-155-2025-26Tele

Closing Date/Time: 16/06/2026 15:00

9	Description:- Supply and installation of Connectors/Pig Tail/Patch cords/ MC/ LIU/ Patch Panels, necessary accessories 24 fiber with termination/ splicing of OFC cable make R&M, 3M or Raychem, Systemax, .Model make approved before supply.							
10	A6	100.00	Metre	33.23	3323.00	AT Par	3323.00	
	Description:- Supply of PVC insulated flexible 3 core x 2.5 sq.mm multi strand power cable as per specification no. IS: 694:1990 reaffirmed 1995 or latest.make-Polycab/finolex,/Anchor/Delton							
11	A6	2.00	Numbers	120078.42	240156.84	AT Par	240156.84	
	Description:- "PCM TDM Integrated access device 1U height /19"" rack mountable; Optical module integrated in the unit supporting dual core OFC and 2E1 one 100Mbps Ethernet Port; optical distance support to be 20 KM; unit consist one E&M module supporting eight 2W/4W (each port configurable); another one slot populated with FSX or FXO for hot line connection .Model : Make : MAPLE-4CS or similar."							
12	A6	2.00	Numbers	20236.32	40472.64	AT Par	40472.64	
	Description:- Optical Module Card having SFP port for connectivity with suitable SFP module or EKT or optical to 4xE1 cinvertor suitable for 4E1.as per requirment of multiplexer MAPPLE -4 C or similar equipmet .which supply item above.							
13	A6	2.00	Numbers	51863.69	103727.38	AT Par	103727.38	
	Description:- Supply of Microcontroller based Quad Cable Conductor's Earth Resistance Sensing Unit, for 24 nos. conductors with metering facility for one conductor at a time.							
14	A6	4.00	Numbers	574.05	2296.20	AT Par	2296.20	
	Description:- Supply of push button telephone having DTMF signalling							
15	A6	200.00	Metre	13.29	2658.00	AT Par	2658.00	
	Description:- Supply & PVC rigid pipe 25mm dia conforming to ISI spec. No. ISI/9537.							
16	A6	305.00	Metre	35.44	10809.20	AT Par	10809.20	
	Description:- Supply of STP (Shielded Twisted Pair) CAT-6 cable compliant with latest EIA/TIA-568-B. 2-1 standard of make D-Link/DAX/Lucent/Crone/Amp. or similar							
17	A6	2.00	Numbers	38848.63	77697.26	AT Par	77697.26	
	Description:- 19" 24 U Cabinet for Housing the operating console, UPS Amplifier and other interfacing unit.or other requirment.							
18	A6	24.00	Numbers	472.13	11331.12	AT Par	11331.12	
	Description:- LC/SC/Euro OFC patch cord 1.5 to 10 mtr log. As per requirement.							
19	A6	1.00	Numbers	1049.24	1049.24	AT Par	1049.24	
	Description:- Supply of crimping tool suitable for 0.5mm and 0.63 mm dia telecom cable. Make-krone or similar							
20	A6	2.00	Numbers	21568.98	43137.96	AT Par	43137.96	
	Description:- UPS 1 KVA online having one hours backup.Make -APC/Numeric/Microtek or similar							
21	A6	305.00	Metre	13.99	4266.95	AT Par	4266.95	
	Description:- Supply of UTP CAT-6 CABLE MAKE:- D LINK,Avaya, CP plus, Finolex,Havells, L&T.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () B1-Execution portion							225678.60	
1	B1	12.00	Numbers	2094.87	25138.44	AT Par	25138.44	
	Description:- Installation, Testing & Commissioning of 2MP day/night vision Full HD P/T/Z (Pan/Tilt/Zoom) IP Colour Camera along with all accessories required including bracket/fixture/angle for fixing camera with ceiling mounting kit and built in features of audio recording : As Per RDSO specification No. RDSO/SPN/TC/65/2021 Version 6.0 or latest.							
2	B1	76.00	Numbers	1418.03	107770.28	AT Par	107770.28	
	Description:- "Installation, Testing & Commissioning of 2MP day/night vision Full HD Bullet type IP Colour Camera along with all accessories required including bracket/fixture/angle for fixing camera with ceiling mounting kit and built in features of audio recording : As Per RDSO specification No. RDSO/SPN/TC/65 /2021 Version 6.0 or latest."							
3	B1	96.00	Numbers	351.39	33733.44	AT Par	33733.44	
	Description:- Splicing of fibers OFC cable and making splice joint with contractor's own splicing machine and tools and consumbles.							
4	B1	1.00	Numbers	15469.00	15469.00	AT Par	15469.00	
	Description:- Portable Handheld Electronic Labeller with 05 nos. of tape cassette having following or better specifications: (1) Print Resolution: 180 dpi,64 dots (2) Print Speed: 20mm/sec (3) No. of Lines Printable: 2 Lines (4) Tape Cassette: 12mm (5) AC Adapter with rechargeable alkaline batteries. (6) Accepted make: Brother/Epson/Casio only. Tenderer should submit make and model of the item for which the offer is being quoted.							

**DYCSTE-C-BRC-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-BRC-155-2025-26Tele

Closing Date/Time: 16/06/2026 15:00

5	B1	2.00	Numbers	14500.00	29000.00	AT Par	29000.00	
	Description:- Supply of Hydraulic LUG Crimping Tool as per Technical Specification.							
6	B1	0.80	Kilometre	9370.00	7496.00	AT Par	7496.00	
	Description:- Laying of OFC/Quad Cable, PIJF cable of different size in the excavated trench/boring This includes loading/unloading & transportation of cables from the stores of SSE/T/C/PRTN to the site/ Wherever several cables of provision of separation of various cables should be as advised by the site incharge of the Railway. Empty cable drums to be retained by the contractor the cable drums with unused cable at site to be returned by the contractor from site to be returned by the contractor from site to Stores of SSE/T/PRTN.							
7	B1	4.00	Numbers	1767.86	7071.44	AT Par	7071.44	
	Description:- Installation of Maintenance free Earth Electrode for Maintenance free earth as supply in sch.A.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () B2-Execution portion							11087434.15	
1	B2	10.00	Kilometre	884.48	8844.80	AT Par	8844.80	
	Description:- Cable route survey & Preparation of as built final cable route and other plans (for OFC as well as other telecom cables whose laying is covered in this schedule) taking into account the points mentioned in chapter II & other chapters of technical requirement on Auto CAD for entire sections for entire sections VG-SIOB. The cable route & other plans shall be prepared by contractor after joint survey, got approved from engineer in charge, changes during course of execution shall be incorporated in the same. After completion of the work all completion documents of tracing papers along with six prints of cable route plan, jointing & splicing schedule, cable hut wiring diagram etc. in six sets for each station and section in folders shall be supplied by the contractor. Contractor shall also supply the Auto CAD documents on CD. All the required materials, accessories including tracings, papers etc, shall be contractor's own.							
2	B2	4500.00	cum	839.00	3775500.00	AT Par	3775500.00	
	Description:- Excavation of trench 300mm wide at the bottom and 1.2 mtr deep, in all type of soils including clearing of trees, bushes, etc. and refilling of cable trench by excavated soil and ramming after laying of HDPE DUCT (laying of HDPE/DWC & 6 Quad. cables, PDF cables etc., will be paid under different items of the schedule). Where desired dimensions of trenches could not be achieved proportionate payment will be made as decided by Engineer-in-charge of the Railway at site. The trenching outside the station limits I.e.) between the home signal of station 'A' to home signal of station 'B' may be done manually or by machine, as per the directions of site in charge. In no case the payment will be made for the trench of higher dimensions, than the dimensions as mentioned above.							
3	B2	100.00	Metre	153.60	15360.00	AT Par	15360.00	
	Description:- Preparation of cable way 150mm wide at bottom and 200mm deep CC road/ Platform and other CC/Stony location and refilling the same (after telecom Cable laying as well as laying PVC pipe which shall be paid separately under different items of the schedule) with concrete mixture of proportion 1:3:6 all along the trench done rocky area with contractor's own cement mixture, sand, water and other required materials and restoration of earth work as original with tiles/marvel/Granite etc.							
4	B2	5000.00	Metre	1187.85	5939250.00	AT Par	5939250.00	
	Description:- Horizontal direction drilling/boring without damage of surface road using Auger Machine. The bore shall be 150 mm dia & shall be done at the depth of minimum 1500 mm from the ground level. The ground level shall be considered ignoring the bank height of the bank of the road as per direction of Engineer In charge and pulling cable/duct No of cable and duct as per Rly site incharge respect size of boring dia. (Payment of laying cable/duct as per given schedule in other item)							
4	B2	4.00	Numbers	2786.05	11144.20	AT Par	11144.20	
	Description:- Installation of fiber distribution management system (Supply covered Above) with all installation materials, restoration wall etc. to original condition , splicing and termination of 48 fiber cable (With all contractor's materials), routing/dressing fibers as per directions of Engineer in-charge.							
5	B2	600.00	Running Metre	468.16	280896.00	AT Par	280896.00	
	Description:- Providing chase in hard rocy soil for laying of S&T cables where optimum depth (0.5m) in not possible and which is verified and agreed by engineer-in - charge .after laying of cables.it should be covered with PCC work in ratio of 1:3:6.							
	B2	0.50	Kilometre	9370.00	4685.00	AT Par	4685.00	

**DYCSTE-C-BRC-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-BRC-155-2025-26Tele

Closing Date/Time: 16/06/2026 15:00

6	Description:- Laying of OFC/Quad Cable, PIJF cable of different size in the excavated trench/boring This includes loading/unloading & transportation of cables from the stores of SSE/T/C/PRTN to the site/ Wherever several cables of provision of separation of various cables should be as advised by the site incharge of the Railway. Empty cable drums to be retained by the contractor the cable drums with unused cable at site to be returned by the contractor from site to be returned by the contractor from site to Stores of SSE/T/PRTN.						
7	B2	60.00	Metre	418.07	25084.20	AT Par	25084.20
	Description:- Fixing & laying of 100 mm /80 mm dia GI pipes or GI trouphing (supply of GI pipe is covered separately in Schedule 'C1') and parapet wall/roof of culverts, including masonry work at both ends with contractors own material and bending of the pipe at the both ends etc. as per Drawing No. SK/CSTE/C/97/05 & directive of Engineer in-charge, Perforation should be done before laying of GI pipes.						
8	B2	500.00	Numbers	302.98	151490.00	AT Par	151490.00
	Description:- Supply & installation of RCC cable route marker engraved on both side and painted on both sides along the route every 50 to 100 mt. & route diversions as per Drg 4014/00/CC4.						
9	B2	200.00	Running Metre	23.83	4766.00	AT Par	4766.00
	Description:- Placing of RCC/DWC/ Split DWC pipe in trench and track/road crossing protruding equally outside the rail/road edge on either side.						
10	B2	2.00	Numbers	1767.86	3535.72	AT Par	3535.72
	Description:- Installation of Maintenance free Earth Electrode for Maintenance free earth as supply in sch.A.						
11	Please see Item Breakup for details.				119164.40	AT Par	119164.40
	Description:- Supply & Fixing of GI trouphing on girder/ other type bridges in yard and mid sections for carrying telecom cable. This includes supply and fixing of 100mmx50mmx06mm and1. 2 mtr long MS channel .Before installation material inspected by Railway repersentative as site engineer instruction.						
12	B2	2.00	cum	2215.53	4431.06	AT Par	4431.06
	Description:- Cement concrete work for miscellaneous items in the ratio 1 : 3 : 6 . Item includes excavation, ramming, curing and plastering with cement & sand mixture (aggregate not exceeding 3.8 cm.) (Aggregate cement & sand to be supplied by the contractor).						
13	B2	2.00	cum	1378.78	2757.56	AT Par	2757.56
	Description:- Providing brick masonry in ratio 1:6 cement and mortar including plastering with 1:4 cement and sand mixture both sides, 20 mm thick each with contractor's owned class II bricks, including excavation, curing, grouting, bolting etc. wherever required. Bricks sand and cement to be supplied by the contractor.						
15	B2	26.00	Kilometre	4810.06	125061.56	AT Par	125061.56
	Description:- Transportation and Laying of HDPE pipe as per approved cable route plan in the excavated trench, taking due care while transporting and laying the same in the trenches or other protective works. Both the end of duct should be sealed with end plugs before laying and should remain sealed till blowing is done.Note- laying Duct as per HQ polcy dated 01.01.2025						
16	B2	2.00	Per Block Section	9339.84	18679.68	AT Par	18679.68
	Description:- End to end testing of all fiber of the optical fibred cable laid under above items between station/cable huts. All required equipments, tools and plants shall be arranged by the contractor. Five nos. of print out of traces in folders of OFC parameters/ results, The per kilometer link loss shall be as per the policy/technical circulars issued by the railways from time to time.						
17	B2	12.00	Numbers	13342.67	160112.04	AT Par	160112.04
	Description:- Supply and installation of straight joint enclosures (SJC) complete with all accessories with latest amendments or Raychems RPG make FOSC-400-B4-A-BJL-4-H -48 or similar make only. (For 48 fiber OFC) and splicing of 2X48 F laid OFC. Insp. By Consignee.						
18	B2	26.00	Kilometre	8637.20	224567.20	AT Par	224567.20
	Description:- Blowing of OFC through HDPE duct & protective work (elicited in above item) already provided. Where it is not feasible to blow OFC due to curves, road/track crossings, bridges or for any other reason, OFC shall be drawn /laid manually as per standard procedure. All the equipments and machinery required shall be arranged by the contractor at his own cost. In case OFC is to be laid adopting 'Direct in trench' method then this item shall be paid as per accepted rate of item no.(6 h) of this schedule. OFC and HDPE pipe shall be supplied by the railway.						
19	B2	12.00	Numbers	3561.51	42738.12	AT Par	42738.12
	Description:- Supply & installation of RCC pre-fabricated OFC jointing pits size 0.6mx1.12mx1m.round type as per RCIL drg No. RAILTEL/WR/OT/DFC/011 The material shall be supplied as per engineer in charge instructions.						
20	B2	2.00	Numbers	6941.98	13883.96	AT Par	13883.96

**DYCSTE-C-BRC-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-BRC-155-2025-26Tele

Closing Date/Time: 16/06/2026 15:00

	Description:- Installtion of 42 U rack and supply necessary ladder for cable way up to 10 Mtr. ladder (cable way) siz 200 mm Wide 4mm thick .all material for ladder given by contractor .							
21	B2	50.00	Hour	656.67	32833.50	AT Par	32833.50	
	Description:- "Hiring of JCB for Excavation work otherthan trenching.like Removal of piles of soil, sloping soil, boulders, debris, rails, sleepers coming in the cable route etc.as per railway site engineer incharge. "							
22	B2	200.00	Metre	73.25	14650.00	AT Par	14650.00	
	Description:- Laying of power cable, telecommunication cable at OFC room ,panel room and station with termination etc as per instruction of railway site engineer.							
23	B2	2.00	Numbers	20193.94	40387.88	AT Par	40387.88	
	Description:- "Supply and Installation of Control IP Telephones without Hands Free and Gooseneck Operation for Way Side Station as Per Clause 11 of RDSO/SPN/TC/99/2012 Rev.2 or latest as per specification no.4.55 of chapter-4 of Tender document. "							
24	B2	2.00	Numbers	15817.62	31635.24	AT Par	31635.24	
	Description:- Supply & installation of Class-B & Class-C Type surge arrestors for single pase supply and as per standard practice & including supply of all the materials required for the work.							
25	B2	2.00	Set	1889.39	3778.78	AT Par	3778.78	
	Description:- Installation, wiring, testing and commissioning of SMPS battery charger & maintenance free VRLA cells at each station. Note:- The rate quoted shall be including the cost of DC bus bar of 48V DC /Power wire suitable stand etc.connection of power supply to the equipments. All the wiring shall be done with the suitable gauge of power wires through suitable casing / capping as per the instructions of railway engineer's. All the materials required for this item shall be supplied by the contractor.(SPMS charger is covered in schedule - A & VRLA battery will be supplied by Railway)							
26	B2	300.00	Metre	9.72	2916.00	AT Par	2916.00	
	Description:- Laying of OFC/Power cable/CAT-6 cable/PA Cable/Data cable and all the other types of telecom cable through HDPE pipe/casing capping/fall ceiling with laying/fixing of HDPE pipe/casing capping/uPVC pipe for connecting/ interfacing various components and system integration. All materials for jointing and termination of power cable/CAT-6 cable as per site requirement are to be supplied by contractor. This item also includes supply of RJ-45 connector with cap for terminating CAT-6 cable and supply and installation of power board with 4 points (3 nos 5 amp sockets and 1 nos 15 Amps socket) as per site requirement.							
27	B2	1.00	Numbers	7429.85	7429.85	AT Par	7429.85	
	Description:- Supply & Installation of Professional 19" mount Equipment Racks 9U for housing telecom Equipment.							
28	B2	2.00	Numbers	10925.70	21851.40	AT Par	21851.40	
	Description:- Installation and commissioning of mapple 4C and interigated acecess device necessary assare necessary accessories (power MCB,OFC patch cord krone and wiring material etc)also provided for installation item above supply.including necessary training of staff.As per engineer inchage.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () B3-Execution portion							5560650.54	
1	B3	6.00	Kilometre	884.48	5306.88	AT Par	5306.88	
	Description:- Cable route survey & Preparation of as built final cable route and other plans (for OFC as well as other telecom cables whose laying is covered in this schedule) taking into account the points mentioned in chapter II & other chapters of technical requirement on Auto CAD for entire sections for entire sections VG-SIOB. The cable route & other plans shall be prepared by contractor after joint survey, got approved from engineer in charge, changes during course of execution shall be incorporated in the same. After completion of the work all completion documents of tracing papers along with six prints of cable route plan, jointing & splicing schedule, cable hut wiring diagram etc. in six sets for each station and section in folders shall be supplied by the contractor. Contractor shall also supply the Auto CAD documents on CD. All the required materials, accessories including tracings, papers etc, shall be contractor's own.							
2	B3	300.00	cum	839.00	251700.00	AT Par	251700.00	
	Description:- Excavation of trench 300mm wide at the bottom and 1.2 mtr deep, in all type of soils including clearing of trees, bushes, etc. and refilling of cable trench by excavated soil and ramming after laying of HDPE DUCT (laying of HDPE/DWC & 6 Quad. cables, PDF cables etc., will be paid under different items of the schedule). Where desired dimensions of trenches could not be achieved proportionate payment will be made as decided by Engineer-in-charge of the Railway at site. The trenching outside the station limits I.e.) between the home signal of station 'A' to home signal of station 'B' may be done manually or by machine, as per the directions of site in charge. In no case the payment will be made for the trench of higher dimensions, than the dimensions as mentioned above.							
	B3	4000.00	Metre	1187.85	4751400.00	AT Par	4751400.00	

**DYCSTE-C-BRC-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-BRC-155-2025-26Tele

Closing Date/Time: 16/06/2026 15:00

3	Description:- Horizontal direction drilling/boring without damage of surface road using Auger Machine. The bore shall be 150 mm dia & shall be done at the depth of minimum 1500 mm from the ground level. The ground level shall be considered ignoring the bank height of the bank of the road as per direction of Engineer In charge and pulling cable/duct No of cable and duct as per Rly site incharge respect size of boring dia. (Payment of laying cable/duct as per given schedule in other item)						
4	B3	300.00	Metre	153.60	46080.00	AT Par	46080.00
4	Description:- Preparation of cable way 150mm wide at bottom and 200mm deep CC road/ Platform and other CC/Stony location and refilling the same (after telecom Cable laying as well as laying PVC pipe which shall be paid separately under different items of the schedule) with concrete mixture of proportion 1:3:6 all along the trench done rocky area with contractor's own cement mixture, sand, water and other required materials and restoration of earth work as original with tiles/marvel/Granite etc.						
4	B3	3.00	Kilometre	9370.00	28110.00	AT Par	28110.00
4	Description:- Laying of OFC/Quad Cable, PIJF cable of different size in the excavated trench/boring This includes loading/unloading & transportation of cables from the stores of SSE/T/C/PRTN to the site/ Wherever several cables of provision of separation of various cables should be as advised by the site incharge of the Railway. Empty cable drums to be retained by the contractor the cable drums with unused cable at site to be returned by the contractor from site to be returned by the contractor from site to Stores of SSE/T/PRTN.						
6	B3	120.00	Metre	418.07	50168.40	AT Par	50168.40
6	Description:- Fixing & laying of 100 mm /80 mm dia GI pipes or GI trouphing (supply of GI pipe is covered separately in Schedule 'C1') and parapet wall/roof of culverts, including masonry work at both ends with contractors own material and bending of the pipe at the both ends etc. as per Drawing No. SK/CSTE/C/97/05 & directive of Engineer in-charge, Perforation should be done before laying of GI pipes.						
7	B3	8.00	Numbers	887.45	7099.60	AT Par	7099.60
7	Description:- Execution of quad cable jointing using thermo shrinkable joint kit straight though/ Derivation / 2T / 3T transformer joints with VF transformer between 6 quad & PIJF cable this i/c transformers on 6 quad / jelly field cable this i/c VF transformation of jointing kit transformer covered in Schedule 'A'.						
8	B3	4.00	Numbers	2435.71	9742.84	AT Par	9742.84
8	Description:- Fabrication of EC socket box, assembly and erection of fabricated assembly at the location indicated in the route chart and as per direction of Engineer in charge. This includes cutting of rails / GI pipe to required size, supply and welding of GI Pipe and base plate, fixing of EC Socket box, transportation of material to site, digging of pit and erection of whole assembly at site. The work also includes the termination of 6 Quad/PIJF derivation cable on the strips of 6 pin EC socket inside emergency socket box. The fabrication of EC Socket box shall be done as per Drg. No. SK/CSTE/C/97/16 & SK/CSTE/C/97/20. Rail/GI Pipe post will be supplied free of cost at the SSE (Tele) C/PRTN depot in full lengths. Note - In addition to above, the centre pins of EC sockets shall be terminated with a dedicated pair of 6 Quad cable (Derivate through the tail PIJF cable) in the entire block section so as to provide magneto/auto telephone communication from each EC socket.(All materials supply by contractor except rails & GI Pipe for post.).						
9	B3	100.00	Numbers	302.98	30298.00	AT Par	30298.00
9	Description:- Supply & installation of RCC cable route marker engraved on both side and painted on both sides along the route every 50 to 100 mt. & route diversions as per Drg 4014/00/CC4.						
10	B3	120.00	Running Metre	23.83	2859.60	AT Par	2859.60
10	Description:- Placing of RCC/DWC/ Split DWC pipe in trench and track/road crossing protruding equally outside the rail/road edge on either side.						
11	B3	8.00	Numbers	1767.86	14142.88	AT Par	14142.88
11	Description:- Installation of Maintenance free Earth Electrode for Maintenance free earth as supply in sch.A.						
12	B3	2.00	cum	2215.53	4431.06	AT Par	4431.06
12	Description:- Cement concrete work for miscellaneous items in the ratio 1 : 3 : 6 . Item includes excavation, ramming, curing and plastering with cement & sand mixture (aggregate not exceeding 3.8 cm.) (Aggregate cement & sand to be supplied by the contractor).						
13	B3	5.00	Kilometre	4810.06	24050.30	AT Par	24050.30
13	Description:- Transportation and Laying of HDPE pipe as per approved cable route plan in the excavated trench, taking due care while transporting and laying the same in the trenches or other protective works. Both the end of duct should be sealed with end plugs before laying and should remain sealed till blowing is done.Note- laying Duct as per HQ polcy dated 01.01.2025						
14	B3	2.00	Per Block Section	9339.84	18679.68	AT Par	18679.68

**DYCSTE-C-BRC-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-BRC-155-2025-26Tele

Closing Date/Time: 16/06/2026 15:00

14	Description:- End to end testing of all fiber of the optical fibred cable laid under above items between station/cable huts. All required equipments, tools and plants shall be arranged by the contractor. Five nos. of print out of traces in folders of OFC parameters/ results, The per kilometer link loss shall be as per the policy/technical circulars issued by the railways from time to time.							
15	B3	6.00	Kilometre	8637.20	51823.20	AT Par	51823.20	
	Description:- Blowing of OFC through HDPE duct & protective work (elicited in above item) already provided. Where it is not feasible to blow OFC due to curves, road/track crossings, bridges or for any other reason, OFC shall be drawn /laid manually as per standard procedure. All the equipments and machinery required shall be arranged by the contractor at his own cost. In case OFC is to be laid adopting 'Direct in trench' method then this item shall be paid as per accepted rate of item no.(6 h) of this schedule. OFC and HDPE pipe shall be supplied by the railway.							
16	B3	6.00	Numbers	3561.51	21369.06	AT Par	21369.06	
	Description:- Supply & installation of RCC pre-fabricated OFC jointing pits size 0.6mx1.12mx1m.round type as per RCIL drg No. RAILTEL/WR/OT/DFC/011 The material shall be supplied as per engineer in charge instructions.							
17	B3	2.00	Numbers	19112.15	38224.30	AT Par	38224.30	
	Description:- "Installation, Commissioning & Testing of LER & LSR IP MPLS Routers including supply & Installation of all the accessories like Power cable, Earthing Cable, Optical Patch Cords of 3 mtr- 6 Nos. for LERs & 10 Nos. for LSRs, Cat 6 Patch Cords of 1 mtr -4 Nos , one 6A MCB for each LER and LSR , wiring etc. as required for Routers as per specification. "							
18	B3	2.00	Numbers	47582.85	95165.70	AT Par	95165.70	
	Description:- "Supply and installation of 16 port E1 Card (2 x 8port) along with Patch panel/Krone Module and wiring for Routers with all accessories etc. as per RDSO Document No. STT/TAN/IP-MPLS/2020 Version 2.0 as per specification. "							
19	B3	4.00	Numbers	20193.94	80775.76	AT Par	80775.76	
	Description:- "Supply and Installation of Control IP Telephones without Hands Free and Gooseneck Operation for Way Side Station as Per Clause 11 of RDSO/SPN/TC/99/2012 Rev.2 or latest as per specification no.4.55 of chapter-4 of Tender document. "							
20	B3	2.00	Numbers	11315.54	22631.08	AT Par	22631.08	
	Description:- "Supply and installation of Executive open standard SIPphone as per specification. As per Railway Board letter no.2022/tele/9(3)/4 dtd.22.09.22. "							
21	B3	30.00	Numbers	219.74	6592.20	AT Par	6592.20	
	Description:- Splicing of fibres of OFC Cable and making Splice joint of fiber with contractor's own splicing machine and tools and consumables.(Payment per fiber which splice not count total fiber of cable)							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () B4-Execution portion							119954.10	
1	B4	1.50	Kilometre	9370.00	14055.00	AT Par	14055.00	
	Description:- Laying of OFC/Quad Cable, PIJF cable of different size in the excavated trench/boring This includes loading/unloading & transportation of cables from the stores of SSE/T/C/PRTN to the site/ Wherever several cables of provision of separation of various cables should be as advised by the site incharge of the Railway. Empty cable drums to be retained by the contractor the cable drums with unused cable at site to be returned by the contractor from site to be returned by the contractor from site to Stores of SSE/T/PRTN.							
2	B4	1700.00	Metre	22.92	38964.00	AT Par	38964.00	
	Description:- Fixing /Claimping of PVC pipe/HDPE pipe/HDPE duct 40/33 mm /Gi Pipe on wall etc .Claimp provide by contractor.							
3	B4	2300.00	Metre	9.72	22356.00	AT Par	22356.00	
	Description:- Laying of OFC/Power cable/CAT-6 cable/PA Cable/Data cable and all the other types of telecom cable through HDPE pipe/casing capping/fall ceiling with laying/fixing of HDPE pipe/casing capping/uPVC pipe for connecting/ interfacing various components and system integration. All materials for jointing and termination of power cable/CAT-6 cable as per site requirement are to be supplied by contractor. This item also includes supply of RJ-45 connector with cap for terminating CAT-6 cable and supply and installation of power board with 4 points (3 nos 5 amp sockets and 1 nos 15 Amps socket) as per site requirement.							
4	B4	6.00	Numbers	7429.85	44579.10	AT Par	44579.10	
	Description:- Supply & Installation of Professional 19" mount Equipment Racks 9U for housing telecom Equipment.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () B5-Execution portion							862874.08	

**DYCSTE-C-BRC-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-BRC-155-2025-26Tele

Closing Date/Time: 16/06/2026 15:00

1	B5	50.00	Metre	153.60	7680.00	AT Par	7680.00	
	Description:- Preparation of cable way 150mm wide at bottom and 200mm deep CC road/ Platform and other CC/Stony location and refilling the same (after telecom Cable laying as well as laying PVC pipe which shall be paid separately under different items of the schedule) with concrete mixture of proportion 1:3:6 all along the trench done rocky area with contractor's own cement mixture, sand, water and other required materials and restoration of earth work as original with tiles/marvel/Granite etc.							
2	B5	20.00	Metre	564.46	11289.20	AT Par	11289.20	
	Description:- Manual horizontal auger boring/drilling of 100mm dia Horizontal Bore across the Railway Track/ Across Road at LC gates by Boring method at a depth of 1.65mm from the ground level/ ground level to be considered ignoring the bank height of the bank/road and insertion of HDPE/DWC/GI pipes etc., as per the instructions of Engineer in charge at site as per drg no. RAILTEL/SR/OFC/2008/10.							
3	B5	2.00	Numbers	1767.86	3535.72	AT Par	3535.72	
	Description:- Installation of Maintenance free Earth Electrode for Maintenance free earth as supply in sch.A.							
4	B5	5.00	cum	2215.53	11077.65	AT Par	11077.65	
	Description:- Cement concrete work for miscellaneous items in the ratio 1 : 3 : 6 . Item includes excavation, ramming, curing and plastering with cement & sand mixture (aggregate not exceeding 3.8 cm.) (Aggregate cement & sand to be supplied by the contractor).							
5	B5	0.50	Kilometre	4810.06	2405.03	AT Par	2405.03	
	Description:- Transportation and Laying of HDPE pipe as per approved cable route plan in the excavated trench, taking due care while transporting and laying the same in the trenches or other protective works. Both the end of duct should be sealed with end plugs before laying and should remain sealed till blowing is done.Note- laying Duct as per HQ policy dated 01.01.2025							
6	B5	200.00	Metre	22.92	4584.00	AT Par	4584.00	
	Description:- Fixing /Claimping of PVC pipe/HDPE pipe/HDPE duct 40/33 mm /Gi Pipe on wall etc .Claimp provide by contractor.							
7	B5	20.00	Numbers	11315.54	226310.80	AT Par	226310.80	
	Description:- "Supply and installation ofExecutive open standard SIPphone as per specification. Asper Railway Board letterno.2022/tele/9(3)/4dtd.22.09.22. "							
8	B5	2000.00	Metre	9.72	19440.00	AT Par	19440.00	
	Description:- Laying of OFC/Power cable/CAT-6 cable/PA Cable/Data cable and all the other types of telecom cable through HDPE pipe/casing capping/fall ceiling with laying/fixing of HDPE pipe/casing capping/uPVC pipe for connecting/ interfacing various components and system integration. All materials for jointing and termination of power cable/CAT-6 cable as per site requirement are to be supplied by contractor. This item also includes supply of RJ-45 connector with cap for terminating CAT-6 cable and supply and installation of power board with 4 points (3 nos 5 amp sockets and 1 nos 15 Amps socket) as per site requirement.							
9	B5	300.00	Numbers	219.74	65922.00	AT Par	65922.00	
	Description:- Splicing of fibres of OFC Cable and making Splice joint of fiber with contractor's own splicing machine and tools and consumables.(Payment per fiber which splice not count total fiber of cable)							
10	B5	60.00	Numbers	191.89	11513.40	AT Par	11513.40	
	Description:- Supply & installation of CAT-6 Surface mount info-outlet as perspecification.							
11	B5	4.00	Numbers	262.22	1048.88	AT Par	1048.88	
	Description:- Installation, testing andcommissioning of Online UPS 1 KVA.							
12	B5	800.00	Metre	141.89	113512.00	AT Par	113512.00	
	Description:- Cutting of wall/floor/road for insertion of HDPE/PVC conduit/pipes ,fixing hardware for fixing the conduit/pipes along with its supply and then replaster it with contractor's own cement mixture, sand, water and other required materials and restoration of wall/floor as original with tiles/marvel/Granite etc. This also includes painting with matching colour as per existing colour of the wall. Proper joints in pipes, bends/ elbows/ junction are to be provided as per site requirements.							
13	B5	4.00	Numbers	44123.18	176492.72	AT Par	176492.72	
	Description:- "Supply, Installation, Testing and Commissioning of 24 port manageable of Layer 2 POE switch "							
14	B5	10.00	Numbers	7958.00	79580.00	AT Par	79580.00	
	Description:- Provision for HD set-top box with 1 year full pack (HD) subscription period complete with installation,testing & commissioning under common disc for Hostel, Guest House & faculty rooms within the area or 100mts.(if other building than provide disc) (TATA SKY/AIRTEL)							
15	B5	6.00	Numbers	21413.78	128482.68	AT Par	128482.68	
	Description:- Supply & fixing of Network Rack 12u Floor Standing 600*600 with accessories like utility tray, Cable managers, 6 Socket PDU, 2 AC Fans, etc.							

**DYCSTE-C-BRC-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-BRC-155-2025-26Tele

Closing Date/Time: 16/06/2026 15:00

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () B6-Execution portion							7837272.77	
1	B6	8.00	Kilometre	884.48	7075.84	AT Par	7075.84	
	Description:- Cable route survey & Preparation of as built final cable route and other plans (for OFC as well as other telecom cables whose laying is covered in this schedule) taking into account the points mentioned in chapter II & other chapters of technical requirement on Auto CAD for entire sections for entire sections VG-SIOB. The cable route & other plans shall be prepared by contractor after joint survey, got approved from engineer in charge, changes during course of execution shall be incorporated in the same. After completion of the work all completion documents of tracing papers along with six prints of cable route plan, jointing & splicing schedule, cable hut wiring diagram etc. in six sets for each station and section in folders shall be supplied by the contractor. Contractor shall also supply the Auto CAD documents on CD. All the required materials, accessories including tracings, papers etc, shall be contractor's own.							
2	B6	1500.00	cum	839.00	1258500.00	AT Par	1258500.00	
	Description:- Excavation of trench 300mm wide at the bottom and 1.2 mtr deep, in all type of soils including clearing of trees, bushes, etc. and refilling of cable trench by excavated soil and ramming after laying of HDPE DUCT (laying of HDPE/DWC & 6 Quad. cables, PDF cables etc., will be paid under different items of the schedule). Where desired dimensions of trenches could not be achieved proportionate payment will be made as decided by Engineer-in-charge of the Railway at site. The trenching outside the station limits i.e.) between the home signal of station 'A' to home signal of station 'B' may be done manually or by machine, as per the directions of site in charge. In no case the payment will be made for the trench of higher dimensions, than the dimensions as mentioned above.							
3	B6	200.00	Metre	153.60	30720.00	AT Par	30720.00	
	Description:- Preparation of cable way 150mm wide at bottom and 200mm deep CC road/ Platform and other CC/Stony location and refilling the same (after telecom Cable laying as well as laying PVC pipe which shall be paid separately under different items of the schedule) with concrete mixture of proportion 1:3:6 all along the trench done rocky area with contractor's own cement mixture, sand, water and other required materials and restoration of earth work as original with tiles/marvel/Granite etc.							
4	B6	100.00	Metre	564.46	56446.00	AT Par	56446.00	
	Description:- Manual horizontal auger boring/drilling of 100mm dia Horizontal Bore across the Railway Track/ Across Road at LC gates by Boring method at a depth of 1.65mm from the ground level/ ground level to be considered ignoring the bank height of the bank/road and insertion of HDPE/DWC/GI pipes etc., as per the instructions of Engineer in charge at site as per drg no. RAILTEL/SR/OFC/2008/10.							
5	B6	5000.00	Metre	1187.85	5939250.00	AT Par	5939250.00	
	Description:- Horizontal direction drilling/boring without damage of surface road using Auger Machine. The bore shall be 150 mm dia & shall be done at the depth of minimum 1500 mm from the ground level. The ground level shall be considered ignoring the bank height of the bank of the road as per direction of Engineer In charge and pulling cable/duct No of cable and duct as per Rly site incharge respect size of boring dia. (Payment of laying cable/duct as per given schedule in other item)							
6	B6	8.00	Kilometre	9370.00	74960.00	AT Par	74960.00	
	Description:- Laying of OFC/Quad Cable, PIJF cable of different size in the excavated trench/boring This includes loading/unloading & transportation of cables from the stores of SSE/T/C/PRTN to the site/ Wherever several cables of provision of separation of various cables should be as advised by the site incharge of the Railway. Empty cable drums to be retained by the contractor the cable drums with unused cable at site to be returned by the contractor from site to be returned by the contractor from site to Stores of SSE/T/PRTN.							
7	B6	100.00	Metre	418.07	41807.00	AT Par	41807.00	
	Description:- Fixing & laying of 100 mm /80 mm dia GI pipes or GI trouphing (supply of GI pipe is covered separately in Schedule 'C1') and parapet wall/roof of culverts, including masonry work at both ends with contractors own material and bending of the pipe at the both ends etc. as per Drawing No. SK/CSTE/C/97/05 & directive of Engineer in-charge, Perforation should be done before laying of GI pipes.							
8	B6	20.00	Numbers	887.45	17749.00	AT Par	17749.00	
	Description:- Execution of quad cable jointing using thermo shrinkable joint kit straight though/ Derivation / 2T / 3T transformer joints with VF transformer between 6 quad & PIJF cable this i/c transformers on 6 quad / jelly field cable this i/c VF transformation of jointing kit transformer covered in Schedule 'A'.							
	B6	8.00	Numbers	2435.71	19485.68	AT Par	19485.68	

**DYCSTE-C-BRC-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-BRC-155-2025-26Tele

Closing Date/Time: 16/06/2026 15:00

9	Description:- Fabrication of EC socket box, assembly and erection of fabricated assembly at the location indicated in the route chart and as per direction of Engineer in charge. This includes cutting of rails / GI pipe to required size, supply and welding of GI Pipe and base plate, fixing of EC Socket box, transportation of material to site, digging of pit and erection of whole assembly at site. The work also includes the termination of 6 Quad/PIJF derivation cable on the strips of 6 pin EC socket inside emergency socket box. The fabrication of EC Socket box shall be done as per Drg. No. SK/CSTE/C/97/16 & SK/CSTE/C/97/20. Rail/GI Pipe post will be supplied free of cost at the SSE (Tele) C/PRTN depot in full lengths. Note - In addition to above, the centre pins of EC sockets shall be terminated with a dedicated pair of 6 Quad cable (Derivate through the tail PIJF cable) in the entire block section so as to provide magneto/auto telephone communication from each EC socket.(All materials supply by contractor except rails & GI Pipe for post.).						
10	B6	4.00	Numbers	263.18	1052.72	AT Par	1052.72
	Description:- Fixing of 20/12 pairs CT box & termination cables as per the details approved by the engineer. All the required materials shall be supplied by the contractor.(for station)						
11	B6	160.00	Numbers	302.98	48476.80	AT Par	48476.80
	Description:- Supply & installation of RCC cable route marker engraved on both side and painted on both sides along the route every 50 to 100 mt. & route diversions as per Drg 4014/00/CC4.						
12	B6	8.00	Numbers	500.40	4003.20	AT Par	4003.20
	Description:- Painting of emergency socket assembly and rail post by applying one coat of red oxide as base color, and then painting the assembly as per zebra painting in white and black colors. The width of each of the black and white colors shall be 100mm. All paints used shall be with ISI mark.						
13	B6	200.00	Metre	23.83	4766.00	AT Par	4766.00
	Description:- Placing of RCC/DWC/ Split DWC pipe in trench and track/road crossing protruding equally outside the rail/road edge on either side.						
14	B6	2.00	Numbers	1767.86	3535.72	AT Par	3535.72
	Description:- Installation of Maintenance free Earth Electrode for Maintenance free earth as supply in sch.A.						
15	B6	1.00	cum	2215.53	2215.53	AT Par	2215.53
	Description:- Cement concrete work for miscellaneous items in the ratio 1 : 3 : 6 . Item includes excavation, ramming, curing and plastering with cement & sand mixture (aggregate not exceeding 3.8 cm.) (Aggregate cement & sand to be supplied by the contractor).						
16	B6	2.00	cum	1378.78	2757.56	AT Par	2757.56
	Description:- Providing brick masonry in ratio 1:6 cement and mortar including plastering with 1:4 cement and sand mixture both sides, 20 mm thick each with contractor's owned class II bricks, including excavation, curing, grouting, bolting etc. wherever required. Bricks sand and cement to be supplied by the contractor.						
17	B6	8.00	Kilometre	4810.06	38480.48	AT Par	38480.48
	Description:- Transportation and Laying of HDPE pipe as per approved cable route plan in the excavated trench, taking due care while transporting and laying the same in the trenches or other protective works. Both the end of duct should be sealed with end plugs before laying and should remain sealed till blowing is done.Note- laying Duct as per HQ polcy dated 01.01.2025						
18	B6	1.00	Per Block Section	9339.84	9339.84	AT Par	9339.84
	Description:- End to end testing of all fiber of the optical fibred cable laid under above items between station/cable huts. All required equipments, tools and plants shall be arranged by the contractor. Five nos. of print out of traces in folders of OFC parameters/ results, The per kilometer link loss shall be as per the policy/technical circulars issued by the railways from time to time.						
19	B6	8.00	Kilometre	8637.20	69097.60	AT Par	69097.60
	Description:- Blowing of OFC through HDPE duct & protective work (elicited in above item) already provided. Where it is not feasible to blow OFC due to curves, road/track crossings, bridges or for any other reason, OFC shall be drawn /laid manually as per standard procedure. All the equipments and machinery required shall be arranged by the contractor at his own cost. In case OFC is to be laid adopting 'Direct in trench' method then this item shall be paid as per accepted rate of item no.(6 h) of this schedule. OFC and HDPE pipe shall be supplied by the railway.						
20	B6	12.00	Numbers	13342.67	160112.04	AT Par	160112.04
	Description:- Supply and installation of straight joint enclosures (SJC) complete with all accessories with latest amendments or Raychems RPG make FOSC-400-B4-A-BJL-4-H -48 or similar make only. (For 48 fiber OFC) and splicing of 2X48 F laid OFC. Insp. By Consignee.						
21	B6	6.00	Numbers	3561.51	21369.06	AT Par	21369.06
	Description:- Supply & installation of RCC pre-fabricated OFC jointing pits size 0.6mx1.12mx1m.round type as per RCIL drg No. RAILTEL/WR/OT/DFC/011 The material shall be supplied as per engineer in charge instructions.						
22	B6	100.00	Metre	73.25	7325.00	AT Par	7325.00

**DYCSTE-C-BRC-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-BRC-155-2025-26Tele

Closing Date/Time: 16/06/2026 15:00

22	Description:- Laying of power cable, telecommunication cable at OFC room ,panel room and station with termination etc as per instruction of railway site engineer.							
23	B6	400.00	Metre	9.72	3888.00	AT Par	3888.00	
	Description:- Laying of OFC/Power cable/CAT-6 cable/PA Cable/Data cable and all the other types of telecom cable through HDPE pipe/casing capping/fall ceiling with laying/fixing of HDPE pipe/casing capping/uPVC pipe for connecting/ interfacing various components and system integration. All materials for jointing and termination of power cable/CAT-6 cable as per site requirement are to be supplied by contractor. This item also includes supply of RJ-45 connector with cap for terminating CAT-6 cable and supply and installation of power board with 4 points (3 nos 5 amp sockets and 1 nos 15 Amps socket) as per site requirement.							
24	B6	2.00	Numbers	7429.85	14859.70	AT Par	14859.70	
	Description:- Supply & Installation of Professional 19" mount Equipment Racks 9U for housing telecom Equipment.							

3. ITEM BREAKUP

Schedule	Schedule A5-Supply portion					
Item- 10	Supply, Installation, Testing & Commissioning of Conference System for meeting Room Make: Sennheiser/Bosch/QSC/Biamp as per spec.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Conference Chairman/Delegate Unit	Numbers	18.00	43076.68	775380.24
2	2	Conference Control Unit	Set	1.00	191403.68	191403.68
					Total	966783.92
Schedule	Schedule B2-Execution portion					
Item- 11	Supply & Fixing of GI troughing on girder/ other type bridges in yard and mid sections for carrying telecom cable. This includes supply and fixing of 100mmx50mmx06mm and 1. 2 mtr long MS channel .Before installation material inspected by Railway representative as site engineer instruction.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	supply and fixing of MS channel	Numbers	20.00	502.27	10045.40
2	2	Supply & fixing of GI troughing	Running Metre	150.00	727.46	109119.00
					Total	119164.40

4. ELIGIBILITY CONDITIONS

Special Financial Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer must have minimum average annual contractual turnover of V/N or V whichever is less; where V= Advertised value of the tender in Crore of Rupees N=Number of years prescribed for completion of work for which bids have been invited. The average annual contractual turnover shall be calculated as an average of "total contractual payments" in the previous three financial years, as per the audited balance sheet. However, in case balance sheet of the previous year is yet to be prepared/ audited, the audited balance sheet of the fourth previous year shall be considered for calculating average annual contractual turnover. The tenderers shall submit requisite information as per Annexure-VIB, along with copies of Audited Balance Sheets duly certified by the Chartered Accountant/ Certificate from Chartered Accountant duly supported by Audited Balance Sheet.	No	No	Allowed (Mandatory)

Special Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
-------	-------------	-----------------------	-----------------	---------------------

**DYCSTE-C-BRC-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-BRC-155-2025-26Tele

Closing Date/Time: 16/06/2026 15:00

1	The tenderer must have successfully completed or substantially completed anyone of the following categories of work(s) during last 07 (seven) years, ending last day of month previous to the one in which tender is invited:(i)Three similar works each costing not less than the amount equal to 30% of advertised value of the tender .(ii) Two similar works each costing not less than the amount equal to 40% of advertised value of the tender(iii) One similar work costing not less than the amount equal to 60% of advertised value of the tender	No	No	Allowed (Mandatory)
2	"Any Telecom work"	No	No	Allowed (Mandatory)

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.
3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.
5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.
6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.
7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.
8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.
9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.
10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description
1	Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. (Click here to download the Format of Self Certification)

5. COMPLIANCE

Commercial-Compliance

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)

**DYCSTE-C-BRC-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-BRC-155-2025-26Tele

Closing Date/Time: 16/06/2026 15:00

2	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)
---	---	----	-----	--------------------

General Instructions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	As per " Tender Documents" Attached	No	No	Not Allowed

Special Conditions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	As per " Tender Documents" Attached	No	No	Not Allowed

Technical-Compliances

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	As per " Tender Documents" Attached	No	No	Allowed (Mandatory)

6. Documents attached with tender

S.No.	Document Name	Document Description
1	TenderDocument-155.pdf	Tender Document

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

Signed By: HEMANT KUMAR MAHAWAR

Designation : Dy.CSTE/C/BRC