

**MUMBAI CENTRAL DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SG_216_2_114_WA_ST_R1

Closing Date/Time: 15/06/2026 15:00

Sr.DSTE/BCT acting for and on behalf of The President of India invites E-Tenders against Tender No **SG_216_2_114_WA_ST_R1** Closing Date/Time 15/06/2026 15:00 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

1. NIT HEADER

Name of Work	Supply, installation, testing & commissioning of signalling items in connection with the work of Reliability improvement and replacement of defective/overaged midlife signalling gears under the jurisdiction of ADSTE /Surat of Virar- Surat Section of Mumbai Division.		
Bidding type	Normal Tender		
Tender Type	Open	Bidding System	Single Packet System
Tender Closing Date Time	15/06/2026 15:00	Date Time Of Uploading Tender	16/05/2026 14:02
Pre-Bid Conference Required	No	Pre-Bid Conference Date Time	Not Applicable
Advertised Value	22601129.33	Tendering Section	SIG/NORTH
Bidding Style	Single Rate for Each Schedule	Bidding Unit	
Earnest Money (Rs.)	452000.00	Validity of Offer (Days)	60
Tender Doc. Cost (Rs.)	0.00	Period of Completion	6 Months
Contract Type	Works - General	Contract Category	Expenditure
Bidding Start Date	01/06/2026		
Are JV allowed to bid	No	Number of JV Member Allowed	0
Are Consortium allowed to bid	No	Number of Consortium Member Allowed	0
Ranking Order For Bids	Lowest to Highest	Expenditure Type	Capital (Works)

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A-Supply and Execution Portion							17663000.25	Above/ Below/P ar
1	Please see Item Breakup for details.				3157254.49	AT Par	3157254.49	
	Description:- VDU & Data logger							
2	Please see Item Breakup for details.				1453145.75	AT Par	1453145.75	
	Description:- Signal							
3	Please see Item Breakup for details.				990030.00	AT Par	990030.00	
	Description:- Point							
4	Please see Item Breakup for details.				39022.30	AT Par	39022.30	
	Description:- Track Circuit							
5	Please see Item Breakup for details.				6027093.36	AT Par	6027093.36	
	Description:- Relays Indoor and Outdoor Works							
6	Please see Item Breakup for details.				1610281.00	AT Par	1610281.00	
	Description:- Location Box							
7	Please see Item Breakup for details.				3038654.26	AT Par	3038654.26	
	Description:- Supply Execution Laying of Cable & Associated Works							
8	Please see Item Breakup for details.				1347519.09	AT Par	1347519.09	
	Description:- Testing and Measuring Equipments							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () B-MSDAC-Supply and Execution Portion							4938129.08	Above/ Below/P ar

**MUMBAI CENTRAL DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SG_216_2_114_WA_ST_R1

Closing Date/Time: 15/06/2026 15:00

1	1	8.00	Per Detection Point (DP)	314195.71	2513565.68	AT Par	2513565.68	
	Description:- Supply of Multi Section Digital Axle Counter (MSDAC) for mentioned detection Point by the purchased & track Section as per SIP, complete with all accessories, cable required with each track device & card viz. Axle detectors, Track Side Electronics/DAC field units, Central Evaluator (Central Evaluator unit should be housed in a pre-fabricated rack to be supplied along with the system), reset unit, Relay unit, Event Logger & Diagnostic terminals, etc. Required for different Detection Points & Track Sections as per RDSO Specifications No. RDSO/SPN/176/2013, Ver.3 or latest and OEM/manufacturer's specification and as per Annexures. (Quantity 01 No. = 01 DP) Inspection Authority: RDSO. The proposed MSDAC system should be similar to the existing MSDAC system installed in the section. Approval of the railway authority should be obtained before supply of the system.							
2	2	8.00	Per Detection Point (DP)	15648.00	125184.00	AT Par	125184.00	
	Description:- Installation of track device (double rail contact) including digging of trench, track crossing, laying of anti-rodent, anti-oxidant & non-flame propagating type Double Walled Corrugated (DWC) pipe as per IS- 14930 part- I or II or latest and all other accessories as per site requirement to be for laying of transmitter and receiver cable. The item also includes installation of EJB / Track side Electronics including foundation & earthing as per OEM's guidelines and Technical requirement & specification with their own material. NOTE: Installation / programming / configuration / commissioning of Axle counter equipment to be carried out in accordance with latest guidelines issued by Railways/RDSO preferably by Authorized representative of OEM.							
3	3	1.00	Numbers	11984.00	11984.00	AT Par	11984.00	
	Description:- Installation of Central Evaluator of axle Counter, wiring from CT rack to Central Evaluator, installation and wiring of the reset box, LV box (if required) and associated power supply wiring. This includes supply of shielded cable of required conductor size for wiring between CT rack to evaluator rack, all other wires, power supply cable and wiring materials. The power supply cable from power room to Central Evaluator should not be less than 10 sq.mm PVC wire. Earthing as per OEM's guidelines & specification with their own material. This also includes painting and writing work on evaluator as per site requirement. NOTE: Installation /programming / configuration / commissioning of Axle counter equipment to be carried out in accordance with latest guidelines issued by Railways/ RDSO preferably by Authorised representative of OEM.							
4	4	20.00	Numbers	99497.60	1989952.00	AT Par	1989952.00	
	Description:- Supply of OFC Modem 1200 Baud rate suitable for MSDAC as per Engineer in-charge as per site requirement.							
5	5	25.00	Numbers	1838.44	45961.00	AT Par	45961.00	
	Description:- Reduction plate 60 kg 1 1470 for suitable MSDAC as per Engineer in-charge as per site requirement.							
6	6	25.00	Numbers	875.56	21889.00	AT Par	21889.00	
	Description:- L- Sensor Clamp for suitable MSDAC as per Engineer in-charge as per site requirement.							
7	7	25.00	Numbers	3422.00	85550.00	AT Par	85550.00	
	Description:- Deflector plate for suitable MSDAC as per Engineer in-charge as per site requirement.							
8	8	1.00	Set	144043.40	144043.40	AT Par	144043.40	
	Description:- Supply of Tools Kit for Digital Axle Counter (Multi section/Single section). (MSDAC comply to the RDSO spec.No. RDSO/SPN/176/2013/Ver.3 or latest and manufacturer's specification and SSDAC comply to the RDSO/SPN/177/2012,Ver.3 or latest respectively). The tool kit shall be minimum equipped with the following equipments: (i) All mechanical tools shall be of reputed make like Taparia/Bosch etc. (ii) Digital multimeter true RMS type of make Fluke 189 or similar reputed make with probe set - 1 No. (iii) Adjustable torque wrenches 25-135 N/mtr with 13 mm and 19 mm inserts- 1 set (iv) Set of spanners screw drivers and soldering iron - 1 set (v) Dummy wheel - 1 No. (vi) Marking Jig - 1 No. (vii) Adapter card - 1 No. (viii) Extended wired socket to interface with diag No. stic plug - 1 No. (viii) Selector switch on panel base - 1 No. (ix) DAC EC card puller etc.							

3. ITEM BREAKUP

Schedule		Schedule A-Supply and Execution Portion					
Item- 1		VDU & Data logger					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount	

**MUMBAI CENTRAL DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SG_216_2_114_WA_ST_R1

Closing Date/Time: 15/06/2026 15:00

1	1	Supply, Installation and Commissioning of EI VDU (Visual Display Unit, 4K with all suitable accessories Compatible to EI Interlocking in Safe Mode 24x7 at controlling station. The item must comply minimum following specification:- a) Screen Size (Diagonal):- As below b) Resolution :- 4K c) Viewing angle degree: - 178x178 degree d) Brightness :- 500 Nits e) contrast ratio 4000:1 f) Backlit :- Direct LED g) Jack Interface: - HDMI -3 no. 1.2 DP, DVI USB 2.0 -2 no. CI Slot RF In AV In Component In (RCA5 Type) Digital Audio Out RGB In (D-sub 15pin)-PC PC Audio Input RS232C (D-Sub 9pin) RJ45 Stereo mini jack. h) Optical Out :- Available Note: - Screen size will be decided as per instruction of engineer incharge. Approximate Screen size 65 inch	Numbers	4.00	124250.00	497000.00
2	2	Supply and Installation of Modular power supply arrangement for VDU and industrial PC (Embedded PC) with input and output redundancy arrangement and Hot pluggable Modules as per RDSO specification. Make Gallant or similar. One set consists of 1. Input O- ring diode module with potential free -1 No contacts (PFC) for two 110 VDC sources from IPS and single 110 VDC bus Qty 1 No. 2. Isolated Inverters (Master / slave) - Input-110 V DC Output: 120 V AC/220V A500VA - 02 Nos. 3. Isolated DC-DC converters- Input : 110 vDC Output : 24 V DC/ 10A, Qty -10 Nos. 4.3 U SS rack with back panel mother board / front panel power connectors inverter auto change over switch and all required over switch and all required protection circuits (3U height for main rack 132.5mm +/-10% & 1U height for mounting 44.5mm +/- 10%) Qty - 1 No. Make Gallant or similar.	Numbers	4.00	272862.00	1091448.00
3	3	Supply & installation of Industrial Grade Embedded PC as per RDSO TAN no. STS/E/TAN/3007 dated 2.11.12 or latest.	Numbers	4.00	179360.00	717440.00
4	4	Portable workstation for Data input & configuration with necessary software/ programs / Accessories, simulation and functional testing, diagnostics, and troubleshooting and commissioning of EI system. A suitable table and chair of a reputed make shall be supplied by the contractor. Note: The specification of the portable workstation shall be as per the Technical specification given in Annexure or higher version as approved by Engineer In-Charge. All the required software should be uploaded. Licensed CD should be given along with the software.	Set	1.00	147350.87	147350.87

**MUMBAI CENTRAL DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SG_216_2_114_WA_ST_R1

Closing Date/Time: 15/06/2026 15:00

5	5	Earthing of EI equipment, relay racks and Power equipment etc. to be done along with the supply of all requisite materials. Earthing shall be in the form of Ring Earth conforming to RDSO specification No.RDSO/SPN/197/2008 (with a min. of 8 maintenance free earth electrodes) & RDSO Drawing issued under Railway Boardletter No. 2010/Sig./SGF/EI (Ansaldo) Dated 22.06.11, made using copper rings with earth resistance less than 1 ohm. The earthing shall be maintenance free & earth enhancement compound should be used. The ring earth shall be connected to copper flat of size 25x3 mm in the relay room and IPS room. This copper flat shall be fixed on the wall to the entire breadth of the Relay room and IPS room as an earth bus bar and all earth connections shall be taken from it. A, B, C, & D class protection shall be provided for all EI equipment. Note: - This will also cover the earthing & necessary protection of EI equipment as per details given in the scope of work of Special Condition of Contract and other requirement given in Chapter of tender document & Pre-commissioning check list of EI system.	Job	1.00	133269.46	133269.46
6	6	Diagnostic Terminal : Multisection Portable operator console for on site programming of Axle Counters as per technical requirement.	Numbers	6.00	91401.00	548406.00
7	7	Supply of 12V, 40 AH VRLA batteries as per specification IRS:S 93/96 with amendment 1.	Numbers	6.00	3723.36	22340.16
					Total	3157254.49
Item- 2 Signal						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Main Signal Post Tubular 140 mm Dia, 5.6 Mtr Length as per IRS: S-6/81 or Latest & RDSO Drg. No. SA-24625 (Advance). (ALL MS PARTS HOT DIP GALVANIZED -100 MICRON)	Numbers	20.00	21240.00	424800.00
2	2	CI Base (As per IRS S-10 & RDSO Drg. No. 2011/M With latest assembly). 2. Pinnacle. 3. Ladder Assembly, as per RDSO Drg. No. SA- 23156, with Base, Ladder Guards, Platform, Front Maintenance Platform, MS Supporting Bracket to Support Ladder. 4. Signal Front Staging Complete Assembly for CLS Unit. 5. Signal back staging as per extent WR Practice (ALL MS PARTS HOT DIP GALVANIZED -100 MICRON).	Set	5.00	3251.33	16256.65
3	3	Fabrication and fixing of Signal Number Plate (CSTE Drg No CSTE/6186) All material required for this work shall be supplied by Contractor. Material used for number plate should be comply to the specification ETI/OHE/33A (12/97) Rev-8. CSTE drawing to be followed for dimensions only.	Numbers	25.00	615.59	15389.75
4	4	2 Aspect LED Signal Housing made of SS-304 (Min 1.6mm thick) duly powder coated in black, with background plates, prewiring for LED Signals, Terminal strip, Reflective strips on rear side, ventilation and Pole Mounting & locking attachment, suitable for RE area. The design shall conform to IP-54 as per unit description as Width 260mm, Depth 200mm, Height 650mm as per Drawing No.- DRM/SG/1021 (2A) of STAINLESS STEEL (SS-304) 2 ASPECT COLOR LIGHT LED SIGNAL UNIT	Numbers	5.00	28577.72	142888.60

**MUMBAI CENTRAL DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SG_216_2_114_WA_ST_R1

Closing Date/Time: 15/06/2026 15:00

5	5	3 Aspect LED Signal Housing made of SS-304 (Min 1.6 mm thick) duly powder coated in black, with background plates, prewiring for LED Signals, Terminal strip, Reflective strips on rear side, ventilation and Pole Mounting & locking attachment, suitable for RE area. The design shall confirm to IP-54 as per unit description as Width 260mm, Depth 200mm, Height 875mm as per Drawing No.- DRM/SG/1021 (3A) of STAINLESS STEEL (SS-304) 3 ASPECT COLOR LIGHT LED SIGNAL UNIT	Numbers	5.00	29823.91	149119.55
6	6	4 Aspect LED Signal Housing made of SS-304 (Min 1.6 mm thick) duly powder coated in black, with background plates, prewiring for LED Signals, Terminal strip, Reflective strips on rear side, ventilation, Pole Mounting & locking attachment, suitable for RE area . The design shall confirm to IP-54 as per unit description as Width 260mm, Depth 200mm, Height 1100mm as per Drawing No.- DRM/SG/1021 (4A) of STAINLESS STEEL (SS-304) 4 ASPECT COLOR LIGHT LED SIGNAL UNIT	Numbers	15.00	33303.86	499557.90
7	7	Excavation and Casting of foundation for main signal post as per CSTE/3122 (WR) with contractor's own materials including cement and anchor bolts of standard size. The required scaffolding Ferma etc. for Casting of foundation will have to be brought by the contractor at his own cost.	Numbers	2.00	12887.18	25774.36
8	8	Erection of CLS Post with base and signal unit on top or on OFF set Bracket, fixing of front and back staging, ladder and guards with contractor's own brackets and fixing materials. This also includes erection of auxiliary signals like calling on, shunt signal if any... The work shall be done as per instructions of Rly engineer at site. It also includes provision & fixing of maintenance platform as per design given by Engineer -In-Charge at site. It also includes supply of padlock for signal units and cable termination box. X' arms to be provided by the contractor till the signals are introduced. The Item includes cutting of Signal post if required by Site In charge. 2/3/4 aspect signal unit mounted directly on signal post.	Numbers	2.00	8338.74	16677.48
9	9	Erection of CLS Post with base and signal unit on top or on OFF set Bracket, fixing of front and back staging, ladder and guards, signal name plates / boards if any with contractor's own brackets and fixing materials. This also includes erection of auxiliary signals like calling on, shunt signal if any. The work shall be done as per instructions of Rly engineer at site. It also includes provision & fixing of maintenance platform as per design given by Engineer -In-Charge at site. It also includes supply of padlock for signal units and cable termination box. X' arms to be provided by the contractor till the signals are introduced. The Item includes cutting of Signal post if required by Site In charge. 2/3/4 aspect signal unit mounted on offset bracket with junction type route indicator 1/2/3 or multilamp lamp route indicators mounted on signal post.	Numbers	2.00	3059.68	6119.36
10	10	Supply of Multi lamp numeric indicator (LED Single/double digit) as per engineer in charge.	Numbers	2.00	62662.54	125325.08

**MUMBAI CENTRAL DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SG_216_2_114_WA_ST_R1

Closing Date/Time: 15/06/2026 15:00

11	11	Supply & Fixing of Protective screen of expanded metal 12SWG of Size 1200 X 1500 mm on Signaling as per standard practice for protecting against voltage in AC Traction area as per instruction of Engineer Incharge.	Numbers	2.00	4520.31	9040.62
12	12	Offset brackets for Main Signal, made of tubular steel, outer diameter 140 mm, thickness of pipe 4.5 mm. horizontal length of pipe 545 mm & vertical length of pipe 324 mm with fixing arrangement on Main Signal post as per Drawing No SW/554/G/R. (ALL MS PARTS HOT DIP GALVANIZED -100 MICRON)	Numbers	5.00	4439.28	22196.40
					Total	1453145.75
Item- 3 Point						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Point insulation Complete set as per RDSO Specification IRS: S-40/84 for Switch bracket, Split-Stretcher bar & Gauge tie plates (52Kg/60Kg as per site requirement)	Numbers	20.00	1345.93	26918.60
2	2	Supply of Point Motor for 110VDC with 400v AC immunity as per IRS S:37/82.	Numbers	15.00	18882.68	283240.20
3	3	Refixing of electrical point machine, ground connection during phase working (No interlocked working) after removing the existing fitting if any, adjustment if necessary, cable termination, wiring ,testing and commissioning of electrically operated point, fixing and connecting point indicator on derail switch if necessary. The work shall be done as per extant practice onWR & the instruction of Railway Engineer at site.	Turn-out	20.00	3120.46	62409.20
4	4	Contractor Unit Assly CU Base Assly 851241034-S, RDSO Drg.No. RDSO/S 10911, CG Drg.No.CHS-10911.	Numbers	20.00	12155.42	243108.40
5	5	Transparent cover sub assembly complete with Cover support LH RH, 853087001-S as per RDSO, approved CG drg. No. CSQ-10920 10915.	Numbers	20.00	368.16	7363.20
6	6	Terminal Bank Assembly complete, 855032009-S as per RDSO, approved CG Drg.No. CPME-1124.	Numbers	20.00	1963.52	39270.40
7	7	Waterproof Galvanized MAIN COVER ASSEMBLY complete spare for POINT Machine comprising of Main cover, CRANK HANDLE HOLE SUB. ASSY, KEY HOLE LOCK SUB.ASSY, DOOR LOCK, RUBBER GASKET of MAIN COVER ASSY, Rubber GASKET (C.H. HOLE LOCK ASSY.), CRANK HANDLE HOLE LOCK BASE, CRANK HANDLE HOLE LOCK LID, PIN (for C.H. HOLE LOCK S/A), RUBBER GASKET (C.H. HOLE LOCK ASSY. LOCKING CAM, KEY code 856051010-s along with Fixing material to trap accumulated air as per Drg no R-ST- 12161, modification in cover as per consignee requirement. Thickness of cover material:-2mm, galvanizing and power coating shall be done on cover. (Inspection Agency-RITIES/Consignee)	Set	20.00	14586.00	291720.00
8	8	Supply of Bend pipe for point machine or as per Engineer in-charge as per site requirement.	Numbers	20.00	600.00	12000.00
9	9	Wiring tree for point machine,as per instructions of Engineer Incharge ,as per site requirement.	Numbers	20.00	1200.00	24000.00
					Total	990030.00
Item- 4 Track Circuit						

**MUMBAI CENTRAL DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SG_216_2_114_WA_ST_R1

Closing Date/Time: 15/06/2026 15:00

S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Charging of Lead Acid Batteries (2V 80AH) with contractors' own battery grade sulphuric acid and distilled water with a minimum of two charge-discharge cycles, installation of charged batteries in groups & their connection & wiring. The work shall be done as per the extant practice of W.Rly & instruction of the Engineer-in-charge. Detailed measurements of initial charging shall be recorded jointly by the contractor & Rly's site-in-charge.	Numbers	100.00	376.10	37610.00
2	2	Hydrometer, Exide make or similar for measuring the specific gravity of Battery Graded acid with mounting stand in location Boxes.	Numbers	5.00	282.46	1412.30
					Total	39022.30
Item- 5	Relays Indoor and Outdoor Works					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Miniature, Plug-in Type, DC Neutral Line AC Immunized Relay, Style QNA1, 24 V DC, 8F-8B/12F-4BContact, Code ABDGH/ABDFH Spec: BRS: 931A; IRS S 34; IRS S 23; IRS S 60-78.	Numbers	30.00	5576.04	167281.20
2	2	Supply of QNNA1, AC immunized relay 24V DC, 4F-4B/6F-2B contacts, along with plug board, retainingclip and connectors. Conforming to BRS: 960, IRS: S60, IRS: S34 & IRS: S23. (No of each configuration will be decidedby Engineer In-charge).	Numbers	10.00	6039.60	60396.00
3	3	Miniature, Plug-in Type, DC Neutral Line Magnetically Latched Relay, Style QL1, 24 V DC, 11F-4BContact, Code ABDEG Spec: BRS:935A ; IRSS 34 ; IRS S 23.	Numbers	30.00	7390.44	221713.20
4	4	Plug in Type,Tractive Armature, ACImmunized, DC Biased Contactor Relay, Style QBCA1,2HF-4BContact,24 V DC, Code BCEJK Spec:BRS:943 ; IRS S 34 ; IRS S 23 ;IRSS 60-78.	Numbers	20.00	7393.68	147873.60
5	5	Miniature, Plug in Type, M to C,DC Neutral ,Track relay, ACI, Style QTA2, 9 Ohm, 2F-1B contact,Code -FGHKX Spec : BRS :939-A & 966 (Appx-F2) & IRS : S-23, S-23,S-34 & 60	Set	5.00	4878.90	24394.50
6	6	Miniature,Plug in type, M to C,AC immunized, DC biased Track Relay, 2F-2B contacts, style QBAT-9 ohms.Code ABEJX Spec:- RDSO/SPN/84 Ver. 2 : IRS -S@ 45"44@IRS-S-23, IRS-S@ 45<45@ 78.	Numbers	5.00	5393.68	26968.40
7	7	Supplying & fixing of key box made of MS sheet/ wood with a glass front and padlocking and sealingarrangements per std practice. Pad lock to be supplied by the contractor. All material i.e. wood, handle, hinges, glasssheet of 3 mm thick to be supplied by the contractor. Box to be powder coated/polished and description/size to be asper instructions of Engineer in - charge.	Set	2.00	1392.83	2785.66
8	8	Supply of self supported aluminum flat step ladder (conforming to ISI) 5 ft. height. Ladder should beself-supported and it should be made up of rust proof Aluminum of Min 16 SWG. No plastic hinges/Step support shouldbe used.	Numbers	2.00	3089.90	6179.80
9	9	Supply of HRC fuses block complete with 2A fuse link as per IS 9224/79.	Numbers	150.00	70.56	10584.00
10	10	Supply of PPTC fuse 12V GP 16-400 (2A)for TF/TR circuit, make Raychem, Epcos, Siemens.	Numbers	1000.00	10.42	10420.00

**MUMBAI CENTRAL DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SG_216_2_114_WA_ST_R1

Closing Date/Time: 15/06/2026 15:00

11	11	Supply of Round head type non deteriorating type low voltage cartridge fuse as per Spec No IRS/S/78/92with latest amendments 2A/4A/6A capacity.	Numbers	10.00	57.21	572.10
12	12	Disconnect Terminal Block, Screw less type, 4-wire front entry (Two in-put & Two out-put) The color willbe decided by Engineer - in - Charge. (Preferably In Blue, Red & Grey Colors in the ratio of 1:2:3). as per RDSO Spec.No. RDSO/SPN/189/2004. With latest amendments. Note: Make to be approved by Railway before supply.	Numbers	2500.00	58.53	146325.00
13	13	Supply of End plate 2.5mm/0.091 in thick as per site requirement.	Numbers	250.00	11.07	2767.50
14	14	Supply of End Stopper 10mm/0.0394 in width as per site requirement.	Numbers	500.00	10.86	5430.00
15	15	Supply of Carrier Rails for above 35mm x 7.5mm, 1mm/0.039 in thickness un-slotted type as per siterequirement	Numbers	20.00	113.88	2277.60
16	16	Supply of 4 connection points single potential through screw less terminal block for 6 Sq.mm - 35 Sq.mm, 4 connection points 284-621/624 or superior, suitable for power cable connection.	Numbers	50.00	270.84	13542.00
17	17	Pad locks Godrej make, Hardened NavTal 7 lever, 65mm Dia with common key or similar product havingsame feature & technical data.	Numbers	100.00	196.79	19679.00
18	18	Miniature 'E' type lock complete with keys as per RDSO Drg. No. SA 3473, 3373 & spec. IRS(S) 30/64.Ward to be specified by Engineer - in - charge.	Numbers	100.00	2081.52	208152.00
19	19	Maintenance Free Earth Electrode of length 3m, including supply of 3 bags of Earth enhancementmaterial for earthling (10KGs/bag) for each electrode & other accessories as per Drg. No. SDO / RDSO/ E&B/001 andRDSO Spec No. RDSO / SPN/197/2008. This item includes the following items: (a) Copper bonded steel earth electrodeof 3.0 meter long & 17.2 mm dia with Cu-bonding thickness of min 250 micron - 1 no. (b) Earth-enhancing compound(10 Kg/Bag) - 3 No. (c) Cu-strip 200 X 25 X 6 mm to terminate earth rod = 1no. (d) Cu-strip 300 X 25 X 6 mm (MEEB)= 1 no. (e) Cu-strip 150 X 25 X 6 mm (SEEB) = 1 no. (Inspection by RDSO)	Numbers	20.00	10403.08	208061.60
20	20	Installation of Maintenance Free Earth Electrode for Maintenance Free Earth spec ofRDSO/SPN/197/2008.	Numbers	20.00	1456.79	29135.80
21	21	Supply of Fiber/ SMC/FRP/RCCEarth Chamber as perinstructions of Engineer Incharge as per siterequirementas per STS/E/TAN/3006 ver 3.0	Numbers	50.00	649.00	32450.00
22	22	ARA Terminal blocks with links made of PBT Spec No.s/75/2006 (Rev - 2) with latest amendments andRDSO Drg.No.SA-23741A Alt.4.	Numbers	500.00	75.00	37500.00
23	23	Fixing of ARA Terminals /Screw less connectors and fuse blocks on phenolic laminated sheets and fixingby stainless steel/brass nuts & bolts. This includes provision of two additional holes on the board on either side for cableconductor entry.	Numbers	1000.00	22.75	22750.00

**MUMBAI CENTRAL DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SG_216_2_114_WA_ST_R1

Closing Date/Time: 15/06/2026 15:00

24	24	Termination of outdoor cables, main cables laid in location boxes, Cable termination rack etc. at bothends on ARA terminal or on 8 way terminals or on screw less connectors. Both ends of a cable core terminated shall becounted as one terminal. This includes all associated works of pulling out the cable from underground, peeling offinsulation, dressing of cable core supported on sting rod with contractor's own material. The work shall be done as perinstructions of Rly engineer at site.	Numbers	1000.00	23.70	23700.00
25	25	Lettering & Numbering of detail and description writing of on relay rack, relays, cable termination rack,battery &power equipments, IPS,operating panel, axle counter etc.constituting entire system with contractor's ownpaint and writing material. The work shall be done as per extant practice on W.R Rly & instruction of Rlyengineer at site.	Station	7.00	3768.86	26382.02
26	26	Providing brick masonry in ratio 1:6 cement and mortar including plastering with 1:4 cement and sandmixture both sides, 20 mm thick each with contractor's owned class II bricks, including excavation, curing, grouting,bolting etc. wherever required. Bricks sand and cement to be supplied by the contractor.	cum	5.00	2061.36	10306.80
27	27	Cement concrete work for miscellaneous items in the ratio 1: 3: 6. Item includes excavation, ramming,curing and plastering with cement & sand mixture (aggregate not exceeding 3.8 cm.) (Aggregate cement & sand to besupplied by the contractor).	cum	10.00	6259.00	62590.00
28	28	Dismantling / Releasing of existing Signaling Gears. One Signalling gear will be all parts of one signal(consisting of CLS unit, Signal post along with base) or lever frame (5 levers set), or one point (consisting of all parts of a mechanical point, point machine, ground connections etc.) or one track circuits (consisting of battery box & otherparts of DC Track circuit / AFTC /DAC) or one Block instruments or One Lifting Barrier or One Location Box etc. .Thisincludes the cost of transportation of release materials to store depot or as decided by consignee in charge. This workto be done by contactors with his own vehicle and labour. (Per unit means Per Gear).	Per Unit	20.00	1062.82	21256.40
29	29	Transportation of S&T material leading up to 1 Km including Loading from Starting point, unloading &Stacking at destination.	MT	50.00	452.58	22629.00
30	30	Extra for each additional 1 Km or part thereof.	Kilometre	24950.00	4.10	102295.00
31	31	As and when required by the Engineer in charge arranging /providing of labors for various safety relatedworks such as protection of track etc. with contractor's T&P, equipment,hand signal flags, spanners,hammers, etc. asper specification special conditionsand detailed scope of work as furnished in the tender and directed by the engineerincharge.	Man-Days	600.00	649.71	389826.00

**MUMBAI CENTRAL DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SG_216_2_114_WA_ST_R1

Closing Date/Time: 15/06/2026 15:00

32	32	Skilled man power to be provided by contractor for Engg. JCBs working to provide marking & supervisory work for the S&T cables during digging work by JCB's and repairing /restoring/jointing of cables, if damaged Cables & Joints Material will be provided by railway. While Chuna marking will be done by his/her Chuna will provided by contractor information for deputing skilled man power for above work will be provided by Railway Engineer in charge before 24 hours from commencement of digging by JCBs. They will check cables route by Cable route tracer and will do chuna marking and will show the cables (on rough sketch) available in a small length approximate 50-100 meters of digging. Note: Minimum two man will be provided at a time including Cable jointer, they will stay whole time during JCB digging work. (The CV to be got approved by Railway).	Man-Days	600.00	707.28	424368.00
33	33	Providing assistance to ESMS/TCM during monitoring Inspection & supervision of signal gears throughout the period as per of instructions of SSE(Sig) In-charge during day/night upto eight hours per day.	Man-Days	3000.00	489.02	1467060.00
34	34	Steel Plain Almirah with 4 adjustable slaves Size: 1980mm height, 915 mm width and 485 mm depth. Make: Godrej Storewel Plain Large or Similar of reputed brand will be specified by Engineer in-charge.	Numbers	5.00	17036.67	85183.35
35	35	Office Chair makes Godrej CH-7B or similar of reputed brand will be specified by Engineer in-charge.	Numbers	30.00	2655.97	79679.10
36	36	Office Revolving Chair Godrej Make Model No.9u02r Bravo Or Similar of reputed brand will be specified by Engineer in-charge.	Numbers	12.00	8188.30	98259.60
37	37	Office table with laminated top with three drawers on left hand side and one locker on the right hand side. Olive brown with duplicate keys. Make: Godrej Model T-9 or Similar of reputed brand will be specified by Engineer in-charge.	Numbers	12.00	16052.54	192630.48
38	38	Supply of SS 304 Troughing with cover of size 150x300x 2.5 mtrs. long and 1.0 mm Thk. Along with fixing clamp and necessary Hardware.	Metre	100.00	4318.80	431880.00
39	39	Supply and Installation of White Zink plated MS channel of size 100x50x1.2mtr.long along with fixing Hardware.	Numbers	100.00	1687.40	168740.00
40	40	Releasing of Old channel & Troughing & Installation of SS Troughing with cover on bridge.	Metre	100.00	649.00	64900.00
41	41	Supply of BIS(15683:2018) Listed Semi Automatic Stainless Steel Fire Extinguisher with UL approved clean gas with Auto Manual Reverse Stainless Steel Valve having Capacity 4 Kgs and made of stainless Steel 304 Grade Cylinder Pressure 14 bar, Range 3-4 , meters valve body Pressure Die-casted SS-304, Unique valve with a leak-proof design, delivery method nozzle with flexible hose pipe , UL listed HFC-236fa clean Gas shelf life with 10 Years Warranty for leakage. Note- Tender specific authorization, warranty of OEM , Test certificate of any NABL approval LAB for Clean Gas and BIS(15383:2018) Listed certificate along with offer / Tender. (Warranty Period : Upto 120 months from the date of supply) Inspection by Consignee.	Numbers	20.00	38586.00	771720.00

**MUMBAI CENTRAL DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SG_216_2_114_WA_ST_R1

Closing Date/Time: 15/06/2026 15:00

42	42	Hot dip Galvanizing as per RDSO Specn. ETI-OHE-13	Kg	300.00	53.05	15915.00
43	43	2-conductor fuse terminal block; with pivoting fuse holder; for 5 x 20 mm miniature metric fuse; with blown fuse indication by LED; 30 - 65 V; for DIN-rail 35 x 15 and 35 x 7.5; 4 mm ² ; CAGE CLAMP; 4,00 mm ² ; gray (Without Fuse)	Numbers	50.00	205.32	10266.00
44	44	Supply of multistrand single core PVC insulated copper cable as per IS:694 of size 35 Sq mm.	Metre	200.00	377.60	75520.00
45	45	Rubber Mat for Power Equipment room. (5mm thick).	Kg	515.00	121.63	62639.45
46	46	Dismantling of Concrete foundation/ Demolishing RCC/CC/Stone work /Cutting Tar/ carpentering/ CC Flooring/Precast concrete slab/ Brick work including leading the debris inside Railway limit or outside Railway limit as directed by site in charge. This work to be done by contactors with his own vehicle and labour.	cum	20.00	605.41	12108.20
					Total	6027093.36
Item- 6 Location Box						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	SS Location box made of Spl Grade SS 304 of size as per drg.No.DRM/SG/948 (Single app. Case). The manufacturer's certificate in regard to grade of stainless steel and test report be submitted at the time of supply. Note:- (1) Enclosure should be made of 1.6 mm & door made of 2 mm thick SS 304 sheet. (2) SS 20 mm (rod) X 100 mm (height) male female hinges for moving door smoothly. (3) SS 16 mm Rod fix handle for both the door. (4) SS sheet stiffener (0.8 to 1 mm thickness) to strengthen the door both side. (5) SS hook (6 mm rod) to be provided on both doors for keeping the door open position. Stoppers to be provided for both doors. (6) E-type locking arrangement (W11) for both door and lifting hook (5X150 mm) 02 Nos (7) SS sheet 450mm x 650 mm for full location box provision of any writing work at front side door etc. (8) Provision of switch board for location light fitted with one two pin holder, One three pin socket (female) and two piano type switches of 6A for location boxes with internal wiring 2.5 sq.mm flexible copper wires, Holders, socket and switch should be of ISI mark. (9) Indian Railway property tag is to be provided on two side with following details, Sr. No, Manufacturing firm name & year of Manufacturing. (10) White enamel paint shall be provided inside location box. (11) SS angle frame 30 mm x 30 mm x 5 mm is provided along with location box. (12) Earth GI clamp 5mm x 50 mm flat is providing to location at two ends to connection earth GI patti. (13) All hardware used in location box for mounting arrangements shall be of SS (nuts, bolts, washer etc). (14) Suitable location box Hylam fabrication to provide the clear space of writing to 18 cm to 20 cm (15) Packing each location box to be shipped using wrapping plastic sheet around location box.	Numbers	5.00	59855.98	299279.90

**MUMBAI CENTRAL DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SG_216_2_114_WA_ST_R1

Closing Date/Time: 15/06/2026 15:00

2	2	SS Location box is made of Spl Grade SS 304 of sizes as per drg. No.DRM/SG/945 (Half app.Case).The manufacturer's certificate in regard to grade of stainless steel and test report shall be submitted at the time of supply.Note:- (1)Enclosed should be made of 1.6mm & door made of 2mm thick SS 304 sheet.(2)SS 20 mm (rod) X 100mm(height) male female hinges for moving doors smoothly. (3)SS 16 mm Rod fix handle for both the door. (4)SS sheet stiffener(0.8 to 1 mm thickness) for strengthen the door both side. (5) SS hook (6 mm rod) to be provided on both doors for keeping the door open position. Stoppers to be provided for both doors.(6)E-type locking arrangement (W11) for both door and lifting hook(5X150 mm) 02 Nos (7)SS sheet 250 mm x 450mm for half location box provision of any writing work at front side door etc. (8) Provision of switch board for location light fitted with one two pin holder, One three pin socket (female) and two piano type switches of 6A for location boxes with internal wiring 2.5 sq.mm flexible copper wires, Holders, socket and switch should be of ISI mark. (9)Indian Railway property tag is provided on two side with following details, Sr. No, Manufacturing firm name & year of Manufacturing.(10)White enamel paint shall be provided inside location box. (11)SS angle frame 30 mm x 30mm x 5 mm is provided along with location box.(12)Earth GI clamp 5mm x 50 mm flat is provided to location at two ends to connection earth GI patti.(13)All hardware used in location box for mounting arrangements shall be of SS (nuts, bolts, washers etc). (14)Suitable location box Hylam fabrication to provide the clear space of writing to 18 cm to 20cm. (15) Packing each location box to be shipped using wrapping plastic sheet around location box.	Numbers	16.00	51998.06	831968.96
3	3	Excavation and Casting of Apparatus Case foundation with contractor's own materials including cement and anchor bolts of standard size. The required scaffolding Ferma etc. for Casting of foundation will have to be brought by the contractor at his own cost. Single Case as per Drg No SK 748 or CSTE/5074 or SS Location	Numbers	5.00	7162.63	35813.15
4	4	Excavation and Casting of Apparatus Case foundation with contractor's own materials including cement and anchor bolts of standard size. The required scaffolding Ferma etc. for Casting of foundation will have to be brought by the contractor at his own cost. Half Case as per Drg No SK 747 or CSTE/5074 or SS Location.	Numbers	16.00	5487.86	87805.76
5	5	Installation of Apparatus Cases with miniature 'E' type lock on CC foundation. This includes filling of location foundations with river bed sand and plastering on top of the sand. 'E' Type lock will be provided by Railway. Single Case	Numbers	5.00	1076.29	5381.45
6	6	Installation of Apparatus Cases with miniature 'E' type lock on CC foundation. This includes filling of location foundations with river bed sand and plastering on top of the sand. 'E' Type lock will be provided by Railway. Half Case	Numbers	16.00	657.15	10514.40

**MUMBAI CENTRAL DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SG_216_2_114_WA_ST_R1

Closing Date/Time: 15/06/2026 15:00

7	7	IS 13410: Glass Reinforced Polyester Sheet Moulding Compounds (SMC) Size of Sheet : 1000x1000x8.	Numbers	21.00	5388.67	113162.07
8	8	Fabrication and fixing of SMC sheet in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated string rods at the back side for cable support with contractor's own materials. The work shall be done as per Drg and arrangement similar to SK 783-1/2. With latest alterations & as per instructions of Rly engineer at site. Note: SMC sheet will be taken in place of phenolic laminated sheet. Single Case	Numbers	5.00	2445.36	12226.80
9	9	Fabrication and fixing of SMC sheet in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated string rods at the back side for cable support with contractor's own materials. The work shall be done as per Drg and arrangement similar to SK 783-1/2. With latest alterations & as per instructions of Rly engineer at site. Note: SMC sheet will be taken in place of phenolic laminated sheet. Half Case	Numbers	16.00	777.78	12444.48
10	10	Preparation and fixing of location box board on 03 mm ACP sheet with size 12 x 18 size A3 for location box including pasting of printed/painted vinyl sheet and lamination (printing/painting of location detail on vinyl sheet covered in schedule item separately).	Numbers	21.00	239.73	5034.33
11	11	Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor's own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy paint will be supplied by Railways. NOTE: - The paint and primer should be from Asian Paints/ Nerolac / Dulux / Berger. The primer / enamel paints (Aluminum synthetic, black enamel, brilliant white and yellow) will be as per (IS 5660 of 1970) / (IS 2932 of 1974). Apparatus Case Full Size. (Outside & inside)	Numbers	5.00	276.86	1384.30
12	12	Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor's own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy paint will be supplied by Railways. NOTE: - The paint and primer should be from Asian Paints/ Nerolac / Dulux / Berger. The primer / enamel paints (Aluminum synthetic, black enamel, brilliant white and yellow) will be as per (IS 5660 of 1970) / (IS 2932 of 1974). Apparatus case Half Size. (Outside & inside)	Numbers	16.00	251.05	4016.80
13	13	Supply of Silane Siloxane Aliphatic urethane Resin blend solvent based high technology membrane radiant heat reflecting insulating thermal barrier coating white colour with a genuine product sticker when removed display "Void" on each container paint 20 litres as per RDSO guidelines. Make: CYPRUS or Similar. Inspection by consignee.	Litre	20.00	7800.46	156009.20

**MUMBAI CENTRAL DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SG_216_2_114_WA_ST_R1

Closing Date/Time: 15/06/2026 15:00

14	14	Application of Silane Siloxane Aliphatic urethane Resin blend solvent based high technology membraneradiant heat reflecting insulating thermal barrier coating white colour on Location boxes as instructed by railwayrepresentative at site	Litre	20.00	10.16	203.20
15	15	Lettering / Numbering Termination particulars, equipments names etc., legibly and neatly inside locationboxes. This includes supply of paints of Asian Paints/ Nerolac / Dulux / Berger make. Full Case.	Numbers	5.00	129.26	646.30
16	16	Lettering / Numbering Termination particulars, equipments names etc., legibly and neatly inside locationboxes. This includes supply of paints of Asian Paints/ Nerolac / Dulux / Berger make. Half Case.	Numbers	16.00	88.18	1410.88
17	17	Shifting of existing full location boxes coming in the alignment of new line. The work includes losing & removal of soil around location boxes by excavating soil around foundation, making of pit for shifting of location boxhorizontally opposite to railway track up to 0.5 to 1.0 mtr. This includes loosing of existing cable coils without anydamage. The excavated soil shall be back filled after shifting of Location Boxes. Location box shall be shifted by pushmethod with the help of jacks or by crane by contractors own expenditure under instructions of engineer in-charge atsite. The work may affect train working hence the work shall be done as per margin only or during traffic block only.	Numbers	6.00	4369.93	26219.58
18	18	Shifting of existing half location boxes coming in the alignment of new line. The work includes losing & removal of soil around location boxes by excavating soil around foundation, making of pit for shifting of location box horizontally opposite to railway This includes loosing of existing cable coils without any damage. The excavated soil shall be back filled after shifting of Location Boxes. Location box shall be shifted by push method with the help of jacks or by crane by contractors own expenditure under instructions of engineer in-charge at site. The work may affect train working hence the work shall be done as per margin only or during traffic block only.	Numbers	2.00	3379.72	6759.44
					Total	1610281.00

Item- 7 Supply Execution Laying of Cable & Associated Works						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Single core multi-strand wire 0.5 sq.mm. (16 conductor each dia. 0.2mm), as per IRS 76/89 (Amd3) or latest.	Kilometre	5.00	5548.54	27742.70
2	2	Flexible cable (Power wire), multi-strand copper conductors cross section 1x6 Sq.mm.(85 conductoreach diameter 0.30 +/- 0.01) as per IS 694/1990 with insulation thickness of 0.80 mm nominal conductor resistance3.30 ohms/km and test parameters are as per IRS(S)76/89 or latest	Kilometre	1.00	33366.21	33366.21
3	3	Flexible cable (Power wire), multi-strand copper conductors cross section (1x16Sq.mm).101 Conductorseach diameter 0.45 +/- 0.01 as per IS 694/2010 with insulation thickness of 1.2mm nominal conductor resistance1.127 Ohms/Km and test parameters as per IRS(S) 76/89 or latest.	Kilometre	1.00	136063.55	136063.55

**MUMBAI CENTRAL DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SG_216_2_114_WA_ST_R1

Closing Date/Time: 15/06/2026 15:00

4	4	Excavation of cable trench as per cable route plan, 1 Mtr. deep and of 0.3 Mtr. to 0.6 Mtr wide advised by Engineer-in-charge alongside the track in normal (all type) soil/strata, conforming to distances as per cable route plan and refilling. This work includes clearing of route from bushes etc., covering of cable laid in trench by loose soil for a layer of 50mm thickness approximately before covering by bricks. The work shall be done as per the extant practice on Western Railway and instructions of Railway Engineer at site. In case 1m depth of trench is not achievable due to site conditions, specific approval of JA grade officer will be required for each site where trench depth of 1m is not possible. Without the approval of JA Grade officer, no payment for trenching will be made for trench depth less than 1m.	cum	900.00	839.00	755100.00
5	5	Digging of trench 1.2 M deep from rail flange/road level and, 0.3 Mtr to 0.6 Mtr wide and back filling after placing of DWC/ RCC/GI pipe. (Placing of DWC/RCC/GI pipe covered separately). The ballast disturbed be screened and dressed as required by Engineer-in-charge or his representatives and road tarred immediately. For track crossing, Drg. No. CSTE/3644 Pg.7 of 11 and for Road Crossing, Drg. No. CSTE/3644 Pg. 5 of 11 are to be followed.	cum	100.00	873.93	87393.00
6	6	Digging of cable trench 0.3 Mtr. Deep and 0.3 Mtr. Wide on Asphalted Platform / Road / Hard rocky area. Refilling with earth leveling of trenches & restoring the original surface of trenches.	cum	20.00	512.76	10255.20
7	7	Providing chase in hard rocky soil for laying of S&T cables where optimum depth (0.5m) is not possible and which is verified and agreed by engineer-in-charge. After laying of cables, it should be covered with PCC work in ratio of 1:3:6.	Running Metre	10.00	468.16	4681.60
8	8	Horizontal direction drilling/boring without damage of surface road using Auger Machine. The bore shall be 150 mm Dia & shall be done at the depth of minimum 1200 mm from the ground level. The ground level shall be considered ignoring the bank height of the bank of the road. The length of the bore shall be minimum 4 Mtr long. The HDD with or without HDPE pipe as per direction of Engineer In charge. Note: HDPE pipe supply is taken as separate item. This item also includes cable laying (HDD boring).	Metre	500.00	1187.85	593925.00
9	9	High density polyethylene pipes (HDPE) of 110 mm/125 mm outer Dia, 10 mm wall thickness, along with one coupler for every 6 Mtr. As per spec. No. IS 4984:2016 with latest amendments and material grade: PE 80.	Metre	500.00	701.00	350500.00

**MUMBAI CENTRAL DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SG_216_2_114_WA_ST_R1

Closing Date/Time: 15/06/2026 15:00

10	10	Double Walled Corrugated(DWC) HDPE Pipe with associated collars etc. as per RDSO Specification No. RDSO/SPN/204/2011 or latest anti-rodent & anti-oxidant and non flame propagating type in 6 meters straight length and of size 120 mm outer dia. & 103.5mm inner dia. (The manufacturers, suppliers must produce valid IS license and should be certified under ISO 9000 and shall submit copy of certificate). One of the following coupling arrangements should also be supplied with each pipe as per the site requirement. 1) Suitable snap fit coupler with rubber 'O-Ring 2) Spacers 3) Tees 4) Bend, 5) End-cap (The total quantity of above items is equal to no. of pipes supplied.) DWC pipe shall be marked at every 1 mtr length in such a way that manufacturer's name, vendor name and year of manufacture can be easily identified.	Numbers	20.00	1912.20	38244.00
11	11	Placing of DWC/RCC pipes along with collars in trenches at places of track and road crossings, platform cuttings etc. also for straight cable laying. (Cable laying is covered separately.)	Running Metre	2500.00	33.22	83050.00
12	12	Laying of S&T Cables of various cores/ pairs/ quads in trenches/ GI pipes/ RCC pipes/ DWC pipes/ Trucking. This also includes laying of cables in track crossings & road crossings. Item includes provision of labels of colored plastic adhesive tapes or any other identifiable material on each cable to give the cable number at each G.P. (Cables will be tagged before and after its laying by contractor under supervision of Railway Representative and he will submit the meggering report of each testing). Length of the cable laid includes the length of the cable coiled for termination purposes.	Running Metre	10000.00	9.37	93700.00
13	13	Supply and installation of RCC cable route marker engraved and painted on both side along the route every 50mm and route diversion as per Drg. No 4014/00/CC4 or latest/ Stone marker.	Numbers	50.00	412.66	20633.00
14	14	Supply of Signalling Rapid Joint UV resistance cable jointing system with two half separated enclosure tapered at both ends filled with cross linked polymer and highly robust insulating plastic case class -2 joint. The joint shall be as per RDSO draft specs no. RDSO/SPN/TC/101/2012, the jointing kit suitable for signalling cable Size 6 x 1.5, 12 x 1.5, 19 x 1.5, 30 x 1.5 mm ² . Note: The joint made by rapid jointing kit for signalling cable will be temporary	Numbers	5.00	11200.00	56000.00
15	15	RCC pipes (Half round) of 150mm internal dia (1 meter long) along with collars as per IS No. 458/2003 of NP type. Tenderer shall submit inspection /test report before supply for prior approval by Engineer in charge. Inspection by RITES	Numbers	2500.00	172.00	430000.00

**MUMBAI CENTRAL DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SG_216_2_114_WA_ST_R1

Closing Date/Time: 15/06/2026 15:00

16	16	Transferring of Signaling/Telecom cables from existing Location box to New Location box . The workinclude breaking/ Dismantling of Existing foundation of locations, excavating and removing / segregating coils of2C/6C/12C/19C/24C/30C/Quad cables which may be about 10 mtrs. in length. These cables are to be disconnected andremoved from the existing location one by one as per the instruction and under the supervision of Railway staff presentat site. The cable is then to be inserted and terminated in new location box. The item includes neatly dressing of cable,making wiring tree etc.The material required to dressing /lacing will be arrange by contactor. The work is required to bedone systematically and with due precaution during the block or disconnection within the time that may be allowed. Theexcavation work to be done carefully without damaging the cable to avoid undue failure. (Termination charges will begiven separately). Note: Proportionate payment will be made if cable of other length. One No unit = One cable of 10 mlength)	Numbers	1000.00	318.00	318000.00
					Total	3038654.26
Item- 8	Testing and Measuring Equipments					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Integrated smoke & heat detector tester with smoke chamber cleaning feature , (required forcommissioning, testing & maintenance of smoke & heat detector) contains following accessories: sensor unit-1, batteryrod-1, injector1, mist liquid-1, charger-1, connect rod-4	Numbers	1.00	96760.00	96760.00
2	2	Supply of Digital Earth Resistance tester three terminal type with LED display, 1999 count, KOICO model5600 or any reputed make approved by engineer in-charge.	Numbers	5.00	13356.84	66784.20
3	3	Supply of Digital Insulation Tester 100V/250V/500V range of Model Rishinsu 20 Make :RISHABH or MECO or similar.	Numbers	5.00	8240.40	41202.00
4	4	Digital low current clamp meter to measure current leaks (parasitic draw down to 1 mA) and electricloads from 1mA to 100 Amp AC/DC, Voltages from 0 to 600V AC/DC, small jaw size to measure current in signallingcircuit, 4 digit display. Make -Fluke, GTC/KEW, Scope or superior with better specification as mentioned with allaccessories like test lead, batteries and carrying case, sample may be got approved from consignee before supply.	Numbers	5.00	18194.34	90971.70
5	5	Digital Multimeter of Fluke 287 Industrial, True RMS with temperature, Analog bar graph, Digital display,Backlight, 1000V AC/DC, measure up to 10A, 20A for up to 30 seconds or Superior.	Numbers	5.00	78421.00	392105.00
6	6	Professional AC/DC clamp meter 3 ¾ digit, true RMS measurement, For Measurement of DC/AC currentsup to 1000A, Voltage up to 600V, resistance up to 40 M, and frequency up to 1 MHz with a set of leads & carrying case.Model - DCM39A or equivalent/ higher make Motwane/Stanley/Fluke/Megger.	Numbers	5.00	12853.59	64267.95
7	7	Road Measuring Cycle, made of Aluminum with 05 digit counter, foldable with the bag.	Numbers	1.00	4515.84	4515.84

**MUMBAI CENTRAL DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SG_216_2_114_WA_ST_R1

Closing Date/Time: 15/06/2026 15:00

8	8	Provision of 10" Data input system with stylus pen of reputed make as decided by Engineer incharge.	Numbers	10.00	29700.00	297000.00
9	9	Cable cutter (SWA cable)Capacity (diameter)- 45 mm/380mm2with precision blades Make:- KNIPEX ,Gedore, Sthwille,Greenlee.	Numbers	2.00	40902.10	81804.20
10	10	Cable Knife System 4-70 withautomatic blade protection andcable bracket for stripping roundcables,Make- Jokari 70000,Weidmuller,Knipex, Phoenix contact.	Numbers	2.00	3963.05	7926.10
11	11	Crimping pliers PEW12 with DieSet (Capacity- 16 mm2 /25mm2) Dimension - 250 x 108 x 43mmMake:- Rennsteig, DMC,Molex,Amphenol	Numbers	2.00	20395.95	40791.90
12	12	Alluminium angle of size(from 25 x 25 x 6 mm to 50 x50x6 mm) along with accessories &transportation.	Kg	50.00	404.10	20205.00
13	13	Alluminium angle of size(from 25 x 6 mm to 50 x 6 mm)along with accessories ,heat shrink sleeves&transportation.	Kg	50.00	422.06	21103.00
14	14	Battery operated Impact wrenchmainly used to easily open thejammed/rusted nuts of Point,signal unitsand other bolts inplain track etc. asper (No.TM/SM/IW dated 09.01.2014) (Rev 02 of 2022) , ISO 28927-2:2009(Amendment-01-2017)	Numbers	1.00	52982.00	52982.00
15	15	Supply of Earth rod clamp madefor terminating cable / flat conductor.	Numbers	100.00	252.18	25218.00
16	16	Rail twist adaptor for7.2mm drill for 19 mm suitable for battery operated rail drill machine makeEibenstok Positron or similar.	Numbers	5.00	606.11	3030.55
17	17	Rail twist adaptor for 13mm drill for 19 mm suitable for battery operated rail drill machine makeEibenstok Positron or similar.	Numbers	5.00	763.47	3817.35
18	18	Rail twist adaptor for 16mm drill for 19 mm suitable for battery operated rail drill machine makeEibenstok Positron or similar.	Numbers	5.00	1035.26	5176.30
19	19	Rail twist drill dia 7.2mmfor adaptor 19 mm suitable for battery operated rail drill machine makeEibenstok Positron or similar	Numbers	5.00	938.84	4694.20
20	20	Rail twist drill dia 13mm adaptor 19 mm suitable for battery operated rail drill machine make EibenstokPositron or similar.	Numbers	5.00	2532.53	12662.65
21	21	Rail twist drill dia 16mmadaptor 19 mm suitable for battery operated rail drill machine make EibenstokPositron or similar	Numbers	5.00	2900.23	14501.15
					Total	1347519.09

4. ELIGIBILITY CONDITIONS

Special Financial Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer must have minimum average annual contractual turnover of V/N or V whichever is less ;where V= Advertised value of the tender in crores of Rupees N=Number of years prescribed for completion of work for which bids have been invited. The average annual contractual turnover shall be calculated as an average of "total contractual payments" in the previous three financial years, asper the audited balance sheet. However, in case balance sheet of the previous year is yet to be prepared/ audited, the audited balance sheet of the fourth previous year shall be considered for calculating average annual contractual turnover. The tenderers shall submit requisite information asper format-6, along with copies of Audited Balance Sheets duly certified by the Chartered Accountant/ Certificate from Chartered Accountant duly supported by Audited Balance Sheet.	No	No	Allowed (Mandatory)

**MUMBAI CENTRAL DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SG_216_2_114_WA_ST_R1

Closing Date/Time: 15/06/2026 15:00

Special Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer must have successfully completed or substantially completed any one of the following categories of work(s) during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: (i) Three similar works each costing not less than the amount equal to 30% of advertised value of the tender, or (ii) Two similar works each costing not less than the amount equal to 40% of advertised value of the tender, or (iii) One similar work costing not less than the amount equal to 60% of advertised value of the tender.	No	No	Allowed (Mandatory)
1.1	Definition of Similar Work :- Any signaling work involving outdoor work and / or addition and /or alteration in existing Indoor signaling system. OR any CLS or RI or EI or TPWS or IBS or ABS or BPAC work involving indoor and/or outdoor. Similar work to include indoor if the tendered work involves addition and / or alteration in existing indoor signaling system and outdoor if the tendered work involves outdoor work. OR Any such work involving activities as given in the name of the tendered work.	No	No	Not Allowed

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.
3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.
5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.
6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.
7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.
8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.
9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.
10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description
1	Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. (Click here to download the Format of Self Certification)

5. COMPLIANCE

Commercial-Compliance

**MUMBAI CENTRAL DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SG_216_2_114_WA_ST_R1

Closing Date/Time: 15/06/2026 15:00

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)

Technical-Compliances

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer shall clearly specify whether the tender is submitted on his own or on behalf of a partnership concern. If the tender is submitted on behalf of a partnership concern, he should submit the certified copy of partnership deed (PD) along with the tender and authorization to sign the tender documents on behalf of partnership firm. If these documents are not enclosed along with the tender documents, the tender will be treated as having been submitted by individual signing the tender documents. The tenderer whether sole proprietor, a limited company or a partnership firm if they want to act through agent or individual partners should submit along with the tender or at a later stage, a power of attorney(POA) duly stamped and authenticated by a Notary public or by Magistrate in favour of the specific person whether he or they be partners of the firm or any other person specifically authorizing him or them to submit the tender, sign the agreement ,receive money, witness measurement, sign Measurement Books, compromise, settle, relinquish any claims preferred by the firm and signed No claim certificate and refer all or any dispute to arbitration.	No	No	Not Allowed
1.1	Tenderer should clearly state the status of firm and submit the relevant document in support of authentication, in absence of following/relevant documents the offer of tenderer is summarily rejected: (A)Self-declaration /proprietorship certificate in case of proprietor firm along with POA if any. (B) Partnership deed and power of attorney in case of partnership firm. (C)Certified copy of an extract of resolution passed by the board of directors in case of limited firm or Private Limited Company	No	No	Allowed (Mandatory)
1.1.1	(a) Sole Proprietorship Firm: (i)All documents in terms of Para 10 of the Tender Form (Second Sheet)of Tender document	No	No	Allowed (Optional)
1.1.2	(b) HUF: (i)A copy of notarized affidavit on Stamp Paper declaring that he who is submitting the tender on behalf of HUF is in the position of 'Karta' of Hindu Undivided Family (HUF) and he has the authority, power and consent given by other members to act on behalf of HUF. (ii)All other documents in terms of Para10 of the Tender Form (Second Sheet)of Tender document	No	No	Allowed (Optional)
1.1.3	(c) Partnership Firm: (i)All documents as mentioned in para18 of the Tender Form document	No	No	Allowed (Optional)
1.1.4	(d) Company registered under Companies Act2013: (i)The copies of MOA (Memorandum of Association) / AOA (Articles of Association) of the company (ii)A copy of Certificate of Incorporation(iii)A copy of Authorization/Power of Attorney issued by the Company (backed by the resolution of Board of Directors) in favour of the individual to sign the tender on behalf of the company and create liability against the company. (iv)All other documents in terms Para 10 of the Tender Form (Second Sheet) of Tender document	No	No	Allowed (Optional)

**MUMBAI CENTRAL DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SG_216_2_114_WA_ST_R1

Closing Date/Time: 15/06/2026 15:00

1.1.5	(e) LLP (Limited Liability Partnership): (i)A copy of LLP Agreement (ii)A copy of Certificate of Incorporation (iii)A copy of Power of Attorney/Authorization issued by the LLP in favour of the individual to sign the tender on behalf of the LLP and create liability against the LLP. (iv)An undertaking by all partners of the LLP that they are not blacklisted or debarred by Railways or any other Ministry / Department of the Govt. of India from participation intenders / contracts as on the date of submission of bids, either in their individual capacity or in any firm/ LLP or JV in which they were/ are partners/members. Concealment /wrong information in regard to above shall make the contract liable for determination under Clause 62 of the Standard General Conditions of Contract.(v)All other documents in terms of Para 10 of the Tender Form(Second Sheet).	No	No	Allowed (Optional)
1.1.6	(f) Registered Society & Registered Trust: (i)A copy of Certificate of Registration (ii)A copy of Memorandum of Association of Society/Trust Deed (iii)A copy of Power of Attorney in favour of the individual to sign the tender documents and create liability against the Society/Trust. (iv)A copy of Rules & Regulations of the Society (v)All other documents in terms of Para 10 of the Tender Form (Second Sheet) of tender document	No	No	Allowed (Optional)
2	Information as per Para 16 of GCC Part (1)(Tender form second sheet Annex-I) related to Employment/Partnership Etc. of Retired Railway Employees and Clauses 59 (9) & 62 (1) (xv) to GCC regarding employment etc. Of retired government officers by railway contractors	No	No	Not Allowed
2.1	Certificate of Information regarding EMPLOYMENT/PARTNERSHIP etc. of Retired Railway Employees with the tender as per the attached proforma, Format 11 of tender document	No	No	Allowed (Mandatory)
2.2	Certificate of NO RELATIVE being an employee of Western Railway as per attached Performa Format10 of Tender document	No	No	Allowed (Mandatory)

Custom

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Please submit a certificate in the prescribed format {As per Annexure II & Annexure II-A (if applicable) of Tender Documents} for verification/ confirmation of the documents submitted for compliance of eligibility / qualifying criteria. Non submission of the certificate, or submission of the certificate either not properly filled in, or in a format other than the prescribed format shall lead to summarily rejection of your offer.	No	No	Allowed (Mandatory)
1.1	Partnership firm/Joint Venture (JV) /Hindu Undivided Family (HUF) /Limited Liability Partnership (LLP)etc. Please submit Annexure II A of the Tender document by each member of a Partnership firm/JV/HUF/LLP etc. as the case may be. Non-submission of the copy of the certificate by the bidder shall result in summarily rejection of is/her bid. It shall be mandatorily incumbent upon the Tenderer to identify , state and submit the supporting documents duly self attested/ digitally signed by which he/they are/is qualifying the qualifying criteria mentioned in the Tender document	No	No	Allowed (Mandatory)

6. Documents attached with tender

S.No.	Document Name	Document Description
1	TD-114-R-ADSTE-ST-R1.pdf	Tender Document

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

**MUMBAI CENTRAL DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SG_216_2_114_WA_ST_R1

Closing Date/Time: 15/06/2026 15:00

Signed By: ANKIT LODHA

Designation : Sr.DSTE/North/BCT