

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWKS2026-27SIG04

Closing Date/Time: 19/06/2026 15:00

Sr.DSTESr. DSTE acting for and on behalf of The President of India invites E-Tenders against Tender No **BPLNWKS2026-27SIG04** Closing Date/Time 19/06/2026 15:00 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

1. NIT HEADER

Name of Work	Interlocking of LC gate No. 146, 131 & 136 along with associated signalling and telecom work in RTA-MKC Section over Bhopal division.		
Bidding type	Normal Tender		
Tender Type	Open	Bidding System	Single Packet System
Tender Closing Date Time	19/06/2026 15:00	Date Time Of Uploading Tender	26/05/2026 15:53
Pre-Bid Conference Required	No	Pre-Bid Conference Date Time	Not Applicable
Advertised Value	30698447.86	Tendering Section	SNT SIG
Bidding Style	Single Rate for Tender	Bidding Unit	Above/Below/Par
Earnest Money (Rs.)	614000.00	Validity of Offer (Days)	60
Tender Doc. Cost (Rs.)	0.00	Period of Completion	9 Months
Contract Type	Works - General	Contract Category	Expenditure
Bidding Start Date	05/06/2026		
Are JV allowed to bid	No	Number of JV Member Allowed	0
Are Consortium allowed to bid	No	Number of Consortium Member Allowed	0
Ranking Order For Bids	Lowest to Highest	Expenditure Type	Capital (Works)

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () 01-Supply Portion-I							11557678.69	
01	Please see Item Breakup for details.				11557678.69	AT Par	11557678.69	
	Description:- Total Supply Portion-I							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () 02-Supply Portion-II							1098626.16	
02	Please see Item Breakup for details.				1098626.16	AT Par	1098626.16	
	Description:- Total Supply Portion-II							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () 03- Supply & Installation Portion							14331709.95	
03	Please see Item Breakup for details.				14331709.95	AT Par	14331709.95	
	Description:- Total Supply & Installation Portion							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () 04-Execution Portion							3710433.06	
04	Please see Item Breakup for details.				3710433.06	AT Par	3710433.06	
	Description:- Total Execution Portion							

3. ITEM BREAKUP

Schedule	Schedule 01-Supply Portion-I					
Item- 01	Total Supply Portion-I					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWS2026-27SIG04

Closing Date/Time: 19/06/2026 15:00

1	01	Supply of Relay rack assembly complete with scaffolding, fixtures and accessories including MS bars for fixing of relay, plug board, string rods, fuse strips with bracket, 11 way Bus bars with cover and mounting brackets, runway for cable/wires, Relay frame, base assembly etc. Siemens type & as per extant practice on W.C. Rly. Typical part list as per Annexure-I. Rack should be made of first class steel powder coated painting and rack manufacturer's certificate should be submitted. (Material Inspected by Consignee)	Set	6.00	38803.23	232819.38
2	02	Supply of Main Cable Termination rack complete with scaffolding, fixtures & accessories including square bars for mounting 8-way terminal/WAGO-make terminal blocks, ladder, string rods, frame, base assembly, insulators, J bolt, nut/bolts & fasteners (bakelite strips) etc. Siemen's type & as per extant practice on W. C. Rly. Typical part list as per Annexure-II and rack arrangement shall be as per sketch Sk-727. (Material Inspected by Consignee)	Set	3.00	35355.34	106066.02
3	03	Supply of Metal-To-Metal Universal LED ECR without base plate, ABB Make or functional equivalent and should be suitable for working with LED Based Signal lighting Unit. (Material Inspected by RDSO)	Numbers	42.00	14604.09	613371.78
4	04	Supply of QNA1 (AC immunised relay), 12F-4B and 8F-8B, 24VDC along with plug board (Base plate), retaining clips and connectors conforming to BRS:931A ; IRS S 34 ; IRS S 23 ; IRS S 60-78. Break-up of configuration will be given by railways before supply of material. (Material Inspected by RDSO)	Numbers	12.00	3569.80	42837.60
5	05	Supply of Relay Non-AC Immune, plug-in-type, DC Neutral Line 60V 4F/4B, 5F/3B, 6F/2B contacts, front and back contacts metal to metal, conforming to IRS: S 46 and firm's specification. The relay housing shall contain two miniature identical relays in mini group housing complete with base plate, Siemens make or functional equivalent. (Material Inspected by RDSO)	Numbers	72.00	9068.82	652955.04
6	06	Supply of Relay plug-in-type, Mechanical Interlocked Relay, 24V/60V (Metal to Metal) IRS:S-46 with Amdt.1 ; firm's specn , IRS S 23-88 ; IRS S 34-68, in mini group housing contain two miniature identical relays with contact configuration 4F-4B, 5F-3B, 6F-2B, metal to metal with base plate of same make. Make - Siemens or equivalent. (Material inspected by RDSO)	Numbers	12.00	7880.44	94565.28
7	07	Supply of Time Element Relay (Clockwork type) AG timer Siemens Make (No. RSK30/0052) or equivalent with timer range up to 120seconds. (Material Inspected by Consignee)	Numbers	12.00	8136.30	97635.60
8	08	Supply of fail safe electronic flasher device as per Specification No.RDSO/SPN/173/2002. (Material Inspected by RDSO)	Numbers	6.00	27047.71	162286.26
9	09	Supply of Key Lock Relay AC immunized 24V DC /60VDC with different ward combinations (Five No. of ward plate for Point Machine to be supplied with each relay) of Siemens Make or functional equivalent. (Material Inspected by RDSO)	Numbers	3.00	11067.16	33201.48

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWKS2026-27SIG04

Closing Date/Time: 19/06/2026 15:00

10	10	Supply of Pre-wired Crank Handle cum key lock relay box along with LEDs,TEKNIC/SIEMENS or similar make push buttons, 8-wayterminal strips / wago terminal,string rod, etc. (Material Inspected by Consignee)	Numbers	3.00	9511.81	28535.43
11	11	12 Volt hooter 12 make Radix,minda, macony or similar. (Material Inspected by Consignee)	Numbers	6.00	396.08	2376.48
12	12	Supply of PVC insulated flexible wire 16/0.2 mm dia as per RDSO spec. Nos.IRS:S-76/89 with latest amendments of various colours to be decided by Sitein-charge.(Material Inspected by RDSO)	Kilometre	1.50	9009.59	13514.39
13	13	Supply of flexible cable single core multistrand copper conductors, 1x10sq. mm confirming to RDSO specification IRS:S:76/89 with latest amendments. (Material Inspected by RDSO)	Kilometre	0.30	136486.96	40946.09
14	14	Supply of flexible cable single core multistrand copper conductors, 1x16sq. mm confirming to RDSO specification IRS:S:76/89 with latest amendments. (Material Inspected by RDSO)	Kilometre	0.30	201848.41	60554.52
15	15	Supply of PVC insulated railway signalling indoor single core [tinned jumper wire] 1X0.6 mm dia. as per RDSOspec. Nos. IRS:S-76/89 with latest amendments of various colors to be decided by Site in-charge. (Material Inspected by RDSO)	Kilometre	12.00	3036.54	36438.48
16	16	Supply of two in two out (4 conductor) Knife edge disconnect terminal block set as per RDSO/SPN/189/2004 version 3.0 with latest amendment.(Material Inspected by RDSO)	Numbers	2700.00	61.33	165591.00
17	17	Supply of end plate suitable for disconnect terminal. (Material Inspected by Consignee)	Numbers	270.00	13.65	3685.50
18	18	Supply of end stop suitable for disconnect terminal block. (Material Inspected by Consignee)	Numbers	540.00	11.95	6453.00
19	19	Supply of steel carrier Din rail suitable for fixing disconnect terminal 1 meter long of dimension 35mm X 7.5 mm, 1mm thickness, unslotted. (Material Inspected by Consignee)	Metre	36.00	163.50	5886.00
20	20	Supply of fire extinguisher having Composite/SS/Aluminum Cylinder of same fire rating as per latest BIS: 15683:2018 and as per specific service pressure requirement for use. Fire Extenguisher CO2 ty (Material Inspected by Consignee)	Numbers	12.00	6680.86	80170.32
21	21	Supply of Goods warning Board/shunting limit board as per Drg No. DyCSTE/C/BPL/003. It also includes supply of M S Channel, Nut & Bolt etc as per drg. (Material Inspected by Consignee)	Numbers	6.00	3657.14	21942.84
22	22	Supply of Fuse auto changeover system for used in Railway Signaling System as per RDSO/SPN/209/2012 Ver - 2with latest amendments. One Automatic changeover Unit comprise 32 nos. of external Non Deteriorating Type or 'G' type fuses from 0.6 Amp to 4 Amp capacities which are in signaling circuits. System shall have 8 cards with monitoring arrangement of 4 fuses in one card. (Unit read as "Per module "). (Material Inspected by RDSO)	Set	6.00	26854.13	161124.78

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWKS2026-27SIG04

Closing Date/Time: 19/06/2026 15:00

23	23	Supply of Non Metallic (FRP) colour light signal housing multi unit type for railway signaling suitable for RE area TWO Aspects. Complete without lenses, lamps and signal transformer as per RDSO DRG.No. SA 23001/A/M (Adv.) and as per SPEC. No.RDSO/SPN/194/2006 Rev.2.0 or latest and FRP material as per RDSO SPEC. No.RDSO/SPN/151/1997 or latest. (Material Inspected by Consignee)	Numbers	18.00	23186.79	417362.22
24	24	Supply of INDICATIVE TYPE OF FUSE INSERTS. With holder 1.6 A. (Material Inspected by RDSO)	Numbers	60.00	117.56	7053.60
25	25	Supply of INDICATIVE TYPE OF FUSE INSERTS. With holder 0.6 A.(Material Inspected by RDSO)	Numbers	60.00	112.66	6759.60
26	26	Supply of INDICATIVE TYPE OF FUSE INSERTS. Without holder 1.6 A.(Material Inspected by RDSO)	Numbers	60.00	34.13	2047.80
27	27	Supply of INDICATIVE TYPE OF FUSE INSERTS. Without holder 0.6 A.(Material Inspected by RDSO)	Numbers	60.00	34.13	2047.80
28	28	Supply of Apparatus Case with miniature 'E' type locks with keys (1key per 5 location boxes) of ward No.42 (E type lock & key as per spec. No.IRS S 30 & RDSO Drg. No. SA 3376/M& 3377/M respectively with latest amendment) on both the doors duly painted with red oxide. Single case as per Drg No. WS-8842/A with latest alteration. (Material Inspected by Consignee)	Numbers	15.00	12934.14	194012.10
29	29	Supply of Phenolic Laminated sheet, resin bonded 10 mm thick, grade P3 in standard size of 1.22 X 1.22 Mtr as perspec. No. IS 2036 of 1974. (Material Inspected by Consignee)	Numbers	15.00	3037.66	45564.90
30	30	Supply of A/AG/C/P/G board as per RDSO Drg. No. SA 23455-56 RST- 5211445 & SA 23476-77 as applicable. (Material Inspected by Consignee)	Numbers	12.00	564.76	6777.12
31	31	Supply of Lamp holder and switches , Two pin (Backelite type) for location boxes (Anchor make or ISI mark) . (Material Inspected by Consignee)	Numbers	15.00	103.64	1554.60
32	32	Supply of Signal No. plates retro reflective type as per WCR standard practice. (Material Inspected by Consignee)	Numbers	12.00	516.01	6192.12
33	33	Supply of Pad locks Godrej/ Hand Cuff Locks with common key. (Material Inspected by Consignee)	Numbers	36.00	281.70	10141.20
34	34	Supply of universal earth leakage detector for 8 channel (110V AC/24VDC /60V DC/110V DC) as per RDSO spec. No. RDSO/SPN/256/2025 version 2.0 with latest amendment.(Material Inspected by RDSO)	Set	6.00	95415.16	572490.96

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWKS2026-27SIG04

Closing Date/Time: 19/06/2026 15:00

35	35	Supply of LED type Indication cum operating panel to be made of size of 54 mm x34mm cover plates depicting the yard layout, unit signal,track etc. of minimum size(12x8) siemens type Dominos complete wired with full components. The panel should have polycarbonate sheet cover on top to avoid damage while in service Each of the working domino should have all 15 terminals components with wiring. Total No. of Domino (12 x 8) = 96 Nos.Size 54 mm x 34 mm. The length approximately 730 mmx 450 mm. The height is approximately 910mm (rearside) and 820 mm (frontside). The panel should have poly carbonated sheet cover on the top. SPARE: 10% of working domino with cover plate completely wired and 10% of LEDs of each colour,10% (minimum three) of buttons, 10% of counter, 2 magnets, 1 buzzer & 4 bulb extractors shall be handed over as spare after commissioning of the installation by the contractor. (Material Inspected by Consignee)	Numbers	3.00	30291.48	90874.44
36	36	Supply of Limit switch New Top Roller type with 2 No + 2 NC contacts as per RDSO 45 Balaji make model No.102TPR A or similar. (Material Inspected by Consignee)	Numbers	3.00	607.42	1822.26
37	37	Supply of Electro Magnetic boom locking system with +VE VC boom locking, LED indicator panel with Buzzer and Indication circuit. Operating Voltage110VAC or 24 V DC with 110VAC/24VDC Adoptor. Electric current 500 MA Magnetic Lockin power 600 lbs. Magnetic convert Area for boom locking arrangement size 150 mm x 35mm. Fitting plate for boom barrier size 180 mm x 35 mm with lifting accessories written in drawing. IRS conditions will be applicable. As per specifications attached. (Material Inspected by Consignee)	Set	6.00	8537.55	51225.30
38	38	Supply of SMPS (Major) IPS system suitable for LC gate/RH hut in RE area along with 2V/300AH battery set along with spares and tools as per RDSO specification No. RDSO/SPN/165/2023 Ver. 4.0 with latest amendment. For connecting IPS to battery bank, 10 meter each of Red and Black colour Power cable of size as per battery 2V/300AH capacity is to be supplied by tenderer. 12 core x 1.5 Sq. mm signalling cable for connecting IPS to status monitoring panel will be supplied by railway. (Material Inspected by RDSO)	Set	3.00	1065598.00	3196794.00
39	39	Supply of Remote Terminal Unit with 128 digital and 16 analog inputs as per RDSO specification No. IRS:S-99/2006 (Amdt-3) or latest.(Material Inspected by RDSO)	Set	3.00	207382.74	622148.22
40	40	Supply of External Modem suitable for Networking of RTU. (Material Inspected by Consignee)	Numbers	3.00	28221.81	84665.43

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWS2026-27SIG04

Closing Date/Time: 19/06/2026 15:00

41	41	Supply of portable "Insulation Monitor with fault locator kit for Railway signaling and telecommunication (S&T) systems with article ID: I30120001 of M/s Bender India Private Limited make including following. 1. i. ISO 685-D-P Insulation Monitoring Device (IMD) with integrated locating current injector .ii EDS195PM Insulation fault locator iii PSA3052 Measuring clamp 52mm iv PSA3352 Measuring clamp 52mm v EDS195PM Accessories for 1no of USB power supply unit:Primary : 100...240 V, 50...60 Hz Secondary: DC 5 V, +/- 10 %,Power consumption 0.5 W vi iso685-D-P Accessories for 3nos of safety measuring cable black along with clamps and 2nos Safety measuring cable green/yellow along with clamps for system connection and 1no Auxiliary supply cable. 2. 2 days of onsite training will be provided for all 2 locations. (Material Inspected by RITES)	Set	2.00	972243.30	1944486.60
42	42	Supply of Relay DOC (BR930 automated relay tester & conditioner).Make MRD Rail Technologies or similar. (Material Inspected by RITES)	Numbers	2.00	752250.00	1504500.00
43	43	Supply of earth electrode assembly as per Drg. No. CR/SK-753. (Material Inspected by Consignee)	Numbers	45.00	1530.87	68889.15
44	44	Supply of cartridge fuse block made of PBT as per RDSO Drg. No. SA - 23748 Alt. 4 and Spec. No. IRS-75/2006 with latest ammendment. Fuse block shall be suitable for round head type fuses. (Material Inspected by RDSO)	Numbers	12.00	225.71	2708.52
45	45	Supply of non detoriating type low voltage cartridge fuse current 4Amp/6Amp in equal proportion round head type as per spec No IRS/S/78/92 with latest ammendment. (Material Inspected by RDSO)	Numbers	12.00	55.29	663.48
46	46	Supply of Metal oxide Varistor(MOV), 20mm dia, for 275V AC/300V DC supply with maximum clamping voltage of 595V at 100A and peak single pulse(8/20us) rating of 8KA. (Bourns/Little fuse/Epcos make or similar). (Material Inspected by Consignee)	Numbers	300.00	31.00	9300.00
47	47	Supply of Metal oxide Varistor(Supply of Metal oxide Varistor(MOV)), 20mm dia, for 11V AC/14V DC supply with maximum clamping voltage of 36V at 20A and peak single pulse(8/20us) rating of 2KA. (Bourns/Little fuse/Epcos make or similar). (Material Inspected by Consignee)	Numbers	240.00	31.00	7440.00
48	48	Supply of Metal oxide Varistor(MOV), 20mm dia, for 25V AC/31V DC supply with maximum clamping voltage of 77V at 20A and peak single pulse(8/20us) rating of 2KA. (Bourns/Little fuse/Epcos make or similar). (Material Inspected by Consignee)	Numbers	240.00	24.00	5760.00
49	49	Supply of Metal oxide Varistor(MOV), 20mm dia, for 40V AC/56V DC supply with maximum clamping voltage of 135V at 20A and peak single pulse(8/20us) rating of 2KA. (Bourns/Little fuse/Epcos make or similar). (Material Inspected by Consignee)	Numbers	120.00	31.00	3720.00

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWKS2026-27SIG04

Closing Date/Time: 19/06/2026 15:00

50	50	Supply of Metal oxide Varistor(MOV), 20mm dia, for 50V AC/65V DC supply with maximum clamping voltage of 135V at 100A and peak single pulse(8/20us) rating of 6.5KA. (Bourns/Little fuse/Epcos make or similar). (Material Inspected by Consignee)	Numbers	120.00	24.00	2880.00
51	51	Supply of Metal oxide Varistor(MOV), 20mm dia, for 95V AC/125V DC supply with maximum clamping voltage of 250V at 100A and peak single pulse(8/20us) rating of 6.5KA.(Bourns/Little fuse/Epcos make or similar). (Material Inspected by Consignee)	Numbers	120.00	24.00	2880.00
52	52	Supply of Metal oxide Varistor(MOV), 20mm dia, for 130V AC/170V DC supply with peak single pulse(8/20us) rating of 8KA. (Bourns/Little fuse/Epcos make or similar). (Material Inspected by Consignee)	Numbers	240.00	48.00	11520.00
53	53	Supply TVS Diode, 1500W peak pulse capability at 10/1000micro-second, Bi-directional, reverse standoff voltage = 8.55V, maximum clamping voltage = 14.5V at 42.1A, maximum reverse leakage current of 10 micro-Amp at 8.55V. (Bourns/Little fuse/Epcos make or similar). (Material Inspected by Consignee)	Numbers	120.00	69.00	8280.00
54	54	Supply of Metal oxide Varistor (MOV), 10mm dia, for 25V AC/31V DC supply with maximum clamping voltage of 77V at 5A and peak single pulse(8/20us) rating of 0.5KA. (Bourns/Little fuse/Epcos make or similar). (Material Inspected by Consignee)	Numbers	120.00	18.00	2160.00
					Total	11557678.69
Schedule Schedule 02-Supply Portion-II						
Item- 02 Total Supply Portion-II						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	01	Supply of main LED signal UNIT110V/AC as per RDSO specification No. RDSO/SPN/199/2025 Rev. 1.2 or latest suitable for existing CLS housing unit.RED Aspect. (Material Inspected by RDSO)	Numbers	12.00	5695.20	68342.40
2	02	Supply of main LED signal UNIT110V/AC as per RDSO specification No.RDSO/SPN/199/2025 Rev. 1.2 or latest suitable for existing CLS housing unit.YELLOW Aspect. (Material Inspected by RDSO)	Numbers	18.00	5695.20	102513.60
3	03	Supply of main LED signal UNIT110V/AC as per RDSO specification No.RDSO/SPN/199/2025 Rev. 1.2 or latest suitable for existing CLS housing unit.GREEN Aspect. (Material Inspected by RDSO)	Numbers	12.00	6514.18	78170.16

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWKS2026-27SIG04

Closing Date/Time: 19/06/2026 15:00

4	04	Supply of Electrically operated lifting barrier with hand generator each set consisting of 2 Nos. of lifting barrier pedestals, each with 8 contact circuit controller with top roller type limit switches (as per Design given in specification & approved by RDSO) hand crank, electric motor 110V DC, 2 GI sheet booms of 32 ft length (4 section of 8 ft long each) with new Octagonal shape as per RDSO approved Drg. No. RDSO/S-11600 without fringes, with 2 stop boards and boom light boxes, MS counter weights and 02 Nos. of boom supports with motorized boom locking along with 01 no. of hand Generator cum Control panel to operate 2 barriers of a set with 1 selector switch, 3 buttons and 5 indicating lamps, contractors MCB's and relays as per RDSO spec No RDSO/SPN/208/2012 or latest. Motorised locking at Lock posts assembly as per RDSO letter No. RDSO-QASTOLKO (VEND /3/2020-O/o ED /QA /SnT /HQ /RDSO dtd 11.08.2025 . (Material Inspected by RDSO)	Set	3.00	283200.00	849600.00
Total					1098626.16	
Schedule	Schedule 03- Supply & Installation Portion					
Item- 03	Total Supply & Installation Portion					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	01	Supply and installation of Perimetric earth (Maintenance Free Earth) arrangement as per RDSO Spec. No.RDSO/SPN/197/2016 Version 1.0 or latest. This also includes supply of all required materials along with Maintenance free earthing item as per latest RDSO Guideline for commissioning of Perimetric earth covering the entire building. Earthing shall comply all guidelines specified in RDSO TAN No. STS/E/TAN/3006 version 3.1 dated 30.06.2025 . Minimum 12 No.of maintenance free earth with all the accessories like connecting tape among others to be supplied under this item in each lot.(Material Inspected by RDSO)	Lot	3.00	163743.48	491230.44
2	02	Supply and fixing Polyolefin cable channel of size width 240/340 mm, height 155/230 internal/external, length 1meter produced of polyolefin with fire protection class K-1 in accordance with DIN 53438Part-II for laying signaling/telecom cables,channel attachable to each other with male female swallow tail connectors and having a suitable detachable cover, as per RDSOSTS/E/cable laying PreciseVol-IV and as per technical specifications. (Material Inspected by RITES)	Metre	7200.00	1666.93	12001896.00
3	03	Supply, Installation, Testing and commissioning of addressable Fire alarm Control panel as per RDSO Specification RDSO/SPN /217/2025 Ver.3.1 with latest amendment. (Material Inspected by RDSO)	Numbers	3.00	78740.99	236222.97
4	04	Supply, Installation, Testing and commissioning of Manual call point as per RDSO Specification RDSO/SPN/217/2025 Ver.3.1 with latest amendment.(Material Inspected by RDSO)	Numbers	3.00	5148.44	15445.32

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWS2026-27SIG04

Closing Date/Time: 19/06/2026 15:00

5	05	Supply, Installation, Testing and commissioning of addressable loop powered wall sounder Beacone as per RDSO Specification RDSO/SPN/217/2025 Ver.3.1 with latest amendment. (Material Inspected by RDSO)	Numbers	3.00	6202.36	18607.08
6	06	Supply, Installation, Testing and commissioning of heat and smoke multisensor as per RDSO Specification RDSO/SPN/217/2025 Ver.3.1 with latest amendment. (Material Inspected by RDSO)	Numbers	30.00	4361.03	130830.90
7	07	Supply, Instalation, Testing and commissioning of Linear heat sensing (LHS) cable as per RDSO Specification RDSO/SPN/217 /2025 Ver.3.1 with latest amendment. (Material Inspected by RDSO)	Metre	900.00	545.12	490608.00
8	08	Supply, Installation, Testing and commissioning of Linear heat sensing(LHS) interface module for LHS cable as per RDSO Specification RDSO/SPN/217/2025 Ver.3.1with latest amendment. (Material Inspected by RDSO)	Numbers	3.00	52090.19	156270.57
9	09	Supply, Installation, Testing & Commissioning of Single Channel Laser Based Aspiration Detection Unit (air sampling) with area coverage of 5000 Sq. Feet with programable 4 stage alarm generation. It should have Auto cleaning facility in optical chamber, electronic discrimination of particle size, ultrasonic airflow sensing Auto learn feature with TCP/IP network Capability, the aspiration system shall also include external power supply unit with battery backup and all associated accessories like Pipe as per standard among others. Approval - UL/LPCB /VDS Listed and shall comply to (air sampling) type smoke detector as per RDSO/SPN/217/2025 Ver 3.1 with latest amendment. This also includes integration of Aspiration unit with existing/new Fire alarm control panel as per instruction of site in-charge.(Material Inspected by RDSO)	Numbers	3.00	198306.15	594918.45
10	10	Supply, Installation, Testing and commissioning of Fire survival circuit integrity cable each lot having 200 mtr.Cable with all accessories connecting of all fire alarm devices as per RDSO/SPN/217/2025 Ver.3.1 with latest amendment. (Material Inspected by RDSO)	Lot	3.00	24227.99	72683.97
11	11	Supply, Installation, Testing & Commissioning of Analog AddressableType Monitor Modules with inbuilt fault isolator or alternate arrangment which shall isolate the module in case of short circuit the module should have visual indication for its operation & complying to RDSO/SPN/217/2025 Ver.3.1 with latest amandment. Operating temprature: -10 to 60 deg C, Humidity- up to 85%, Approval - UL/LPCB Listed. (Material Inspected by RDSO)	Numbers	15.00	6500.83	97512.45
12	12	Supply, Installation, Testing & Commissioning of addressable loop powered control module fitted with bidirectional inbuilt isolator as per RDSO/SPN/217/2025 Ver.3.1 with latest amendment. (Material Inspected by RDSO)	Numbers	3.00	5560.24	16680.72

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWS2026-27SIG04

Closing Date/Time: 19/06/2026 15:00

13	13	Supply, installation,testing and commissioning of Auto Telephone Dialer (GSM) as per RDSO Spec. No. RDSO/SPN/217/2025 Ver 3.1 with latest amendment. (Material Inspected by RDSO)	Numbers	3.00	2934.36	8803.08
					Total	14331709.95
Schedule Schedule 04-Execution Portion						
Item- 04 Total Execution Portion						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	01	Excavation of trench as per cable route plan 1.2 mtr deep, 300mm wide at the bottom along main line in normal soil.This work includes covering of cable laid in trenches by loose soil for a layer of 50 mm thickness approximately before covering by shahabad stone/bricks, clearing of route, bushes etc and refilling of the trench by excavated soil and ramming after laying of the required quantity of cables as per instructions of Engineer at site. If it is not possible to reach the required depth at any location, then the contractor shall obtain prior approval of Engineer-in-charge before commencement of cable laying process and only then shall the proportionate payment	Kilometre	9.00	72578.93	653210.37
2	02	Excavation of trench as per cable route plan 1 mtr deep, 300 mm wide at the bottom along main line in hard soil /murum. This work includes covering of cable laid in trenches by loose soil for a layer of 50 mm thickness approximately before covering by Shahabad stone/bricks, clearing of route, bushes etc and refilling of the trench by excavated soil and ramming after laying of the required quantity of cables as per instructions of Engineer at site. If it is not possible to reach the required depth at any location, then the contractor shall obtain prior approval of Engineer-in-charge before commencement of cable laying process and only then shall the proportionate payment be made to the contractor.	Kilometre	0.30	107543.11	32262.93
3	03	Laying of signalling/Power/Telecom cable of various cores/sizes in trenches. The work shall be done as per extant practice followed on W.C.Railway and as per the instructions of Railway Engineer at site. Cable must entry in Location/Relay room after only payment will be done.	Kilometre	27.00	4865.85	131377.95
4	04	Fixing of GI pipes for crossing of culverts, bridges etc. and concreting of ends with brick masonry at both ends as per the instructions of Railway Engineers at site.	Metre	18.00	52.49	944.82
5	05	Transportation & Laying of DWC/GI pipes along with collars in trenches at places wherever required as per extant practice on WCR and instruction of engineer at site.	Metre	36.00	30.34	1092.24
6	06	Excavation of cable trench 1 mtr. deep and 300mm wide across the track for track crossing and refilling after laying of DWC pipes and restore the track to its original condition. The work shall be done as per extant practice on W.C. Rly& instruction of Rly engineer at site.	Metre	36.00	75.92	2733.12

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWKS2026-27SIG04

Closing Date/Time: 19/06/2026 15:00

7	07	Cutting of all types of Roads preparatory to trenching & excavation to depth of 1Mtr X 300 mm wide approximately and refilling after laying of DWC/GI pipes and restore to its original condition as per WCR Drg. No. TS/Cable laying/12/03/04 attached. The work shall be done as per extant practice on W.C. Rly & instruction of Rly engineer at site.	Metre	18.00	187.18	3369.24
8	08	Supply and installation of RCC Cable route marker engraved and painted on both side along the route every 50 m and route diversion.	Numbers	186.00	585.41	108886.26
9	09	Wiring in Relay Room: Fixing of Q series relay base plate/Metal to Metal relay mini group and major group base plates, laying, lacing, dressing & packeting of 60/40 core PVC indoor cable/flexible wire and termination of 60/40 core cable/flexible wire on tag block/base plate & soldering. Wiring of circuits to be done as per the approved diagram based on relay interlocking system using metal to metal/metal to carbon type relays and soldering after testing. This also includes fuse wiring, function wiring (interconnection between relay rack & CT rack), material required like jumper wire of 0.6mm, 1.0 mm and 16/0.02 multi strand flexible etc. resin core, solder wire, lacing thread, adhesive tapes, resistance, condensers, diodes, lugs etc. of various ratings and capacity as per site requirement will be supplied by the contractor free of cost and will be used after approval of Rly. engineer at site. The work shall be done as per approved plan extant practice on W.C.Rly & the instruction of Rly.engineer at site. NOTE: The jumper wire required for carrying out the indoor wiring shall be as per standard. The quantity required for Jumpering shall be assessed jointly with the engineer in charge in the beginning itself. All type of resistances, capacitors etc.required for commissioning will be provided by the contractor. (No. - Per Rack)	Numbers	6.00	16112.51	96675.06
10	10	Wiring of Q series relay, Metal to Metal relay/relay groups. Energization of the system, making the panel through, 1/2 wire testing, functional test as per control table/selection table, square sheet testing with contractor's own mock panel, break test if applicable in presence of Rly.Engineers. This will include wiring alterations required if any at that stage, preparation and submission of wire count detail register etc. The work shall be done as per extant practice on W.C. Rly & the instruction of Rly engineer at site. All type of resistances, capacitors etc. required for commissioning have to be provided by the contractor free of cost. (No. - Per Rack)	Numbers	6.00	1392.41	8354.46
11	11	Soldering of tag block, fixing and wiring of G type fuse, busbar wiring per tag block as per approved plan, extant practice of WCR & as per instruction of site engineer (Solder wire, resin core, etc. material will be supplied by contractor) (No. - Per Tag Block)	Numbers	69.00	226.19	15607.11

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWS2026-27SIG04

Closing Date/Time: 19/06/2026 15:00

12	12	Circuit wiring/ Jumpering as per diagram in the relay rack/IDF rack/tag block. This includes preparation of jumper sheet duly checked by firm's site supervisor & wire to wire testing as per wiring diagram. Any wrong jumper done by wire man will be consider & payment for wrong jumper will not be done by the railway. Jumper wire will be supplied by railway & other material like solder wire will be supplied by contractor. Unit- per jumper	Numbers	4650.00	19.06	88629.00
13	13	Installation of Relay Rack Assembly including IDF pillars complete with wall supports, scaffolding, ladders, runway for cables, Relay/Relay group base plates, fixing of Tag blocks etc. The work shall be done as per approved plan, extant practice on W.C.Railway & the instructions of Rly. engineer at site.	Numbers	6.00	1707.06	10242.36
14	14	Installation of Cable Termination Rack Assembly complete including wall supports, scaffolding, 8war/ARA terminal, 96-way tag block & other necessary accessories etc. The work shall be done as per approved plan, extant practice on WCRly. & the instructions of Rly. engineer at site.	Numbers	3.00	1201.38	3604.14
15	15	Termination of cable cores on ARA terminal/Wago/Pheonix terminal and fuse blocks in apparatus cases/ cable termination rack etc. This includes all associated works of pulling out the cable from underground dressing of cable making wiring etc. Both end of cable core shall be counted as per conductor. It includes cable armouring earthing with contractor's own material. The work shall be done as per location plan and instruction of Rly. engineer at site. (UNIT =Per conductor both side)	Per Conductor	2700.00	12.09	32643.00
16	16	Fixing of ARA/WAGO Terminals/Pheonix terminal in locations with provision of hole in location boxes/CT rack and else where. This includes provision of two additional holes on the hylam board on either side for cable conductor entry. The work shall be done as per instruction of site engineer at site.	Numbers	2700.00	8.93	24111.00
17	17	Installation wiring testing and commissioning of Fuse changeover system (FACS). This includes provision of common Buzzer & indication at ASM Room & ESM Duty Room and painting of fuse details. This also includes fabrication of frame for installation of FACS at Station/ LC gate where installation of relay racks not feasible. (UNIT READ AS 'PERMODULE')	Set	6.00	1222.08	7332.48
18	18	Excavation, casting and plastering (above ground level) of main signal foundation as per Drg. No.WCR/S&T/SIG/01 with contractor's own materials including cement and galvanised anchor bolts of standard size. The hole for cable entry should be kept as per site requirement and instruction of Rly engineer at site. The required scaffolding Ferma etc. for casting of foundation will have to be brought by the contractor at his own cost.	Numbers	18.00	8606.10	154909.80

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWKS2026-27SIG04

Closing Date/Time: 19/06/2026 15:00

19	19	Erection of CLS Post with Surface base and signal unit on top or on OFF set Bracket, fixing of front and back staging, ladder and guards, signal name plates and A/AG/C/P/G marker board, protective screen, blanking of ladder (0.6mm MS sheet), if any, with contractors own brackets and fixing materials. This also includes erection of auxiliary signals like calling on, shunt signal, if any. The work shall be done as per instructions of Rly engineer at site. Wooden white cross- arms(1000x100 mm) to be provided by the contractor till the signals are commissioned with contractor's own material.	Numbers	18.00	2970.95	53477.10
20	20	Termination of tail cable on main & auxiliary signal units and wiring with contractor own material, fixing of LED signal units etc. Flexible Single core copper wire 2.5 sq.mm (50/0.25) conforming to IS-694:1990 (as per aspect colour) and lugs etc. will be supplied by the contractor. This includes insertion of tail cables from ground to signal unit. The work shall be done as per instruction of Rly engineer at site.	Numbers	18.00	12.09	217.62
21	21	Excavation, casting and plastering (above ground level) of Apparatus case foundation with contractors own Metal Sheet frame, cement, anchor bolts with nuts & washers and other materials. The items also include additional earth work, if required, as per instruction of Rly. Engineer at site. Single case as per Drg No. WS-8842/A	Numbers	15.00	8902.65	133539.75
22	22	Erection of apparatus cases. This includes filling of location foundation with river bed sand and plastering on top of the sand. Single case	Numbers	15.00	934.09	14011.35
23	23	Fabrication and fixing of phenolic board in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated string rods at the back side for cable support with contractor's own materials. Lacing and dressing of cables/wires terminated with contractors own supply of lacing thread. The work shall be done as per instructions of Rly engineer at site. Single case	Numbers	15.00	1458.23	21873.45
24	24	Painting two coats of enamel paint over one coat of Red Oxide primer on the following items after scrapping and cleaning of the surface wherever necessary. Primer and Paints both Asian paints / Berger / Shalimar are to be supplied by Contractor. The work shall be done as per instructions of Rly engineer at site and extant practice on W.C. Rly on location boxes, signal posts, TLJB. This includes lettering/Numbering of signals, point machine, TLJB, Block joints, apparatus cases also Termination particulars, equipment names etc. legibly and neatly inside location boxes etc. Apparatus case full size	Numbers	15.00	417.70	6265.50

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWS2026-27SIG04

Closing Date/Time: 19/06/2026 15:00

25	25	Painting two coats of enamel paint over one coat of Red Oxide primer on the following items after scrapping and cleaning of the surface wherever necessary. Primer and Paints both Asian paints / Berger / Shalimar are to be supplied by Contractor. The work shall be done as per instructions of Rly engineer at site and extant practice on W.C. Rly on location boxes, signalposts, TLJB. This includes lettering/Numbering of signals, point machine, TLJB, Block joints, apparatus cases also Termination particulars, equipment names etc. legibly and neatly inside location boxes etc. Main Signal post with signal unit, surface base and complete fittings as per W.C.Rly. Standard practice.	Numbers	18.00	168.99	3041.82
26	26	Lettering numbering termination particulars, equipments names etc. legibly and neatly inside location boxes.	Numbers	15.00	253.48	3802.20
27	27	Lettering numbering of signals, point machine, track lead junction boxes, block joint, apparatus cases etc.	Numbers	33.00	56.29	1857.57
28	28	Lettering & Numbering of detail and description writing of particulars of terminations & equipments on relay rack, relays, cable termination rack, battery & power equipments, IPS, operating panel, axle counter etc. constituting entire system with contractor's own paint and writing material ("Asian" make or similar enamel paint or similar paint only to be used). This includes supply and fixing of Teflon strips 3mm thick and 25 mm wide for each row of relays and cable terminations. The work shall be done as per extant practice on W.C. Rly & instruction of Rly engineer at site. (unit is per LC gate)	LC Gate	3.00	4021.33	12063.99
29	29	Installation & fixing of earth electrode assembly including earth wire connected through GI wire 8 SWG supported on M.S. flat of size 6mm x 40mm to earth electrode for signaling Equipment such as lever frames, apparatus cases, signals, relay racks, block instruments etc. as per RE manual. The earth value should be less than 10 ohms including the lead wire. It should be documented and painted on earth enclosure made of concrete (only earth electrodes will be supplied by Rly.) Contractor will bring Earth enclosure and all other material required for provision of earthing.	Numbers	45.00	1827.17	82222.65

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWKS2026-27SIG04

Closing Date/Time: 19/06/2026 15:00

30	30	IPS Installation and Wiring:Installation and Wiring from Integrated Power Supply System including Connection to change-over unit. This includes transportation,Loading and unloading of IPS system complete and batteries from depot to the site of installation and power distribution connection to busbars and relay racks in the room with contractor's own wiring materials, Ladder, DWC pipe and including his own supply of power wire required like 6 Sq mm, 16 Sq. mm &25 Sq. mm etc. and fabrication and fixing of AC/DC power distribution board if required made on Hylum sheet with connections suitable for 32 Amp. Ring supply arrangement will be made with own contractor materials. All connectors as per site requirement to be arranged by contractor as per instructions of railway engineer at site. This also includes fixing and wiring of one exhaust fan in the IPS room. Fan will be supplied by the railway.	Set	3.00	30343.50	91030.50
31	31	Installations, wiring, testing and commissioning of Remote Terminal Unit complete along with accessories with Contractors own wiring & fixing material, (It includes loading of NETWORKING software and networking with data logger, The requisite communication cable/channel for networking will be arranged by Railway.	Set	3.00	23426.22	70278.66
32	32	Providing earth Electrode and earthing connections in Rocky area with mechanized drilling of 6 inch (150mm) dia hole, 3 meter deep. All other items for installation of earth electrode assembly shall be followed as per WCR Drg. No. S&T/CON/KOTA/ EARTHING/01 ALT - 01 and connecting through stainless steel wire 8 SWG supported on M.S. flat of size 5mm x 40mm to earth electrode as per drg. No. T/2014/1 for signals and T 2014/5 for location boxes. The earth value should be less than 10 Ohms including the lead wire. The value should be measured in presence of Rly. Supervisors. It should be documented and painted on earth enclosure made of concrete. Only earth electrode will be supplied by Railway. All other material required for provision of earthing will be brought by the contractor. This earth can be provided for DPs, block instruments & ELD etc. also, so as to achieve the desired earth resistance value. Earth enclosure to be manufactured & supplied by contractors own material of ratio 1:3:6, without cover. Additional connection of Earth pipe including parallel connection with other earth pipes with the function shall be done using left over pieces of signalling cable. Laying of cable pieces shall be covered in laying of cable item and cable shall be supplied by Railways.	Numbers	3.00	15792.69	47378.07

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWS2026-27SIG04

Closing Date/Time: 19/06/2026 15:00

33	33	Preparation & submission of cable route plan of main & tail cables, cable corage plan, location particulars, CT rack particulars, meggering report, earth resistance particulars, traction bonding diagram and any other drawing / particular required in Auto CAD in minimum A3 size. Each sheet should have a block for signature of Railway Officials as well as block for signature of the firm, where signature shall be put up by the authorized signatory of the firm. The name of the work as given by the Railways shall be written on every sheet under the WORK column. One complete set of tracings and four sets of copies of complete above detailed particulars / drawings alongwith one CD to be supplied by the contractor in thick plastic folder. UNIT- Per LC with station.	Lot	3.00	20827.37	62482.11
34	34	Design and supply of Detailed Signalling Circuits including panel diagram, GWR, Control table, Route section plan, Selection Table, Fuse & Negative Tag Analysis, Contact Analysis, Relay Rack Arrangement and wire count sheet etc. as applicable in A3 size, Completion circuit shall be plotted in Autocad. The contractor shall initially supply 2 Sets of circuits duly signed by the circuit designer having substantial experience on design side for making such circuits , complete for approval of Railways. Railway will return one set of circuit to the contractor duly approved with alterations/ corrections, if any. The contractor shall incorporated Railway's alterations/corrections in the original tracings & CD without any deviation and submit two copies of the modified circuits. Original tracings so modified & final CD complete in all respects alongwith 4 sets of final approved circuits (out of which one set shall be supplied in transparent polythene bags. Only two sheets of circuits shall be placed in one polythene bag/cover each) shall be submitted to the Railways in case there are no further alteration suggested by Railways. (Unit=per stn/LC)	Numbers	3.00	87022.04	261066.12
35	35	All works pertaining to horizontal directional drilling (HDD)/boring and trenchless cabling. It includes supply, transportation and insertion of self lubricated HDPE pipe and laying of cable in boring under the track /road /platform / circulating area by using different size of pipes depending on the total number of cables will be crossed. The depth of horizontal boring should be minimum 2 meter upto 3.0 meter from rail flange/road level/ ground level as per direction of Engineer in-charge. This item will be used for track crossing of running line, road crossing and circulating area. By using self lubricated HDPE pipe of 120mm outer dia and 103.5mm inner dia in the bore and laying of cable in the bore under the track/road/ circulating area.	Metre	300.00	1871.31	561393.00

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWKS2026-27SIG04

Closing Date/Time: 19/06/2026 15:00

36	36	Dismantling / Releasing of existing Signaling Gears. One Signalling gear will be all parts of one signal (consisting of CLS unit, Signal post along with base) or lever frame (5levers set), or one point (consisting of all parts of a mechanical point, point machine, ground connections etc.) or one track circuits (consisting of battery box & other parts of DC Track circuit /AFTC /DAC) or one Block instruments etc. This includes the cost of transportation of release materials to store depot or as decided by consignee in charge. This work to be done by contactors with his own vehicle and labour.	Numbers	12.00	1254.62	15055.44
37	37	Printing of WMS 3.2 (EX5)RI YE-Shrink sleeve Roll, unperforated, mounting type: slide-on, Number of individual labels: 1, roll length: 30 m, Shrink rate -3:1 ,Halogen-free, Polyolefin Material , Wipe resistance DIN EN 61010-1 (VDE 0411-1) , Colour : Yellow, Green, Blue, Red, Orange, unlabeled, suitable for 0.25 Sq.mm to 1.5 Sq.mm wire size (Inclusive of Materials). 1 Lot = 1000 Nos.	Lot	6.00	9899.00	59394.00
38	38	Printing of WMS 4.8 (EX9)RI YE Shrink sleeve Roll, unperforated, mounting type: slide-on, Number of individual labels: 1, roll length: 30 m, Shrink rate-3:1 ,Halogen-free, Polyolefin Material , Wipe resistance DIN EN 61010-1 (VDE 0411-1) , Colour : Yellow, Green, Blue, Red, Orange, unlabeled, suitable for 0.6 Sq.mm to 2.5Sq.mm wire size (Inclusive of Materials) 1 Lot = 1000 Nos.	Lot	6.00	11962.16	71772.96
39	39	Patching work in existing location consisting (i) Digging of pit, cleaning of earth from all sides, breaking of seal of location boxes, removal of sand , from location, marking of new cable hole. (ii) Insertion of cable from ground. (iii) making place from cable termination in old location, shifting of ARA, fuse etc after removal of termination, including shifting of ARA.(iv) Fixing and Termination of cable in old location. (v) Sand filling and plastering.	Numbers	3.00	10307.69	30923.07
40	40	Installation testing and commissioning of electrically operated lifting barrier,complete with casting of cement concrete foundation for boom rest post, pedestal,cablling, power supply connection & wiring with complete indoor/outdoor work.	Set	3.00	12628.21	37884.63
41	41	Fabrication, supply, transport,erection at site, sliding type mechanical type boom, make assembly, movement drive mechanism, resting stand etc.as per following technical specification: Note: Rates included for all required nut and bolts, chains, padlocks 2No. and other miscellaneous are to be supplied by contractor. MS Boom 65 mmdia. 10/12 mtr. Long (dividing in two pieces nut and bolts arrangements, pulling handand boom locking arrangements etc.	Numbers	6.00	15321.03	91926.18

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWS2026-27SIG04

Closing Date/Time: 19/06/2026 15:00

42	42	Fabrication, supply, transport,erection at site, sliding type mechanical type boom, make assembly, movement drive mechanism, resting stand etc.as per following technical specification: Note: Rates included for all required nutand bolts, chains and other miscellaneous are to be supplied by contractor.Resting stand made up of C channel 150mm x 75mm x6mm thick for resting the boom movement frame/meeting post grouting type.	Numbers	30.00	7660.49	229814.70
43	43	Fabrication, supply, transport,erection at site, sliding type mechanical type boom, make assembly, movement drive mechanism, resting stand etc.as per following technical specification: Note: Rates included for all required nut and bolts, chains and other miscellaneous are to be supplied by contractor. Boom movement rectangular frame made up by C channel 75 mmx 37 mm x 6 mm 9.5 mtr.long and 250 mm width (it should divided in two pieces nut and bolt arrangement)with necessary boom movement rollers arrangement and boom driving mechanism made upof 4 ball bearings, boom replacement arrangements etc.	Numbers	6.00	27224.82	163348.92
44	44	Fabrication, supply, transport,erection at site, sliding type mechanical type boom, make assembly, movement drive mechanism, resting stand etc.as per following technical specification: Note: Rates included for all required nut and bolts, chains and other miscellaneous are to be supplied by contractor. MSPlate of size 20"x20"x6 mm form boom locking arrangements with front and back covers. (only E types lock will be supplied by Railways)	Numbers	6.00	4624.87	27749.22
45	45	Fabrication, supply, transport,erection at site, sliding type mechanical type boom, make assembly, movement drive mechanism, resting stand etc.as per following technical specification: Note: Rates included for all required nut and bolts, chains and other miscellaneous are to be supplied by contractor. Supply of teak wood/ Iron board for fixing 2 No. of EKTs with 2 No.of push button, 6 No. 10 mm Led resistance holders etc.(Only EKTs will be supplied byRailways)	Set	3.00	7337.04	22011.12
46	46	Fabrication, supply, transport,erection at site, sliding type mechanical type boom, make assembly, movement drive mechanism, resting stand etc.as per following technical specification: Note: Rates included for all required nut and bolts, chains and other miscellaneous are to be supplied by contractor.Fabrication, supply, fixing of MS of size 10'x18'x9' with locking arrangement for locking the boom in standby mode.	Numbers	6.00	4144.14	24864.84

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWS2026-27SIG04

Closing Date/Time: 19/06/2026 15:00

47	47	Fabrication, supply, transport,erection at site, sliding type mechanical type boom, make assembly, movement drive mechanism, resting stand etc.as per following technical specification: Note: Rates included for all required nut and bolts, chains and other miscellaneous are to be supplied by contractor. Supply and fixing of retro reflective aluminum sheeted stop board.	Numbers	6.00	4144.45	24866.70
48	48	Fabrication, supply, transport,erection at site, sliding type mechanical type boom, makeassembly, movement drive mechanism, resting stand etc.as per following technical specification: Note: Rates included for all required nut and bolts, chains. and other miscellaneous are to be supplied by contractor.Excavation of pit and concreting foundations for resting stand/meeting stand. (unit=LS)	Lumpsum	3.00	27208.64	81625.92
49	49	Fabrication, supply, transport,erection at site, sliding type mechanical type boom, make assembly, movement drive mechanism, resting stand etc.as per following technical specification: Note: Rates included for all required nut and bolts, chains and other miscellaneous are to be supplied by contractor. Supply of paint approved quality and painting of sliding type boom,boom movement frame,resting stand, meeting postetc. as per regular standard practice with 2 coats of enamel paint black and yellow colour with 12mm width retro reflective RED, YELLOW striker. (UNIT=LS)	Lumpsum	3.00	9069.52	27208.56
					Total	3710433.06

4. ELIGIBILITY CONDITIONS

Standard Financial Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	IR GCC 2022 ACS 1 CLAUSE 10.2 Financial Eligibility Criteria: The tenderer must have minimum average annual contractual turnover of V/N or 'V' whichever is less; where: V= Advertised value of the tender in Crores of Rupees, N= Number of years prescribed for completion of work for which bids have been invited. The average annual contractual turnover shall be calculated as an average of "total contractual payments" in the previous three financial years, as per the audited balance sheet. However, in case balance sheet of the previous year is yet to be prepared/audited, the audited balance sheet of the fourth previous year shall be considered for calculating average annual contractual turnover. The Tenderers shall submit requisite information as per Annexure-VIB, along with copies of Audited Balance Sheets duly certified by the Chartered Accountant/ Certificate from Chartered Accountant duly supported by Audited Balance Sheet.	No	No	Allowed (Mandatory)

Standard Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
-------	-------------	-----------------------	-----------------	---------------------

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWKS2026-27SIG04

Closing Date/Time: 19/06/2026 15:00

1	IR GCC 2022 ACS 1 CLAUSE 10.1 - 1. Technical Eligibility Criteria: (As Per IR GCC Clause 10.1) (a)The tenderer must have successfully completed or substantially completed any one of the following categories of work(s) during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: (i) Three similar works each costing not less than the amount equal to 30% of advertised value of the tender, or (ii) Two similar works each costing not less than the amount equal to 40% of advertised value of the tender, or (iii) One similar work costing not less than the amount equal to 60% of advertised value of the tender. (b) (1) In case of tenders for composite works (e.g. works involving more than one distinct component, such as Civil Engineering works, S&T works, Electrical works, OHE works etc. and in the case of major bridges - substructure, superstructure etc.), tenderer must have successfully completed or substantially completed any one of the following categories of work(s) during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: (i) Three similar works each costing not less than the amount equal to 30% of advertised value of each component of tender, or (ii) Two similar works each costing not less than the amount equal to 40% of advertised value of each component of tender, or (iii) One similar work each costing not less than the amount equal to 60% of advertised value of each component of tender. Note for b(1): Separate completed works of minimum required values shall also be considered for fulfillment of technical eligibility criteria for different components. Note - Works Completion certificate of Similar work along with copy of LOA as per IR GCC 2022 may be submitted (If MEC Applicable), this shall be on bidder's name. NOTE - SUBSTANTIALLY COMPLETED WORKS IS DEFINED IN TENDER DOCUMENT ATTACHED HERewith vide Para 10.5 of GCC April 2022 with latest applicable ACS.Similar nature of the work:- Any work of EI / PI / RRI / ABS/ IBH/ LC Gate interlocking work which include indoor and outdoor signalling work.	No	No	Allowed (Mandatory)
1.1	Work experience certificate from private individual shall not be considered. However, in addition to work experience certificates issued by any Govt. Organisation, work experience certificate issued by Public listed company having average annual turnover of Rs 500 crore and above in last 3 financial years excluding the current financial year, listed on National Stock Exchange or Bombay Stock Exchange, incorporated/registered at least 5 years prior to the date of closing of tender, shall also be considered provided the work experience certificate has been issued by a person authorized by the Public listed company to issue such certificates. In case tenderer submits work experience certificate issued by public listed company, the tenderer shall also submit along with work experience certificate, the relevant copy of work order, bill of quantities, bill wise details of payment received duly certified by Chartered Accountant, TDS certificates for all payments received and copy of final/last bill paid by company in support of above work experience certificate.	No	No	Allowed (Mandatory)

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.
3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.
5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.
6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.
7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWS2026-27SIG04

Closing Date/Time: 19/06/2026 15:00

8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.
9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.
10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description
1	Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. (Click here to download the Format of Self Certification)

5. COMPLIANCE

Commercial-Compliance

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The local content requirement for this work is minimum 50% for Make in India compliance. The offer submitted by the firm against this tender shall be in compliance of Order No. P-45021/2/2017-PP (BE-II)-Part(4)Vol.II dated 19.07.2024 of Department of Promotion of Industry and Internal Trade, Ministry of Commerce and Industry attached with this tender as PDF. Non-compliance of this Make in India order in the offer submitted by the firm shall lead to summarily rejection of the offer. The tenderer shall enter local content percentage under Sl. No. 2 of Commercial-Compliance with their offer.	No	No	Not Allowed
2	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)
3	The said suppliers of goods and/or services would be subject to GST Act and rules as applicable from time to time. Tenderers are requested to submit their offers as per GST Tax regime. All the bidders/tenderers should ensure that they are GST compliant and their quoted tax structure/rates are as per GST Law.	No	No	Not Allowed

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWKS2026-27SIG04

Closing Date/Time: 19/06/2026 15:00

4	In case of sole proprietorship Firm: A copy of notarized affidavit on Stamp Paper declaring that his Concern is a proprietary Concern and he is sole proprietor of the Concern OR HUF: A copy of notarized affidavit on Stamp Paper declaring that he who is submitting the tender on behalf of HUF is in the position of 'Karta' of Hindu Undivided Family (HUF) and he has the authority, power and consent given by other members to act on behalf of HUF. OR for Partnership Firms: (i) A notarized copy of the Partnership Deed or a copy of the Partnership deed registered with the Registrar. (ii) A notarized or registered copy of Power of Attorney in favour of the individual to tender for the work, sign the agreement etc. and create liability against the firm. OR For Company registered under the Company's Act: (i) The copies of MOA (Memorandum of Association) / AOA (Articles of Association) of the company. (ii) A copy of Certificate of Incorporation. (iii) A copy of Authorization /Power of Attorney issued by the Company (backed by the resolution of Board of Directors) in favour of the individual to sign the tender on behalf of the company and create liability against the company. OR For Registered Society and Registered Trust: (i) A copy of Certificate of Registration. (ii) A copy of Memorandum of Association of Society/Trust Deed. (iii) A copy of Power of Attorney in favour of the individual to sign the tender documents and create liability against the Society/Trust. (iv) A copy of Rules & Regulations of the Society. OR For Limited Liability Partnership (LLP) Firms: (i) A copy of LLP Agreement. (ii) A copy of Certificate of Incorporation. (iii) A copy of Power of Attorney /Authorization issued by the LLP in favour of the individual to sign the tender on behalf of the LLP and create liability against the LLP. Concealment / wrong information in regard to above shall make the contract liable for determination under Clause 62 of the Standard General Conditions of Contract. In Absence of these documents, offer of the firm will be summarily rejected. For more clarification regarding this, pls refer GCC April 2022 with latest ACS available on railway official website.	No	No	Allowed (Mandatory)
---	--	----	----	------------------------

General Instructions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	I/We agree to carry out all works with use of modern equipments of required capacity for the work without extra payment. The decision of railway engineer shall be final and binding in this regard.	No	No	Not Allowed
2	It is the responsibility of contractor to arrange the payment of the labour employed for the work through bank and to deduct PF as per the provisions of Minimum Wages Act.	No	No	Not Allowed
3	The quantities shown above are approximate and to give a general guideline. Railway reserves a right to increase, decrease or to delete any of the items mentioned in schedule.	No	No	Not Allowed

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWKS2026-27SIG04

Closing Date/Time: 19/06/2026 15:00

4	Special Conditions of Contract for Mandatory Updating of Labor Data or Railway's Shramikkalyan Portal by Contractor as per Railway Board's letter No2018/CE-I /CT/4 dated 17.10.2018: In order to increase in payment of contract labour wages and other payments aweb-based e- application has been developed and hosted on website www.shramikkalyan.indianrailways.gov.in All contractors are required to upload details of their LOAs, engaged workmen, wage payment details, PF/ESI details, bonus details etc., on monthly basis. The details so uploaded shall be available in public domain.. In order to ensure the compliance and fulfillment of these instructions, following action is required to be completed by contractors: A) Contractor is to abide by the provisions of Payment of Wages Act and Minimum wages Act in terms of Clause 54 and 55 or Indian Railways General Conditions of Contract. In order to ensure the same, an application has been developed and hosted on website www.shramikkalyan.indianrailways.gov.in . Contractor shall register his firm/company etc. and upload requisite details of labor and their payment in this portal. These details shall be available in public domain. The Registration/updating of Portal shall be done as under:-a)contractor shall apply for one time registration of his company/firm etc. in the Shramikkalyan portal with requisite details subsequent to issue of Letter of Acceptance Engineer shall approve the contractor's registration on the portal within 7 days of receipt of such request. b)Contractor once approved by any Engineer, can create password with login 1D (PAN No.) for subsequent use of portal for all LoAs issued in his favor. c)The contractor once registered on the portal, shall provide details of his letter of Acceptance (LOA)/Contract Agreements on Shramikkalyan portal within 15 days of issue of any LoA for approval of concerned Engineer. Engineer shall update (if required) and approve the details of LoA filled by contractor within 7 days of receipt of such requested) After approval of LoA by Engineer, contractor shall fill the salient details of contract labours engaged in the contract and ensure updating of each wage payment to them on Shramikkalyan portal on monthly basis. e)It shall be mandatory upon the contractor to ensure correct and prompt uploading of all salient details of engaged contractual labour and payments made thereof after each wage period. B)While processing payment of any On Account bill or Final bill or release of Advances or Performance Guarantee/Security Deposit, Contractor shall submit a certificate to the Engineer or Engineer's representatives that I have uploaded the correct details of contract labours engaged in connection with this contract and payments made to them during the wage period in Railway's Shramikkalyan portal atwww.shramikkalyan.indianrailways.gov.in till..Month... Year.....	No	No	Not Allowed
5	GCC April 2022 with latest ACS has been introduced and published/available on railways website. The provisions of GCC 2022 or latest amendments released till the time of date of publishing of tender will be applicable on this tender. Tenderers are requested to download the same from the railways website and ensure the implementation of the latest provisions made in GCC while execution of work.	No	No	Not Allowed

Undertakings

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	I/we have carefully gone through the IR GCC 2022 with latest ACS, tender documents, specifications, special conditions, Annexures etc. attached with the tender documents.	No	No	Not Allowed
2	I/We undertake to keep this offer valid for a period indicated in tender documents from the date of opening of tender and further not to revoke the same before the expiry of such period.	No	No	Not Allowed
3	I/We have Visited the works site and I We am/ are aware of the site Conditions.	No	No	Not Allowed

Custom

**BHOPAL DIVISION-S AND T/WEST CENTRAL RLY
TENDER DOCUMENT**

Tender No: BPLNWKS2026-27SIG04

Closing Date/Time: 19/06/2026 15:00

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Maintenance period for this work will be 12 months from the date of successful completion of work.	No	No	Not Allowed

6. Documents attached with tender

S.No.	Document Name	Document Description
1	GCCApril2022.pdf	GCC April 2022
2	GCCAPRIL2022ACS1toACS112.pdf	GCC April 2022 ACS01 to ACS11
3	AnnexureVI-B.pdf	Annexure VIB
4	MII_Revision_Order_19July2024.pdf	MI Order
5	TenderbookletLC1461311362.pdf	Tender booklet

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

Signed By: SANJEEV KUMAR JAIN

Designation : Sr.DSTE