

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2026-03

Closing Date/Time: 25/06/2026 15:00

Sr.DSTE acting for and on behalf of The President of India invites E-Tenders against Tender No **KOTA-SNT-SIG-2026-03** Closing Date/Time 25/06/2026 15:00 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

1. NIT HEADER

Name of Work	Replacement of old and outlived POLB's over Kota Division for improving reliability of Signalling installation.		
Bidding type	Normal Tender		
Tender Type	Open	Bidding System	Single Packet System
Tender Closing Date Time	25/06/2026 15:00	Date Time Of Uploading Tender	26/05/2026 17:00
Pre-Bid Conference Required	No	Pre-Bid Conference Date Time	Not Applicable
Advertised Value	41954293.17	Tendering Section	SIGNAL
Bidding Style	Single Rate for Tender	Bidding Unit	Above/Below/Par
Earnest Money (Rs.)	839100.00	Validity of Offer (Days)	60
Tender Doc. Cost (Rs.)	0.00	Period of Completion	18 Months
Contract Type	Works - General	Contract Category	Expenditure
Bidding Start Date	11/06/2026		
Are JV allowed to bid	No	Number of JV Member Allowed	0
Are Consortium allowed to bid	No	Number of Consortium Member Allowed	0
Ranking Order For Bids	Lowest to Highest	Expenditure Type	Capital (Works)

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () sch-schedule							41954293.17	
1	Please see Item Breakup for details.				22880198.70	AT Par	22880198.70	
	Description:- SCHEDULE-A							
2	Please see Item Breakup for details.				19074094.47	AT Par	19074094.47	
	Description:- SCHEDULE-B							

3. ITEM BREAKUP

Schedule	Schedule sch-schedule					
Item- 1	SCHEDULE-A					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply of QNA1 (AC immunised relay), 12F-4B and 8F-8B, 24VDC along with plug board (Base plate), retaining clips and connectors conforming to BRS:931A, IRS:S34 & IRS:S23. Break-up of configuration will be given by railways before supply of material.	Numbers	168.00	5437.68	913530.24
2	2	Supply of relay QN1 (Non ACimmunized relay), 8F-8B/12F-4B (24V) along with plug board (Baseplate), retaining clips and connectors conforming to BRS:930, IRS:S34 & IRS:S23. Break-up to be taken from Railways before supply of material.No.2846459.07 542,561.88	Numbers	84.00	6459.07	542561.88
3	3	Supply of Relay QNNA1 4F/4B	Numbers	84.00	4987.24	418928.16

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2026-03

Closing Date/Time: 25/06/2026 15:00

4	4	Supply of Plug In type, two DC neutral line, mechanically interlocked, in mini group housing, complete with base plate each 60V 4F/4B, front and back contacts metal to metal conforming to IRS:S 46, S23, S34 as applicable and firms specification The relays of various contact configuration shall be 5F/3B - 35%, 4F/4B - 65% or as specified by site incharge.	Numbers	168.00	11484.76	1929439.68
5	5	Supply of Key Lock Relay AC immunised with different ward combinations (Five extra sets of ward plates to be supplied with each relay). Siemens make working on 24/60V DC 4F/4B or equivalent (Extra No. of wards to be supplied with the consultation of Engineer in charge of work, as per requirement of site and no additional cost will be paid for extra wards). The ward combination shall be A, B, C, D, E, F, G-----Z.	Numbers	84.00	14091.15	1183656.60
6	6	Supply of PVC insulated flexible wire 16/0.2 mm dia as per RDSO spec. Nos.IRS:S-76/89 with latest amendments of various colours to be decided by Sitein-charge.	Kilometre	26.00	8160.65	212176.90
7	7	Supply of PVC indoor cable 1x24x1 mm dia colour coding of insulation of inner core shall be in six colour viz. Blue, Red, Green, Grey, Brown & Black conforming to IRS 76/89 or latest	Kilometre	3.00	181786.28	545358.84
8	8	Supply of two in two out (4 conductor) Knife edge disconnect terminal block set as per RDSO/SPN/189/2004 ver. 3.0 with latest amendment.	Numbers	8400.00	90.50	760200.00
9	9	Supply of Earth Electrode assembly as per Drg. No. S&T/CON/KOTA/EARTHING/01 ALT - 01. All nut, Bolts & Lugs to be of stainless steel. The earth electrode pipe shall be 'B' Class/ Medium Grade as per Specification No. IS: 1239 Pt. 1/ 2004 of Nominal Inner Dia 50mm, Outside dia (Max 60.8 mm, Min 59.7 mm), Thickness (3.6mm), Tolerance in Thickness ('+' not limited, '-' 12.5 percent).	Numbers	252.00	1779.60	448459.20
10	10	Supply of maintenance free earth consisting as per Latest RDSO TAN " STS/E/TAN/3006 Ver 3.1 Dated:25/06/2025" consisting of single earth pit which includessupply of 35 mm ² /16 mm ² /10 mm ² multistrand single core PVC insulatedcopper cable as per IS 694 forconnecting main earth electrode toMEEB in the equipment room induplicate as per manufacturersrecommendations and as per RDSOspecifications as follow: (MaterialInspected by RITES) (a) Supplyportion (b) Copper bonded steelelectrode of 3.0 meters long, 17 mmdiameter with copper bondingthickness of minimum 250 micronsand UL listed and marked: 1 Nos. (c)Earth enhancement compound ofRDSO approved brand supplied insealed bag of minimum 10 KG: 3Nos. (d) Copper strip of 150mm X 25mm X 6 mm to terminate earth rod:1 Nos. (e) Copper strip of 300mm X25 mm X 6 mm (MEEB): 1 Nos. (f)Copper strip of 150mm X 25 mm X 6mm (MEEB): 1 Nos.	Set	20.00	26145.40	522908.00

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2026-03

Closing Date/Time: 25/06/2026 15:00

11	11	Supply of Electrically operated Lifting Barrier assembly as per RDSO spec. No. - RDSO/SPN/208/2012 Version 2.0 or latest without hand generator operated on 110 V AC voltage. This consists of 2 No. of electrically operated lifting barriers, each boom barrier shall be 32 feet long (4 sections of 8 feet long), 2 pedestals, 8 band circuit controller with limit switches, hand cranks, 2 electric motors 110V AC with maximum current rating, 2 stop boards, 2 No. boom light boxes, CI counter weight & 2 No. of boom support for resting boom and Motorised locking at Lock posts assembly, without fringes, push button type gate control to operate the gate. Crank handle arrangement will be as per Rly. requirement. The movement of the boom over 85 degrees to be restricted mechanically. Motorised locking at Lock posts assembly as per RDSO letter No. RDSO-QASTOLKO (VEND /3/2020-O/o ED /QA /SnT /HQ /RDSO dtd 11.08.2025. TAN spcs: STS/E/TAN/3020 Ver 1.0	Set	42.00	283200.00	11894400.00
12	12	Supply of LED type Indicationcum operating panel to be made of size of 54 mm x34mm cover plates depicting the yard layout, unit signal, track etc. of minimum size(12x8) siemens type Dominos complete wired with full components. The panel should have polycarbonate sheet cover on top to avoid damage while in service Each of the working domino should have all 15 terminals components with wiring. Total No. of Domino (12 x 8) = 96 Nos. Size 54 mm x 34 mm. The length approximately 730 mm x 450 mm. The height is approximately 910mm (rear side) and 820 mm (front side). The panel should have poly carbonated sheet cover on the top. SPARE: 10% of working domino with cover plate completely wired and 10% of LEDs of each colour, 10% (minimum three) of buttons, 10% of counter, 2 magnets, 1 buzzer & 4 bulb extractors shall be handed over as spare after commissioning of the installation by the contractor.	Numbers	5.00	29438.08	147190.40
13	13	Supply of Motorized Locking. One Set Consists of 2 Numbers of Locking arrangements units for 110 AC ELB complete with motor, gear rack & pinion slide unit, 4 no. limit switch, wiring, terminals, enclosure box & base stand compatible with existing Heidz make Electrically operated lifting barrier.	Set	38.00	61360.00	2331680.00
14	14	Supply of Electro Magnetic boom locking system with +VE VC boom locking, LED indicator panel with Buzzer and Indication circuit. Operating Voltage 110VAC or 24 V DC with 110VAC/24VDC Adoptor. Electric current 500 MA Magnetic Lock in power 600 lbs. Magnetic convert Area for boom locking arrangement si As per specifications attached in Drawing No. DRM/KOTA/LC BOOM MAGNET/2024.	Numbers	80.00	5548.36	443868.80
15	15	Supply of Timing Belt for locking in ELB. confirming to RDSO/SPN/208/2012 ver. 2.0 or latest amendment.	Numbers	320.00	460.20	147264.00
16	16	Supply of Limit switch New Top Roller type with 2 No + 2 NC contacts as per RDSO 45 Balaji make model No.102TPR A or similar.	Numbers	480.00	913.70	438576.00
					Total	22880198.70
Item- 2 SCHEDULE-B						

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2026-03

Closing Date/Time: 25/06/2026 15:00

S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Wiring , Alteration, Additional Relays & changes in old control panel as per requirement and instructions of Site supervisorSet38 1,076,160.00	Set	38.00	28320.00	1076160.00
2	2	Excavation of trench as per cable route plan 1.2 mtr deep, 300mm wide at the bottom along main line in normal soil. This work includes covering of cable laid in trenches by loose soil for a layer of 50 mm thickness approximately before covering by shahabad stone/bricks, clearing of route, bushes etc and refilling of the trench by excavated soil and ramming after laying of the required quantity of cables as per instructions of Enginee rat site. If it is not possible to reach the required depth at any location, then the contractor shall obtain prior approval of Engineer-in-charge before commencement of cable laying process and only then shall the proportionate payment.	Kilometre	8.40	153816.39	1292057.68
3	3	Excavation of trench as per cable route plan 1 mtr deep, 300 mm wide at the bottom along main line in hard soil /murum. This work includes covering of cable laid in trenches by loose soil for a layer of 50 mm thickness approximately before covering by Shahabad stone/bricks, clearing of route, bushes etc and refilling of the trench by excavated soil and ramming after laying of the required quantity of cables as per instructions of Engineer at site. If it is not possible to reach the required depth at any location, then the contractor shall obtain prior approval of Engineer-in-charge before commencement of cable laying process and only then shall the proportionate payment be made to the contractor.	Kilometre	2.50	120994.64	302486.60
4	4	Laying of signalling/Power/Telecom cable of various cores/sizes in trenches. The work shall be done asper extant practice followed on W.C.Railway and as per the instructions of Railway Engineer at site.	Kilometre	26.00	18123.56	471212.56
5	5	Transportation & Laying of DWC/GI pipes along with collars in trenches at places wherever required as per extant practice on WCR and instruction of engineer at site.	Metre	252.00	70.71	17818.92
6	6	Excavation of cable trench 1 mtr. deep and 300mm wide across the track for track crossing and refilling after laying of DWC pipes and restore the track to its original condition. The work shall be done as per extant practice on W.C. Rly& instruction of Rly engineer at site.	Metre	252.00	316.51	79760.52
7	7	Cutting of all types of Roads prepratory to trenching & excavation to depth of 1Mtr X 300 mm wide approximately and refilling after laying of DWC/GI pipes and restore to its original condition as per WCR Drg. No. TS/Cable laying/12/03/04 attached. The work shall be done as per extant practice onW.C. Rly & instruction of Rly engineer at site.	Metre	252.00	336.91	84901.32

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2026-03

Closing Date/Time: 25/06/2026 15:00

8	8	Termination of cable cores on ARA terminal/Wago/Pheonix terminal and fuse blocks in apparatus cases/ cable termination rack etc.This includes all associated works of pulling out the cable from underground dressing of cable making wiring etc. Both end of cable core shall be counted as per conductor. It includes cable armouring earthing with contractor's own material. The work shall be done as per location plan and instruction of Rly.engineer at site. (UNIT PER TERMINAL)	Per Conductor	8400.00	13.32	111888.00
9	9	Fixing of ARA/WAGO Terminals/Pheonix terminal in locations with provision of hole in location boxes/CT rack and else where. This includes provision of two additional holes on the hylam board on either side for cable conductor entry.The work shall be done as per instruction of site engineer at site.	Numbers	8400.00	17.76	149184.00
10	10	Lettering & Numbering of detail and description writing of particulars of terminations & equipments on relay rack,relays, cable termination rack,battery & power equipments,IPS, operating panel, axle counter etc. constituting entire system with contractor's own paint and writing material ("Asian"make or similar enamel paintsor similar paint only to beused). This includes supply and fixing of Teflon strips 3mm thick and 25 mm wide for each row of relays and cable terminations. The work shall be done as per extant practice on W.C. Rly & instruction of Rly engineer atsite. (unit is per LC gate)the item per unit will be Per LC gate	Per Unit	42.00	1640.45	68898.90
11	11	Modification of KLCR relay so that KLCR key may take out from CH box when there is NO power supply at station and IPS failure condition.	Numbers	84.00	5214.00	437976.00
12	12	Installation of Motorized Boom locking taken in supply above	Set	38.00	18408.00	699504.00
13	13	Installation & fixing of earth electrode assembly including earth wire connected through GI wire 8 SWG supported on M.S. flat of size 6mm x40mm to earth electrode for signaling Equipment such as lever frames,apparatus cases, signals, relay racks,block instruments etc. as per RE manual. The earth value should be less than 10 ohms including the lead wire.It should be documented and painted on earth enclosure made of concrete(only earth electrodes will be supplied by Rly.) Contractor will bring Earth enclosure and all other material required for provision of earthing.	Numbers	252.00	4831.36	1217502.72

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2026-03

Closing Date/Time: 25/06/2026 15:00

14	14	"Installation of maintenance free earth in Rocky Area as per item supplied against with contractors own materials required for the same. This includes :I. Digging/Auguring/Boring of single earth pit of 100mm to 150mm dia to the depth of approximate 3 M in rocky area. II. Insertion of 3 Mtr electrode and penetrating it at least 0.2 Mtr. By pushing gently with sledge hammer where the neutral soil is assumed. III. Filling of earth pit with earth enhancement compound (EEC) in slurry form and back filling. IV. Filling of earth pit with earth enhancement compound (EEC) in slurry form and back filling. V. Carrying out exothermic weld connection of single earth electrode to a copper tape of 150 x 25 x 6 mm VI. Filling of earth pit with earth enhancement compound (EEC) in slurry form and back filling. VII. Carrying out exothermal weld connection on the copper tape of 150 x 25 x 6 mm on earth electrode for connecting two 35 Sq. mm cable for redundancy VIII. The exothermal welding material for bonding the earth system shall be procured from RDSO approved firms which include graphite moulds, clamps, weld metal powder. IX. The 35 sq mm wire out from building connected to earth shall be in GI pipe of heavy duty. (x) 300mm X 300 mm X 300 mm (inside dimension) concrete earth pit with a concrete lid approximately 50 mm thick with pulling hooks shall be provided to cover the pit. Back side of the cover will be painted in black and date of testing and average earth resistance value shall be written. "The item to be executed as per the guideline of RDSO TAN " STS/E/TAN/3006 Ver 3.1 Dated:25/06/2025"	Set	20.00	20910.76	418215.20
15	15	Dismantling / Releasing of existing Signaling Gears. One Signalling gear will be all parts of one signal (consisting of CLS unit, Signal post along with base) or lever frame (5 levers set), or one point (consisting of all parts of a mechanical point, point machine, ground connections etc.) or one track circuits (consisting of battery box & other parts of DC Track circuit /AFTC /DAC) or one Block instruments or One LC gate etc. This includes the cost of transportation of release materials to store depot or as decided by consignee in charge. This work to be done by contactors with his own vehicle and labour.	Numbers	84.00	1326.24	111404.16
16	16	Preparation of cable duct 150mm x300mm deep for laying of cable in rocky area and refilling the duct (after cable laying) with concrete mixture of proportion 1:3:6 and grouting the ends at either side of the rocky portion using concrete mixture with contractors own cement and other materials.	Metre	1000.00	654.86	654860.00
17	17	Patching work in existing location consisting (i) Digging of pit, cleaning of earth from all sides, breaking of seal of location boxes, removal of sand , from location, marking of new cable hole. (ii) Insertion of cable from ground. (iii) making place from cable termination in old location, shifting of ARA, fuse etc after removal of termination, including shifting of ARA.(iv) Fixing and Termination of cable in old location. (v) Sand filling and plastering.	Numbers	84.00	10412.65	874662.60

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2026-03

Closing Date/Time: 25/06/2026 15:00

18	18	Dismantling of Concrete foundations/Demolishing RCC/CC/Stone Work /Cutting Tarcarpenting/CC Flooring/Pricast Concrete slabs etc./Brick work includingleading the debris inside Railway limit or outside Railway limit as directed by Engineer in charge.	cum	42.00	687.41	28871.22
19	19	Preparation & submission of complete cable route plan of main & tail cables, cable corage plan,location particulars, CT rack particulars, meggering report,earth resistance particulars,traction bonding diagram and any other drawing / particular required in Auto CAD inminimum A3 size. The contractor shall supply the complete documentation mentioned in this item of each Location. The circuits alteration done with respect to the scope of work will be prepared by contractor and existing document will be provided by Railway. The contractor shall merge existing and new circuit alteration to the new Circuits/documents and supply in this item. Each sheet should have a block for signature of Railway Officials as well as block for signature of the firm, where signature shall be put up by the authorized signatory of the firm. The name of the work as given by the Railways shall be written on every sheet under the WORK column. One complete set of tracings and four sets of copies of complete above detailed particulars / drawings alongwith one Pendrive to be supplied by the contractor in thick plastic folder. UNIT- Per LC with station.The tem unit will be Per LC Gate	Per Unit	42.00	31029.32	1303231.44
20	20	Design and supply of Detailed Signalling Circuits including panel diagram, GWR, Control table, Route section plan, Selection Table, Fuse & Negative Tag Analysis, Contact Analysis, Relay Rack Arrangement and wire count sheet etc. as applicable in A3 size, Completion circuit shall be plotted in Autocad. The contractor shall supply the complete documentation mentioned in this item of each Location. The circuits alteration done with respect to the scope of work will be prepared by contractor and existing document will be provided by Railway. The contractor shall merge existing and new circuit alteration to the new Circuits/documents and supply in this item.The contractor shall initially supply 2 Sets of circuits duly signed by the circuit designer having substantial experience on design side for making such circuits , complete for approval of Railways. Railway will return one set of circuit to the contractor duly approved with alterations/ corrections, if any. The contractor shall incorporated Railway's alterations/corrections in the original tracings & Pendrive without any deviation and submit two copies of the modified circuits. Original tracings so modified & final Pendrive complete in all respects alongwith 4 sets of final approved circuits (out of which one set shall be supplied in transparent polythene bags. Only two sheets of cicuits shall be placed in one polythene bag/cover each) along with AutoCad soft copy of all documents shall be submitted to the Railways in case there are no further alteration suggested by Railways. The item unit will be per stn/LC	Per Unit	42.00	78611.79	3301695.18

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2026-03

Closing Date/Time: 25/06/2026 15:00

21	21	Provision of cement concrete work 1:3:6 with 25 mm graded stone aggregated and curing of same as per above.	cum	42.00	3930.30	165072.60
22	22	Installation, transportation, testing and commissioning of electrically operated lifting barrier, complete with casting of cement concrete foundation for pedestal and boom rest post, cabling power supply connection & wiring, painting and lettering with complete outdoor work. The work shall be done as per approved plan, extant practice on W.C. Railway & the instructions of Rly engineer at site (1 Set = 2 Nos. of POLB)	Set	80.00	18883.64	1510691.20
23	23	Installation and complete wiring of of operating cum indication panel for LC gate as per technical specification and site requirement. The indoor wiring inside panel shall be terminated on tag block as per instructions of Engineer-in-charge. The wiring on panel tag blocks shall be repeated on tag blocks located in relay room. This includes laying & termination of cable, if any from Panel Room to Relay Room in HDPE pipe.	Numbers	5.00	6529.86	32649.30
24	24	Fabrication, supply, transport, erection at site, sliding type mechanical type boom, make assembly, movement drive mechanism, resting stand etc. as per following technical specification: Note: Rates included for all required nut and bolts, chains, padlocks 2 No. and other miscellaneous are to be supplied by contractor. MS Boom 65 mm dia. 10/12 mtr. Long (dividing in two pieces nut and bolts arrangements, pulling hand and boom locking arrangements etc.	Numbers	30.00	20653.41	619602.30
25	25	Fabrication, supply, transport, erection at site, sliding type mechanical type boom, make assembly, movement drive mechanism, resting stand etc. as per following technical specification: Note: Rates included for all required nut and bolts, chains and other miscellaneous are to be supplied by contractor. Resting stand made up of C channel 150mm x 75mm x 6mm thick for resting the boom movement frame/meeting post grouting type.	Numbers	150.00	10326.70	1549005.00
26	26	Fabrication, supply, transport, erection at site, sliding type mechanical type boom, make assembly, movement drive mechanism, resting stand etc. as per following technical specification: Note: Rates included for all required nut and bolts, chains and other miscellaneous are to be supplied by contractor. Boom movement rectangular frame made up by C channel 75 mm x 37 mm x 6 mm 9.5 mtr. long and 250 mm width (it should be divided in two pieces nut and bolt arrangement) with necessary boom movement rollers arrangement and boom driving mechanism made up of 4 ball bearings, boom replacement arrangements etc.	Numbers	30.00	36700.17	1101005.10

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2026-03

Closing Date/Time: 25/06/2026 15:00

27	27	Fabrication, supply, transport,erection at site, sliding type mechanical type boom, make assembly, movement drive mechanism, resting stand etc.as per following technical specification: Note: Rates included for all required nut and bolts, chains and other miscellaneous are to be supplied by contractor. MSPlate of size 20"x20'x6 mm form boom locking arrangements with front and back covers. (only E types lock will be supplied by Railways)	Numbers	30.00	7881.47	236444.10
28	28	Fabrication, supply, transport,erection at site, sliding type mechanical type boom, make assembly, movement drive mechanism, resting stand etc.as per following technical specification: Note: Rates included for all required nut and bolts, chains and other miscellaneous are to be supplied by contractor.Fabrication, supply, fixing of MS of size 10'x18'x9' with locking arrangement for locking the boom in standby mode.	Numbers	30.00	7062.78	211883.40
29	29	Fabrication, supply, transport,erection at site, sliding type mechanical type boom, make assembly, movement drive mechanism, resting stand etc.as per following technical specification: Note: Rates included for all required nut and bolts, chains and other miscellaneous are to be supplied by contractor. Supply and fixing of retro reflective aluminum sheeted stop board.	Numbers	30.00	7062.78	211883.40
30	30	Fabrication, supply, transport,erection at site, sliding type mechanical type boom, makeassembly, movement drive mechanism, resting stand etc.as per following technical specification: Note: Rates included for all required nut and bolts, chains. and other miscellaneous are to be supplied by contractor.Excavation of pit and concreting foundations for resting stand/meeting stand.	Numbers	15.00	36678.34	550175.10
31	31	Fabrication, supply, transport,erection at site, sliding type mechanical type boom, make assembly, movement drive mechanism, resting stand etc.as per following technical specification: Note: Rates included for all required nut and bolts, chains and other miscellaneous are to be supplied by contractor. Supply of paint approved quality and painting of sliding type boom,boom movement frame,resting stand, meeting postetc. as per regular standard practice with 2 coats of enamel paint black and yellow colour with 12mm width retro reflective RED, YELLOW striker.	Numbers	15.00	12226.13	183391.95
					Total	19074094.47

4. ELIGIBILITY CONDITIONS

Special Financial Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
-------	-------------	-----------------------	-----------------	---------------------

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2026-03

Closing Date/Time: 25/06/2026 15:00

1	Financial Eligibility Criteria: The tenderer must have minimum average annual contractual turnover of V/N or 'V' whichever is less; where: V= Advertised value of the tender in Crores of Rupees. N= Number of years prescribed for completion of work for which bids have been invited. The average annual contractual turnover shall be calculated as an average of "total contractual payments" in the previous three financial years, as per the audited balance sheet. However, in case balance sheet of the previous year is yet to be prepared/ audited, the audited balance sheet of the fourth previous year shall be considered for calculating average annual contractual turnover.	No	No	Allowed (Mandatory)
1.1	The Tenderers shall submit requisite information as per Annexure-VIB, along with copies of Audited Balance Sheets duly certified by the Chartered Accountant/ Certificate from Chartered Accountant duly supported by Audited Balance Sheet.	No	No	Allowed (Mandatory)

Special Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer must have successfully completed or substantially completed any one of the following categories of work(s) during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: 1Three similar works each costing not less than the amount equal to 30% of advertised value of the tender OR 2Two similar works each costing not less than the amount equal to 40% of advertised value of the tender OR 3One similar work costing not less than the amount equal to 60% of advertised value of the tender	No	No	Allowed (Mandatory)
1.1	UPLOADING OF THE CERTIFICATE:-The tenderers shall submit a copy of certificate stating that all their statements/documents submitted along with bid are true and factual. Standard format of certificate to be submitted by the bidder is enclosed as Annexure-V. In addition to Annexure-V, in case of other than Company/Proprietary firm. Annexure-V(A) shall also be submitted by the each member of a Partnership Firm/ Joint Venture (JV) / Hindu Undivided Family (HUF / Limited Liability Partnership (LLP)etc., as the case may be. Non submission of above certificate(s) by the bidder shall result in summarily rejection of his/their bid. It shall be mandatorily incumbent upon the tenderer to identify, state and submit the supporting documents duly self-attested/digitally signed by which they/he is qualifying the Qualifying Criteria mentioned in the Tender Document.	No	No	Allowed (Mandatory)
1.1.1	DEFINATION OF SIMILIAR NATURE OF WORK:-Any Work of PI / RRI /ABS/IBH work /LC gate interlocking which includes indoor and out door signalling work.	No	No	Allowed (Optional)

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.
3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.
5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.
6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.
7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.
8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2026-03

Closing Date/Time: 25/06/2026 15:00

9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.
10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description
1	Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. (Click here to download the Format of Self Certification)

5. COMPLIANCE

Commercial-Compliance

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)

General Instructions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	All payment and other conditions are attached with tender document.	No	No	Not Allowed
1.1	Although year of specification is given in the schedule, last amendment, if any, shall apply.	No	No	Not Allowed
1.2	All tenderer must have valid GSTN number and rates must be inclusive of GST Act and its amendment.	No	No	Not Allowed
1.3	Compliance of GST act/rules & correction/modification issue by railway board with regard to GST act shall be binding on contractor & railway.	No	No	Not Allowed

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2026-03

Closing Date/Time: 25/06/2026 15:00

1.4	Genral instruction :- 1 The offer will be evaluated based on certificates enclosed with the original offer only. The Railways will not enter into any correspondence to get these certificates subsequently and the offer shall be evaluated based on the documents submitted along with the offer. 2 Tenderer may please note that meeting of eligibility criteria is strictly based on completion certificates issued by the executive in charge of work and not linked with mere list of works claimed to have been executed by the tenderer or a copy of work order from Railways. 3 Tenderer may please note that fulfilling of eligibility clause shall be ascertained only from the completion certificates issued by the executive-in-charge of work and mere list of works claimed to have been executed by the tenderer or a copy of work order from Railways shall not be enough. It may also be noted that cognizance of those works, which are nearing completion or have been almost completed, shall not be taken only those completion certificates, wherein successful commissioning satisfactory performance of work have been clearly unambiguously acknowledged by Executive-in-charge of any Railway Unit or any Govt. Dept./Undertaking for any similar work shall be considered for this purpose. 4 Any variation to quantities in any item and its associated wiring material account of supply and installation will have to be born by the tenderer. Railway Engineer's decision in this regard shall be final. 5 All drawings related with the work can be obtained from the office of DRM Kota on any working day during office hours.	No	No	Not Allowed
-----	---	----	----	-------------

Custom

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenders whether being submitted on behalf of Sole Proprietorship Firm /HUF / Partnership Firm / Joint Venture (JV) / Companies Registered Under Companies Act, 2013/LLP (Limited Liability Partnership) / Registered Society or Registered Trust are required to UPLOAD an UNDERTAKING that - They are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of opening of bids, either in individual capacity or as a member of the partnership firm or JV in which the tenderer was / is a partner/member. Concealment / wrong information in regard to above shall make the contract liable for determination under Clause 62 of the General Conditions of Contract.	No	No	Allowed (Mandatory)

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2026-03

Closing Date/Time: 25/06/2026 15:00

1.1	The tenderers shall UPLOAD VALID DOCUMENTS pertaining to prove the constitution of their firm - 1.In case tenderer is Sole proprietorship firm The tenderer shall submit Valid documents or Notarized Affidavit (As per prevailing law) (Annexure E) of Tender document. 2. In case of HUF: A copy of notarized affidavit on Stamp Paper declaring that he who is submitting the tender on behalf of HUF is in the position of 'Karta' of Hindu Undivided Family(HUF) and he has the authority, power and consent given by other members to act on behalf of HUF. 3.In case of Partnership Firm: The tenderer shall submit :(i) A copy of Partnership Deed and (ii) a copy of Power of Attorney)(Annexure D) of Tender document (duly registered /Notarized as perprevailing law) in favour of an individual to sign the tender documents and create liability against the Firm. 4.Joint Venture (JV): The tenderer shall submit documents as mentioned in Clause 17 of the Tender document (Second Sheet). 5.Company registered under Companies Act-2013: The tenderer shall submit (i) the copies of MOA (Memorandum of Association) / AOA (Articles of Association) of the company; and (ii) A copy of Authorization/Power of Attorney issued by the Company (backed by the resolution of Board of Directors) in favour of the individual to sign the tender on behalf of the company and create liability against the company. 6.LLP (Limited Liability Partnership) Firm: If the tender is submitted on behalf of a LLP Firm registered under LLP Act-2008,the tenderer shall submit alongwith the tender- (i) a copy of LLP Agreement,(ii) a copy of Certificate of Incorporation; and (iii) a copy of Power of Attorney/Authorisation issued by the LLP Firm in favour of the individual to sign the tender on behalf of the LLP Firm and create liability against the Firm.7.Registered Society & Registered Trust: The tenderer shall submit (i) a copy of the Certificate of Registration, (ii) Deed of Formation; and (iii) a copy of Power of Attorney in favour of the individual to sign the tender documents and create liability against the Society/Trust. If the above required documents are not uploaded along with the tender, to prove the STATUS of firm that thetender was submitted on behalf of a Sole Proprietorship firm /HUF/ Partnership firm / Joint Venture / Company registered under Companies Act-2013/ LLP(Limited Liability Partnership) Firm: / Registered Society & Registered Trust: etc., then the tender shall be treated as having been submitted by the individual who has signed the tender and the offer will be dealt accordingly.	No	No	Allowed (Mandatory)
-----	--	----	----	------------------------

6. Documents attached with tender

S.No.	Document Name	Document Description
1	TDKOTA-SNT-SIG-2026-03- UPLOAD.pdf	TD SIG 2026 03

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

Signed By: RAHUL . JAREDA

Designation : Sr.DSTECO/KOTA