

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

Sr. DSTE acting for and on behalf of The President of India invites E-Tenders against Tender No **DRM-RJT-26-27-SnT-E-02R1** Closing Date/Time 22/06/2026 15:30 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

1. NIT HEADER

Name of Work	Rajkot division-S&T Work in connection with (i) Providing ROB in lieu of LC No 135 at Km 755/0-1 Between KHDH - PDH section(2 lanes) (ii) Providing ROB in lieu of LC No 147 at Km 770/1-2 Between PDH - CX section(2 lanes) (iii) Proposed LHS in lieu of LC No. 92 at Km 698/1-2 bet LXR-WKR (iv) Kanalus: Rectification of bad layout from Pt 112 towards PBR side by shifting the turnout by 18m towards RJT.		
Bidding type	Normal Tender		
Tender Type	Open	Bidding System	Single Packet System
Tender Closing Date Time	22/06/2026 15:30	Date Time Of Uploading Tender	23/05/2026 12:37
Pre-Bid Conference Required	No	Pre-Bid Conference Date Time	Not Applicable
Advertised Value	13952517.02	Tendering Section	SRDSTE/RJT
Bidding Style	Single Rate for Tender	Bidding Unit	Above/Below/Par
Earnest Money (Rs.)	279100.00	Validity of Offer (Days)	60
Tender Doc. Cost (Rs.)	0.00	Period of Completion	12 Months
Contract Type	Works - General	Contract Category	Expenditure
Bidding Start Date	08/06/2026		
Are JV allowed to bid	No	Number of JV Member Allowed	0
Are Consortium allowed to bid	No	Number of Consortium Member Allowed	0
Ranking Order For Bids	Lowest to Highest	Expenditure Type	Capital (Works)

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A1-Supply Items (SIGNAL Items for ROB in lieu of LC No 135 at Km 755/0-1 Bet. KHDH - PDH section)							2200800.85	
1	1	1.00	Set	488523.30	488523.30	AT Par	488523.30	
	Description:- Electrically Operated Lifting Barrier complete set suitable for 24V DC supply with out hand generator & motorized boom locking arrangements as per RDSO Spec. SPN/208/2012 with latest amendment. One set consisting 02 Nos of Barriers of length 09.76 Mtrs. along with Spares & tool kit mentioned in RDSO Spec. SPN/208/2012 clause 10.1 & 10.2. (Should be Individual operation of both boom)							
2	2	1.00	Set	66080.63	66080.63	AT Par	66080.63	
	Description:- LED type control-cum indication panel complete with prewired Tag- Blocks, Wires MS angles etc. for LC gate , depicting the yard layout Signal, Point, Track circuit, Operating / emergency Push Button, counter with sealing arrangements, house in a Steel metal cabinet. This shall be consist 15 x 10 exchangeable Domino Unit as per Spec. SPN/186/2004 ver. 1 or latest amendment							
3	3	1.00	Set	1918.60	1918.60	AT Par	1918.60	
	Description:- Cost of supply & fixing of yellow retro-reflective sheet on lifting barrier boom. Intensity grade,encapsulated grade prismatic grade Size 305x290mm one set consist 18 pieces							
4	4	1.00	Numbers	30815.59	30815.59	AT Par	30815.59	
	Description:- Non Metallic (FRP) colour light signal housing multi unit type for railway signalling suitable for RE area FOUR Aspects. Complete without lenses, lamps and signal transformer as per RDSO DRG. No. SA 23001/A/M Adv. Alt- S and as per SPEC. No. RDSO/SPN/194/2006 (Vol. 1.0) or latest and FRP material as per RDSO SPEC. No. RDSO/SPN/151/1997 or latest.							
5	5	4.00	Numbers	31801.84	127207.36	AT Par	127207.36	
	Description:- Non Metallic (FRP) colour light signal housing multi unit type for railway signalling suitable for RE area THREE Aspects complete (without lanse, lamp, holder, transformer) suitable for LED signal as per RDSO DRG. No. SA 23001/A/M Adv. Alt- S and as per SPEC. NoRDSO/SPN/194/2006 (Vol.1.0) or latest and FRP material as per RDSO SPEC. No. RDSO/SPN/151/1997 or latest. (Supply of LED Unit is not covered in this item).							

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

6	6	4.00	Numbers	30356.11	121424.44	AT Par	121424.44	
	Description:- Non Metallic (FRP) colour light signal housing multi unit type for railway signalling suitable for RE area TWO Aspects complete (without lanse, lamp, holder, transformer) suitable for LED signal as per RDSO DRG. No. SA 23No. RDSO/SPN/194/2006 (Vol. 1.0) or latest and FRP material as per RDSO SPEC. No. RDSO/SPN/151/1997 or latest. (Supply of LED Unit is not covered in this item)							
7	7	9.00	Numbers	12161.18	109450.62	AT Par	109450.62	
	Description:- "Colour Light Signal Complete. This includes: - (1). Post Tubular 140 mm Dia, as per IRS: S-6/81 or Latest & RDSO Drg. No. SA-24625 (Advance). (2). CI Base (As per IRS S-10 & RDSO Drg. No. 2011/M with latest assembly). (3). Pinnacle. (4). Ladder Assembly, as per RDSO Drg. No. SA-23156, with Base, Ladder Guards, Platform, Front Maintenance Platform, MS Supporting bracket to Support Ladder. (5). Signal Front Staging Complete Assembly for CLS Unit. (6). Signal back staging as per extent WR Practice. Note: Height of the Post shall be 5.5m / 4.5m/ 3.5m Long. Quantity of each will be decided by the engineer in charge."							
8	8	10.00	Numbers	1867.85	18678.50	AT Par	18678.50	
	Description:- Double Walled Corrugated (DWC) HDPE Pipe with associated collars etc. as per RDSO Specification No. RDSO/SPN/204/2011 or latest anti-rodent & anti-oxidant and non flame propagating type in 6 meters straight length and of size 120 mm outer dia, & 103.5 mm inner dia. (The manufacturers, suppliers must produce valid IS license and should be certified under ISO 9000 and shall submit copy of certificate). One of the following coupling arrangements should also be supplied with each pipe as per the site requirement. 1) Suitable snap fit coupler with rubber 'O-Ring . 2) Spacers 3) Tees 4) Bend, 5) End-cap (The total quantity of above items is equal to no. of pipes supplied.) DWC pipe shall be marked at every 1 mtr length in such a way that manufacturer's name, vender name and year of manufacture can be easily identified.							
9	9	6.00	Running Metre	643.79	3862.74	AT Par	3862.74	
	Description:- Medium Class G.I. Pipes to IS : 1239 (Pt.I)-2004 or latest ; 100mm dia. (int. dia) 3.65 mm+/- 10% thick with coupling. G.I. pipes shall have ISI mark on it and contractor should submit manufacturer's test certificate of G.I. pipes.							
10	10	250.00	Numbers	77.02	19255.00	AT Par	19255.00	
	Description:- ARA Terminal blocks with links made of PBT Spec No.IRS/75/2006(Rev - 2) with latest amendments and RDSO Drg.No.SA-23741A Alt.4.							
11	11	150.00	Numbers	61.79	9268.50	AT Par	9268.50	
	Description:- "Disconnect Terminal Block, Screw less type, as per RDSO Spec. No. RDSO/SPN/189/2004. With latest amendments.Disconnect Terminal Block, Screw less type, 4-wire front entry (Two in-put & Two out-put) The colour will be decided by Engineer - in - Charge. (Preferably In Blue, Red & Grey Colors in the ratio of 1:2:3)"							
12	12	15.00	Numbers	11.50	172.50	AT Par	172.50	
	Description:- Supply of End plate for above item (I) 2.5mm/0.091 in thick as per site requirement.							
13	13	15.00	Numbers	11.50	172.50	AT Par	172.50	
	Description:- Supply of End Stopper for above item (I) 10mm/0.0394 in width as per site requirement.							
14	14	3.00	Metre	120.88	362.64	AT Par	362.64	
	Description:- Supply of Carrier Rails for above 35mm x 7.5mm, 1mm/0.039 in thickness un-slotted type as per site requirement.							
15	15	1.00	Numbers	17.63	17.63	AT Par	17.63	
	Description:- Markers strip for above item (i)							
16	16	3.00	Numbers	5251.96	15755.88	AT Par	15755.88	
	Description:- Phenolic laminated Sheet, grade P3 in standard size of 1220 X 1220 x 10 mm as per spec. No IS 2036 of 1995 or latest. Test report of manufacture to be supplied.							
17	17	3.00	Numbers	2516.29	7548.87	AT Par	7548.87	
	Description:- Thermo shrink Universal Jointing kit for Quad Cable (for straight joints) as per RDSO spec IRS/TC-77/2012 revision 3 With latest Amd.							
18	18	100.00	Numbers	145.65	14565.00	AT Par	14565.00	
	Description:- Cartridge fuse block made of PBT as per RDSO Drg No SA-23748 Alt 4 & Spec No IRS S 75/2006 with latest amendment. Fuse block shall be suitable for round head type voltage fuses. This also includes supply of equivalent no of ND type Fuses of 20A capacity as per specification IRS S-78/92.							
19	19	100.00	Numbers	63.21	6321.00	AT Par	6321.00	
	Description:- Round head type non deteriorating type low voltage cartridge fuse as per Spec No IRS/S/78/92 with latest amendments 6A/10A capacity.							
20	20	50.00	Numbers	57.17	2858.50	AT Par	2858.50	
	Description:- Indicative type Fuse base/ holder with cap, suitable to G type fuse of capacity 0.63A - 3.0A. (System, Rapid, Malnad or RBCO make or similar).							

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

21	21	50.00	Numbers	20.87	1043.50	AT Par	1043.50	
	Description:- Indicative type Fuse suitable to G type fuse base/holder of capacity 0.63 A - 3.0 A (System, Rapid, Malnad or RBCO make or similar).							
22	22	200.00	Numbers	54.28	10856.00	AT Par	10856.00	
	Description:- ND Fuse Cylindrical Type 16 Amp IRS:S. 78/92							
23	23	200.00	Numbers	56.64	11328.00	AT Par	11328.00	
	Description:- ND Fuse Cylindrical Type 20 Amp IRS:S.78/92							
24	24	1.00	Numbers	25617.82	25617.82	AT Par	25617.82	
	Description:- Cable termination racks as per Drg. no. CSTE 5004, 5005, 5006 complete along with fitting arrangements and also with arrangement for fixing four 8-way terminal strips/ Screw less terminals on each row having 16 such rows. Supply of 8 way terminal strips/ Screw less terminals not covered under this item. Cable termination rack shall be Powder Coated.							
25	25	1.00	Numbers	27887.12	27887.12	AT Par	27887.12	
	Description:- Relay racks assembly complete with scaffolding bus bars, fuse strips, fuses, resistors, capacitors, insulators, grouting bolts, tripods etc. as per Drg. No. CSTE /6028 .[Scaffolding should include 20% extra (with minimum of 2 relay rack positions) as spare for future expansion]. Relay rack shall be Powder Coated. (Quantity of Resistance, capacitor & Other items as Annexure.)"							
26	26	3.00	Kilometre	5916.42	17749.26	AT Par	17749.26	
	Description:- Single core multi-strand wire 0.5 sq.mm. (16 conductor each dia. 0.2mm), as per IRS 76/89 (Amd3).							
27	27	1.00	Numbers	41554.88	41554.88	AT Par	41554.88	
	Description:- "Ferro resonant type automatic AC voltage regulator 3 KVA capacity input 160-270V, output 230V as per RDSO Specn IRS S:74/89 with amendment-6 or latest. Accepted Make - ESTAR. "							
28	28	30.00	Kg	114.26	3427.80	AT Par	3427.80	
	Description:- Rubber Mat for Power Equipment room. (5mm thick-RE fit)							
29	29	6.00	Numbers	5638.38	33830.28	AT Par	33830.28	
	Description:- Universal AC ECR of Q series, type "QECX61" suitable for AC LED all signal aspect, Front & back contact Metal to Carbon type complete with plug board retaining clip & connectors conforming to Spec STS/E/Relays/AC Lit LED Signal/09/ 2002, BRS: 941A, IRS:S34 and IRS:S23 (as applicable)							
30	30	8.00	Numbers	5618.29	44946.32	AT Par	44946.32	
	Description:- Relay, AC Immune, Plug-in-type, style "QNA1K" ACI DC Netural line, 24V DC 1000 Ohms 6F.6B contacts, front contacts metal to carbon and back contacts metal to cabon. complete with plugboard, retaining clip and connectors confirming to IRS:S34, IRS:S23, BRS931A. As per RDSO Specification No. STS/E/Relays/UEA(PI) Dt.30/05/97. Annexure II. The interlocking pin code CDEKY.							
31	31	2.00	Numbers	7050.39	14100.78	AT Par	14100.78	
	Description:- Fail safe electronic time delay device mounted on Q series relay base & covered with fixed timing of 60/120/180/240 seconds as specified by purchaser conforming to IRS.S. 61-2000 or latest.							
32	32	3.00	Numbers	8544.44	25633.32	AT Par	25633.32	
	Description:- Key Lock Relay working on 24V DC, AC Immunized with different ward combinations (Three ward plates to be supplied with each relay).							
33	33	2.00	Numbers	8933.44	17866.88	AT Par	17866.88	
	Description:- Fail safe electronic flasher device 24 DC/110V AC as per RDSO Spec No. RDSO/SPN/173/2002 (Amd.2) or latest.							
34	34	3.00	Numbers	9292.09	27876.27	AT Par	27876.27	
	Description:- Dual tone bell/buzzer with 25W horn, working on 24 V DC for road user.							
35	35	2.00	Numbers	1957.72	3915.44	AT Par	3915.44	
	Description:- Road warning flasher kit for L.C. gate as per circuit design.							
36	36	4.00	Set	8850.47	35401.88	AT Par	35401.88	
	Description:- Maintenance Free Earth Electrode of length 3m, including supply of 3 bags of Earth enhancement material for earthling (20KGs /bag) for each electrode & other accessories as per Drg. No. SDO / RDSO/ E&B/001 and RDSO Spec No. RDSO / SPN/197/ 2008.							
37	37	0.20	Kilometre	43762.05	8752.41	AT Par	8752.41	
	Description:- Flexible cable (Power wire), multi-strand copper conductors cross section 1x6 Sq.mm. (85 conductor each diameter 0.30 +/- 0.01) as per IS 694/1990 with insulation thickness of 0.80 mm nominal conductor resistance 3.30 ohms/km and test parameters are as per IRS(S)76/89.							
38	38	0.20	Kilometre	140354.46	28070.89	AT Par	28070.89	

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

	Description:- Flexible cable (Power wire), multi-strand copper conductors cross section (1x16Sq.mm).101 Conductors each diameter 0.45 + 0.01 as per IS 694/2010 with insulation thickness of 1.2mm nominal conductor resistance 1.127 Ohms/ Km and test parameters as per IRS(S) 76/89.							
39	39	1.00	Set	34791.99	34791.99	AT Par	34791.99	
	Description:- Provision of T-Networking suitable for Networking to the existing Data Logger equipments. This includes supply of all equipment / accessories required for the purpose.							
40	40	2.00	Numbers	7382.54	14765.08	AT Par	14765.08	
	Description:- Fire Extinguisher CO2 type (capacity 5 kg or more.)							
41	41	8.00	Numbers	3771.88	30175.04	AT Par	30175.04	
	Description:- Earth Electrode as per Drg. No. CSTE / 6091.							
42	42	1.00	Numbers	21150.00	21150.00	AT Par	21150.00	
	Description:- Supply of ladder (Inspection authority : Consignee)							
43	43	10.00	Numbers	290.41	2904.10	AT Par	2904.10	
	Description:- Hydrometer, Exide make or similar for measuring specific gravity of Battery Graded acid with mounting stand in location Boxes.							
44	44	2.00	Numbers	41822.69	83645.38	AT Par	83645.38	
	Description:- Battery Charger for Railway S&T installation self regulating floor mounting type with 230V AC single phase input and output 24 V DC, as per spec. IRS.S.86/2000 with latestamendments.50 Amp							
45	45	2.00	Numbers	7009.20	14018.40	AT Par	14018.40	
	Description:- "Transformer 230V/110-130V Single phase 1 KVA as per Spec. IRS S-72/88 with latest amendments. (For Signal Lighting)"							
46	46	1.00	Numbers	22414.10	22414.10	AT Par	22414.10	
	Description:- Digital Multimeter of Fluke 287 Industrial, True RMS with temperature, Analog bar graph, Digital display, Backlight, 1000V AC/DC, measure up to 10A, 20A for up to 30 second or Superior.							
47	47	1.00	Numbers	5243.92	5243.92	AT Par	5243.92	
	Description:- Supply of digital Earth tester 4 Terminal for measurement of Earth resistance as per technical specifications .							
48	48	1.00	Numbers	39332.94	39332.94	AT Par	39332.94	
	Description:- Megger 100V to 500V X 20 mega ohms as per specification make: Fluke model No 1507,Motawani or similar.							
49	49	1.00	Numbers	39819.00	39819.00	AT Par	39819.00	
	Description:- Mini AC/DC Low Current Clamp Meter as per Specn. High Sensitivity, Miniature type Clamp, Resolution of 0.1 mA for AC,1 mA for DC Current, Measurement range 0-20 A MakeKEW, Fluke or similar.							
50	50	3.00	Numbers	63420.00	190260.00	AT Par	190260.00	
	Description:- SS AC Box HALF(Fabricated of 2.5mm SS Sheet, Fixed Type)							
51	51	2.00	Numbers	73004.00	146008.00	AT Par	146008.00	
	Description:- SS AC Box FULL(Fabricated of 2.5mm SS Sheet, Fixed Type)							
52	52	1.00	Set	132154.25	132154.25	AT Par	132154.25	
	Description:- MS Sliding type mechanical Boom barrier assembly 11 to 12 Meter Long, movement drive mechanism, resetting & supporting stand suitable for Mechanical/Electrical level crossing gate as an emergency arrangements as per Drg.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A2-Supply Items (SIGNAL Items for ROB in lieu of LC No 147 at Km 770/1-2 Bet. PDH - CX section)							1984863.82	
1	1	1.00	Set	488523.30	488523.30	AT Par	488523.30	
	Description:- Electrically Operated Lifting Barrier complete set suitable for 24V DC supply with out hand generator & motorized boom locking arrangements as per RDSO Spec. SPN/208/2012 with latest amendment. One set consisting 02 Nos of Barriers of length 09.76 Mtrs. along with Spares & tool kit mentioned in RDSO Spec. SPN/208/2012 clause 10.1 & 10.2. (Should be Individual operation of both boom)							
2	2	1.00	Set	66080.63	66080.63	AT Par	66080.63	
	Description:- LED type control-cum indication panel complete with prewired Tag- Blocks, Wires MS angles etc. for LC gate , depicting the yard layout Signal, Point, Track circuit, Operating / emergency Push Button, counter with sealing arrangements, house in a Steel metal cabinet. This shall be consist 15 x 10 exchangeable Domino Unit as per Spec. SPN/186/2004 ver. 1 or latest amendment							

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

3	3	1.00	Set	1918.96	1918.96	AT Par	1918.96	
	Description:- Cost of supply & fixing of yellow retro-reflective sheet on lifting barrier boom. Intensity grade, encapsulated grade prismatic grade Size 305x290mm one set consist 18 pieces							
4	4	2.00	Numbers	31801.84	63603.68	AT Par	63603.68	
	Description:- Non Metallic (FRP) colour light signal housing multi unit type for railway signalling suitable for RE area THREE Aspects complete (without lanse, lamp, holder, transformer) suitable for LED signal as per RDSO DRG. No. SA 23001/A/M Adv. Alt- S and as per SPEC. No RDSO/SPN/194/2006 (Vol.1.0) or latest and FRP material as per RDSO SPEC. No. RDSO/SPN/151/1997 or latest. (Supply of LED Unit is not covered in this item).							
5	5	2.00	Numbers	30356.11	60712.22	AT Par	60712.22	
	Description:- Non Metallic (FRP) colour light signal housing multi unit type for railway signalling suitable for RE area TWO Aspects complete (without lanse, lamp, holder, transformer) suitable for LED signal as per RDSO DRG. No. SA 23No. RDSO/SPN/194/2006 (Vol. 1.0) or latest and FRP material as per RDSO SPEC. No. RDSO/SPN/151/1997 or latest. (Supply of LED Unit is not covered in this item)							
6	6	4.00	Numbers	12161.18	48644.72	AT Par	48644.72	
	Description:- "Colour Light Signal Complete. This includes: - (1). Post Tubular 140 mm Dia, as per IRS: S-6/81 or Latest & RDSO Drg. No. SA-24625 (Advance). (2). CI Base (As per IRS S-10 & RDSO Drg. No. 2011/M with latest assembly). (3). Pinnacle. (4). Ladder Assembly, as per RDSO Drg. No. SA-23156, with Base, Ladder Guards, Platform, Front Maintenance Platform, MS Supporting bracket to Support Ladder. (5). Signal Front Staging Complete Assembly for CLS Unit. (6). Signal back staging as per extent WR Practice. Note: Height of the Post shall be 5.5m / 4.5m/ 3.5m Long. Quantity of each will be decided by the engineer in charge."							
7	7	10.00	Numbers	1867.85	18678.50	AT Par	18678.50	
	Description:- Double Walled Corrugated (DWC) HDPE Pipe with associated collars etc. as per RDSO Specification No. RDSO/SPN/204/2011 or latest anti-rodent & anti-oxidant and non flame propagating type in 6 meters straight length and of size 120 mm outer die, & 103.5 mm inner dia. (The manufacturers, suppliers must produce valid IS license and should be certified under ISO 9000 and shall submit copy of certificate). One of the following coupling arrangements should also be supplied with each pipe as per the site requirement. 1) Suitable snap fit coupler with rubber 'O-Ring'. 2) Spacers 3) Tees 4) Bend, 5) End-cap (The total quantity of above items is equal to no. of pipes supplied.) DWC pipe shall be marked at every 1 mtr length in such a way that manufacturer's name, vender name and year of manufacture can be easily identified.							
8	8	6.00	Running Metre	643.79	3862.74	AT Par	3862.74	
	Description:- Medium Class G.I. Pipes to IS : 1239 (Pt.I)-2004 or latest ; 100mm dia. (int. dia) 3.65 mm +/- 10% thick with coupling. G.I. pipes shall have ISI mark on it and contractor should submit manufacturer's test certificate of G.I. pipes.							
9	9	250.00	Numbers	77.02	19255.00	AT Par	19255.00	
	Description:- ARA Terminal blocks with links made of PBT Spec No. IRS/75/2006 (Rev - 2) with latest amendments and RDSO Drg.No.SA-23741A Alt.4 or latest.							
10	10	150.00	Numbers	61.79	9268.50	AT Par	9268.50	
	Description:- "Disconnect Terminal Block, Screw less type, as per RDSO Spec. No. RDSO/SPN/189/2004. With latest amendments. Disconnect Terminal Block, Screw less type, 4-wire front entry (Two in-put & Two out-put) The colour will be decided by Engineer - in - Charge. (Preferably In Blue, Red & Grey Colors in the ratio of 1:2:3)"							
11	11	15.00	Numbers	11.50	172.50	AT Par	172.50	
	Description:- Supply of End plate for above item (I) 2.5mm/0.091 in thick as per site requirement.							
12	12	15.00	Numbers	11.50	172.50	AT Par	172.50	
	Description:- Supply of End Stopper for above item (I) 10mm/0.0394 in width as per site requirement.							
13	13	3.00	Metre	120.88	362.64	AT Par	362.64	
	Description:- Supply of Carrier Rails for above 35mm x 7.5mm, 1mm/0.039 in thickness un-slotted type as per site requirement.							
14	14	1.00	Numbers	17.63	17.63	AT Par	17.63	
	Description:- Markers strip for above item (i)							
15	15	3.00	Numbers	5251.96	15755.88	AT Par	15755.88	
	Description:- Phenolic laminated Sheet, grade P3 in standard size of 1220 X 1220 x 10 mm as per spec. No IS 2036 of 1995 or latest. Test report of manufacture to be supplied.							
16	16	3.00	Numbers	2516.29	7548.87	AT Par	7548.87	
	Description:- Thermo shrink Universal jointing kit for Quad Cable (for straight joints) as per RDSO spec IRS/TC-77/2012 revision 3 With latest Amd.							
	17	100.00	Numbers	145.65	14565.00	AT Par	14565.00	

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

17	Description:- Cartridge fuse block made of PBT as per RDSO Drg No SA-23748 Alt 4 & Spec No IRS S 75/2006 with latest amendment. Fuse block shall be suitable for round head type voltage fuses. This also includes supply of equivalent no of ND type Fuses of 20A capacity as per specification IRS S-78/92.						
18	18	100.00	Numbers	63.21	6321.00	AT Par	6321.00
	Description:- Round head type non deteriorating type low voltage cartridge fuse as per Spec No IRS/S/78/92 with latest amendments 6A/10A capacity.						
19	19	50.00	Numbers	57.17	2858.50	AT Par	2858.50
	Description:- Indicative type Fuse base/ holder with cap, suitable to G type fuse of capacity 0.63A - 3.0A. (System, Rapid, Malnad or RBCO make or similar).						
20	20	50.00	Numbers	20.87	1043.50	AT Par	1043.50
	Description:- Indicative type Fuse suitable to G type fuse base/holder of capacity 0.63 A - 3.0 A (System, Rapid, Malnad or RBCO make or similar).						
21	21	200.00	Numbers	54.28	10856.00	AT Par	10856.00
	Description:- ND Fuse Cylindrical Type 16 Amp IRS:S. 78/92						
22	22	200.00	Numbers	56.64	11328.00	AT Par	11328.00
	Description:- ND Fuse Cylindrical Type 20 Amp IRS:S.78/92						
23	23	1.00	Numbers	25617.82	25617.82	AT Par	25617.82
	Description:- Cable termination racks as per Drg. no. CSTE 5004, 5005, 5006 complete along with fitting arrangements and also with arrangement for fixing four 8-way terminal strips/ Screw less terminals on each row having 16 such rows. Supply of 8 way terminal strips/ Screw less terminals not covered under this item. Cable termination rack shall be Powder Coated.						
24	24	1.00	Numbers	27887.12	27887.12	AT Par	27887.12
	Description:- Relay racks assembly complete with scaffolding bus bars, fuse strips, fuses, resistors, capacitors, insulators, grouting bolts, tripods etc. as per Drg. No. CSTE /6028 .[Scaffolding should include 20% extra (with minimum of 2 relay rack positions) as spare for future expansion]. Relay rack shall be Powder Coated. (Quantity of Resistance, capacitor & Other items as Annexure.)"						
25	25	3.00	Kilometre	5916.42	17749.26	AT Par	17749.26
	Description:- Single core multi-strand wire 0.5 sq.mm. (16 conductor each dia. 0.2mm), as per IRS 76/89 (Amd3).						
26	26	1.00	Numbers	41554.88	41554.88	AT Par	41554.88
	Description:- "Ferro resonant type automatic AC voltage regulator 3 KVA capacity input 160-270V, output 230V as per RDSO Specn IRS S:74/89 with amendment-6 or latest. Accepted Make - ESTAR. "						
27	27	30.00	Kg	114.26	3427.80	AT Par	3427.80
	Description:- Rubber Mat for Power Equipment room.(5mm thick-RE fit)						
28	28	6.00	Numbers	5638.38	33830.28	AT Par	33830.28
	Description:- Universal AC ECR of Q series, type "QECX61" suitable for AC LED all signal aspect, Front & back contact Metal to Carbon type complete with plug board retaining clip & connectors conforming to Spec STS/E/Relays/AC Lit LED Signal/09/ 2002, BRS: 941A, IRS:S34 and IRS:S23 (as applicable)						
29	29	8.00	Numbers	5618.29	44946.32	AT Par	44946.32
	Description:- Relay, AC Immune, Plug-in-type, style "QNA1K" ACI DC Netural line, 24V DC 1000 Ohms 6F.6B contacts, front contacts metal to carbon and back contacts metal to cabon. complete with plugboard, retaining clip and connectors conforming to IRS:S34, IRS:S23, BRS931A. As per RDSO Specification No. STS/E/Relays/UEA(PI) Dt.30/05/97. Annexure II. The interlocking pin code CDEKY.						
30	30	2.00	Numbers	7050.39	14100.78	AT Par	14100.78
	Description:- Fail safe electronic time delay device mounted on Q series relay base & covered with fixed timing of 60/120/180/240 seconds as specified by purchaser conforming to IRS.S. 61-2000 or latest.						
31	31	3.00	Numbers	8544.44	25633.32	AT Par	25633.32
	Description:- Key Lock Relay working on 24V DC, AC Immunized with different ward combinations (Three ward plates to be supplied with each relay).						
32	32	2.00	Numbers	8933.44	17866.88	AT Par	17866.88
	Description:- Fail safe electronic flasher device 24 DC/110V AC as per RDSO Spec No. RDSO/SPN/173/2002 (Amd.2) or latest.						
33	33	3.00	Numbers	9292.09	27876.27	AT Par	27876.27
	Description:- Dual tone bell/buzzer with 25W horn, working on 24 V DC for road user.						
34	34	2.00	Numbers	1957.72	3915.44	AT Par	3915.44
	Description:- Road warning flasher kit for L.C. gate as per circuit design.						
	35	4.00	Set	8850.47	35401.88	AT Par	35401.88

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

35									Description:- Maintenance Free Earth Electrode of length 3m, including supply of 3 bags of Earth enhancement material for earthing (20KGs /bag) for each electrode & other accessories as per Drg. No. SDO / RDSO/ E&B/001 and RDSO Spec No. RDSO / SPN/197/ 2008.
36	36	0.20	Kilometre	43762.05	8752.41	AT Par	8752.41		Description:- Flexible cable (Power wire), multi-strand copper conductors cross section 1x6 Sq.mm. (85 conductor each diameter 0.30 +/- 0.01) as per IS 694/1990 with insulation thickness of 0.80 mm nominal conductor resistance 3.30 ohms/km and test parameters are as per IRS(S)76/89.
37	37	0.20	Kilometre	140354.46	28070.89	AT Par	28070.89		Description:- Flexible cable (Power wire), multi-strand copper conductors cross section (1x16Sq.mm).101 Conductors each diameter 0.45 + 0.01 as per IS 694/2010 with insulation thickness of 1.2mm nominal conductor resistance 1.127 Ohms/ Km and test parameters as per IRS(S) 76/89.
38	38	1.00	Set	34791.99	34791.99	AT Par	34791.99		Description:- Provision of T-Networking suitable for Networking to the existing Data Logger equipments. This includes supply of all equipment / accessories required for the purpose.
39	39	2.00	Numbers	7382.54	14765.08	AT Par	14765.08		Description:- Fire Extinguisher CO2 type (capacity 5 kg or more.)
40	40	8.00	Numbers	3771.88	30175.04	AT Par	30175.04		Description:- Earth Electrode as per Drg. No. CSTE / 6091.
41	41	1.00	Numbers	21150.00	21150.00	AT Par	21150.00		Description:- Supply of ladder (Inspection authority : Consignee)
42	42	10.00	Numbers	290.41	2904.10	AT Par	2904.10		Description:- Hydrometer, Exide make or similar for measuring specific gravity of Battery Graded acid with mounting stand in location Boxes.
43	43	2.00	Numbers	41822.69	83645.38	AT Par	83645.38		Description:- Battery Charger for Railway S&T installation self regulating floor mounting type with 230V AC single phase input and output 24 V DC, as per spec. IRS.S.86/2000 with latest amendments.50 Amp
44	44	2.00	Numbers	7009.20	14018.40	AT Par	14018.40		Description:- "Transformer 230V/110-130V Single phase 1 KVA as per Spec. IRS S-72/88 with latest amendments. (For Signal Lighting)"
45	45	1.00	Numbers	22414.10	22414.10	AT Par	22414.10		Description:- Digital Multimeter of Fluke 287 Industrial, True RMS with temperature, Analog bar graph, Digital display, Backlight, 1000V AC/DC, measure up to 10A, 20A for up to 30 second or Superior.
46	46	1.00	Numbers	5243.92	5243.92	AT Par	5243.92		Description:- Supply of digital Earth tester 4 Terminal for measurement of Earth resistance as per technical specifications .
47	47	1.00	Numbers	39332.94	39332.94	AT Par	39332.94		Description:- Megger 100V to 500V X 20 mega ohms as per specification make: Fluke model No 1507,Motawani.
48	48	1.00	Numbers	39819.00	39819.00	AT Par	39819.00		Description:- Mini AC/DC Low Current Clamp Meter as per Specn. High Sensitivity, Miniature type Clamp, Resolution of 0.1 mA for AC,1 mA for DC Current, Measurement range 0-20 A MakeKEW, Fluke.
49	49	3.00	Numbers	63420.00	190260.00	AT Par	190260.00		Description:- SS AC Box HALF(Fabricated of 2.5mm SS Sheet, Fixed Type)
50	50	2.00	Numbers	73004.00	146008.00	AT Par	146008.00		Description:- SS AC Box FULL(Fabricated of 2.5mm SS Sheet, Fixed Type)
51	51	1.00	Set	132154.25	132154.25	AT Par	132154.25		Description:- MS Sliding type mechanical Boom barrier assembly 11 to 12 Meter Long, movement drive mechanism, resetting & supporting stand suitable for Mechanical/Electrical level crossing gate as an emergency arrangements as per Drg.
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit	
Schedule () A3-Supply Items (SIGNAL Items for LHS in lieu of LC No.92 at Km 698/1-2 Between LXR-WKR.)							647182.37		
	1	5.00	Numbers	1912.20	9561.00	AT Par	9561.00		

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

1	Description:- Double Walled Corrugated (DWC) HDPE Pipe with associated collars etc. as per RDSO Specification No. RDSO/SPN/204/2011 or latest anti-rodent & anti-oxidant and non flame propagating type in 6 meters straight length and of size 120 mm outer dia, & 103.5 mm inner dia. (The manufacturers, suppliers must produce valid IS license and should be certified under ISO 9000 and shall submit copy of certificate). One of the following coupling arrangements should also be supplied with each pipe as per the site requirement. 1) Suitable snap fit coupler with rubber 'O-Ring'. 2) Spacers 3) Tees 4) Bend, 5) End-cap (The total quantity of above items is equal to no. of pipes supplied.) DWC pipe shall be marked at every 1 mtr length in such a way that manufacturer's name, vender name and year of manufacture can be easily identified.						
2	2	2.00	Metre	1170.28	2340.56	AT Par	2340.56
	Description:- Medium Class G.I. Pipes to IS : 1239 (Pt.I)-2004 or latest ; 100mm dia. (int. dia) 3.65 mm +/- 10% thick with coupling. G.I. pipes shall have ISI mark on it and contractor should submit manufacturer's test certificate of G.I. pipes.						
3	3	100.00	Numbers	83.92	8392.00	AT Par	8392.00
	Description:- ARA Terminal blocks with links made of PBT Spec No.IRS/75/2006(Rev - 2) with latest amendments and RDSO Drg.No.SA-23741A Alt.4.						
4	4	1.00	Numbers	5722.34	5722.34	AT Par	5722.34
	Description:- Phenolic laminated Sheet, grade P3 in standard size of 1220 X 1220 x 10 mm as per spec. No IS 2036 of 1995 or latest. Test report of manufacture to be supplied.						
5	5	10.00	Numbers	129.41	1294.10	AT Par	1294.10
	Description:- Cartridge fuse block made of PBT as per RDSO Drg No SA-23748 Alt 4 & Spec No IRS S 75/2006 with latest amendment. Fuse block shall be suitable for round head type voltage fuses. This also includes supply of equivalent no of ND type Fuses of 2A capacity as per specification IRS S-78/92.						
6	6	3.00	Kilometre	5548.54	16645.62	AT Par	16645.62
	Description:- Single core multi-strand wire 0.5 sq.mm. (16 conductor each dia. 0.2mm), as per IRS 76/89 (Amd3).1-R,01B						
7	7	2.00	Kilometre	33366.21	66732.42	AT Par	66732.42
	Description:- Flexible cable (Power wire), multi-strand copper conductors cross section 1x6 Sq.mm. (85 conductor each diameter 0.30 +/- 0.01) as per IS 694/1990 with insulation thickness of 0.80 mm nominal conductor resistance 3.30 ohms/km and test parameters are as per IRS(S)76/89.						
8	8	1.00	Kilometre	136063.55	136063.55	AT Par	136063.55
	Description:- Flexible cable (Power wire), multi-strand copper conductors cross section (1x16Sq.mm).101 Conductors each diameter 0.45 + 0.01 as per IS 694/2010 with insulation thickness of 1.2mm nominal conductor resistance 1.127 Ohms/ Km and test parameters as per IRS(S) 76/89.						
9	9	2.00	Numbers	2798.99	5597.98	AT Par	5597.98
	Description:- Earth Electrode as per Drg. No. CSTE / 6091.						
10	10	10.00	Numbers	5613.10	56131.00	AT Par	56131.00
	Description:- Universal AC ECR of Q series, type "QECX61" suitable for AC LED all signal aspect, Front & back contact Metal to Carbon type complete with plug board retaining clip & connectors conforming to Spec STS/E/Relays/AC Lit LED Signal/09/2002, BRS: 941A, IRS:S34 and IRS:S23 (as applicable)						
11	11	10.00	Numbers	5525.31	55253.10	AT Par	55253.10
	Description:- "Relay, AC Immune, Plug-in-type, style ""QNA1K"" ACI DC Neutral line, 24V DC 1000 Ohms 6F.6B contacts, front contacts metal to carbon and back contacts metal to carbon. complete with plugboard, retaining clip and connectors conforming to IRS:S34, IRS:S23, BRS931A. As per RDSO Specification No. STS/E/Relays/UEA(PI) Dt.30/05/97. Annexure II. The interlocking pin code CDEKY"						
12	12	20.00	Numbers	5576.04	111520.80	AT Par	111520.80
	Description:- Relay QNA1, AC immunized, 08F/08B, 12F-4B/8F-8B, 24VDC along with plug board, retaining clip and connectors conforming to BRS: 931A, IRS: S60, IRS: S34 & IRS: S24.						
13	13	10.00	Numbers	4878.90	48789.00	AT Par	48789.00
	Description:- Relay, AC Immune, plug-in-type, Style 'QTA2', DC Neutral track, 9 ohm DC 2F. 1B contacts, front and back contacts metal to carbon, complete with plug board, retaining clip & connectors conforming to BRS:939A, BRS:966 (Appendix F2), IRS:S 34 & IRS:S 23 & 60 (as applicable).						
14	14	2.00	Numbers	3523.27	7046.54	AT Par	7046.54
	Description:- Track feed battery chargers, 110V AC input, 2 to 6 V DC Output; as per Specn.No.IRS.S 89/ 2013 with latest amendments. Charger shall be suitable for charging 80 AH battery.						
15	15	2.00	Numbers	42435.11	84870.22	AT Par	84870.22

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

	Description:- Mini AC/DC Low Current Clamp Meter as per Specn. High Sensitivity, Miniature type Clamp, Resolution of 0.1 mA for AC,1 mA for DC Current, Measurement range 0-20 A MakeKEW, Fluke OR SIMILAR.							
16	16	2.00	Numbers	15611.07	31222.14	AT Par	31222.14	
	Description:- Apparatus Case half NE Rly Type as per Drg. No. W. Rly/SW/47/68 Alt-A fitted two nos E Type lock of (ward No will be specified by Engineer-in Charge) as per RDSO Drg. No. SA 3376/3473 and Key to Drg. No. 3377. Note: This item includes the supply & fixing of 2 Nos E Type Lock fitted on both doors, along with two Keys.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A4-Supply Items (SIGNAL Items Kanalus: Rectification of bad layout from Pt 112 towards towards RJT.)							1694079.23	
1	1032700	1.00	Numbers	4530.07	4530.07	AT Par	4530.07	
	Description:- Position Light Shunt Signal Unit Complete with Post (made of GI Pipe of 80 mm Diameter Medium Class IS Spec. No. IS: 1239 Pt. 1/1990) Base, Hood, and Cover, etc. as per Drg. No. SA-23840, Signal Number Plate, suitable for LED Signal Lighting Unit. (Supply of LED Unit is not covered in this item).							
2	1040300	5.00	Numbers	1345.93	6729.65	AT Par	6729.65	
	Description:- Point insulation Complete set as per RDSO Specification IRS: S-40/84 for Switch bracket, Split-Stretcher bar & Gauge tie plates (52 Kg/60Kg as per site requirement).							
3	1050101	1.00	Numbers	3523.27	3523.27	AT Par	3523.27	
	Description:- Track feed battery chargers, 110V AC input, 2 to 6/10 V DC Output; as per Specn. No. IRS.S 89/ 2013 with latest amendments. Charger shall be suitable for charging 80 AH battery.							
4	1050102	2.00	Numbers	2129.53	4259.06	AT Par	4259.06	
	Description:- Choke Coil for Single Rail Track Circuit on 25 KV 50 Hz AC Electrified Section as per Spec No IRS S 65/1983 with latest amendments.							
5	1050103	3.00	Numbers	2213.81	6641.43	AT Par	6641.43	
	Description:- Low maintenance Lead acid secondary cell 2V/80 AH (Track feed Battery), shelf mounting type conforming to IRS:S- 88/2004 or latest (uncharged).							
6	1050104	2.00	Numbers	978.46	1956.92	AT Par	1956.92	
	Description:- Adjustable Track Feed Resistance disc type 30 ohms as per RDSO Drg. No. SA 20166/M (Adv.) with latest amendments (with Phenolic molded base).							
7	1050402	100.00	Kg	68.17	6817.00	AT Par	6817.00	
	Description:- GI wire 8 SWG (4mm Dia) suitable for track circuit rail bonding.							
8	1050403	100.00	Numbers	6.04	604.00	AT Par	604.00	
	Description:- Channel Pins MS (Galvanized) single groove, 7 mm suitable for 4mm Dia bonding wire as per spec No IRS S 17 & RDSO Drg No. S-69/M.							
9	1060400	1.00	Set	750808.56	750808.56	AT Par	750808.56	
	Description:- Supply, Installation, Testing and Commissioning of High Availability Single section digital axle counters with Dual sensor system as per RDSO/SPN/177/2012 version 3or latest. This includes The supply of High frequency web mounting type Tx coil/Rx coil, VR/PR Box duly wired, Vital relays, PR Relays, Clamp with deflector plates & hardware, Dual display reset box with auto resetting facility, Surge voltage protection devices and filter card to be mounted on din rail etc. as per OEM for complete installation & testing& commissioning of(HASSDAC) system NOTE: One set of HASSDAC system will include equipment required to monitor One Up line or One Den line of a full Block Section between two stations. Note: - "Supply of HASSDAC as per RDSO specification along with outdoor industrial grade enclosure (Approved by Railways) similar to Rattle/Pyrotech make.							
10	1070100	15.00	Numbers	4284.48	64267.20	AT Par	64267.20	
	Description:- Miniature, Plug-in Type, DC Neutral Line, Non AC Immunized Relay, Style QN1, 24 V DC, 8F-8B/12F-4BContact, Code ABCDF/ABCDE Spec: BRS: 930; IRS S 34; IRS S 23.							
11	1070200	15.00	Numbers	5576.04	83640.60	AT Par	83640.60	
	Description:- Miniature, Plug-in Type, DC Neutral Line AC Immunized Relay, Style QNA1, 24 V DC, 8F-8B/12F-4BContact, Code ABDGH/ABDFH Spec: BRS: 931A; IRS S 34; IRS S 23; IRS S 60-78.							
12	1070600	5.00	Numbers	5613.10	28065.50	AT Par	28065.50	
	Description:- Universal AC ECR of Q series, type "QECX61" suitable for AC LED all signal aspect, Front & back contact Metal to Carbon type complete with plug board retaining clip & connectors conforming to Spec STS/E/Relays/AC Lit LED Signal/09/2002, BRS: 941A, IRS: S34 and IRS: S23 (as applicable).							
13	1070700	15.00	Numbers	7390.44	110856.60	AT Par	110856.60	
	Description:- Miniature, Plug-in Type, DC Neutral Line Magnetically Latched Relay, Style QL1, 24 V DC, 11F-4B Contact, Code ABDEG Spec: BRS:935A ; IRSS 34 ; IRS S 23.							
	1070900	15.00	Numbers	7393.68	110905.20	AT Par	110905.20	

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

14	Description:- Plug in Type, Tractive Armature, AC Immunized, DC Biased Contactor Relay, Style QBCA1,2HF-4B Contact,24 V DC, Code BCEJK Spec:BRS:943 ; IRS S 34 ; IRS S 23 ;IRSS 60-78.								
15	1071000	50.00	Numbers	4878.90	243945.00	AT Par	243945.00		
	Description:- Miniature, Plug in Type, M to C,DC Neutral ,Track relay, ACI, Style QTA2, 9 Ohm, 2F-1B contact, Code - FGHKX Spec : BRS :939-A & 966 (Appx-F2) & IRS : S-23, S-23,S-34 & 60.								
16	1080200	1.00	Numbers	3089.90	3089.90	AT Par	3089.90		
	Description:- Supply of self supported aluminum flat step ladder (conforming to ISI) 8 ft. height. Ladder should be self-supported and it should be made up of rust proof Aluminum of Min 16 SWG. No plastic hinges/Step support should be used.								
17	1082501	120.00	Numbers	58.53	7023.60	AT Par	7023.60		
	Description:- Disconnect Terminal Block, Screw less type, 4-wire front entry (Two in-put & Two out-put) The color will be decided by Engineer - in - Charge. (Preferably In Blue, Red & Grey Colors in the ratio of 1:2:3). as per RDSO Spec. No. RDSO/SPN/189/2004. With latest amendments. Note: Make to be approved by Railway before supply.								
18	1082502	20.00	Numbers	11.07	221.40	AT Par	221.40		
	Description:- Supply of End plate 2.5mm/0.091 in thick as per site requirement.								
19	1082503	20.00	Numbers	10.86	217.20	AT Par	217.20		
	Description:- Supply of End Stopper 10mm/0.0394 in width as per site requirement.								
20	1082504	10.00	Numbers	113.88	1138.80	AT Par	1138.80		
	Description:- Supply of Carrier Rails for above 35mm x 7.5mm, 1mm/0.039 in thickness un-slotted type as per site requirement.								
21	1082800	2.00	Numbers	3354.08	6708.16	AT Par	6708.16		
	Description:- Desk type Electronic Magneto Telephone as per spec No IRS/TC-79/2000 or with latest amendments.								
22	1083600	4.00	Numbers	2798.99	11195.96	AT Par	11195.96		
	Description:- Earth Electrode as per Drg. No. CSTE / 6091.								
23	1084000	4.00	Numbers	649.00	2596.00	AT Par	2596.00		
	Description:- Supply of Fiber/ SMC/FRP/RCC Earth Chamber.								
24	1084100	120.00	Numbers	75.00	9000.00	AT Par	9000.00		
	Description:- ARA Terminal blocks with links made of PBT Spec No.s/75/2006 (Rev - 2) with latest amendments and RDSO Drg.No.SA-23741A Alt.4.								
25	1090100	2.00	Numbers	51998.06	103996.12	AT Par	103996.12		
	Description:- SS Location box made of Spl Grade SS 304 of size as per Drg. No. DRM/SG/945 dtd 03.03.2011 (Half app. Case) or latest. Manufacturer's certificate in regard to grade of stainless steel and its protection level shall be submitted at the time of supply.								
26	1090200	1.00	Numbers	59855.98	59855.98	AT Par	59855.98		
	Description:- SS Location box made of Spl Grade SS 304 of size as per Drg. No. DRM/SG/948 dt. 26.04.2011 (Single app. Case) or latest. Manufacturer's certificate in regard to grade of stainless steel and its protection level shall be submitted at the time of supply.								
27	1090900	2.00	Numbers	5388.67	10777.34	AT Par	10777.34		
	Description:- IS 13410: Glass Reinforced Polyester Sheet Moulding Compounds (SMC) Size of Sheet : 1000x1000x8								
28	1100700	3.00	Kilometre	5548.54	16645.62	AT Par	16645.62		
	Description:- Single core multi-strand wire 0.5 sq.mm. (16 conductor each dia. 0.2mm), as per IRS 76/89 (Amd3) or latest.								
29	1100800	0.60	Kilometre	33366.21	20019.73	AT Par	20019.73		
	Description:- Flexible cable (Power wire), multi-strand copper conductors cross section 1x6 Sq.mm. (85 conductor each diameter 0.30 +/- 0.01) as per IS 694/1990 with insulation thickness of 0.80 mm nominal conductor resistance 3.30 ohms/km and test parameters are as per IRS(S)76/89 or latest.								
30	1102300	12.00	Running Metre	1170.28	14043.36	AT Par	14043.36		
	Description:- Medium Class G.I. Pipes to IS: 1239 (Pt.)-2004 or latest; 100mm dia. (int. Dia) 3.65 mm thick or above with coupling. G.I. pipes shall have ISI mark on it and contractor should submit manufacturer's test certificate of G.I. pipes.								
	S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	
								Bidding Unit	
	Schedule () B1-Execution Items(SIGNAL Items for ROB in lieu of LC No 135 at Km 755/0-1 Bet. KHDl - PDH section)							4594423.90	
	1		1.00	Set	52531.41	52531.41	AT Par	52531.41	

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

1									Description:- Installation, testing and commissioning of electrically operated lifting barrier, complete with Casting of cement concrete foundation for pedestal and boom rest post, cabling, power supply connection & wiring with complete outdoor work as per approved drawing, wiring etc.
2	2	1.00	Set	7937.57	7937.57	AT Par	7937.57		Description:- Installation and complete wiring of of operating cum indication panel for LC gate as per technical specification and site requirement. The indoor wiring inside panel shall be terminated on tag block as per instructions of Engineer-in-charge. The wiring on panel tag blocks shall be repeated on tag blocks located in relay room. This includes laying & termination of cable, if any from Panel Room to Relay Room in HDPE pipe.
3	3	1.00	Numbers	24343.92	24343.92	AT Par	24343.92		Description:- "Complete Indoor wiring testing & commissioning of station / LC Gate. This includes: (i) Prewiring & fixing of all base plates as per approved wiring diagram. (Supply of relay base covered in schedule 'A'. Excess quantity of base plate, if required will be supplied by Railways, prewiring of which will be done by the contractor.) (ii) Fixing of Relay groups on relay racks. (iii) Soldering of tag block terminals, dressing of wires as per approved rack arrangements/ Circuit diagrams. iv) Wiring on bus bar, fuse base condenser , resistance etc. as per wiring diagram (v) Wiring on Relay rack to relay rack via IDF, IDF to CT rack in relay room. vi) Wiring on panel tag block shall be repeated on tag blocks located on IDF & CT rack in relay room. vii) Wiring between control panel room & relay room. (viii) Supply of simulation panel, which shall be separate for each station and shall be left after commissioning. (ix) Provision 200 way tag blocks for data logger and providing jumpers between voltage free terminals on relay racks and data loggers, tag block with 0.6 sq mm cable. (x) Wiring between Integrated power supply and data logger tag block with one square mm /0.6 sq mm cable as per instruction of Engineer in-charge. (xi) Wiring of key lock arrangement at SM's office/ site & Earth leakage detectors. (xii) Wiring of block instruments from CT rack to block instrument terminals and includes supply & laying of indoor cables for this purpose as per standard arrangements xiii) All wiring & wiring materials necessary to complete Station/ LC gate (Within station limit) Installation but not covered in the schedule anywhere (xiv) Writing of description on all relays & other indoor equipments Note: All wiring will be done as per standard practice of Railways with neat dressing & threading. Detailed testing will include functional testing, selection table, locking table and cross sheet testing with the help of operating panel and simulation panel in the presence of railway officials to their satisfaction. a copy of tested selection table, locking table and cross sheet duly signed by contractor to be submitted to field office for record. This includes supply of lamps for simulation panel for testing. Contractor will Put sufficient Staff to carry out the testing round the clock, if desired by Railway Engineer and will ensure that any alteration which become necessary during testing are carried out & testing is repeated wherever required ."" (ii)LC Gates"
4	4	1.00	Numbers	3639.10	3639.10	AT Par	3639.10		Description:- Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor's own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy paint will be supplied by Railways. NOTE:- The paint and primer should be from Asian Paints/ Nerolac / Dulux / Berger. The primer / enamel paints (Aluminum synthetic, black enamel, brilliant white and yellow) will be as per (IS 5660 of 1970) / (IS 2932 of 1974). :- Complete painting ,writting and varnishing work at a LC gate. Painting and lettering of power operated lifting barrier(All items of one LC gate to be taken as one Lot)
5	5	9.00	Numbers	398.40	3585.60	AT Par	3585.60		Description:- Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor's own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy paint will be supplied by Railways. NOTE:- The paint and primer should be from Asian Paints/ Nerolac / Dulux / Berger. The primer / enamel paints (Aluminum synthetic, black enamel, brilliant white and yellow) will be as per (IS 5660 of 1970) / (IS 2932 of 1974):- Main Signal Post with Signal Units, Surface base and complete fittings as per Western Railways standard practice.
6	6	9.00	Numbers	8284.88	74563.92	AT Par	74563.92		Description:- Excavation and Casting of foundation for main signal post as per CSTE/3122 (WR) with contractor's own materials including cement and anchor bolts of standard size. The required scaffolding Ferma etc for Casting of foundation will have to be brought by the contractor at his own cost.
7	7	9.00	Numbers	2458.58	22127.22	AT Par	22127.22		Description:- Erection of CLS Post with base and signal unit on top or on OFF set Bracket, fixing of front and back staging, ladder and guards, signal name plates / boards if any with contractor's own brackets and fixing materials. This also includes erection of auxiliary signals like calling on, shunt signal if any. The work shall be done as per instructions of Rly engineer at site. It also includes provision & fixing of maintenance platform as per design given by Engineer -In-Charge at site. The item includes cutting of Signal post if required by Site In charge. (ii)2/3/4 aspect signal unit mounted directly on signal post
	8	9.00	Numbers	1375.07	12375.63	AT Par	12375.63		

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

8	Description:- Fabrication and fixing of Signal Number Plate(CSTE Drg No CSTE/6186) , 'A' Marker (Drg No. CSTE/6180), 'AG' Marker (Drg No. CSTE/6181), 'P' Marker (Drg No. CSTE/6182), Arrow Marker (Drg No. CSTE/6183), 'G' Marker (Drg No. CSTE/6184), 'C' Marker (Drg No. CSTE/6185). marker disk on signals as per standard practice All material required for this work shall be supplied by Contractor.						
9	9	1.00	Numbers	6512.14	6512.14	AT Par	6512.14
	Description:- Supply & Fixing of Stop Board, Block section limit Board, goods warning board with contractors own material. The work shall be done as per instruction of Rly. Engineer at site.						
10	10	7000.00	Running Metre	10.18	71260.00	AT Par	71260.00
	Description:- "Laying of S&T Cables of various cores/ pairs/ quads in trenches/ GI pipes/ RCC pipes/ DWC pipes/ Trunking. This also includes laying of cables in track crossings & road crossings. Item includes provision of labels of coloured plastic adhesive tapes or any other identifiable material on each cable to give the cable number at each G.P.(Cables will be maggered before and after its laying by contractor under supervision of Railway Representative and he will submit the maggering report of each testing). Length of the cable laid includes the length of the cable coiled for termination purposes."						
11	11	600.00	cum	308.34	185004.00	AT Par	185004.00
	Description:- Excavation of cable trench as per cable route plan,1Mtr. deep and of 0.3 Mtr. to 0.6 Mtrs wide advised by Engineer-in-charge alongside the track in normal (all type) soil/strata, conforming to distances as per cable route plan and refilling. This work includes clearing of route from bushes etc, covering of cable laid in trench by loose soil for a layer of 50mm thickness approximately before covering by bricks. The work shall be done as per the extant practice on Western Railway and instructions of Railway Engineer at site. In case 1m depth of trench is not achievable due to site conditions, specific approval of JA grade officer will be required for each site where trench depth of 1m is not possible. Without the approval of JA Grade officer, no payment for trenching will be made for trench depth less than 1m.						
12	12	20.00	cum	567.95	11359.00	AT Par	11359.00
	Description:- Digging of cable trench 0.3 Mtrs. Deep and 0.3 Mtrs. Wide on Asphalted Platform / Road / Hard rocky area. Refilling with earth leveling of trenches & restoring the original surface of trenches.						
13	13	50.00	Metre	641.39	32069.50	AT Par	32069.50
	Description:- Providing chase in hard rocky soil for laying of S&T cables where optimum depth (0.5m) in not possible and which is verified and agreed by engineer incharge.						
14	14	1.00	Numbers	14683.70	14683.70	AT Par	14683.70
	Description:- Digging of cable pit (min 2x2x1m) as per instruction of Site Engineer, supplying and filling of sand before and after coiling the cables, covering top of the cable pit with stones and providing brick masonry on all four sides of the cable pit and plastering thereafter.						
15	15	5.00	cum	4077.86	20389.30	AT Par	20389.30
	Description:- Cement concrete work for miscellaneous items in the ratio 1 : 3 : 6 . Item includes excavation, ramming, curing and plastering with cement & sand mixture (aggregate not exceeding 3.8 cm.) (Aggregate cement & sand to be supplied by the contractor).						
16	16	36.00	Running Metre	1352.02	48672.72	AT Par	48672.72
	Description:- Horizontal direction drilling/boring without damage of surface road using Auger Machine. The bore shall be 150 mm dia & shall be done at the depth of minimum 1200 mm from the ground level. The ground level shall be considered ignoring the bank height of the bank of the road. The length of the bore shall be minimum 4 Mtrs long. this include insertion of different dia DWC pipe/ GI pipes coupling etc. as per direction of Engineer In charge. Note:- Pipe will be supplied by railway. Contactor shall provide all material required for boring and adequate nos. of labours for proper laying of cables into the bore. Cable shall be laid cautiously so that it should not get damage due to rough handling & pressure on cable.						
17	17	900.00	Numbers	442.29	398061.00	AT Par	398061.00
	Description:- Supply and placing of Half Round RCC pipes & collars of 150 mm internal dia, 2 meter long (or two pieces of 1 meter long) along with collars as per IS No. 458/2003 of NP type						
18	18	10.00	Running Metre	15.80	158.00	AT Par	158.00
	Description:- Supplying and placing of one layer of standard size of 'B' grade quality bricks of the local make spreading on cables laid.Lengthwise (up to 2 cables).						
19	19	10.00	Numbers	461.81	4618.10	AT Par	4618.10
	Description:- Supply and installation of RCC Cable route marker as per Drg.No.4014/00/CC4 or latest/stone marker						
	20	400.00	Per Conductor	2.44	976.00	AT Par	976.00

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

20	Description:- Termination of cable cores on ARA terminal/fuse blocks, 8 way terminals block/ Screw less connectors in the apparatus Cases/ cable termination rack. This includes all associated works of pulling out the cable from underground. The work shall be done as per location plans and instructions of Railway Engineer at site. This item includes dressing of Cable, making wiring tree etc.						
21	21	3.00	Numbers	768.73	2306.19	AT Par	2306.19
	Description:- Fabrication and fixing of phenolic laminated sheet of size 10mm thick in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated string rods at the back side for cable support with contractor's own materials. The work shall be done as per drg and arrangement similar to SK 783-1/2. with latest alterations & as per instructions of Rly engineer at site. Half Case						
22	22	3.00	Numbers	5910.80	17732.40	AT Par	17732.40
	Description:- Excavation and Casting of Apparatus Case foundation with contractor's own materials including cement and anchor bolts of standard size. The required scaffolding Fermaetc for Casting of foundation will have to be brought by the contractor at his own cost. Half Case as per Drg No SK 747or CSTE/5074 or SS Location						
23	23	3.00	Numbers	711.20	2133.60	AT Par	2133.60
	Description:- Installation of Apparatus Cases with miniature 'E' type lock on CC foundation. This includes filling of location foundations with river bed sand and plastering on top of the sand. 'E' Type lock will be provided by Railway. (Half Case)						
24	24	3.00	Numbers	97.09	291.27	AT Par	291.27
	Description:- Lettering / Numbering Termination particulars, equipments names etc., legibly and neatly inside location boxes. This includes supply of paints of Asian Paints/ Nerolac / Dulux / Berger make. - MO INF-SRAPL/ODK/J/0132 Date July 30 ,2021 Half Loc.						
25	25	2.00	Numbers	6848.79	13697.58	AT Par	13697.58
	Description:- Excavation and Casting of Apparatus Case foundation with contractor's own materials including cement and anchor bolts of standard size. The required scaffolding Ferma etc for Casting of foundation will have to be brought by the contractor at his own cost. Single Case as per Drg No SK 748 or CSTE/5074 .						
26	26	2.00	Numbers	1032.72	2065.44	AT Par	2065.44
	Description:- Installation of Apparatus Cases with miniature 'E' type lock on CC foundation. This includes filling of location foundations with river bed sand and plastering on top of the sand. 'E' Type lock will be provided by Railway. Single Case						
27	27	2.00	Numbers	2330.38	4660.76	AT Par	4660.76
	Description:- Fabrication and fixing of phenolic laminated sheet of size 10mm thick in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated string rods at the back side for cable support with contractor's own materials. The work shall be done as per drg and arrangement similar to SK 783-1/2. with latest alterations & as per instructions of Rly engineer at site. Single Case						
28	28	2.00	Numbers	252.47	504.94	AT Par	504.94
	Description:- Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor's own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy paint will be supplied by Railways. NOTE:- The paint and primer should be from Asian Paints/ Nerolac / Dulux / Berger. The primer / enamel paints (Aluminum synthetic, black enamel, brilliant white and yellow) will be as per (IS 5660 of 1970) / (IS 2932 of 1974). Apparatus Case Full Size. (Outside & inside)						
29	29	2.00	Numbers	159.60	319.20	AT Par	319.20
	Description:- Lettering / Numbering Termination particulars, equipments names etc., legibly and neatly inside location boxes. This includes supply of paints of Asian Paints/ Nerolac / Dulux / Berger make. - App case Full size						
30	30	2.00	Numbers	9763.56	19527.12	AT Par	19527.12
	Description:- Installation of Cable Termination Racks Assembly complete including wall supports, scaffolding, 8 way/ARA terminals /Screw less connectors, Tag blocks & other necessary accessories etc. The work shall be done as per approved plan, extant practice on WR & the instruction of Rly engineer at site.						
31	31	1.00	Numbers	1578.37	1578.37	AT Par	1578.37
	Description:- Supplying & fixing of crank handle box 450 x 250 x 150 mm made of 12mm thick teakwood with a glass front and padlocking and sealing arrangements as per std practice. Pad lock to be supplied by the contractor. All material i.e. teakwood, handle, hinges, glass sheet of 3 mm thick to be supplied by the contractor. Box to be polished and description to be as per instructions of Engineer in - charge.						
32	32	2.00	Numbers	426.00	852.00	AT Par	852.00
	Description:- Installation of Dual tone bell/buzzer for LC gate user. To be installed on CLS post erected on either side of gate as per instruction of Engineer in charge.						

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

33	33	4.00	Numbers	1367.15	5468.60	AT Par	5468.60	
	Description:- Installation of Maintenance free Earth Electrode for Maintenance free earth spec of RDSO/SPN/197/2008							
34	34	2.00	Each Module	995.16	1990.32	AT Par	1990.32	
	Description:- Installation wiring testing and commissioning of Fuse change over system (FACS). This includes provision of common Buzzer & indication at ASM Room & ESM Duty Room and painting of fuse details. This also includes fabrication of frame for installation of FACS at Station/ LC gate where installation of relay racks not feasible.(Per unit means Per module)							
35	35	1.00	Set	33029.82	33029.82	AT Par	33029.82	
	Description:- Casting of CC foundations in the ratio of 1:3:6 for sliding boom as per Drg. Minimum 10 Nos of foundation per set shall be cast using standard size holding down bolts & nuts for erection. Item include excavation, ramming, curing and plastering 1:4 cement and sand mixture. Aggregate, cement, sand and holding down bolts & nuts to be supplied by the contractor.							
36	36	5.00	cum	163.15	815.75	AT Par	815.75	
	Description:- Earthwork in filling in embankment, guide bunds, around buried type abutments, bridge gaps, trolley refuges, rain bunds if provided, platforms etc. with earth excavated from outside railway boundary entirely arranged by the contractor at his own cost as per RDSO's latest guidelines and specifications and special condition of contract including all leads, royalty, lifts, ascents, descents, crossing of nallahs or any other obstructions. The rates shall include all dressing of bank to final profile, demarcation and setting out of profile, site clearance, removing of shrubs, roots of vegetations growth, heavy grass, benching of existing slope of old bank, all handling/re-handling. Taxes, Octroi and royalty etc. As a complete job. Cut trees shall be property of railways and to be deposited in the railway godown unless specified otherwise in the Special conditions of contract							
37	37	1.00	Set	17205.57	17205.57	AT Par	17205.57	
	Description:- Installation & commissioning of Sliding booms with E type lock and KLCR. This includes wiring of KLCR, running of cables, necessary painting & transportation of materials from store to site. All material required to commissioning of slide booms on gate will be supplied by the contractor							
38	38	1.00	Set	7438.64	7438.64	AT Par	7438.64	
	Description:- Installations, wiring, testing and commissioning of Remote Terminal Unit complete along with accessories using Contractor's own wiring & fixing materials. (It includes loading of NETWORKING software and networking with data logger. The requisite communication cable/channel for networking will be arranged by Railway.							
39	39	3.00	Numbers	1503.71	4511.13	AT Par	4511.13	
	Description:- Supply and fixing of KLCR boxes 450x250X150 mm in {field / in location boxes / in SM office / at LC gate as per site condition' It should be made of Hytium/wooden.(teak wood) of high quality as per requirement. Item includes supply of any minor bracket, nuts, bolts and hole drilling, MS angle, MS plate etc. Its also includes fixing of KLCR relays in the boxes							
40	40	2.00	Numbers	1343.27	2686.54	AT Par	2686.54	
	Description:- Jointing of 4 / 6 quad /Signaling cable with Heat Shrinkable straight through Jointing Kit. All the material required for the work are to be arrange by contractor himself at his own cost except Thermo shrinkable Joint Kit . After jointing the cable through test such as insulation test, continuity cable losses etc. to be carried out jointly with Railway Engineer. If any defect or any damage is observed during jointing, the contractor has to redo the joint free of cost.							
41	41	8.00	Numbers	1775.20	14201.60	AT Par	14201.60	
	Description:- Installation of earth electrode as per std. practice and connecting it to equipments to be earthed. This item includes digging of pit in earth 3 m deep & fixing earth electrode pipe, casting of cement concrete enclosure & cover as per Drg No. S&T/Tender/27.Soil treatment to be done as per std. practice. This item includes provision of MS flat/earth lead wires as per instruction and soldering of lead wires. The other end of the wire is to be connected to block equipment, power equipment, cable sheath, signals etc. as per site requirements. 7strand GI wire shall be used as earth lead wire. (Supply of earth electrode is covered in Sch. 'A').							
42	42	500.00	Kg	218.50	109250.00	AT Par	109250.00	
	Description:- Supply & installation of Fencing work around S&T apparatus case or building/office etc.							
43	43	1.00	Station	3208322.25	3208322.25	AT Par	3208322.25	

43

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

44	44	2.00	Numbers	18690.50	37381.00	AT Par	37381.00	
	Description:- Modification/ Alterations/augmentation of existing electronic interlocking (EI) system as per RDSO specn No. RDSO/SPN/192/2005 or latest as per approved Signaling Plans and Selection Table/ Locking Table of stations (for additional loop lines, Gate removal etc.) technical specifications & special conditions of contract. This includes supplies necessary for alteration /modification in VDU's software. This also includes supplies necessary for earthing the modification/alterted/augmented EI those needed for rewiring external data logger and fuse alarm system. This also includes 12 months warranty period of all supplied equipment. Item includes preparation of Selection Table/ Locking Table, Control Panel and Route Section Plan, Wiring Diagram and other diagrams (other Technical documents if any) based on Signalling Plan supplied by Railways. Completion Documents as per special condition of Contract."							
45	45	2.00	Numbers	6454.30	12908.60	AT Par	12908.60	
	Description:- Dismantling Existing Electric lifting barrier / mechanical lifting barriers, Sliding Booms & other material at LC gates complete and transporting them to Consignee's Stores Depot / nearest DS8 yard. This includes complete mechanical items including levers, rodding iron, point fittings, lock bar, compensators, Electrical fittings in the cabin and other miscellaneous items (whatever applicable to the particular installation). Removal of Trestle from the soft soiland bottom, top roller and strand of rod etc. The field items such as Junction boxes, AC boxes etc. shall also be dismantled as per instruction of Engineer - in - charge.							
46	46	2.00	Numbers	4974.46	9948.92	AT Par	9948.92	
	Description:- Dismantling of all signals complete with signal unit, route indicator, signal foundation and other accessories complete with transporting them to consignee's depot or DS-8 depot as per the instruction of Engineer In-charge by contactors own vehicle & labour.(Rate to be consider when total gear to be dismantled at a station is less than 10)							
47	47	2.00	Numbers	32681.69	65363.38	AT Par	65363.38	
	Description:- Installation, wiring and commissioning of all type power supply equipments like charger, transformer, auto changeover and inverter etc. at LC gate.							
48	48	4.00	cum	841.27	3365.08	AT Par	3365.08	
	Description:- Dismantling of Concrete foundations/Dimolishing RCC/CC/Stone Work/Cutting Tarcarpenting/CC Flooring/Pricast Concrete slabs etc./Brick work includingleading the debris inside Railway limit or outside Railway limit as directed by site in charge.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () B2-Execution Items (SIGNAL Item for ROB in lieu of LC No 147 at Km 770/1-2 Bet. PDH - CX section)							1323517.00	
1	1	1.00	Set	52531.41	52531.41	AT Par	52531.41	
	Description:- Installation, testing and commissioning of electrically operated lifting barrier, complete with Casting of cement concrete foundation for pedestal and boom rest post, cabling, power supply connection & wiring with complete outdoor work as per approved drawing, wiring etc.							
2	2	1.00	Set	7937.57	7937.57	AT Par	7937.57	
	Description:- Installation and complete wiring of of operating cum indication panel for LC gate as per technical specification and site requirement. The indoor wiring inside panel shall be terminated on tag block as per instructions of Engineer-in-charge. The wiring on panel tag blocks shall be repeated on tag blocks located in relay room. This includes laying & termination of cable, if any from Panel Room to Relay Room in HDPE pipe.							
	3	1.00	Numbers	24343.92	24343.92	AT Par	24343.92	

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

3	Description:- "Complete Indoor wiring testing & commissioning of station / LC Gate. This includes: (i) Prewiring & fixing of all base plates as per approved wiring diagram. (Supply of relay base covered in schedule 'A'. Excess quantity of base plate, if required will be supplied by Railways, prewiring of which will be done by the contractor.) (ii) Fixing of Relay groups on relay racks. (iii) Soldering of tag block terminals, dressing of wires as per approved rack arrangements/ Circuit diagrams. iv) Wiring on bus bar, fuse base condenser , resistance etc. as per wiring diagram (v) Wiring on Relay rack to relay rack via IDF, IDF to CT rack in relay room. vi) Wiring on panel tag block shall be repeated on tag blocks located on IDF & CT rack in relay room. vii) Wiring between control panel room & relay room. (viii) Supply of simulation panel, which shall be separate for each station and shall be left after commissioning. (ix) Provision 200 way tag blocks for data logger and providing jumpers between voltage free terminals on relay racks and data loggers, tag block with 0.6 sq mm cable. (x) Wiring between Integrated power supply and data logger tag block with one square mm /0.6 sq mm cable as per instruction of Engineer in-charge. (xi) Wiring of key lock arrangement at SM's office/ site & Earth leakage detectors. (xii) Wiring of block instruments from CT rack to block instrument terminals and includes supply & laying of indoor cables for this purpose as per standard arrangements xiii) All wiring & wiring materials necessary to complete Station/ LC gate (Within station limit) Installation but not covered in the schedule anywhere (xiv) Writing of description on all relays & other indoor equipments Note: All wiring will be done as per standard practice of Railways with neat dressing & threading. Detailed testing will include functional testing, selection table, locking table and cross sheet testing with the help of operating panel and simulation panel in the presence of railway officials to their satisfaction. a copy of tested selection table, locking table and cross sheet duly signed by contractor to be submitted to field office for record. This includes supply of lamps for simulation panel for testing. Contractor will Put sufficient Staff to carry out the testing round the clock, if desired by Railway Engineer and will ensure that any alteration which become necessary during testing are carried out & testing is repeated wherever required ."" (ii)LC Gates"						
4	4	1.00	Numbers	3639.10	3639.10	AT Par	3639.10
	Description:- Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor's own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy paint will be supplied by Railways. NOTE:- The paint and primer should be from Asian Paints/ Nerolac / Dulux / Berger. The primer / enamel paints (Aluminum synthetic, black enamel, brilliant white and yellow) will be as per (IS 5660 of 1970) / (IS 2932 of 1974). :- Complete painting ,writting and varnishing work at a LC gate. Painting and lettering of power operated lifting barrier(All items of one LC gate to be taken as one Lot)						
5	5	4.00	Numbers	398.40	1593.60	AT Par	1593.60
	Description:- Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor's own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy paint will be supplied by Railways. NOTE:- The paint and primer should be from Asian Paints/ Nerolac / Dulux / Berger. The primer / enamel paints (Aluminum synthetic, black enamel, brilliant white and yellow) will be as per (IS 5660 of 1970) / (IS 2932 of 1974):- Main Signal Post with Signal Units, Surface base and complete fittings as per Western Railways standard practice.						
6	6	4.00	Numbers	8284.88	33139.52	AT Par	33139.52
	Description:- Excavation and Casting of foundation for main signal post as per CSTE/3122 (WR) with contractor's own materials including cement and anchor bolts of standard size. The required scaffolding Ferma etc for Casting of foundation will have to be brought by the contractor at his own cost.						
7	7	4.00	Numbers	2458.58	9834.32	AT Par	9834.32
	Description:- Erection of CLS Post with base and signal unit on top or on OFF set Bracket, fixing of front and back staging, ladder and guards, signal name plates / boards if any with contractor's own brackets and fixing materials. This also includes erection of auxiliary signals like calling on, shunt signal if any. The work shall be done as per instructions of Rly engineer at site. It also includes provision & fixing of maintenance platform as per design given by Engineer -In-Charge at site. The Item includes cutting of Signal post if required by Site In charge. (ii)2/3/4 aspect signal unit mounted mounted directly on signal post						
8	8	4.00	Numbers	1375.07	5500.28	AT Par	5500.28
	Description:- Fabrication and fixing of Signal Number Plate(CSTE Drg No CSTE/6186) , 'A' Marker (Drg No. CSTE/6180), 'AG' Marker (Drg No. CSTE/6181), 'P' Marker (Drg No. CSTE/6182), Arrow Marker (Drg No. CSTE/6183), 'G' Marker (Drg No. CSTE/6184), 'C' Marker (Drg No. CSTE/6185). marker disk on signals as per standard practice All material required for this work shall be supplied by Contractor.						
9	9	1.00	Numbers	6512.14	6512.14	AT Par	6512.14
	Description:- Supply & Fixing of Stop Board, Block section limit Board, goods warning board with contractors own material. The work shall be done as per instruction of Rly. Engineer at site.						
	10	7000.00	Running Metre	10.18	71260.00	AT Par	71260.00

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

10	Description:- "Laying of S&T Cables of various cores/ pairs/ quads in trenches/ GI pipes/ RCC pipes/ DWC pipes/ Trunking. This also includes laying of cables in track crossings & road crossings. Item includes provision of labels of coloured plastic adhesive tapes or any other identifiable material on each cable to give the cable number at each G.P.(Cables will be maggered before and after its laying by contractor under supervision of Railway Representative and he will submit the maggering report of each testing). Length of the cable laid includes the length of the cable coiled for termination purposes."						
11	11	600.00	cum	308.34	185004.00	AT Par	185004.00
	Description:- Excavation of cable trench as per cable route plan,1Mtr. deep and of 0.3 Mtr. to 0.6 Mtrs wide advised by Engineer-in-charge alongside the track in normal (all type) soil/strata, conforming to distances as per cable route plan and refilling. This work includes clearing of route from bushes etc, covering of cable laid in trench by loose soil for a layer of 50mm thickness approximately before covering by bricks. The work shall be done as per the extant practice on Western Railway and instructions of Railway Engineer at site. In case 1m depth of trench is not achievable due to site conditions, specific approval of JA grade officer will be required for each site where trench depth of 1m is not possible. Without the approval of JA Grade officer, no payment for trenching will be made for trench depth less than 1m.						
12	12	20.00	cum	567.95	11359.00	AT Par	11359.00
	Description:- Digging of cable trench 0.3 Mtrs. Deep and 0.3 Mtrs. Wide on Asphalted Platform / Road / Hard rocky area. Refilling with earth leveling of trenches & restoring the original surface of trenches.						
13	13	50.00	Metre	641.39	32069.50	AT Par	32069.50
	Description:- Providing chase in hard rocky soil for laying of S&T cables where optimum depth (0.5m) in not possible and which is verified and agreed by engineer incharge.						
14	14	1.00	Numbers	14683.70	14683.70	AT Par	14683.70
	Description:- Digging of cable pit (min 2x2x1m) as per instruction of Site Engineer, supplying and filling of sand before and after coiling the cables, covering top of the cable pit with stones and providing brick masonry on all four sides of the cable pit and plastering thereafter.						
15	15	5.00	cum	4077.86	20389.30	AT Par	20389.30
	Description:- Cement concrete work for miscellaneous items in the ratio 1 : 3 : 6 . Item includes excavation, ramming, curing and plastering with cement & sand mixture (aggregate not exceeding 3.8 cm.) (Aggregate cement & sand to be supplied by the contractor).						
16	16	36.00	Running Metre	1352.02	48672.72	AT Par	48672.72
	Description:- Horizontal direction drilling/boring without damage of surface road using Auger Machine. The bore shall be 150 mm dia & shall be done at the depth of minimum 1200 mm from the ground level. The ground level shall be considered ignoring the bank height of the bank of the road. The length of the bore shall be minimum 4 Mtrs long. this include insertion of different dia DWC pipe/ GI pipes coupling etc. as per direction of Engineer In charge. Note:- Pipe will be supplied by railway. Contactor shall provide all material required for boring and adequate nos. of labours for proper laying of cables into the bore. Cable shall be laid cautiously so that it should not get damage due to rough handling & pressure on cable.						
17	17	900.00	Numbers	442.29	398061.00	AT Par	398061.00
	Description:- Supply and placing of Half Round RCC pipes & collars of 150 mm internal dia, 2 meter long (or two pieces of 1 meter long) along with collars as per IS No. 458/2003 of NP type						
18	18	10.00	Running Metre	15.80	158.00	AT Par	158.00
	Description:- Supplying and placing of one layer of standard size of 'B' grade quality bricks of the local make spreading on cables laid.Lengthwise (up to 2 cables).						
19	19	10.00	Numbers	461.81	4618.10	AT Par	4618.10
	Description:- Supply and installation of RCC Cable route marker as per Drg.No.4014/00/CC4 or latest/stone marker						
20	20	400.00	Per Conductor	2.44	976.00	AT Par	976.00
	Description:- Termination of cable cores on ARA terminal/fuse blocks, 8 way terminals block/ Screw less connectors in the apparatus Cases/ cable termination rack. This includes all associated works of pulling out the cable from underground. The work shall be done as per location plans and instructions of Railway Engineer at site. This item includes dressing of Cable, making wiring tree etc.						
21	21	3.00	Numbers	768.73	2306.19	AT Par	2306.19
	Description:- Fabrication and fixing of phenolic laminated sheet of size 10mm thick in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated string rods at the back side for cable support with contractor's own materials. The work shall be done as per drg and arrangement similar to SK 783-1/2. with latest alterations & as per instructions of Rly engineer at site. Half Case						
	22	3.00	Numbers	5910.80	17732.40	AT Par	17732.40

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

22	Description:- Excavation and Casting of Apparatus Case foundation with contractor's own materials including cement and anchor bolts of standard size. The required scaffolding Fermaetc for Casting of foundation will have to be brought by the contractor at his own cost. Half Case as per Drg No SK 747or CSTE/5074 or SS Location						
23	23	3.00	Numbers	711.20	2133.60	AT Par	2133.60
23	Description:- Installation of Apparatus Cases with miniature 'E' type lock on CC foundation. This includes filling of location foundations with river bed sand and plastering on top of the sand. 'E' Type lock will be provided by Railway. (Half Case)						
24	24	3.00	Numbers	97.09	291.27	AT Par	291.27
24	Description:- Lettering / Numbering Termination particulars, equipments names etc., legibly and neatly inside location boxes. This includes supply of paints of Asian Paints/ Nerolac / Dulux / Berger make. - MO INF-SRAPL/ODK/J/0132 Date July 30 ,2021 Half Loc.						
25	25	2.00	Numbers	6848.79	13697.58	AT Par	13697.58
25	Description:- Excavation and Casting of Apparatus Case foundation with contractor's own materials including cement and anchor bolts of standard size. The required scaffolding Ferma etc for Casting of foundation will have to be brought by the contractor at his own cost. Single Case as per Drg No SK 748 or CSTE/5074 .						
26	26	2.00	Numbers	1032.72	2065.44	AT Par	2065.44
26	Description:- Installation of Apparatus Cases with miniature 'E' type lock on CC foundation. This includes filling of location foundations with river bed sand and plastering on top of the sand. 'E' Type lock will be provided by Railway. Single Case						
27	27	2.00	Numbers	2330.38	4660.76	AT Par	4660.76
27	Description:- Fabrication and fixing of phenolic laminated sheet of size 10mm thick in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated string rods at the back side for cable support with contractor's own materials. The work shall be done as per drg and arrangement similar to SK 783-1/2. with latest alterations & as per instructions of Rly engineer at site. Single Case						
28	28	2.00	Numbers	252.47	504.94	AT Par	504.94
28	Description:- Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor's own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy paint will be supplied by Railways. NOTE:- The paint and primer should be from Asian Paints/ Nerolac / Dulux / Berger. The primer / enamel paints (Aluminum synthetic, black enamel, brilliant white and yellow) will be as per (IS 5660 of 1970) / (IS 2932 of 1974). Apparatus Case Full Size. (Outside & inside)						
29	29	2.00	Numbers	159.60	319.20	AT Par	319.20
29	Description:- Lettering / Numbering Termination particulars, equipments names etc., legibly and neatly inside location boxes. This includes supply of paints of Asian Paints/ Nerolac / Dulux / Berger make. - App case Full size						
30	30	2.00	Numbers	9763.56	19527.12	AT Par	19527.12
30	Description:- Installation of Cable Termination Racks Assembly complete including wall supports, scaffolding, 8 way/ARA terminals /Screw less connectors, Tag blocks & other necessary accessories etc. The work shall be done as per approved plan, extant practice on WR & the instruction of Rly engineer at site.						
31	31	1.00	Numbers	1578.37	1578.37	AT Par	1578.37
31	Description:- Supplying & fixing of crank handle box 450 x 250 x 150 mm made of 12mm thick teakwood with a glass front and padlocking and sealing arrangements as per std practice. Pad lock to be supplied by the contractor. All material i.e. teakwood, handle, hinges, glass sheet of 3 mm thick to be supplied by the contractor. Box to be polished and description to be as per instructions of Engineer in - charge.						
32	32	2.00	Numbers	426.00	852.00	AT Par	852.00
32	Description:- Installation of Dual tone bell/buzzer for LC gate user. To be installed on CLS post erected on either side of gate as per instruction of Engineer in charge.						
33	33	4.00	Numbers	1367.15	5468.60	AT Par	5468.60
33	Description:- Installation of Maintenance free Earth Electrode for Maintenance free earth spec of RDSO/SPN/197/2008						
34	34	2.00	Each Module	995.16	1990.32	AT Par	1990.32
34	Description:- Installation wiring testing and commissioning of Fuse change over system (FACS). This includes provision of common Buzzer & indication at ASM Room & ESM Duty Room and painting of fuse details. This also includes fabrication of frame for installation of FACS at Station/ LC gate where installation of relay racks not feasible.(Per unit means Per module)						
	35	1.00	Set	33029.82	33029.82	AT Par	33029.82

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

35	Description:- Casting of CC foundations in the ratio of 1:3:6 for sliding boom as per Drg. Minimum 10 Nos of foundation per set shall be cast using standard size holding down bolts & nuts for erection. Item include excavation, ramming, curing and plastering 1:4 cement and sand mixture. Aggregate, cement, sand and holding down bolts & nuts to be supplied by the contractor.						
36	36	5.00	cum	163.15	815.75	AT Par	815.75
36	Description:- Earthwork in filling in embankment, guide bunds, around buried type abutments, bridge gaps, trolley refuges, rain bunds if provided, platforms etc. with earth excavated from outside railway boundary entirely arranged by the contractor at his own cost as per RDSO's latest guidelines and specifications and special condition of contract including all leads, royalty, lifts, ascents, descents, crossing of nallahs or any other obstructions. The rates shall include all dressing of bank to final profile, demarcation and setting out of profile, site clearance, removing of shrubs, roots of vegetations growth, heavy grass, benching of existing slope of old bank, all handling/re-handling. Taxes, Octroi and royalty etc. As a complete job. Cut trees shall be property of railways and to be deposited in the railway godown unless specified otherwise in the Special conditions of contract						
37	37	1.00	Set	17205.57	17205.57	AT Par	17205.57
37	Description:- Installation & commissioning of Sliding booms with E type lock and KLCR. This includes wiring of KLCR, running of cables, necessary painting & transportation of materials from store to site. All material required to commissioning of slide booms on gate will be supplied by the contractor						
38	38	1.00	Set	7438.64	7438.64	AT Par	7438.64
38	Description:- Installations, wiring, testing and commissioning of Remote Terminal Unit complete along with accessories using Contractor's own wiring & fixing materials. (It includes loading of NETWORKING software and networking with data logger. The requisite communication cable/channel for networking will be arranged by Railway.						
39	39	3.00	Numbers	1503.71	4511.13	AT Par	4511.13
39	Description:- Supply and fixing of KLCR boxes 450x250X150 mm in {field / in location boxes / in sM office / at LC gate as per site condition' It should be made of Hytun/wooden.(teak wood) of high quality as per requirement. Item includes supply of any minor bracket, nuts, bolts and hole drilling, MS angle, MS plate etc. Its also includes fixing of KLCR relays in the boxes						
40	40	2.00	Numbers	1343.27	2686.54	AT Par	2686.54
40	Description:- Jointing of 4 / 6 quad /Signaling cable with Heat Shrinkable straight through Jointing Kit. All the material required for the work are to be arrange by contractor himself at his own cost except Thermo shrinkable Joint Kit . After jointing the cable through test such as insulation test, continuity cable losses etc. to be carried out jointly with Railway Engineer. If any defect or any damage is observed during jointing, the contractor has to redo the joint free of cost.						
41	41	8.00	Numbers	1775.20	14201.60	AT Par	14201.60
41	Description:- Installation of earth electrode as per std. practice and connecting it to equipments to be earthed. This item includes digging of pit in earth 3 m deep & fixing earth electrode pipe, casting of cement concrete enclosure & cover as per Drg No. S&T/Tender/27.Soil treatment to be done as per std. practice. This item includes provision of MS flat/earth lead wires as per instruction and soldering of lead wires. The other end of the wire is to be connected to block equipment, power equipment, cable sheath, signals etc. as per site requirements. 7strand GI wire shall be used as earth lead wire. (Supply of earth electrode is covered in Sch. 'A').						
42	42	500.00	Kg	218.50	109250.00	AT Par	109250.00
42	Description:- Supply & installation of Fencing work around S&T apparatus case or building/office etc.						
43	43	2.00	Numbers	18690.50	37381.00	AT Par	37381.00
43	Description:- Dismantling/Releasing of the existing Indoor Signalling items at station & LC gate connected with station such as dismantling of relay racks, removal of relays, batteries & power equipments, cable termination racks, SM's slide etc.This includes transportation of released material from station to store for DS-8.						
44	44	2.00	Numbers	6454.30	12908.60	AT Par	12908.60
44	Description:- Dismantling Existing Electric lifting barrier / mechanical lifting barriers, Sliding Booms & other material at LC gates complete and transporting them to Consignee's Stores Depot / nearest DS8 yard. This includes complete mechanical items including levers, rodding iron, point fittings, lock bar, compensators, Electrical fittings in the cabin and other miscellaneous items (whatever applicable to the particular installation). Removal of Trestle from the soft soil and bottom, top roller and strand of rod etc. The field items such as Junction boxes, AC boxes etc. shall also be dismantled as per instruction of Engineer - in - charge.						
45	45	2.00	Numbers	4974.46	9948.92	AT Par	9948.92
45	Description:- Dismantling of all signals complete with signal unit, route indicator, signal foundation and other accessories complete with transporting them to consignee's depot or DS-8 depot as per the instruction of Engineer In-charge by contractors own vehicle & labour.(Rate to be consider when total gear to be dismantled at a station is less than 10)						
46	46	2.00	Numbers	32681.69	65363.38	AT Par	65363.38

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

40	Description:- Installation, wiring and commissioning of all type power supply equipments like charger, transformer, auto changeover and inverter etc. at LC gate.							
47	47	4.00	cum	841.27	3365.08	AT Par	3365.08	
	Description:- Dismantling of Concrete foundations/Dimolishing RCC/CC/Stone Work/Cutting Tarcarpenting/CC Flooring/Pricast Concrete slabs etc./Brick work including leading the debris inside Railway limit or outside Railway limit as directed by site in charge.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () B3-Execution Items (SIGNAL Items for LHS in lieu of LC No.92 at Km 698/1-2 Between LXR-WKR.)							126830.18	
1	1	3000.00	Running Metre	9.37	28110.00	AT Par	28110.00	
	Description:- "Laying of S&T Cables of various cores/ pairs/ quads in trenches/ GI pipes/ RCC pipes/ DWC pipes/ Trunking. This also includes laying of cables in track crossings & road crossings. Item includes provision of labels of coloured plastic adhesive tapes or any other identifiable material on each cable to give the cable number at each G.P.(Cables will be maggered before and after its laying by contractor under supervision of Railway Representative and he will submit the maggering report of each testing). Length of the cable laid includes the length of the cable coiled for termination purposes."							
2	2	100.00	Numbers	22.75	2275.00	AT Par	2275.00	
	Description:- Fixing of ARA Terminals /Screw less connectors and fuse blocks on phenolic laminated sheets and fixing by stainless steel/brass nuts & bolts. This includes provision of two additional holes on the board on either side for cable conductor entry.							
3	3	100.00	Per Conductor	23.70	2370.00	AT Par	2370.00	
	Description:- Termination of cable cores on ARA terminal/fuse blocks, 8 way terminals block/ Screw less connectors in the apparatus Cases/ cable termination rack. This includes all associated works of pulling out the cable from underground. The work shall be done as per location plans and instructions of Railway Engineer at site. This item includes dressing of Cable, making wiring tree etc.							
4	4	30.00	cum	839.00	25170.00	AT Par	25170.00	
	Description:- Excavation of cable trench as per cable route plan, 1Mtr. deep and of 0.3 Mtr. to 0.6 Mtrs wide advised by Engineer-in-charge alongside the track in normal (all type) soil/strata, conforming to distances as per cable route plan and refilling. This work includes clearing of route from bushes etc, covering of cable laid in trench by loose soil for a layer of 50mm thickness approximately before covering by bricks. The work shall be done as per the extant practice on Western Railway and instructions of Railway Engineer at site. In case 1m depth of trench is not achievable due to site conditions, specific approval of JA grade officer will be required for each site where trench depth of 1m is not possible. Without the approval of JA Grade officer, no payment for trenching will be made for trench depth less than 1m.							
5	5	10.00	cum	438.73	4387.30	AT Par	4387.30	
	Description:- Cutting of Hard rock in trenches /Preparation of cable way/Chase 150mm wide at the bottom and 300 mm deep in hard rock (Drg prepared by contactor & approved by Engineer In charge) for laying of S&T cables where minimum required depth not possible & which is verified and agreed by Engineer In charge of the work or his representative shall be made as per Drg. No RE/S&T/ALD/SK/301/85. Refilling of the same with concrete mixture of 1:3:6 from top of the cable way/ chase. Payment of concrete will be made separately through a separate item in the schedule of work.							
6	6	30.00	Metre	468.16	14044.80	AT Par	14044.80	
	Description:- Providing chase in hard rocky soil for laying of S&T cables where optimum depth (0.5m) is not possible and which is verified and agreed by engineer incharge.							
7	7	50.00	Numbers	480.81	24040.50	AT Par	24040.50	
	Description:- Supply and placing of Half Round RCC pipes & collars of 150 mm internal dia, 2 meter long (or two pieces of 1 meter long) along with collars as per IS No. 458/2003 of NP type							
8	8	5.00	Numbers	412.66	2063.30	AT Par	2063.30	
	Description:- Supply and installation of RCC Cable route marker as per Drg.No.4014/00/CC4 or latest/stone marker							
9	9	2.00	Numbers	5487.86	10975.72	AT Par	10975.72	
	Description:- Excavation and Casting of Apparatus Case foundation with contractor's own materials including cement and anchor bolts of standard size. The required scaffolding Fermaetc for Casting of foundation will have to be brought by the contractor at his own cost. Half Case as per Drg No SK 747or CSTE/5074 or SS Location							
	10	2.00	Numbers	777.78	1555.56	AT Par	1555.56	

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

10	Description:- Fabrication and fixing of phenolic laminated sheet of size 10mm thick in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated string rods at the back side for cable support with contractor's own materials. The work shall be done as per drg and arrangement similar to SK 783-1/2. with latest alterations & as per instructions of Rly engineer at site. Half Case.							
11	11	2.00	Numbers	251.05	502.10	AT Par	502.10	
	Description:- Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor's own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-incharge. Epoxy paint will be supplied by Railways. NOTE:- The paint and primer should be from Asian Paints/ Nerolac /Dulux / Berger. The primer / enamel paints (Aluminum synthetic, black enamel, brilliant white and yellow) will be as per (IS 5660 of 1970) / (IS 2932 of 1974). Painting of Apparatus case Half Size.(Outside & inside)							
12	12	2.00	Numbers	88.18	176.36	AT Par	176.36	
	Description:- Lettering / Numbering Termination particulars, equipments names etc., legibly and neatly inside location boxes. This includes supply of paints of Asian Paints/ Nerolac / Dulux / Berger make. - MO INFSRAPL/ODK/J/0132 Date July 30 ,2021 Half Loc.							
13	13	2.00	Numbers	5579.77	11159.54	AT Par	11159.54	
	Description:- Installation of earth electrode as per std. practice and connecting it to equipments to be earthed. This item includes digging of pit in earth 3 m deep & fixing earth electrode pipe, casting of cement concrete enclosure & cover as per Drg No. S&T/Tender/27.Soil treatment to be done as per std. practice. This item includes provision of MS flat/earth lead wires as per instruction and soldering of lead wires. The other end of the wire is to be connected to block equipment, power equipment, cable sheath, signals etc. as per site requirements. 7strand GI wire shall be used as earth lead wire. (Supply of earth electrode is covered in Sch. 'A').							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () B4-Execution Items (SIGNAL Items for Kanalus: Rectification of bad layout from Pt 112 towards towards RJT.)							128909.47	
1	1032901	1.00	Numbers	6139.76	6139.76	AT Par	6139.76	
	Description:- Excavation and Casting of foundation for Shunt Signal as per Drg. No. CSTE/6090 with Contractor's own materials including Cement and Anchor Bolts of Standard Size. The required scaffolding, Ferma etc. for Casting of foundation will have to be brought by the Contractor at his own cost.							
2	1032902	1.00	Numbers	4169.37	4169.37	AT Par	4169.37	
	Description:- Erection of Position Light Shunt signal with Base, Post, and Signal unit. Wiring & Fixing of Number Plate .The work shall be done as per instructions of Rly engineer at site.							
3	1033100	1.00	Set	1280.82	1280.82	AT Par	1280.82	
	Description:- Fabrication and fixing of 'A' Marker (Drg No. CSTE/6180), 'AG' Marker (Drg No. CSTE/6181), 'P' Marker (Drg No. CSTE/6182), Arrow Marker (Drg No. CSTE/6183), 'G' Marker (Drg No. CSTE/6184), 'C' Marker (Drg No. CSTE/6185). Marker disk on signals as per standard practice All material required for this work shall be supplied by Contractor.							
4	1040500	1.00	Numbers	22354.53	22354.53	AT Par	22354.53	
	Description:- Fixing of Electrical Point Machine on the extended sleepers at points as per std. practice and as per RDSO Drg No. SA 91 51-52 or 9710 or 9161 as per section of rails used. Item includes fixing switch extension bracket, providing insulation for switch extension bracket, fixing ground connection, adjusting opening of the switches and adjusting the point machine with crank handle. The item also includes : (i) Complete material for installation like ground-connections, switch extension brackets, point insulation material, I pipes, wiring materials, various fixing nuts & bolts including castle nuts, spring washers (ii) All smithy & fitting works required at site for complete installation. (iii) Installation of gauge tie plate & providing insulation for gauge tie plate (Insulation in William Stretcher Bar will be Provide by Railways). (iv) Wiring inside the point machine, insertion and termination of tail cable in point machine and junction boxes / location box /cable hut as per extent practice on WR and the instruction of Railway Engineer at site. (v) Supply and fixing of suitable size GI pipes with flange for taking cable into point machine. Note ; The ground connections shall be suitable to the Point Machines as specified by Engineer-in-charge and shall be suitable to the point lay out i.e. 60 Kg. / 52 Kg / 90R as per yard layout. Electrical Point Machine and M-6 / Screw less terminals will be supplied by Railways / covered in Schedule separately.							
5	1050200	1.00	Per Track Circuit	6667.03	6667.03	AT Par	6667.03	

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

	Description:- Fixing and wiring of DC track circuit equipments i.e. track feed charger, resistance, track relay, battery, PPTC fuses etc., in the Apparatus Case and battery box as per standard practice. Termination of tail cable on M 6 / Screw less terminals WAGO or FINOLEX or similar approved make terminals/ fuse blocks / HRC fuse. Item includes testing /commissioning of track circuit. Complete wiring material (including PPTC fuses) which are not covered in Schedule will be supplied by contractor. (Supply of Track feed battery charger, track feed battery, resistances & 'B' type choke & Track relays will be supplied by Railways / covered in Schedule separately).						
6	1050300	1.00	Set	7328.72	7328.72	AT Par	7328.72
	Description:- Installation of DC track circuits covering points zones also. The item includes provision of continuity bonds of seven strand PVC jacketed wire/ GI wire 8 SWG on rail joints after drilling bond-hole of 7.0/7.1/7.2mm Dia (double bond with sleeves and rail clips are to be provided at each rail joint), insertion of insulated block joint, fixing of Track lead Junction box on MS angle two numbers of size 40X40X5 mm 1200 mm length for track feed/ jumper / track relay ends of track CCTs (as per double TLJB arrangements) and also for fixing jumper cables as per insulation diagram WR Drg No. CSTE/6055 and standard practice, making rail connections through suitable insulated sleeves from Track lead Junction box at TF, jumper & TR end with seven strand PVC jacketed wire /GI wire 8 SWG, rail clips for fixing bond wire on the TLJB as per standard practice, termination of tail cables on bootleg terminals etc. TF/TR wiring shall be fixed on the suitable arrangement on PRC sleepers with the help of hooks. Hooks shall be provided on PRC sleepers with the help of suitable steel bracket. This item also includes fixing & supply of channel pins etc. The item also includes supply of MS angles/ trestles, GI wire 8 SWG / seven strand PVC jacketed wire, hooks, rail clips etc.						
7	1060700	1.00	Station	6954.45	6954.45	AT Par	6954.45
	Description:- Installation, wiring & testing / commissioning of Axle Counter's Reset Box of all types in Cabin/Panel room and wiring the same to integrate with the Axle counter as per the instructions of Railway Engineer at site. This includes laying & termination of cable if any form Panel Room/Axle Counter room /Relay room to Reset Box in DWC pipe / existing ladder.(When reset box is shifted from existing building to new building).						
8	1071200	5.00	Numbers	366.58	1832.90	AT Par	1832.90
	Description:- Fixing & wiring of QNA1 / QNA1K relays for GPR Circuit in apparatus case as per Standard practice. Fixing and wiring material shall be supplied by the contractor.						
9	1083700	4.00	Numbers	5579.77	22319.08	AT Par	22319.08
	Description:- Installation of Earth Electrode including MS flat for clamp etc. and connection to signalling equipments, lever frames, apparatus cases, signal, relay rack, block instrument, etc. as per technical specification given. This item includes digging of pit in earth 3 M deep & fixing earth electrode pipe, casting of cement concrete enclosure & cover as per RDSO/SPN/ 197/2016.Soiltreatment to be done as per std. practice. This item includes provision of MS Flat, Earth lead wires and Soldering of lead wires. The other end of the wire is to be connected to block equipment, power equipment, cable sheath, and signals etc. as per site requirements. 7strand GI wire shall be used as earth lead wire. Supply of earth electrode is covered in other Item').						
10	1084200	120.00	Numbers	22.75	2730.00	AT Par	2730.00
	Description:- Fixing of ARA Terminals /Screw less connectors and fuse blocks on phenolic laminated sheets and fixing by stainless steel/brass nuts & bolts. This includes provision of two additional holes on the board on either side for cable conductor entry.						
11	1084300	60.00	Numbers	23.70	1422.00	AT Par	1422.00
	Description:- Termination of outdoor cables, main cables laid in location boxes, Cable termination rack etc. at both ends on ARA terminal or on 8 way terminals or on screw less connectors. Both ends of a cable core terminated shall be counted as one terminal. This includes all associated works of pulling out the cable from underground, peeling off insulation, dressing of cable core supported on sting rod with contractor's own material. The work shall be done as per instructions of Rly engineer at site.						
12	1084600	5.00	cum	2061.36	10306.80	AT Par	10306.80
	Description:- Providing brick masonry in ratio 1:6 cement and mortar including plastering with 1:4 cement and sand mixture both sides, 20 mm thick each with contractor's owned class II bricks, including excavation, curing, grouting, bolting etc. wherever required. Bricks sand and cement to be supplied by the contractor.						
13	1084700	5.00	cum	6259.00	31295.00	AT Par	31295.00
	Description:- Cement concrete work for miscellaneous items in the ratio 1: 3: 6. Item includes excavation, ramming, curing and plastering with cement & sand mixture (aggregate not exceeding 3.8 cm.) (Aggregate cement & sand to be supplied by the contractor).						
	1084800	5.00	cum	154.51	772.55	AT Par	772.55

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

14	Description:- Earthwork in filling in embankment, guide bunds, around buried type abutments, bridge gaps, trolley refuges, rain bunds if provided, platforms etc. with earth excavated from outside railway boundary entirely arranged by the contractor at his own cost as per RDSO's latest guidelines and specifications and special condition of contract including all leads, royalty, lifts, ascents, descents, crossing of nallahs or any other obstructions. The rates shall include all dressing of bank to final profile, demarcation and setting out of profile, site clearance, removing of shrubs, roots of vegetation growth, heavy grass, benching of existing slope of old bank, all handling/re-handling. Taxes, Octroi and royalty etc. as a complete job. Cut trees shall be property of railways and to be deposited in the railway godown unless specified otherwise in the Special conditions of contract.							
	1084900	2.00	Per Unit	1062.82	2125.64	AT Par	2125.64	
15	Description:- Dismantling / Releasing of existing Signaling Gears. One Signalling gear will be all parts of one signal (consisting of CLS unit, Signal post along with base) or lever frame (5 levers set), or one point (consisting of all parts of a mechanical point, point machine, ground connections etc.) or one track circuits (consisting of battery box & other parts of DC Track circuit / AFTC /DAC) or one Block instruments or One Lifting Barrier or One Location Box etc. This includes the cost of transportation of release materials to store depot or as decided by consignee in charge. This work to be done by contactors with his own vehicle and labour. (Per unit means Per Gear).							
	1085000	2.00	cum	605.41	1210.82	AT Par	1210.82	
16	Description:- Dismantling of Concrete foundation/ Demolishing RCC/CC/Stone work /Cutting Tar/ carpentering/ CC Flooring / Precast concrete slab/ Brick work including leading the debris inside Railway limit or outside Railway limit as directed by site in charge. This work to be done by contactors with his own vehicle and labour.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () C1-Supply items (Telecom Items for ROB in lieu of LC No 135 at Km 755/0-1 Bet. KHDI-PDH section (2 lanes))							91204.26	
	1	10.00	Numbers	1880.18	18801.80	AT Par	18801.80	
1	Description:- Double Walled Corrugated (DWC) HDPE Pipe with associated collars etc. as per RDSO Specification No. RDSO/SPN/204/2011 or latest anti-rodent & anti-oxidant and non flame propagating type in 6 meters straight length and of size 120 mm outer dia, & 103.5 mm inner dia. (The manufacturers, suppliers must produce valid IS license and should be certified under ISO 9000 and shall submit copy of certificate). One of the following coupling arrangements should also be supplied with each pipe as per the site requirement. 1) Suitable snap fit coupler with rubber 'O' Ring 2) Spacers 3) Tees 4) Bend, 5) End-cap (The total quantity of above items is equal to no. of pipes supplied.) DWC pipe shall be marked at every 1 mtr length in such a way that manufacturer's name, vender name and year of manufacture can be easily identified as per technical specification of tender condition.							
	2	30.00	Numbers	266.48	7994.40	AT Par	7994.40	
2	Description:- Supply of Half round RCC pipe with 150mm mm inner dia as per technical specification of tender condition.(appx. 2 mtr Long As per I.S. 458/2003)							
	3	4.00	Numbers	2647.96	10591.84	AT Par	10591.84	
3	Description:- Supply of Thermo shrinkable joint kit as per RDSO spec no. IRS TC 77/2010 Rev-2 or latest suitable for 2T joint RTSF3 suitable to 6-quad cable of spec no. IRS TC-30/2005, Ver-1, Amd-4 or latest as per technical specification of tender condition. With VF tapping transformer (RDSO spec.IRS:TC:76/2000 with amendment 1.)							
	4	4.00	Numbers	5083.91	20335.64	AT Par	20335.64	
4	Description:- Supply of 2x24 fiber optic fiber splice straight joint enclosure (SJC) complete with all accessories as per TEC Spec no. GR/OJC/02/02.MARCH 99 TEC specs for 24 fiber OFC cable with latest amendment as per technical specification of tender condition.							
	5	2.00	Numbers	5191.68	10383.36	AT Par	10383.36	
5	Description:- Supply of Plasto crate pre-fabricated OFC jointing pits size 0.6mx0.8mx1m.The material shall be supplied as per engineer in charge instructions as per technical specification of tender condition.							
	6	0.40	Kilometre	57743.05	23097.22	AT Par	23097.22	
6	Description:- Supply of HDPE duct 40/33 mm as per TEC GR No. G/CDS 08/02 NOV-2004 with latest amendments as available. For each Km of HDPE duct following items are to be supplied a) End Plugs-2no b) Cable sealing plugs -2 no. (c) Plastic couplers slip fit/push fit type - 2no d) End plugs to be provided along with drum -2 nos. (as per technical specification of tender condition)							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () C2-Supply Items (Telecom Items for ROB in lieu of LC No 147 at Km 770/1-2 Bet. PDH-CX section (2 lanes))							91204.26	
	1	10.00	Numbers	1880.18	18801.80	AT Par	18801.80	

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

1	Description:- Double Walled Corrugated (DWC) HDPE Pipe with associated collars etc. as per RDSO Specification No. RDSO/SPN/204/2011 or latest anti-rodent & anti-oxidant and non flame propagating type in 6 meters straight length and of size 120 mm outer dia, & 103.5 mm inner dia. (The manufacturers, suppliers must produce valid IS license and should be certified under ISO 9000 and shall submit copy of certificate). One of the following coupling arrangements should also be supplied with each pipe as per the site requirement. 1) Suitable snap fit coupler with rubber 'O' Ring 2) Spacers 3) Tees 4) Bend 5) End-cap (The total quantity of above items is equal to no. of pipes supplied.) DWC pipe shall be marked at every 1 mtr length in such a way that manufacturer's name, vender name and year of manufacture can be easily identified as per technical specification of tender condition.							
2	2	30.00	Numbers	266.48	7994.40	AT Par	7994.40	
	Description:- Supply of Half round RCC pipe with 150mm mm inner dia as per technical specification of tender condition. (appx. 2 mtr. Long As per (I.S. 458/2003)							
3	3	4.00	Numbers	2647.96	10591.84	AT Par	10591.84	
	Description:- Supply of Thermo shrinkable joint kit as per RDSO spec no. IRS TC 77/2010 Rev-2 or latest suitable for 2T joint RTSF3 suitable to 6-quad cable of spec no. IRS TC-30/2005, Ver-1, Amd-4 or latest as per technical specification of tender condition. With VF tapping transformer (RDSO spec. IRS:TC:76/2000 with amendment 1)							
4	4	4.00	Numbers	5083.91	20335.64	AT Par	20335.64	
	Description:- Supply of 2x24 fiber optic fiber splice straight joint enclosure (SJC) complete with all accessories as per TEC Spec no. GR/OJC/02/02.MARCH 99 TEC specs for 24 fiber OFC cable with latest amendment as per technical specification of tender condition.							
5	5	2.00	Numbers	5191.68	10383.36	AT Par	10383.36	
	Description:- Supply of Plasto crate pre-fabricated OFC jointing pits size 0.6mx0.8mx1m. The material shall be supplied as per engineer in charge instructions as per technical specification of tender condition.							
6	6	0.40	Kilometre	57743.05	23097.22	AT Par	23097.22	
	Description:- Supply of HDPE duct 40/33 mm as per TEC GR No. G/CDS 08/02 NOV-2004 with latest amendments as available. For each Km of HDPE duct following items are to be supplied a) End Plugs- 2no b) Cable sealing plugs -2 no. (c) Plastic couplers slip fit/push fit type - 2no d) End plugs to be provided along with drum -2 nos. (as per technical specification of tender condition)							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () C3-Supply Items (Telecom items For LHS in lieu of LC No.92 at Km 698/1-2 Between LXR-WKR.)							540390.49	
1	1	12.00	Numbers	1980.62	23767.44	AT Par	23767.44	
	Description:- Double Walled Corrugated (DWC) HDPE Pipe with associated collars etc. as per RDSO Specification No. RDSO/SPN/204/2011 or latest anti-rodent & anti-oxidant and non flame propagating type in 6 meters straight length and of size 120 mm outer dia, & 103.5 mm inner dia. (The manufacturers, suppliers must produce valid IS license and should be certified under ISO 9000 and shall submit copy of certificate). One of the following coupling arrangements should also be supplied with each pipe as per the site requirement. 1) Suitable snap fit coupler with rubber 'O' Ring 2) Spacers 3) Tees 4) Bend 5) End-cap (The total quantity of above items is equal to no. of pipes supplied.) DWC pipe shall be marked at every 1 mtr length in such a way that manufacturer's name, vender name and year of manufacture can be easily identified as per technical specification of tender condition.							
2	2	60.00	Numbers	277.73	16663.80	AT Par	16663.80	
	Description:- Supply of Half round RCC pipe with 150mm mm inner dia as per technical specification of tender condition. (appx. 2no. X 1 mtr. Long As per I.S. 458/2003)							
3	3	8.00	Numbers	2623.54	20988.32	AT Par	20988.32	
	Description:- Supply of Thermo shrinkable joint kit as per RDSO spec no. IRS TC 77/2010 Rev-2 or latest suitable for 2T joint RTSF3 suitable to 6-quad cable of spec no. IRS TC-30/2005, Ver-1, Amd-4 or latest as per technical specification of tender condition. With VF tapping transformer (RDSO spec. IRS:TC:76/2000 with amendment 1)							
4	4	4.00	Numbers	5074.18	20296.72	AT Par	20296.72	
	Description:- Supply of 2x24 fiber optic fiber splice straight joint enclosure (SJC) complete with all accessories as per TEC Spec no. GR/OJC/02/02.MARCH 99 TEC specs for 24 fiber OFC cable with latest amendment as per technical specification of tender condition.							
5	5	1.00	Kilometre	60349.57	60349.57	AT Par	60349.57	
	Description:- Supply of HDPE duct 40/33 mm as per TEC GR No. G/CDS 08/02 NOV-2004 with latest amendments as available. For each Km of HDPE duct following items are to be supplied a) End Plugs- 2no b) Cable sealing plugs -2 no. c) Plastic couplers slip fit/push fit type - 2no d) End plugs to be provided along with drum -2 nos. (As per technical specification of tender condition)							
	6	1.00	Numbers	10665.68	10665.68	AT Par	10665.68	

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

6	Description:- Supply of ultra isolation transformer 230V/230V-1.5 KVA with MOVR protection on either side to provide X protection and supply of crow bar surge protection circuit for 48v DC side to provide Y protection as per the schematic diagram (at HQ) supplied by the railways. Conforming to Technical specification, tender documents and telecom manual and WR practices. (As per technical specification of tender condition)						
7	7	100.00	Metre	52.51	5251.00	AT Par	5251.00
	Description:- Supply of SWITCH BOARD CABLE (10PAIR) CONFIRMING TO ITD SPECIFICATION G/WIR-06/03 MAR02 OR LATEST MAKE:- NETWORKCABLE OR SIMILAR. (As per technical specification of tender condition)						
8	8	4.00	Pair	2099.98	8399.92	AT Par	8399.92
	Description:- supply of optical to ethernet media converter for single mode single fiber as per RDSO specification RDSO/SPN/TC/103/2013 rev2 or latest of make D link/ TP link/ Tenda as per technical specification of tender condition.						
9	9	1.00	Pair	19808.24	19808.24	AT Par	19808.24
	Description:- Supply of E1 extender (24v at datalogger end) with following specifications: operations on 2-wirecopper circuits using G'SHDSL'Driving range:6.5 km at 2048 kbps on 24 AWG(0.5mm dia) unloaded copper pair under error -free conditions. Power supply input-options for 230VAC, 48VDC, 24VDCor various combinations 'Make:Cygnus/Anda/Team link or similar as per technical specification of tender condition. (Should be supply in pair)						
10	10	4.00	Numbers	3381.94	13527.76	AT Par	13527.76
	Description:- Supply of Netgear /D-Link/Hikvision 8 port POE switch with fast ethernet or higher unmanaged switch with 60 watt capacity. Accepted firms offer Make: hikvision (As per technical specification of tender condition)						
11	11	8.00	Numbers	5054.46	40435.68	AT Par	40435.68
	Description:- Supply of Surge protection device (SPD) 4- Pole, 5 V versions as detailed in Annexure A. similar to model no MDP- 4 D-5-T of OBO make. Make OBO, Phoenix, ABB or DEHN. Detailed specification Annexure "A" (As per technical specification of tender condition)						
12	12	4.00	Numbers	553.41	2213.64	AT Par	2213.64
	Description:- LAN TESTER compatible and suitable with Cat 5,Cat 6e cable & RJ 45 . Make/model: LED Fluke,3C3LED LAN, Cable Master 200 or similar or latest. As per technical specification of tender condition.						
13	13	2.00	Numbers	1823.42	3646.84	AT Par	3646.84
	Description:- Supply of Light Weight portable control telephone as per RDSO specification no.IRSTC 78/2000 with Amdt.2 or latest as per technical specification of tender condition.						
14	14	100.00	Metre	28.40	2840.00	AT Par	2840.00
	Description:- Supply of PVC Switch Board 5 Pair 0.5 MM DIA ANNEALED COPPER TELEPHONE CABLE as per technical specification of tender condition.						
15	15	100.00	Metre	124.90	12490.00	AT Par	12490.00
	Description:- 20 pair pvc indoor cable 0.5 mm dia as per attached specification. Make: phinox or Network cable or similar as per technical specification of tender condition.						
16	16	1.00	Numbers	19279.30	19279.30	AT Par	19279.30
	Description:- Tool Kit consisting of Optical power meter (Fiber shot 9990V), Multimeter (Fluke101),Ethernet Crimping tool (Standard Make), Console cable (Cisco=RJ45-DB9), Wrist ripper (Standard Make), Universal Spanner Set (Taparia), Screw Driver Set (Taparia-7 Pieces set), Cutting plier (Taparia), Wire Stripper, Industrial grade USB to Serial cable with all accessories or Similar. [Detailed Specification in Technical Document]. Inspection: Consignee (As per technical specification of tender condition)						
17	17	2.00	Numbers	1750.05	3500.10	AT Par	3500.10
	Description:- Caller ID Landline telephone with 2way speaker and 8 no. of one touch memory FSK/DTMF CLI compatible Tone/pulse make-Bettle model M71N or similar as per technical specification of tender condition.						
18	18	2.00	Numbers	2093.91	4187.82	AT Par	4187.82
	Description:- Caller ID Landline telephone with 2way speaker and 16 no. of one touch memory FSK/DTMF CLI compatible Tone/pulse make-Bettle model M90N or similar as per technical specification of tender condition.						
19	19	2.00	Numbers	1661.34	3322.68	AT Par	3322.68
	Description:- Supply of 20 pairs CT box with wago terminal for termination cables. The Box is rugged, weatherproof, and highly reliable and uses Universal Test Disconnect Terminal Blocks of PHOENIX OR WAGO Make. Epsilon/SARASWAT ENTERPRISES or as approved by Railway. As per technical specification of tender condition.						
20	20	4.00	Numbers	2470.86	9883.44	AT Par	9883.44

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

20	Description:- Supply of Thermo shrinkable joint kit as per RDSO spec no. IRS TC 57/2006 Rev-0 Amd-1 suitable to 10/20/50 pair PJJFU/G telecom cable of spec no. IRS TC-41/97, Amd-2 with latest Amd. Size of the cable will be advised by consignee incharge. Inspection Authority-RDSO (As per technical specification of tender condition)							
21	21	1.00	Numbers	23413.09	23413.09	AT Par	23413.09	
	Description:- Supply of Fiber Distribution management System size 1 U-2 U size (As per RDSO/spec IRS-TC-37/2000 (Ver-3) Amd-1 or latest suitable for termination of 2x24 Fibers. 3M/RAYCHEM/ or Make/model to be approved before supply by railway. As per technical specification of tender condition.							
22	22	2.00	Numbers	1104.77	2209.54	AT Par	2209.54	
	Description:- Supply of 20/50 Pair Krone box with krone terminal. Krone module suitable for 0.5 and 0.63 mm conductor for cable termination with locking facility. As per Spec.							
23	23	2.00	Numbers	4354.77	8709.54	AT Par	8709.54	
	Description:- Road Measuring Cycle, made of Aluminium with 05 digit counter, foldable with bag. As per technical specification of tender condition.							
24	24	500.00	Running Metre	36.75	18375.00	AT Par	18375.00	
	Description:- Supply of 25 mm dia. HDPE pipe (TEC spec. No.G/CDS-08/02, Nov'04 or latest) with accessories on wall or structure/ in trench etc. for drawing of CAT-6/OFC cable/ power cable in the same to suit All materials for jointing, fixing, clamping of HDPE pipe as per technical specification of tender condition.							
25	25	12.00	Numbers	1759.98	21119.76	AT Par	21119.76	
	Description:- Supply of Wall Mount 6 core OFC Termination Box complete with basehousing, basemounting with fixing arrangement, etc. & as per specification.							
26	26	100.00	Metre	153.00	15300.00	AT Par	15300.00	
	Description:- Supply of 16 Sq.MM Single Core Multi-Strand Copper Wire as per specification.							
27	27	1000.00	Metre	24.23	24230.00	AT Par	24230.00	
	Description:- Supply of Armoured Optical Fibre Cable, 6Core, Single Mode as per specification.							
28	28	305.00	Metre	27.53	8396.65	AT Par	8396.65	
	Description:- Supply of STP (Shielded Twisted Pair) CAT-6 cable compliant with latest EIA/TIA-568-B. 2-1 standard of make: D-Link/ DAX/ Lucent/Crone/Amp. As per technical specification of tender condition.							
29	29	100.00	Metre	54.68	5468.00	AT Par	5468.00	
	Description:- Supply of power cable 3 core, 2.5 sqmm, multi strand [36/0.3mm dia.] cable as per IS 694:1990 reaffirmed 1995 or latest suitable for Railway electrification area, shall be of reputed make like Havells, Delton, LAPP, Finolex or superior. Inspection By-Consignee (As per technical specification of tender condition)							
30	30	100.00	Numbers	22.83	2283.00	AT Par	2283.00	
	Description:- Supply of Shielded RJ-45 Connectors for CAT6 / CAT6A STP Cables - Pass Through Connectors Gold Plated 3 Prong 8P8C Modular Plugs for FTP/STP Stranded Ethernet Cable and Solid wire 23AWG of D-Link / Digisole / Spectra / DAX / Megabyte / Opti-Link. As per technical specification of tender condition.							
31	31	4.00	Numbers	12497.09	49988.36	AT Par	49988.36	
	Description:- Supply of 10 Port Gigabit Smart Managed POE+ Layer-2 switch, 08x1G POE+ ports @ 150W; 2x1Gb SFP+ Slots as Uplink ports and as per specification. Make: TP-Link/Netgear. As per technical specification of tender condition.							
32	32	4.00	Numbers	4688.14	18752.56	AT Par	18752.56	
	Description:- Dual band GSM Fixed wireless FCT phone supporting 4G SIM with VoLTE facility and battery and extendable battery charger with 230V AC input and 3.8V DC output. Make Beetle model F3-4G or similar from beetle or motorola or matrix only. As per technical specification of tender condition.							
33	33	1.00	Numbers	40627.04	40627.04	AT Par	40627.04	
	Description:- Supply of hand Held Multimeter, True RMS, ;40,000, rechargeable battery Make: Stanley 180. true RMS or equivalent. INSPECTION BY CONSIGNEE (As per technical specification of tender condition)							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () D1-Execution Items (Telecom Items for ROB in lieu of LC No 135 at Km 755/0-1 Bet. KHDH-PDH section)							144223.18	
	1	248.00	cum	305.04	75649.92	AT Par	75649.92	

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

1	Description:- Excavation of trench 300mm wide at the bottom and 1.2 mtr deep, in all type of soils including clearing of trees, bushes, etc. and refilling of cable trench by excavated soil and ramming after laying of HDPE DUCT (laying of HDPE/DWC & 6 Quad. cables, PDF cables etc., will be paid under different items of the schedule). Where desired dimensions of trenches could not be achieved proportionate payment will be made as decided by Engineer-in-charge of the Railway at site. The trenching outside the station limits i.e.) between the home signal of station 'A' to home signal of station 'B' may be done manually or by machine, as per the directions of site in charge. In no case the payment will be made for the trench of higher dimensions, than the dimensions as mentioned above (as per technical specification of tender condition)							
2	2	60.00	Running Metre	24.02	1441.20	AT Par	1441.20	
	Description:- Laying of half round RCC pipe after laying the cables in the trenches as per technical specification of tender condition. (Cable laying is covered separately)							
3	3	60.00	Running Metre	31.38	1882.80	AT Par	1882.80	
	Description:- Placing of DWC/RCC/GI pipes along with collars in trenches at places of track and road crossings, platform cuttings etc. (as per technical specification of tender condition)							
4	4	400.00	Running Metre	10.69	4276.00	AT Par	4276.00	
	Description:- Laying of S&T Cables of various cores/ pairs/ quads in trenches/ GI pipes/ RCC pipes/ DWC pipes/ Trunking. This also includes laying of cables in track crossings & road crossings. Item includes provision of labels of coloured plastic adhesive tapes or any other identifiable material on each cable to give the cable number at each G.P.(Cables will be maggered before and after its laying by contractor under supervision of Railway Representative and he will submit the maggering report of each testing). Length of the cable laid includes the length of the cable coiled for termination purposes. (as per technical specification of tender condition)							
5	5	16.00	Numbers	449.77	7196.32	AT Par	7196.32	
	Description:- Supply and installation of RCC cable route marker engraved and painted on both side along the route every 50m and route diversion as per technical specification of tender condition.							
6	6	4.00	Numbers	8485.29	33941.16	AT Par	33941.16	
	Description:- Splicing of laid under above items OFC cable and making the splice joint in dust free environment with contractor's own equipments and labour. Straight joint enclosure (SJC) is covered under schedule 'A' remaining all required materials, tools , plants shall be arranged by the contractor. splicing shall be started from one end and each splicing shall be monitored after splicing and after closing the enclosure for all the fibers from one central location by contractor's engineer with his own OTDR and optic Talk set with railway engineer , trace for the fibers shall be taken and signed jointly, if any fibred splice shows high loss/lossy event, the same shall be redone before completion of splicing work. The splice loss shall be as per the policy/technical circulars issued by the railways from time to time. (as per technical specification of tender condition)							
7	7	0.40	Kilometre	6492.63	2597.05	AT Par	2597.05	
	Description:- Transportation and Laying of HDPE pipe as per approved cable route plan in the excavated trench, taking due care while transporting and laying the same in the trenches or other protective works. Both the end of duct should be sealed with end plugs before laying and should remain sealed till blowing is done. (as per technical specification of tender condition)							
8	8	0.40	Kilometre	12388.12	4955.25	AT Par	4955.25	
	Description:- Blowing of OFC through HDPE duct & protective work (elicited in above item) already provided. Where it is not feasible to blow OFC due to curves, road/track crossings, bridges or for any other reason, OFC shall be drawn /laid manually as per standard procedure. All the equipment and machinery required shall be arranged by the contractor at his own cost. OFC and HDPE pipe shall be supplied by the railway as per technical specification of tender condition.							
9	9	2.00	cum	3786.30	7572.60	AT Par	7572.60	
	Description:- Cement concrete work for miscellaneous items in the ration 1:3:6, Item includes excavation, ramming, curing and plastering with cement & sand misture (aggregate not exceeding 3.8 cm) (aggregate cement and sand to be supplied by the contractor)							
10	10	4.00	Numbers	1177.72	4710.88	AT Par	4710.88	
	Description:- Jointing of 4 / 6 quad /Signaling cable with Heat Shrinkable straight through Jointing Kit. All the material required for the work are to be arrange by contractor himself at his own cost except Thermo shrinkable Joint Kit . After jointing the cable through test such as insulation test, continuity cable losses etc. to be carried out jointly with Railway Engineer. If any defect or any damage is observed during jointing, the contactor has to redo the joint free of cost. (as per technical specification of tender condition)							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () D2-Execution Items (Telecom Items For ROB in lieu of LC No 147 at Km 770/1-2 Bet. PDH-CX section (2 lanes))							144223.18	

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

1	1	248.00	cum	305.04	75649.92	AT Par	75649.92	
	Description:- Excavation of trench 300mm wide at the bottom and 1.2 mtr deep, in all type of soils including clearing of trees, bushes, etc. and refilling of cable trench by excavated soil and ramming after laying of HDPE DUCT (laying of HDPE/DWC & 6 Quad. cables, PDF cables etc., will be paid under different items of the schedule). Where desired dimensions of trenches could not be achieved proportionate payment will be made as decided by Engineer-in-charge of the Railway at site. The trenching outside the station limits I.e.) between the home signal of station 'A' to home signal of station 'B' may be done manually or by machine, as per the directions of site in charge. In no case the payment will be made for the trench of higher dimensions, than the dimensions as mentioned above as per technical specification of tender condition.							
2	2	60.00	Running Metre	24.02	1441.20	AT Par	1441.20	
	Description:- Laying of half round RCC pipe after laying the cables in the trenches as per technical specification of tender condition. (Cable laying is covered separately)							
3	3	60.00	Running Metre	31.38	1882.80	AT Par	1882.80	
	Description:- Placing of DWC/RCC/GI pipes along with collars in trenches at places of track and road crossings, platform cuttings etc. (as per technical specification of tender condition)							
4	4	400.00	Running Metre	10.69	4276.00	AT Par	4276.00	
	Description:- Laying of S&T Cables of various cores/ pairs/ quads in trenches/ GI pipes/ RCC pipes/ DWC pipes/ Trunking. This also includes laying of cables in track crossings & road crossings. Item includes provision of labels of coloured plastic adhesive tapes or any other identifiable material on each cable to give the cable number at each G.P.(Cables will be maggered before and after its laying by contractor under supervision of Railway Representative and he will submit the maggering report of each testing). Length of the cable laid includes the length of the cable coiled for termination purposes. (As per technical specification of tender condition)							
5	5	16.00	Numbers	449.77	7196.32	AT Par	7196.32	
	Description:- Supply and installation of RCC cable route marker engraved and painted on both side along the route every 50m and route diversion as per technical specification of tender condition.							
6	6	4.00	Numbers	8485.29	33941.16	AT Par	33941.16	
	Description:- Splicing of laid under above items OFC cable and making the splice joint in dust free environment with contractor's own equipments and labour. Straight joint enclosure (SJC) is covered under schedule 'A' remaining all required materials, tools , plants shall be arranged by the contractor. splicing shall be started from one end and each splicing shall be monitored after splicing and after closing the enclosure for all the fibers from one central location by contractor's engineer with his own OTDR and optic Talk set with railway engineer , trace for the fibers shall be taken and signed jointly, if any fibred splice shows high loss/lossy event, the same shall be redone before completion of splicing work. The splice loss shall be as per the policy/technical circulars issued by the railways from time to time. (As per technical specification of tender condition)							
7	7	0.40	Kilometre	6492.63	2597.05	AT Par	2597.05	
	Description:- Transportation and Laying of HDPE pipe as per approved cable route plan in the excavated trench, taking due care while transporting and laying the same in the trenches or other protective works. Both the end of duct should be sealed with end plugs before laying and should remain sealed till blowing is done. (As per technical specification of tender condition)							
8	8	0.40	Kilometre	12388.12	4955.25	AT Par	4955.25	
	Description:- Blowing of OFC through HDPE duct & protective work (elicited in above item) already provided. Where it is not feasible to blow OFC due to curves, road/track crossings, bridges or for any other reason, OFC shall be drawn /laid manually as per standard procedure. All the equipment and machinery required shall be arranged by the contractor at his own cost. OFC and HDPE pipe shall be supplied by the railway. (As per technical specification of tender condition)							
9	9	2.00	cum	3786.30	7572.60	AT Par	7572.60	
	Description:- Cement concrete work for miscellaneous items in the ration 1:3:6, Item includes excavation, ramming, curing and plastering with cement & sand misture (aggregate not exceeding 3.8 cm) (aggregate cement and sand to be supplied by the contractor)							
10	10	4.00	Numbers	1177.72	4710.88	AT Par	4710.88	
	Description:- Jointing of 4 / 6 quad /Signaling cable with Heat Shrinkable straight through Jointing Kit. All the material required for the work are to be arrange by contractor himself at his own cost except Thermo shrinkable Joint Kit . After jointing the cable through test such as insulation test, continuity cable losses etc. to be carried out jointly with Railway Engineer. If any defect or any damage is observed during jointing, the contactor has to redo the joint free of cost as per technical specification of tender condition.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

Schedule () D3-Execution Items (Telecom Items For LHS in lieu of LC No 92 at Km 698/1-2 bet LXR-WKR)							240664.83	
1	1	288.00	cum	303.73	87474.24	AT Par	87474.24	
	Description:- Excavation of trench 300mm wide at the bottom and 1.2 mtr deep, in all type of soils including clearing of trees, bushes, etc. and refilling of cable trench by excavated soil and ramming after laying of HDPE DUCT (laying of HDPE/DWC & 6 Quad. cables, PDF cables etc., will be paid under different items of the schedule). Where desired dimensions of trenches could not be achieved proportionate payment will be made as decided by Engineer-in-charge of the Railway at site. The trenching outside the station limits i.e.) between the home signal of station 'A' to home signal of station 'B' may be done manually or by machine, as per the directions of site in charge. In no case the payment will be made for the trench of higher dimensions, than the dimensions as mentioned above as per technical specification of tender condition.							
2	2	120.00	Running Metre	25.03	3003.60	AT Par	3003.60	
	Description:- Laying of half round RCC pipe after laying the cables in the trenches as per technical specification of tender condition. (Cable laying is covered separately)							
3	3	60.00	Running Metre	31.41	1884.60	AT Par	1884.60	
	Description:- Placing of DWC/RCC/GI pipes along with collars in trenches at places of track and road crossings, platform cuttings etc as per technical specification of tender condition.							
4	4	1000.00	Running Metre	11.14	11140.00	AT Par	11140.00	
	Description:- Laying of S&T Cables of various cores/ pairs/ quads in trenches/ GI pipes/ RCC pipes/ DWC pipes/ Trunking. This also includes laying of cables in track crossings & road crossings. Item includes provision of labels of coloured plastic adhesive tapes or any other identifiable material on each cable to give the cable number at each G.P.(Cables will be maggered before and after its laying by contractor under supervision of Railway Representative and he will submit the maggering report of each testing). Length of the cable laid includes the length of the cable coiled for termination purposes. (As per technical specification of tender condition)							
5	5	20.00	Numbers	447.36	8947.20	AT Par	8947.20	
	Description:- Supply and installation of RCC cable route marker engraved and painted on both side along the route every 50m and route diversion as per technical specification of tender condition.							
6	6	4.00	Numbers	9156.53	36626.12	AT Par	36626.12	
	Description:- Splicing of laid under above items OFC cable and making the splice joint in dust free environment with contractor's own equipments and labour. Straight joint enclosure (SJC) is covered under schedule 'A' remaining all required materials, tools , plants shall be arranged by the contractor. splicing shall be started from one end and each splicing shall be monitored after splicing and after closing the enclosure for all the fibers from one central location by contractor's engineer with his own OTDR and optic Talk set with railway engineer , trace for the fibers shall be taken and signed jointly, if any fibred splice shows high loss/lossy event, the same shall be redone before completion of splicing work. The splice loss shall be as per the policy/technical circulars issued by the railways from time to time. (As per technical specification of tender condition)							
7	7	1.00	Kilometre	6705.45	6705.45	AT Par	6705.45	
	Description:- Transportation and Laying of HDPE pipe as per approved cable route plan in the excavated trench, taking due care while transporting and laying the same in the trenches or other protective works. Both the end of duct should be sealed with end plugs before laying and should remain sealed till blowing is done as per technical specification of tender condition.							
8	8	1.00	Kilometre	13282.20	13282.20	AT Par	13282.20	
	Description:- Blowing of OFC through HDPE duct & protective work (elicited in above item) already provided. Where it is not feasible to blow OFC due to curves, road/track crossings, bridges or for any other reason, OFC shall be drawn /laid manually as per standard procedure. All the equipments and machinery required shall be arranged by the contractor at his own cost. OFC and HDPE pipe shall be supplied by the railway as per technical specification of tender condition.							
9	9	10.00	cum	3774.50	37745.00	AT Par	37745.00	
	Description:- Cement concrete work for miscellaneous items in the ration 1:3:6, Item includes excavation, ramming, curing and plastering with cement & sand misture (aggregate not exceeding 3.8 cm) (aggregate cement and sand to be supplied by the contractor)							
10	10	4.00	Numbers	1150.03	4600.12	AT Par	4600.12	
	Description:- Jointing of 4 / 6 quad /Signaling cable with Heat Shrinkable straight through Jointing Kit. All the material required for the work are to be arrange by contractor himself at his own cost except Thermo shrinkable Joint Kit . After jointing the cable through test such as insulation test, continuity cable losses etc. to be carried out jointly with Railway Engineer. If any defect or any damage is observed during jointing, the contactor has to redo the joint free of cost. (As per technical specification of tender condition)							
	11	1.00	Kilometre	1668.18	1668.18	AT Par	1668.18	

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

11	Description:- Cable route survey & Preparation of as built final cable route and other plans(for OFC as well as other telecom cables whose laying is covered in this schedule) taking into account the points mentioned in chapter II & other chapters of technical requirement on Auto CAD for entire sections for entire sections VG-SIOB. The cable route & other plans shall be prepared by contractor after joint survey, got approved from engineer in charge, changes during course of execution shall be incorporated in the same. After completion of the work all completion documents of tracing papers along with six prints of cable route plan, jointing & splicing schedule, cable hut wiring diagram etc. in six sets for each station and section in folders shall be supplied by the contractor. Contractor shall also supply the Auto CAD documents on CD. All the required materials, accessories including tracings, papers etc shall be contractor's own. (As per technical specification of tender condition)							
12	12	20.00	cum	338.27	6765.40	AT Par	6765.40	Description:- Excavation of cable trench in rocky area, 450 mm wide at the top, 300 mm at the bottom and minimum 0.5 meter deep in rocky area (hard rocky soil mixed with boulders/hardmurrum) including cleaning of trees, bushes. The trenching will be done manually only and limited to the stretch between the home signal to home signal of each station and other locations as per the directives of the site in charge. Where desired dimensions of trenches could not be not achieved proportionate payment will be made as decided by Engineer-in-charge of the Railway at site. In no case the payment will be made for trench of higher dimensions than the dimensions as mentioned above.
13	13	4.00	Numbers	5205.68	20822.72	AT Par	20822.72	Description:- Supply & installation of RCC pre-fabricated OFC jointing pits size 0.6mx1.12mx1m.round type as per As per technical specification of tender condition.

3. ITEM BREAKUP

No item break up added

4. ELIGIBILITY CONDITIONS

Special Financial Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer must have minimum average annual contractual turnover of V/N or V whichever is less; where V= Advertised value of the tender in crores of Rupees, N= Number of years prescribed for completion of work for which bids have been invited. The average annual contractual turnover shall be calculated as an average of "total contractual payments" in the previous three financial years, as per the audited balance sheet. However, in case balance sheet of the previous year is yet to be prepared/ audited, the audited balance sheet of the fourth previous year shall be considered for calculating average annual contractual turnover. The tenderers shall submit requisite information as per Annexure-VIB, along with copies of Audited Balance Sheets duly certified by the Chartered Accountant/ Certificate from Chartered Accountant duly supported by Audited Balance Sheet.	No	No	Allowed (Mandatory)

Special Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
-------	-------------	-----------------------	-----------------	---------------------

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

1	The tenderer must have successfully completed or substantially completed any of the following during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: Three similar works each costing not less than the amount equal to 30% of advertised value of tender, or Two similar works each costing not less than the amount equal to 40% of advertised value of tender, or One similar work each costing not less than the amount equal to 60% of advertised value of tender. NOTE: Work experience certificate from private individual shall not be considered. However, in addition to work experience certificates issued by any Govt. Organisation, work experience certificate issued by Public listed company having average annual turnover of Rs. 500 crore and above in last 3 financial years excluding the current financial year, listed on National Stock Exchange or Bombay Stock Exchange, incorporated/registered atleast 5 years prior to the date of opening of tender, shall also be considered provided the work experience certificate has been issued by a person authorized by the Public listed company to issue such certificates. In case tenderer submits work experience certificate issued by public listed company, the tenderer shall also submit along with work experience certificate, the relevant copy of work order, bill of quantities, bill wise details of payment received duly certified by Chartered Accountant, TDS certificates for all payments received and copy of final/last bill paid by company in support of above workexperience certificate.	No	No	Allowed (Mandatory)
2	Definition of Similar Nature: - "Any signaling work involving outdoor work and/or addition and/or alteration in existing indoor signaling system. OR any CLS or RI or EI or TPWS or IBS or ABS or BPAC work involving Indoor and /or Outdoor. Similar work to include indoor if the tendered work involves addition and/or alteration in existing indoor signaling system and outdoor if the tendered work involves outdoor work OR Any such work involving activities as given in the name of tendered work."	No	No	Allowed (Mandatory)
2.1	Alteration is required in Existing Westrace make Electronic Interlocking System and Existing VDU layout of KHDl station. therefore "The successful bidder shall submit an undertaking from RDSO approved EI OEM, before the supply of material, to confirm compliance with extant RDSO guidelines and to meet contract specific requirements."	No	No	Not Allowed
3	Undertaking by the tenderer that the equipment of EI shall be procured from RDSO approved sources and modification, alteration, installation and testing of EI shall also be got done from the same source/OEM including after sales support required during warranty period should be submitted.	No	No	Allowed (Mandatory)

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.
3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.
5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.
6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.
7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.
8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.
10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description
1	Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. (Click here to download the Format of Self Certification)

5. COMPLIANCE

Check Lst

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	1.EMD/Bid security is deposited as per Clause 5 of Part I "regulations for tenders and contract " of tender document. 2. EMD need to be deposited online on www.ireps.gov.in . 3. For the tenders costing upto 50 Lakhs: - No technical and financial credentials required but firm's documents and any other mandatory documents which are demanded in tender are require to be submit at the time of bidding. 4. tender having value more than 50 Lakhs: - Financial and technical credentials required as per GCC applicable and firm's documents and any other mandatory documents which are demanded in tender are require to be submit at the time of bidding.	No	No	Not Allowed

Commercial-Compliance

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	1. If Tenderer is sole proprietor: Affidavit on Stamp paper of appropriate value declaring that his/her concern is a Proprietary concern or any other documents such as GST Certificate, PAN Card of firm Name etc. is to be submitted. 2. If Tenderer is partnership firm: Notarized partner ship deed Original/Notarized power of attorney. 3. If Tenderer is JV/Limited Company: Copy of Memorandum and Articles of Association of the company. Power of Attorney (duly registered/notarized as per prevailing law) by the company authorizing the person to do/act on behalf of the company. 4. If Tenderer is Company: Copies of MOA (Memorandum of Association) & AOA (Articles of Association) of the company. Power of attorney duly registered/notarized by the company in favour of the individual signing the tender on behalf of the company. Resolution of Board of directors in regards of approving Power of attorney issued. 5. If Tenderer is Society: Attested copy of the certificate of registration. Deed of formation. Power of attorney in favour of the tender signatory. 6.Copy of PAN number and TIN number.	No	No	Allowed (Mandatory)
2	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)

General Instructions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
-------	-------------	-----------------------	-----------------	---------------------

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

1	No post tender correspondence for submission of additional documents shall be entertained after opening of the Technical & Commercial offers. Even suo-moto post tender letters of the tenders shall be treated as NULL & Void.	No	No	Not Allowed
2	It is responsibility of the tenderer that they ensure to see any corrigendum of the tenderer to check the corrigendum on the IREPS website from time to time.	No	No	Not Allowed
3	Refer to attached tender documents for complete information, Terms & Conditions of contract, scope of work, schedule of rates, inspection authority and special conditions of contract etc.	No	No	Not Allowed
4	The Railway reserves the right to verify all statements, information and documents submitted by the bidder in his tender offer, and the bidder shall, when so required by the Railway, make available all such information, evidence and documents as may be necessary for such verification. Any such verification or lack of such verification, by the Railway shall not relieve the bidder of its obligations or liabilities hereunder nor will it affect any rights of the Railway thereunder.	No	No	Not Allowed
5	After opening of the tender, any document pertaining to the constitution of Sole Proprietorship Firm /Partnership Firm / Registered Company/ Registered Trust / Registered Society / HUF etc. shall be neither asked nor considered, if submitted. Further, no suo moto cognizance of any document available in public domain (i.e., on internet etc.) or in Railway's record/office files etc. will be taken for consideration of the tender, if no such mention is available in tender offer submitted.	No	No	Not Allowed
6	Any bidder from a country which shares land border with India will be eligible to bid in this tender only if the bidder is registered with the competent authority.	No	No	Not Allowed

Technical-Compliances

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The following document should be submitted along with Tender Form :- (a) List of personnel, organization available on hand and proposed to be engaged for the subject work. (b) List of plant & machinery available on hand (own) and proposed to be inducted (own) and hire to be given separately for the subject work. (c) List of work completed in the last three financial years given description of work, organization for whom executed, approximate value of contract at the time of award, date of award and date of scheduled completion and final value of contract should also be given. (d) List of work on hand indicating description of work, contract value, and approximate value of balance work yet to be done and date of award. (e) An audited balance sheet duly certified by Chartered Accountant for last three financial years other relevant documents to be given in support of financial turn over. Tender committee shall still examine the over all financial soundness of the tenderers based upon the volume of work handled, turnover, balance sheet etc.	No	No	Not Allowed
1.1	Note:- (1) In case of item (c) and (d) above supportive documents/certificate from the organizations with whom they worked / are working should be enclosed. (2) Certificate from private individuals, private organizations / private limited company / public limited company (Private sector) shall not be accepted.	No	No	Not Allowed
2	Deviation Statement: The tenderer shall submit a statement indicating any deviations against any clause of this tender including all the technical specification concerned to this work, duly signed and stamped on each page. If there are no deviation whatsoever, a NIL deviation statement should be submitted. (As per "Deviation Statement" Annexure A in Tender document Attached.	No	No	Allowed (Mandatory)

Undertakings

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
-------	-------------	-----------------------	-----------------	---------------------

**RAJKOT DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: DRM-RJT-26-27-SnT-E-02R1

Closing Date/Time: 22/06/2026 15:30

1	I have read the entire tender document including uploaded documents.	No	No	Not Allowed
2	I/we have visited the site and I am/We are aware about site condition.	No	No	Not Allowed
3	It is certified that I/We have not been blacklisted or debarred by railways or any other ministry/department/public sector undertaking of the government of India/State Government from participation in tenders/contract on the date of tender opening of bids, either in individual capacity or as a member of JV firm in which I/We were/are members.	No	No	Not Allowed
4	I hereby certify that no retired Engineer / Gazatted Officer of the Railways who has retired within 1 years of date of submission of tender and has not obtained permission of competent authority has been engaged by me/our firm.	No	No	Not Allowed

Custom

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Digital Police verification of labour engaged in awarded work is compulsory. If engaged labour found without digital police verification necessary action will be taken by Railway Police (RPF) and execution of work will be stop immediately. Hence, police verification of labour is must to execute work in Railway premises. Original Copy of Digital police verification is to be submitted to this office without fail otherwise billing of work will not process.	No	No	Not Allowed
2	All bidders are required to go through tender documents , relevant annexures, tender forms etc. attached with tender for detailed tender conditions before submitting their bid online on website.	Yes	No	Not Allowed

6. Documents attached with tender

S.No.	Document Name	Document Description
1	ACSUPTO11_compressed.pdf	ACS up to 11
2	DRM-RJT-26-27-SnT-E-02R1-GCC2022ACS11.pdf	GCC 2022 ACS upto 11
3	SpecialconditionofContract.pdf	Special condition of Contract

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

Signed By: SMITA KUMARI

Designation : DSTE