

**SOLAPUR DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-N-T-2026-27-13

Closing Date/Time: 19/06/2026 15:30

Sr. DSTE Solapur acting for and on behalf of The President of India invites E-Tenders against Tender No **SUR-N-T-2026-27-13** Closing Date/Time 19/06/2026 15:30 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

1. NIT HEADER

Name of Work	S&T works in connection with development of Goods Sheds at Tajsultanpur and Dharashiv stations of Solapur Division.		
Bidding type	Normal Tender		
Tender Type	Open	Bidding System	Single Packet System
Tender Closing Date Time	19/06/2026 15:30	Date Time Of Uploading Tender	25/05/2026 11:31
Pre-Bid Conference Required	No	Pre-Bid Conference Date Time	Not Applicable
Advertised Value	7964927.18	Tendering Section	SUR DIV
Bidding Style	Single Rate for Tender	Bidding Unit	Above/Below/Par
Earnest Money (Rs.)	159300.00	Validity of Offer (Days)	60
Tender Doc. Cost (Rs.)	0.00	Period of Completion	12 Months
Contract Type	Works - General	Contract Category	Expenditure
Bidding Start Date	05/06/2026		
Are JV allowed to bid	No	Number of JV Member Allowed	0
Are Consortium allowed to bid	No	Number of Consortium Member Allowed	0
Ranking Order For Bids	Lowest to Highest	Expenditure Type	Capital (Works)

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () 01-SOR SUPPLY							2310844.42	
01	Please see Item Breakup for details.				2310844.42	AT Par	2310844.42	
	Description:- SUPPLY OF SOR ITEMS							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () 02-SOR EXECUTION							1483020.21	
01	Please see Item Breakup for details.				1483020.21	AT Par	1483020.21	
	Description:- EXECUTION OF SOR ITEMS							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () 03-NS SUPPLY AND EXECUTION							2098048.69	
01	Please see Item Breakup for details.				2098048.69	AT Par	2098048.69	
	Description:- SUPPLY AND EXECUTION OF NON SOR ITEMS							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () 04-TELECOM SUPPLY AND EXECUTION							2073013.86	
01	Please see Item Breakup for details.				2073013.86	AT Par	2073013.86	
	Description:- SUPPLY AND EXECUTION OF TELECOM ITEMS							

3. ITEM BREAKUP

Schedule	Schedule 01-SOR SUPPLY					
Item- 01	SUPPLY OF SOR ITEMS					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount

**SOLAPUR DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-N-T-2026-27-13

Closing Date/Time: 19/06/2026 15:30

1	01	Supply of Signal No.plates. as per Drg No RST-11393 / SK-842. (Inspection by Consignee)	Numbers	50.00	521.69	26084.50
2	02	Supply of A/AG/C/P/G/IB Board as per Drg. RST-11444/1(A), RDSO Drg No SA 23460(AG), SA-23461©, RST-11445. SA 23456(P), SA 23477(G) & SA 23476-77(IB) as applicable respectively with Latest Amendment. (Inspection by Consignee)	Numbers	5.00	561.74	2808.70
3	03	Supply of Stop Board/IB Board as per RST-11791 (STOP BOARD)/ RDSO Drg No.7235/B as per extent C.Rly practice. (Inspection by Consignee)	Numbers	2.00	3340.11	6680.22
4	04	Supply of Hand Cuff Locks/ Godrej Navtal lock with Three common keys. (Inspection by Consignee)	Numbers	50.00	286.20	14310.00
5	05	Supply of ARA Terminal blocks with links made of PBT Specn No.IRS:S-75/2006 (Rev - 2) with latest amendments and RDSO Drg.No.SA-23741A Alt.4, SA-23745 Alt.5, SA-23746, SA-23748 Alt.4 & SA-23756A Alt.3. (Inspection by RDSO)	Numbers	2000.00	72.61	145220.00
6	06	Supply of cartridge fuse block made of PBT as per RDSO Drg No SA-23748 Alt 4, SA-23749 & Spec No IRS:S-75/2006 (Rev - 2) with latest amendment. Fuse block shall be suitable for round head type voltage fuses. (Inspection by RDSO)	Numbers	30.00	162.94	4888.20
7	07	Supply of round head type non deteriorating type low voltage cartridge fuse as per Specn No IRS/S/78/92 with latest amendments 2A/4A/6A capacity(Inspection by RDSO)	Numbers	60.00	70.13	4207.80
8	08	Supply of Tik-tak, piano type switches,5 A (as per IS Specification).(Inspection by Consignee)	Numbers	6.00	33.41	200.46
9	09	Supply of three pole plug and socket 5 Amp (as per IS Specification).(Inspection by Consignee)	Numbers	6.00	230.86	1385.16
10	10	Supply of Lamp 110V/24W, 2 Pin for Loc. (Inspection by Consignee)	Numbers	100.00	22.73	2273.00
11	11	Supply of Apparatus Case with godown locks with detachable handle on both the doors. .Single Case as per Drg. No.SK 783-1 & 2 with latest alteration.(Inspection by RITES)	Numbers	2.00	16020.05	32040.10
12	12	Supply of Apparatus Case with godown locks with detachable handle on both the doors. Half Case as per Drg. No.SK 783-1 & 2 with latest alteration.(Inspection by RITES)	Numbers	2.00	12853.94	25707.88
13	13	Supply of earth electrode assembly as per Drg.No. CR/S&T/SK-815(Inspection by Consignee)	Numbers	10.00	1078.08	10780.80
14	14	Supply of Track Lead Junction Boxes as per C.Rly Drg. No.RST 11509 made from fiber glass alongwith terminal blocks.(Inspection by Consignee)	Numbers	20.00	1047.98	20959.60
15	15	Supply of Channel Pins single groove, galvanised, 7 mm suitable for 4mm dia bonding wire as per spec No. IRS: S 17-75 Revision 3. (Inspection by Consignee)	Numbers	5000.00	2.01	10050.00
16	16	Supply of PVC jacketed wire rope for Track Lead connections. PVC jacketed wire rope should be of Galvanised steel wire rope 6 mm dia (6x19 stranded wire with steel core of 6 mm dia) sheathed with PVC 2mm wall thickness, overall thickness being 10 mm. PVC sheath should be made of type 6 compound as per IS 5831 of 1984 Reaffirmed 2001 and steel wire rope as per IS: 2266:2019. Reclaimed or recycled material should not be used.(Inspection by Consignee)	Metre	1000.00	52.29	52290.00

**SOLAPUR DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-N-T-2026-27-13

Closing Date/Time: 19/06/2026 15:30

17	17	Supply of 8 SWG GI wire (4mm dia) suitable for track circuit rail bonding. As per IRS Specification S:13 - 62 (Inspection by Consignee)	Kg	500.00	86.82	43410.00
18	18	Supply of GI pipe, inner dia. 100mm dia. B-class as per spec. No.IS 1239 PT. 1/2004 or latest with sockets and fittings. TATA/JINDAL/ZENITH BIRLA make.(Inspection by Consignee)	Metre	60.00	1029.32	61759.20
19	19	Supply of DWC HDPE pipe with one snap fit coupler and 'O' ring fire resistant, anti rodent, in 6 meter length of size 120 mm outer dia as per RDSO/SPN/204/2011 Ver. 1.1 with Amd.1 or latest.(Inspection by Consignee)	Metre	60.00	321.43	19285.80
20	20	Supply of RCC pipes half round of size 150mm dia outer and 100 mm dia internal 1 mtr long matching to IS No. 458/2003 amendment-1 with Rev.4.(Inspection by RITES)	Numbers	1500.00	206.14	309210.00
21	21	Supply of modular terminal block of 2.5 sq mm 2 IN 2 OUT type disconnect type terminal alongwith as per RDSO SPN/189/2004 Ver. 3.0. (Or latest) . The current capacity of 16 Amps and more. The terminal should have marking at centre to view description from front. Material to be procured from RDSO approved firms only.(Inspection by RDSO)	Numbers	1500.00	117.12	175680.00
22	22	Supply of DIN Channel for the above Terminal. 1 Mtrs each(Inspection by Consignee).	Numbers	30.00	216.73	6501.90
23	23	Supply of End plate for modular terminal block. (Inspection by Consignee).	Numbers	300.00	23.39	7017.00
24	24	Supply of End clamp for the modular terminal block.(Inspection by Consignee).	Numbers	300.00	16.81	5043.00
25	25	Fuse terminal block with LED indication up to 2.5 sqmm screw type one in out (suitable for 400 mA,630 mA, 1A,1.6A,2A,4A,6.3A & 10A) as per RDSO SPN/189/2004 Ver.03 (or latest) (without fuse)(Inspection by RDSO)	Numbers	200.00	181.85	36370.00
26	26	End plate for through terminal block with LED indication.(Inspection by Consignee)	Numbers	100.00	13.62	1362.00
27	27	Fuse links of (400 mA, 630 mA, 1A, 1.6A, 2A, 4A, 6.3A & 10A). (Inspection by RDSO)	Numbers	400.00	43.14	17256.00
28	28	Shorting link insulated Grey in colour. (Inspection by Consignee).	Numbers	100.00	14.75	1475.00
29	29	Operating tool (operating tool, screw driver & tripper as per Annexure -VII.(Inspection by Consignee)	Numbers	1.00	8660.20	8660.20
30	30	Supply of Paints as per relevant IS specification preferably Asian/ Apcolite/Dulux make in different colours in one kg pack. (Inspection by Consignee)	Kg	50.00	353.07	17653.50
31	31	Supply of Plug In type Relay Metal to Metal type neutral relay mini groups (Non AC Immunized) Siemens make (No. RSSK 30/0011) (Ref.IRS:S46/74 with Amd.1 & firms specification). or functional equivalent without base plates. Contact configuration 5F/3B or 6F/2B or 4F/4B to be specified by Engineer incharge.(Inspection by RDSO).	Numbers	152.00	8159.70	1240274.40
					Total	2310844.42
Schedule	Schedule 02-SOR EXECUTION					
Item- 01	EXECUTION OF SOR ITEMS					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount

**SOLAPUR DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-N-T-2026-27-13

Closing Date/Time: 19/06/2026 15:30

1	01	Fabrication and fixing of phenolic laminated/Fibre glass sheet in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated/with PVC pipe covered string rods at the back side for cable support with contractor's own materials. The work shall be done as per drg and arrangement similar to SK 783-1&2. with latest alterations & as per instructions of Rly engineer at site. Single Case.	Numbers	2.00	2251.73	4503.46
2	02	Fabrication and fixing of phenolic laminated/Fibre glass sheet in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated/with PVC pipe covered string rods at the back side for cable support with contractor's own materials. The work shall be done as per drg and arrangement similar to SK 783-1&2. with latest alterations & as per instructions of Rly engineer at site. Half Case	Numbers	2.00	1984.78	3969.56
3	03	Fixing of cutting in relay bases & wiring of relays with Contractors own material obtained from approved sources in location box as per the instuctions of Engineer in charge.	Numbers	4.00	566.24	2264.96
4	04	Fixing of ARA Terminals and fuse blocks on phenolic laminated sheets and fixing by stainless steel/brass nuts & bolts.This includes provision of two additional holes on the board on either side for cable conductor entry.	Numbers	2030.00	14.05	28521.50
5	05	Termination of cable cores on ARA terminal/fuse blocks in the apparatus Cases/ cable termination rack.This includes all associated works of pulling out the cable from underground. The work shall be done as per location plans and instructions of Rly engineer at site.	Per Conductor	4060.00	10.58	42954.80
6	06	Excavation and Casting of Apparatus Case foundation with contractors Anchor bolts, cement, ballast and other materials. The required scaffolding Ferma etc for Casting of foundation will have to be brought by the contractor at his own cost. Single Case as per Drg No . SK-803	Numbers	2.00	9887.02	19774.04
7	07	Excavation and Casting of Apparatus Case foundation with contractors Anchor bolts, cement, ballast and other materials. The required scaffolding Ferma etc for Casting of foundation will have to be brought by the contractor at his own cost. Half Case as per Drg No . SK-804	Numbers	2.00	9693.93	19387.86
8	08	Erection of Apparatus Cases. This includes filling of location foundations with river bed sand and plastering on top of the sand. Single Case.	Numbers	2.00	1098.04	2196.08
9	09	Erection of Apparatus Cases. This includes filling of location foundations with river bed sand and plastering on top of the sand.Half Case.	Numbers	2.00	842.40	1684.80
10	10	Installation of Eqpt. (Relays, resistance, chargers batteries etc.as applicable) & wiring of the same in apparatus Cases as per location diagrams & circuit diagrams, as per Instruction of site incharge and practice.Single Case.	Numbers	2.00	1497.72	2995.44
11	11	Installation of Eqpt. (Relays, resistance, chargers batteries etc.as applicable) & wiring of the same in apparatus Cases as per location diagrams & circuit diagrams, as per Instruction of site incharge and practice.Half Case.	Numbers	2.00	1017.78	2035.56

**SOLAPUR DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-N-T-2026-27-13

Closing Date/Time: 19/06/2026 15:30

12	12	Installation of earth electrode assembly as per Drg.No.RE/S&T/SIG/Tender/SK726/85 including earth wire connected through GI wire 8 SWG supported on M.S. flat of size 6mm x 40 mm to earth electrode as per drg. No. CR/S&T/SK-815 for sigg. Equipment such as lever frames, apparatus case, signals, relay racks,block instruments, and etc. as per RE manual. The earth value should be less than 10 Ohms including the lead wire. The value should be measured in presence of Rly. supervisor. It should be documented and painted on earth enclosure made of concrete.(only earth electrode will be supplied by Railway). All other material required for provision of earthing will be brought by the contractor.	Numbers	10.00	2528.14	25281.40
13	13	Erection, Fitting and Rail connection of Track Lead Juntion Box on two supports(M.S.angle) with contractor's fixing material and PVC jacketed wire for track lead connection including angles of size 40 x 40 x 5 mm 1200 mm length. This will include drilling of holes for track lead/side connections on rail. The work shall be carried out as per Drg. No. SK-845 or/& instructions of Rly engineer at site.	Numbers	20.00	1305.34	26106.80
14	14	Provision of bonding with contractor's PVC jacketed wire rope for Track Lead connection. PVC jacketed wire rope should be of Galvanised steel wire rope 6mm dia (6 x 19 stranded wire with steel core of 6 mm dia) sheathed with PVC 2mm wall thickness, overall thickness being 10mm PVC sheath should be made of type 6 compound as per IS 5831 of 1984 Reaffirmed 2001 and steel wire rope as per IS:2266:2019. Reclaimed or recycled material should not be used. This will include drilling of 7.1mm dia holes in rails (4 Nos) and provision of two jumpers for each bond, clipping of bonds etc. with contractors own materials and tools as per instruction of Rly engineer at site.	Numbers	20.00	169.65	3393.00
15	15	Provision of bonding with GI wire 4mm dia (8 SWG) for track jumper & fish plate joints bonds. This will include drilling of 7.1mm dia holes in rails (4 Nos) and provision of two jumpers for each bond, clipping of bonds etc. with contractors own tools as per instruction of Rly engineer at site.	Numbers	20.00	160.48	3209.60
16	16	Refixing of electrical point machine, ground connection during phase working (Non interlocked working) after removing the existing fitting if any, adjustment if necessary, cable termination, wiring , testing and commissioning of electrically operated point, fixing and connecting point indicator on derail switch if necessary. The work shall be done as per extant practice on C. Rly & the instruction of Rly engineer at site.(UNIT=Turn-out= PER T/O)	Turn-out	2.00	4550.77	9101.54

**SOLAPUR DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-N-T-2026-27-13

Closing Date/Time: 19/06/2026 15:30

17	17	Fixing of point machine on newly laid turnout on Wooden/MBC sleepers , fixing of ground connections, adjustment and testing with crank handle operations,Removal of ground connection & point machines duly numbered. This will include fixing of bend pipes with welded frame for cable entry to machine. This will also includes necessary adjustment and smithy work, drilling of holes to tounge rails, fitting of insulation for tounge attachment, gauge plate & stretcher bars, cable termination & wiring if required. The work shall be done as per extant practice on C. Rly & the instruction of Rly engineer at site.(UNIT=Turn-out= PER T/O)	Turn-out	2.00	3526.79	7053.58
18	18	Excavation of cable trench as per cable route plan,1.0 mt. deep and 300mm wide along side the track in normal soil/strata, conforming to distances as per cable route plan and refilling after cable laying. This work includes covering of cable laid in trench by loose soil for a layer of 50mm thickness after clearing of route,bushes etc. It shall be ensured that top of the cables laid is at a depth of 0.8m or more. If it is less, then the width and depth shall be suitably increased and accordingly proportionate payment shall be made. In case depth of trench is not achievable due to site conditions proportionate payment will be made as per procedure. The work shall be done as per the extant practice on Central Railway and instructions of Railway Engineer at site. Drg. No. SK 805	cum	400.00	350.00	140000.00
19	19	Excavation of cable trench as per cable route plan,1.0 mt. deep and 300mm wide along side the track in hard soil, conforming to distances as per cable route plan and refilling after cable laying. This work includes covering of cable laid in trench by loose soil for a layer of 50mm thickness after clearing of route,bushes etc. It shall be ensured that top of the cables laid is at a depth of 0.8m or more. If it is less, then the width and depth shall be suitably increased and accordingly proportionate payment shall be made. In case depth of trench is not achievable due to site conditions proportionate payment will be maden as per procedure. The work shall be done as per the extant practice on Central Railway and instructions of Railway Engineer at site. Drg. No. SK 805	cum	100.00	583.33	58333.00
20	20	Cutting of all types of Roads/ platforms (ecxcept concrete type) for trenching and excavation to depth of 300mmx300mm wide approx. and refilling after laying of RCC/GI /DWC pipe & to restore them to original condition. The work shall be done as per extant practice on C.Rly & instructions of Rly engineer at site. Drg. No. SK 807	cum	5.00	2916.67	14583.35
21	21	Fixing of GI pipes for crossing the culverts, bridges etc. and concreting of ends with brick masonry at both ends as per the instruction of Rly engineer at site.	Metre	60.00	69.97	4198.20
22	22	Digging of trench 1.0 M deep from rail flange/road level (for LC) and 0.3Mtrs. to 0.6 Mtrs wide and back filling after placing of DWC/RCC/GI pipe.(Placing of DWC/RCC/GI pipe coverd separately. The ballast disturbed be screened and dressed as required by Engineer-in-charge or his representatives and road tarred immediately. Drg. No. SK 806	cum	50.00	583.33	29166.50

**SOLAPUR DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-N-T-2026-27-13

Closing Date/Time: 19/06/2026 15:30

23	23	Laying of DWC/RCC pipes alongwith collars/RCC Half round pipes in trenches at places of track and road crossings, platform cuttings etc.	Numbers	1560.00	56.85	88686.00
24	24	Laying of signalling/Power/Telecom cable of various cores/sizes in trenches.	Kilometre	5.00	5197.42	25987.10
25	25	Horizontal boring of cable duct of minimum 2.0 Mtr. depth alongwith laying of 120mm HDPE pipe for track crossing with minimum depth reckoned from the bottom of the rail/road crossing with minimum depth reckoned from ground level. The work shall be done as per extant practice & instructions of site Engineer. Preperation of site for Horizondal boring shall be carried out in presence of Railway Representative. HDPE will be supplied by Railways. Note:- Contractor shall provide all material required for boring and adequate nos. of labours for proper laying of cables into the bore. Cable shall be laid cautiously so that it should not get damage due to rough handling & pressure on cable.	Metre	180.00	2610.46	469882.80
26	26	Horizontal boring of cable duct of minimum 2.0 Mtr. depth alongwith laying of 120mm HDPE pipe for other locations with minimum depth reckoned from the ground level. The work shall be done as per extant practice & instructions of site Engineer. Preparation of site for Horizondal boring shall be carried out in presence of Railway Representative.HDPE will be supplied by Railway. Note:- Contractor shall provide all material required for boring and adequate nos. of labours for proper laying of cables into the bore. Cable shall be laid cautiously so that it should not get damage due to rough handling & pressure on cable. BORING upto the length of 150 mtrs. Preparation of site for Horizontal boring shall be carried out in presence of Railway Representative.	Metre	180.00	1828.99	329218.20
27	27	Wherever depth of 0.5M cable trench is not feasible, cable shall be protected as under:- Preparation of cement mixture 1:3:6 with contractor's own materials and spreading cement concrete mixture layer of 100 mm thick over the already laid cables in the excavated trench.	cum	2.00	5329.55	10659.10
28	28	Fixing of modular terminal/fuse blocks along with all accessories with provision of holes on hylum sheets/side angles of location box and fixing by galvanised nuts & bolts. This includes fixing of DIN channel along with PVC comb type "C" channel (size 2 inch x 2 inch) for cable termination on modular terminal. The PVC channel with cover to be supplied by firm as required. The work shall be done as per the instructions of Rly. engineer at site.	Numbers	1500.00	19.05	28575.00
29	29	Patching work in old location box consisting 1) Digging of pit, cleaning of earth from all sides, breaking of seal of location boxes removal sand from location, marking of new cable holes 2) insertion of cable from ground 3) making place for cable termination in old location, shifting ARA, fuse etc after removal and termination including fixing of ARA. 4) Termination of cable in old location 5) Filling of sand and plastering to all sides upto 50mm below ground level.	Numbers	10.00	6279.91	62799.10

**SOLAPUR DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-N-T-2026-27-13

Closing Date/Time: 19/06/2026 15:30

30	30	Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor' own supply of paints.Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge.Epoxy paint will be supplied by Railways. NOTE:- The paint and primer should be from M/s Asian paints Co. Ltd.,. The paints will be primer (IS 5660 of 1970) the Aluminium synthetic black enamel (IS 2932 of 1974) brilliant white and yellow Painting two coats of enamel paint over one coat of primer. Apparatus Case Full Size.	Numbers	2.00	435.44	870.88
31	31	Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor' own supply of paints.Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge.Epoxy paint will be supplied by Railways. NOTE:- The paint and primer should be from M/s Asian paints Co. Ltd.,. The paints will be primer (IS 5660 of 1970) the Aluminium synthetic black enamel (IS 2932 of 1974) brilliant white and yellow Painting two coats of enamel paint over one coat of primer. Apparatus case Half Size.	Numbers	2.00	326.99	653.98
32	32	Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor' own supply of paints.Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge.Epoxy paint will be supplied by Railways. NOTE:- The paint and primer should be from M/s Asian paints Co. Ltd.,. The paints will be primer (IS 5660 of 1970) the Aluminium synthetic black enamel (IS 2932 of 1974) brilliant white and yellow Painting two coats of enamel paint over one coat of primer. Main Signal Post with Signal Units, Surface base and complete fittings as per Central Railways standard practice.	Numbers	4.00	756.95	3027.80
33	33	Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor' own supply of paints.Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge.Epoxy paint will be supplied by Railways. NOTE:- The paint and primer should be from M/s Asian paints Co. Ltd.,. The paints will be primer (IS 5660 of 1970) the Aluminium synthetic black enamel (IS 2932 of 1974) brilliant white and yellow Painting two coats of enamel paint over one coat of primer. Shunt signal post with signal unit, surface base as per Central Railway's Standard Practice.	Numbers	4.00	180.66	722.64

**SOLAPUR DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-N-T-2026-27-13

Closing Date/Time: 19/06/2026 15:30

34	34	Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor' own supply of paints.Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge.Epoxy paint will be supplied by Railways. NOTE:- The paint and primer should be from M/s Asian paints Co. Ltd.,. The paints will be primer (IS 5660 of 1970) the Aluminium synthetic black enamel (IS 2932 of 1974) brilliant white and yellow Painting two coats of enamel paint over one coat of primer. Track lead Junction Box. (Black enamel outside only)	Numbers	20.00	89.24	1784.80
35	35	Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor' own supply of paints.Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge.Epoxy paint will be supplied by Railways. NOTE:- The paint and primer should be from M/s Asian paints Co. Ltd.,. The paints will be primer (IS 5660 of 1970) the Aluminium synthetic black enamel (IS 2932 of 1974) brilliant white and yellow Painting two coats of enamel paint over one coat of primer. Point Machine with ground connections complete (Point Machine with Black enamel only outside and ground connections with Red Oxide)	Numbers	4.00	156.27	625.08
36	36	Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor' own supply of paints.Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge.Epoxy paint will be supplied by Railways. NOTE:- The paint and primer should be from M/s Asian paints Co. Ltd.,. The paints will be primer (IS 5660 of 1970) the Aluminium synthetic black enamel (IS 2932 of 1974) brilliant white and yellow Painting two coats of enamel paint over one coat of primer. Axle Counter devices.	Numbers	10.00	107.55	1075.50
37	37	Lettering / Numbering of Signals, Point Machine, Track Lead Junction Boxes, Block Joints, Apparatus Cases etc. (each item to be taken as One Unit) This work will be carried out as per the standard practice being followed in Central Railway.	Numbers	122.00	56.64	6910.08
38	38	Lettering / Numbering Termination particulars, equipments names etc., legibly and neatly inside location boxes. Full Case.	Numbers	2.00	263.53	527.06
39	39	Lettering / Numbering Termination particulars, equipments names etc., legibly and neatly inside location boxes. Half Case.	Numbers	2.00	150.03	300.06
					Total	1483020.21
Schedule	Schedule 03-NS SUPPLY AND EXECUTION					
Item- 01	SUPPLY AND EXECUTION OF NON SOR ITEMS					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	01	HDPE Pipe 110 mm Diameter,PE63, Class PN6, with confirming to IS4984 with ISI marked (or) Latest. Type test report from Central Govt./state Govt/ NABL / ILAC to be submitted at the time of supply. (Inspection by Consignee)	Metre	400.00	475.28	190112.00

**SOLAPUR DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-N-T-2026-27-13

Closing Date/Time: 19/06/2026 15:30

2	02	Supply & installation of Concrete Earth enclosure as per drg.(Inspection by Consignee)	Numbers	10.00	1036.50	10365.00
3	03	Execution of S & T work related to engineering /Signalling block of CTR/TTR/TSR or others, in one block, five unskilled manpower have to be provided during block for S&T connection removing & refixing as per Railway site engineer instruction.	Job	50.00	3392.24	169612.00
4	04	Arrangement of battery operated rail core drill along with additional 18 mm TCT rail core drill. Maximum core cutting capacity 36mm, rated speed 250/450ZRPm, Battery type Lion, Battery voltage 50V, Battery pack capacity 4AH, Number of battery supplied-2No. Charger-1No. Special design pressurised internal spindle cooling to give maximum life of core cutter by avoiding heating. 3sets of 22,13,16,7.1 gauge drills adapters to be provided along with the machine. weight of machine with battery-18.5 Kg Make Eibenstok, Bosch, KPTL. (Inspection by consignee).	Numbers	5.00	160226.47	801132.35
5	05	Retro reflective sheet BLACK Colour ultra light high intensity along with supply make-Royal, Nikkilite, scotchlite (Inspection by Consignee).	Square Foot	500.00	100.00	50000.00
6	06	High-intensity grade retro reflective luminous sheet - Yellow colour, size 305 mm wide, IS: 14221, 1995, Grade I, FIRMS OFFER OFFERGRADE 1 EQUALS ASTM D 4956TYPE 1, ONE SAMPLE TO BE APPROVED BEFORE BULK SUPPLY.WE QUOTED FOR SIZE 305 MM X ONE METER.(Inspection by Consignee).	Metre	500.00	86.60	43300.00
7	07	RETROREFLECTIVE RADIUM STICKER HORIZONTAL BAND, COLOUR: RED T-6000 SERIES WITH HIGH INTENSITY MICRO PRISMATIC (HIP) OF WIDTH: 01 FEET, THICKNESS 0.24Mmm T 6508 RED .MAKE: KIWALITE / 3M / AVERY DENNISON / DM REFLECTIVE OR ITS EQUIVALENT (Inspection by Consignee).	Square Foot	1000.00	26.00	26000.00
8	08	Supply of Extended IPS unit for housing DC-DC converters for Dual Detection of SSDAC for BPAC.(Inspection by Consignee)	Numbers	1.00	115640.00	115640.00
9	09	Supply of 24-40V/5A DC-DC converters for IPS as per RDSO spec.No.RDSO/SPN/ 165/ 2012 (Ver.3.0) or Latest. (Inspection by RDSO)	Numbers	20.00	17540.70	350814.00
10	10	"Supply of Analog Mother Board (EFF827) for 99/06.(Inspection by Consignee)	Numbers	1.00	36000.00	36000.00
11	11	Supply of Analog with Controller Card (EFF-828) for 99/06(Inspection by Consignee).	Numbers	1.00	23625.00	23625.00
12	12	Supply of Protection strip for 99/06 DL with ribbons and other accessories.(Inspection by Consignee).	Numbers	1.00	1420.00	1420.00
13	13	Supply and Installation of 230V AC to DC Converter with 3 Input/Output as per specification RDSO Spec No. IRS S.99/2006 (AMDT -3 OR Latest version. 'Make compatible with efftronics.(Inspection by Consignee)	Numbers	1.00	1770.00	1770.00
14	14	Supply of EURO Rack.(Inspection by Consignee)	Numbers	1.00	15866.94	15866.94
15	15	Testing and commissioning-32 Analog Inputs.	Numbers	1.00	18345.40	18345.40
16	16	Supply and installation of concrete (RCC) route indicators at intervals of 50 meters as per technical specification. They should be standard RCC with letters on one side "CR" and the other side "S&T Cables" as per drawing SK12/10 of RVNL SC. In case of Telecom quad cable joint locations it shall be painted with RED colour.(Inspection by Consignee)	Numbers	200.00	1220.23	244046.00

**SOLAPUR DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-N-T-2026-27-13

Closing Date/Time: 19/06/2026 15:30

					Total	2098048.69
Schedule	Schedule 04-TELECOM SUPPLY AND EXECUTION					
Item- 01	SUPPLY AND EXECUTION OF TELECOM ITEMS					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	01	Supply of 6 Core Single mode armoured Optical Fibre Cable Make: Polywire or Finolex or Network Cable or Vidhya Telelinks or Sterlite Technologies.(Inspection by Consignee)	Metre	2000.00	25.80	51600.00
2	02	Supply of 12 port LIU, 19 inch rack mountable as per following specification: a) It should have 12 SP type ports for termination of SM optical fibres. b) It should be rack mountable with 1U height. c) It should be equipped with front managed saddle for jumper/patch cord management. d) It should have 12 SC termination. e) It should be equipped with adequate nos. of splicing trays to splice 12 fibres. f) It should have proper rubber grommet for cable protection and to minimize dust build up. g) It should be fully loaded with all the accessories for splicing and termination of fibres. h) It shall be of reputed make like D-Link or 3M or Digilink or Molex make. (Inspection by Consignee)	Numbers	4.00	7917.65	31670.60
3	03	Installation & commissioning of 12 port LIU with all accessories and shall be used for terminations of optical fibers into the splice trays supplied with it, it shall be installed inside the 19 inch rack using all required fixing/ installation material like nuts, bolts, screws and cable ties etc. as per requirement. The splice trays shall be placed and secured into the LIU after splicing. The SC terminations shall be fixed and secured after splicing of the pigtails into the LIU. It shall be ensured that the movement of the trays is easy and free of any obstructions.	Numbers	4.00	1167.39	4669.56
4	04	Supply of optic fiber pigtails for termination of OFC cables with following specification: a) It shall be single mode SC/SC type with push pull mechanism or as per site requirement and fully compliance with latest industry standard. b) It shall have length of 2 Meters at least. c) It shall have SC connector at one end and other shall be loose for splicing. d) It should be of reputed make D-Link or 3M or Digilink or Molex. (Inspection by Consignee)	Numbers	20.00	500.15	10003.00
5	05	Blowing/drawing of OFC cable in HDPE/DWC duct and protective work, as per direction of site engineer.	Kilometre	2.00	13696.26	27392.52
6	06	Splicing/ dropping/termination of each fiber/pigtail in LIU/IO box/terminal joint through fusion splicing for termination of OFC cables. The fibers terminated shall be tested and test report (hard copy and soft copy) shall be submitted to the Railways site in-charge for records. each fiber shall be properly marked with necessary ferrules/tags, as per specification.	Numbers	20.00	167.10	3342.00
7	07	Supply of 24 port (manageable) with 4 nos. 1000 baseX SM SFP port with optical module and Minimum 20 nos. ethernet (SFP based) port Layer 2, POE switch loaded with SFP module, as per clause no. 13.0 of RDSO Spec No.RDSO/SPN/TC/83/2014 Rev.1 (Clause no.3.3) or latest. (Inspection by Consignee).	Numbers	4.00	30290.94	121163.76

**SOLAPUR DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-N-T-2026-27-13

Closing Date/Time: 19/06/2026 15:30

8	08	Supply of 1G BiDi SFP modules compatible to switches of any make and model from Cisco or Watchdog or Dlink or similar reputed make. (OEMGC & TC required during delivery of the equipment) (Inspection by Consignee)	Numbers	20.00	3699.85	73997.00
9	09	Excavation of cable trench as per cable route plan, 1.0 mt. deep and 300mm wide along side the track in normal soil/strata, conforming to distances as per cable route plan and refilling after cable laying. This work includes covering of cable laid in trench by loose soil for a layer of 50mm thickness after clearing of route, bushes etc. It shall be ensured that top of the cable laid is at a depth of 0.8m or more. If it is less, then the width and depth shall be suitably increased and accordingly proportionate payment will be made. In case depth of trench is not achievable due to site condition, proportionate payment will be made as per procedure. as per procedure. The work shall be done as per the extant practice on Central Railway and instructions of Railway Engineer at site. Drawing No.SK 805	cum	600.00	343.38	206028.00
10	10	Excavation of cable trench as per cable route plan, 1 mt. deep and 300mm wide along side the track in hard soil, conforming to distances as per cable route plan and refilling. This work includes covering of cable laid in trench by loose soil for a layer of 50mm thickness after clearing of route, bushes etc. It shall be ensured that top of the cable laid is at a depth of 0.8m or more. If it is less, then the width and depth shall be suitably increased and accordingly proportionate payment will be made. In case depth of trench is not achievable due to site condition, proportionate payment will be made as per procedure. as per procedure. The work shall be done as per the extant practice on Central Railway and instructions of Railway Engineer at site. Drawing No.SK 805	cum	150.00	579.38	86907.00
11	11	Wherever depth of 0.5 m cable trench is not feasible cable shall be protected as under:- Preparation of cement mixture 1:3:6 with contractor's own materials and spreading cement concrete mixture layer of 100 mm thick over the already laid cables in the excavated trench.	cum	9.00	5214.42	46929.78
12	12	Cutting of all types of Roads/ platforms preparatory to trenching and excavation to depth of 300mmx300mm wide approx. and refilling after laying of RCC/GI /DWC pipe & to restore them to original condition. The work shall be done as per extant practice on C.Rly & instructions of Rly engineer at site.	cum	4.00	2876.84	11507.36
13	13	Laying of signalling/Power/Telecom cable of various cores/sizes in trenches.	Kilometre	1.00	5359.56	5359.56
14	14	Supply of Media converters with one Fiber port (SC connector) and four Ethernet ports, supporting port isolation and with built in AC Power supply. Model: FABIO 104L of make MRO-TEK or similar model of RAD, ANDA Telecom, ZYXEL or CTC only. (Inspection by Consignee)	Pair	4.00	6305.53	25222.12
15	15	Supply of High throughput LAN extenders as per CR's specification no. CR/SPN/TC/80/2016 Rev 1.0 effective from 17.10.2016. (Inspection by Consignee)	Pair	3.00	27018.99	81056.97

**SOLAPUR DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-N-T-2026-27-13

Closing Date/Time: 19/06/2026 15:30

16	16	Supply of STP (shielded Twisted Pair) CAT-6 cable from D-Link,Finolex., Lucent or DAX Make(1Box-305 mtrs) (Inspection by Consignee)	Boxes	4.00	8344.77	33379.08
17	17	Laying & drawing of communication/ power/ data cable through 1" PVC conduit pipe. This includes fixing of pipe with all accessories as required as per site condition.	Metre	915.00	38.36	35099.40
18	18	Supply of OFC patch cord with required connectors at both ends single mode Simplex 5 Mtr. Make of 3M or Sterlite or Finolex or Raychem only.(Inspection by Consignee)	Numbers	20.00	145.59	2911.80
19	19	Supply of HDPE duct 50mm dia, inner dia 42mm and wall thickness 4mm, permanently luricated etc supplied from TEC approved sources (Specification TEC GR No. GR/TX/ CDS-008/03/ March 11 with latest amendment). (Inspection by Consignee)	Metre	2000.00	71.11	142220.00
20	20	Laying & fixing of HDPE duct for protection of cable in trenches or roof wall etc as per route given by site Engineer of Railways.	Metre	2000.00	10.29	20580.00
21	21	Supply of fiber distribution management system (24 fiber) as per RDSO spec No.RDSO-SPN-TC-37-2000 (ver 3.0) with 24 No., FC/PC connector, 24 No. pigtaills and 24 No. patch cords of 3 mtr suitable for above FDMS.	Numbers	1.00	17249.93	17249.93
22	22	Supply and installation of concrete (RCC) route indicators at intervals of 50 meters as per technical specification. They should be standard RCC with letters on one side "CR" and the other side "S&T Cables" as per drawing SK 12/10 of RVNL SC. In case of Telecom quad cable joint locations it shall be painted with RED colour.(Inspection by Consignee)	Numbers	38.00	1414.48	53750.24
23	23	Supply of Lighting surge arrestors for LAN network class C type as per VDE classification housed in a suitable impact resistance box. The equipment shall support one input and one output port with provision for ground connection for surge suppression. the equipment shall be from Ubiquiti or Tuvpavco or DiTek or Tripp-Lite.(Inspection by Consignee)	Numbers	2.00	6955.88	13911.76
24	24	Supply of factory moulded Cat-6 patch cord 1 Mtr from DAX or D-Link or Finolex or Krone make only.(Inspection by Consignee)	Numbers	24.00	91.92	2206.08
25	25	Supply of Analog Display, metal body hand driven Insulation Tester 100V 100 MOHMS with lead cables; make Waco-WI 104, Nippen, Fluke, Motwani.(Inspection by Consignee)	Numbers	1.00	4704.50	4704.50
26	26	Supply of PVC casing & capping of size 25mm x 25/36mm heavy duty with all accessories like joint, bends etc of Precision, Garware make or similar standard make.(Inspection by Consignee)	Metre	120.00	73.82	8858.40
27	27	Supply of PVC channel of size 50x50 mm with all accessories like joint, bends etc of precision, Garvare make or similar standard make. (Inspection by Consignee)	Metre	100.00	143.34	14334.00
28	28	Fixing of PVC casing & caping or PVC Channels or conduit pipe on wall etc. with suitable fasteners as per route given by and as per instruction of site engineer of Rly. This includes breaking up of wall for cabling & painting it to original level & laying of cables.(Inspection by Consignee)	Metre	220.00	5.23	1150.60

**SOLAPUR DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-N-T-2026-27-13

Closing Date/Time: 19/06/2026 15:30

29	29	Supply of multiport I/O box surface mounting having two RJ-45 port and three RJ-11 port from D-Link or Legrand or Anchor or similar reputed make.(Inspection by Consignee)	Numbers	12.00	435.55	5226.60
30	30	Fixing of UTP I/O box as per the instruction of site Engineers of the Railways.	Numbers	12.00	34.45	413.40
31	31	Supply of RCC pipes half round of size 150mm dia outer and 100 mm dia internal 1 mtr long matching to IS No. 458/2003 amendment-1 with Rev.4.As per Drg No. DRM(S&T) SUR/06/2023/A (Inspection by RITES).	Numbers	2400.00	223.02	535248.00
32	32	Laying of RCC half round cement pipe of approximate size (150/300 mm dia X 2 Meter length) inside the trench after laying of cable. Pipes shall be placed as per directives of engineer.	Numbers	1200.00	34.22	41064.00
33	33	Supply of PVC switch board 10 Pair, 0.5mm dia twisted pair PVC insulated, PVC sheathed, ATC copper conductor as per TEC specification no. TEC/GR/WIR009/05 March 2011 or latest from Network or Finolex or Synergy or Delton make. (Inspection by Consignee).	Metre	500.00	39.98	19990.00
34	34	Supply of PVC Switch Board Cables 05 pair / 0.5 mm conductor dia. as per TEC specification GR/WIR-06/03 of march 02 or latest from Network or Finolex or Polycab or Delton make. (Inspection by Consignee)	Metre	800.00	26.55	21240.00
35	35	Supply of GI pipe, inner dia. 100mm dia. B-class as per spec. No.IS 1239 PT. 1/2004 or latest with sockets and fittings. TATA,JINDAL/ZENITH BIRLA make.(Inspection by Consignee)	Metre	24.00	1071.44	25714.56
36	36	Fixing of GI pipes for crossing the culverts, bridges etc. and concreting of ends with brick masonry at both ends as per the instruction of Rly engineer at site.	Metre	24.00	70.80	1699.20
37	37	Laying of DWC/RCC pipes alongwith collars/RCC Half round pipes/poleolefin channel in trenches at places of track and road crossings, platform cuttings etc.	Metre	2400.00	57.82	138768.00
38	38	Maintenance free earth as per RDSO/SPN/197/2008 or latest consisting of: (1) Copper bond steel electrode 3 Mtr long 17 mm dia with copper bonding thickness of min 250 micron & UL listed & marked-01 No. (2) Earth Enhance compound RDSO approved in sealed bag of 10 Kg-03 Nos. (3) Copper strip 150 x 25 x 6 mm-02 Nos. (4) Copper strip 300 x 25 x 6 mm-01 No. (5) 35 Sqmm copper cable to connect earth electrode to MEEB-15 Mtr. approximately.(Inspection by RDSO)	Set	2.00	18491.78	36983.56
39	39	Installation of unit earth as per RDSO/SPN/197/Ver 1 or latest, to construct earthing of <= 1 Ohm consisting of: a) Digging the earth to required depth, insertion of electrode, filling of earth enhancing compound & construction of chamber, measurement of earth value and other work of earthing as per code of practice. All the consumables for mounting the copper tape inside the equipment room, exothermic weld material and tools & fixtures for the welding copper tapes and electrodes etc. shall be arranged by the contractor.	Set	2.00	5170.76	10341.52

**SOLAPUR DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-N-T-2026-27-13

Closing Date/Time: 19/06/2026 15:30

40	40	Supply of Class B&C surge protection Device (SPD) type I & II with visual indication and potential free contact to remote monitoring as per RDSO spec No. RDSO/SPN/165/2012 version 3.0 or latest and IEC standard 61643 for signals line 230 V AC application with handling lightning surges of 10/350 microseconds and switching surges of 8/20 microseconds. One set consists of 3 Nos of SPD (Two Nos of B Class (L N, N-E) and one no of C class (L-N) all enclosed in a box with KEMA or VDE certified as per latest IEC 61643-11-2011 standard class B&C surge protection device required with Three modules only. (Inspection by RITES).	Numbers	20.00	4956.00	99120.00
Total					2073013.86	

4. ELIGIBILITY CONDITIONS

Standard Financial Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer must have minimum average annual contractual turnover of V/N or V whichever is less, where V= Advertised value of the tender in crores of Rupees & N= Number of years prescribed for completion of work for which bids have been invited. The average annual contractual turnover shall be calculated as an average of "total contractual payments" in the previous three financial years, as per the audited balance sheet. However, in case balance sheet of the previous year is yet to be prepared/ audited, the audited balance sheet of the fourth previous year shall be considered for calculating average annual contractual turnover. The tenderers shall submit requisite information as per Annexure-VIB, along with copies of Audited Balance Sheets duly certified by the Chartered Accountant/ Certificate from Chartered Accountant duly supported by Audited Balance Sheet.	No	No	Allowed (Mandatory)

Standard Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer must have successfully completed any of the following during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: Three similar works each costing not less than the amount equal to 30% of advertised value of the tender, or Two similar works each costing not less than the amount equal to 40% of advertised value of the tender, or One similar work each costing not less than the amount equal to 60% of advertised value of the tender.	No	No	Allowed (Mandatory)
1.1	Defination of Similar Work :- Trenching cable laying location and signal foundation /erection/ termination wiring in connection with any Signaling work. OR Any Indoor or combined Indoor & Outdoor Signaling work including Supply, Installation testing and commissioning of relay interlocking (RRI/PI) system for passenger carrying lines.	No	No	Not Allowed

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.
3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.
5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.

**SOLAPUR DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-N-T-2026-27-13

Closing Date/Time: 19/06/2026 15:30

6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.
7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.
8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.
9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.
10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description
1	Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. (Click here to download the Format of Self Certification)

5. COMPLIANCE

Commercial-Compliance

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)

General Instructions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Please refer to GCC with ACS and Instructions to Tenderer attached in documents.	No	No	Not Allowed

Special Conditions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Please refer to Special conditions attached in documents	No	No	Not Allowed

Undertakings

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Undertakings :- I have read all the tender document enclosed in the Documents tab and hereby agree to abide all terms and conditions mention in them.	No	No	Not Allowed

6. Documents attached with tender

S.No.	Document Name	Document Description
1	Instructions_To_Tenderer_TJSP_and_DRSV.pdf	Instructions to Tenderer
2	Special_Conditions_TJSP_and_DRSV.pdf	Special conditions
3	GCC_April-2022_with_ACS_11_13032026.pdf	GCC with ACS
4	Tender_form_Annexure-I.pdf	Annexure I

**SOLAPUR DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-N-T-2026-27-13

Closing Date/Time: 19/06/2026 15:30

5	Cable_cut_policy_CR_1st_Sept_23.pdf	Cable cut policy
6	annexures_and_Drawings_TJSP_and_DRSV.pdf	Annexures and Drawings

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

Signed By: AYUSH MEHTO

Designation : DSTEWks