

**DYCSTE-C-RTM-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-RTM-122-2026-27

Closing Date/Time: 29/06/2026 15:00

Dy.CSTE/C/RTM acting for and on behalf of The President of India invites E-Tenders against Tender No **SnT-C-RTM-122-2026-27** Closing Date/Time 29/06/2026 15:00 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

1. NIT HEADER

Name of Work	Supply, Installation, Testing, Commissioning, and Utility Shifting of S&T Gears at UJN Yard for Provision of Stabling Lines and Relocation of PQRS Siding in Loco Yard, as well as Provision of Stabling Lines in NC Yard, in Connection with Simhastha-2028, Ratlam Division, Western Railway (MP).		
Bidding type	Normal Tender		
Tender Type	Open	Bidding System	Single Packet System
Tender Closing Date Time	29/06/2026 15:00	Date Time Of Uploading Tender	28/05/2026 10:14
Pre-Bid Conference Required	No	Pre-Bid Conference Date Time	Not Applicable
Advertised Value	5735096.00	Tendering Section	TENDERING
Bidding Style	Single Rate for Tender	Bidding Unit	Above/Below/Par
Earnest Money (Rs.)	114700.00	Validity of Offer (Days)	60
Tender Doc. Cost (Rs.)	0.00	Period of Completion	12 Months
Contract Type	Works - General	Contract Category	Expenditure
Bidding Start Date	15/06/2026		
Are JV allowed to bid	No	Number of JV Member Allowed	0
Are Consortium allowed to bid	No	Number of Consortium Member Allowed	0
Ranking Order For Bids	Lowest to Highest	Expenditure Type	Capital (Works)

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A-Suply & Execution of S& T Items for Provision of Stabling Line and Relocation of PQRS Siding in Loco Yard							2703625.00	
1	1	10.00	Numbers	3571.00	35710.00	AT Par	35710.00	
	Description:- Earth Electrode as per Drg. No. CSTE / 6091.							
2	2	10.00	Numbers	4961.00	49610.00	AT Par	49610.00	
	Description:- Installation of Earth Electrode including MS flat for clamp etc. and connection to signalling equipments, lever frames, apparatus cases, signal, relay rack, block instrument, etc. as per technical specification given. This item includes digging of pit in earth 3 M deep & fixing earth electrode pipe, casting of cement concrete enclosure & covers per RDSO/SPN/197/2016. Soil treatment to be done as per std. practice. This item includes provision of MS Flat, Earth lead wires and Soldering of lead wires. The other end of the wire is to be connected to block equipment, power equipment, cable sheath, and signals etc. as per site requirements. 7strand GI wire shall be used as earth lead wire. Supply of earth electrode is covered in other Item').							
3	3	4.00	Numbers	10583.00	42332.00	AT Par	42332.00	
	Description:- Maintenance Free Earth Electrode of length 3m, including supply of 3 bags of Earth enhancement material for earthing (10KGs /bag) for each electrode & other accessories as per Drg. No. SDO / RDSO/ E&B /001 and RDSO Spec No. RDSO / SPN/197/2008.							
4	4	4.00	Numbers	1416.00	5664.00	AT Par	5664.00	
	Description:- Installation of Maintenance Free Earth Electrode for Maintenance Free Earth spec of RDSO/SPN/197/2008.							
5	5	200.00	Numbers	71.00	14200.00	AT Par	14200.00	
	Description:- ARA Terminal blocks with links made of PBT Spec No.s/75/2006 (Rev - 2) with latest amendments and RDSO Drg.No.SA-23741A Alt.4.							
6	6	200.00	Numbers	13.00	2600.00	AT Par	2600.00	
	Description:- Fixing of ARA Terminals /Screw less connectors and fuse blocks on phenolic laminated sheets and fixing by stainless steel/brass nuts & bolts. This includes provision of two additional holes on the board on either side for cable conductor entry.							

**DYCSTE-C-RTM-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-RTM-122-2026-27

Closing Date/Time: 29/06/2026 15:00

7	7	5000.00	Numbers	4.00	20000.00	AT Par	20000.00	
	Description:- Termination of outdoor cables, main cables laid in location boxes, Cable termination rack etc. at both ends on ARA terminal or on 8 way terminals or on screw less connectors. Both ends of a cable core terminated shall be counted as one terminal. This includes all associated works of pulling out the cable from underground, peeling off insulation, dressing of cable core supported on sting rod with contractor's own material. The work shall be done as per instructions of Rly engineer at site.							
8	8	2.00	cum	1847.00	3694.00	AT Par	3694.00	
	Description:- Providing brick masonry in ratio 1:6 cement and mortar including plastering with 1:4 cement and sand mixture both sides, 20 mm thick each with contractor's owned class II bricks, including excavation, curing, grouting, bolting etc. wherever required. Bricks sand and cement to be supplied by the contractor.							
9	9	9.00	cum	3975.00	35775.00	AT Par	35775.00	
	Description:- Cement concrete work for miscellaneous items in the ratio 1 : 3 : 6. Item includes excavation, ramming, curing and plastering with cement & sand mixture (aggregate not exceeding 3.8 cm.) (Aggregate cement & sand to be supplied by the contractor).							
10	10	2.00	cum	136.00	272.00	AT Par	272.00	
	Description:- Earthwork in filling in embankment, guide bunds, around buried type abutments, bridge gaps, trolley refuges, rain bunds if provided, platforms etc. with earth excavated from outside railway boundary entirely arranged by the contractor at his own cost as per RDSO's latest guidelines and specifications and special condition of contract including all leads, royalty, lifts, ascents, descents, crossing of nallahs or any other obstructions. The rates shall include all dressing of bank to final profile, demarcation and setting out of profile, site clearance, removing of shrubs, roots of vegetation growth, heavy grass, benching of existing slope of old bank, all handling/re-handling. Taxes, Octroi and royalty etc. as a complete job. Cut trees shall be property of railways and to be deposited in the railway godown unless specified otherwise in the Special conditions of contract.							
11	11	280.00	Man-Days	555.00	155400.00	AT Par	155400.00	
	Description:- "As and when required by the Engineer in charge arranging /providing of labors for various safety related works such as protection of track etc. with contractor's T&P, equipment, hand signal flags, spanners, hammers, etc. as per specification special conditions and detailed scope of work as furnished in the tender and directed by the engineer in charge."							
12	12	4.00	Numbers	13442.00	53768.00	AT Par	53768.00	
	Description:- Apparatus Case Single NE Rly Type as per Drg. No.W. Rly/SW/47/68 Alt-A, fitted with two no.s of E Type lock (ward No will be specified by Engineer-in Charge) as per RDSO Drg. No. SA 3376/3473 and Key to Drg. No. 3377. Note: This item includes the supply & fixing of 2 No.s E Type Lock fitted on both doors, along with two Keys.							
13	13	2.00	Numbers	8524.00	17048.00	AT Par	17048.00	
	Description:- Apparatus Case half NE Rly Type as per Drg. No. W. Rly/SW/47/68 Alt-A fitted two no.s E Type lock of (ward No will be specified by Engineer-in Charge) as per RDSO Drg. No. SA 3376/3473 and Key to Drg. No. 3377. Note: This item includes the supply & fixing of 2 No.s E Type Lock fitted on both doors, along with two Keys.							
14	Please see Item Breakup for details.				36720.00	AT Par	36720.00	
	Description:- Excavation and Casting of Apparatus Case foundation with contractor's own materials including cement and anchor bolts of standard size. The required scaffolding Ferma etc. for Casting of foundation will have to be brought by the contractor at his own cost.							
15	Please see Item Breakup for details.				5192.00	AT Par	5192.00	
	Description:- "Installation of Apparatus Cases with miniature 'E' type lock on CC foundation. This includes filling of location foundations with river bed sand and plastering on top of the sand. 'E' Type lock will be provided by Railway."							
16	Please see Item Breakup for details.				10352.00	AT Par	10352.00	
	Description:- Fabrication and fixing of SMC sheet in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated string rods at the back side for cable support with contractor's own materials. The work shall be done as per Drg and arrangement similar to SK 783-1/2. With latest alterations & as per instructions of Rly engineer at site. Note: SMC sheet will be taken in place of phenolic laminated sheet.							
17	17	6.00	Numbers	210.00	1260.00	AT Par	1260.00	
	Description:- "Preparation and fixing of location box board on 03 mm ACP sheet with size 12 x 18 size A 3 for location box including pasting of printed/ painted vinyl sheet and lamination (printing/painting of location detail on vinyl sheet covered in schedule item separately)."							
18	Please see Item Breakup for details.				1432.00	AT Par	1432.00	

**DYCSSTE-C-RTM-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-RTM-122-2026-27

Closing Date/Time: 29/06/2026 15:00

	Description:- Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor's own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in- charge. Epoxy paint will be supplied by Railways. NOTE: - The paint and primer should be from Asian Paints/ Nerolac / Dulux / Berger. The primer / enamel paints (Aluminum synthetic, black enamel, brilliant white and yellow) will be as per (IS 5660 of 1970) / (IS 2932 of 1974).						
19	19	4.00	Numbers	114.00	456.00	AT Par	456.00
	Description:- "Lettering / Numbering Termination particulars, equipments names etc., legibly and neatly inside location boxes. This includes supply of paints of Asian Paints/ Nerolac / Dulux / Berger make. Full Case."						
20	20	2.00	Numbers	78.00	156.00	AT Par	156.00
	Description:- "Lettering / Numbering Termination particulars, equipments names etc., legibly and neatly inside location boxes. This includes supply of paints of Asian Paints/ Nerolac / Dulux / Berger make. Half Case."						
21	21	500.00	cum	258.00	129000.00	AT Par	129000.00
	Description:- Excavation of cable trench as per cable route plan, 1 Mtr. deep and of 0.3 Mtr. to 0.6 Mtr wide advised by Engineer-in-charge alongside the track in normal (all type) soil/strata, conforming to distances as per cable route plan and refilling. This work includes clearing of route from bushes etc., covering of cable laid in trench by loose soil for a layer of 50mm thickness approximately before covering by bricks. The work shall be done as per the extant practice on Western Railway and instructions of Railway Engineer at site. In case 1m depth of trench is not achievable due to site conditions, specific approval of JA grade officer will be required for each site where trench depth of 1m is not possible. Without the approval of JA Grade officer, no payment for trenching will be made for trench depth less than 1m.						
22	22	1000.00	Running Metre	1016.00	1016000.00	AT Par	1016000.00
	Description:- Horizontal direction drilling/boring without damage of surface road using Auger Machine. The bore shall be 150 mm Dia& shall be done at the depth of minimum 1200 mm from the ground level. The ground level shall be considered ignoring the bank height of the bank of the road. The length of the bore shall be minimum 4 Mtr long. The HDD with or without HDPE pipe as per direction of Engineer In charge. Note: HDPE pipe supply is taken as separate item. This item also includes cable laying (HDD boring).						
23	23	10.00	Numbers	1777.00	17770.00	AT Par	17770.00
	Description:- Double Walled Corrugated (DWC) HDPE Pipe with associated collars etc. as per RDSO Specification No. RDSO/SPN/204/2011 or latest anti-rodent & anti-oxidant and non-flame propagating type in 6 meters straight length and of size 120 mm outer dia,& 103.5 mm inner dia. . One of the following coupling arrangements should also be supplied with each pipe as per the site requirement. 1) Suitable snap fit coupler with rubber 'O- Ring 2) Spacers 3) Tees 4) Bend, 5) End-cap (The total quantity of above items is equal to no. of pipes supplied.) DWC pipe shall be marked at every 1 mtr length in such a way that manufacturer's name, vender name and year of manufacture can be easily identified. Color -Bright Orange; Min Weight = 4kg. Test Check by Consignee & Sample check by JAG officer.						
24	24	30000.00	Running Metre	9.00	270000.00	AT Par	270000.00
	Description:- Laying of S&T Cables of various cores/ pairs/ quads in trenches/ GI pipes/ RCC pipes/ DWC pipes/ Trucking. This also includes laying of cables in track crossings & road crossings. Item includes provision of labels of colored plastic adhesive tapes or any other identifiable material on each cable to give the cable number at each G.P.(Cables will be daggered before and after its laying by contractor under supervision of Railway Representative and he will submit the meggering report of each testing). Length of the cable laid includes the length of the cable coiled for termination purposes.						
25	25	20.00	Numbers	381.00	7620.00	AT Par	7620.00
	Description:- "Supply and installation of RCC cable route marker engraved and painted on both side along the route every 50mm and route diversion as per Drg. No 4014/00/CC4 or latest/ Stone marker."						
26	26	1.00	Numbers	18194.00	18194.00	AT Par	18194.00
	Description:- Digital low current clamp meter to measure current leaks (parasitic draw down to 1 mA) and electric loads from 1mA to 100 Amp AC/DC, Voltages from 0 to 600V AC/DC, small jaw size to measure current in signalling circuit, 4 digit display. Make -Fluke, GTC/KEW, Scope or superior with better specification as mentioned with all accessories like test lead, batteries and carrying case, sample may be got approved from consignee before supply.						
27	27	5000.00	Numbers	7.00	35000.00	AT Par	35000.00
	Description:- Provision of ferrules on Cable, As per the latest guideline of Railways, which includes all associated work like printing, identifying, fixing, etc.(POLICY NO-02/2024/latest).						
28	28	2.00	Numbers	4982.00	9964.00	AT Par	9964.00

**DYCSTE-C-RTM-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-RTM-122-2026-27

Closing Date/Time: 29/06/2026 15:00

			Description:- Phenolic laminated Sheet, grade P3 in standard size of 1220 X 1220 x 10 mm as per spec. No IS 2036 of 1995 or latest. Test report of manufacture to be supplied.				
29	29	2.00	Numbers	9550.00	19100.00	AT Par	19100.00
			Description:- Phenolic laminated Sheet, grade P3 in standard size of 1220 X 1220 x 20 mm as per spec. No IS 2036 of 1995 or latest. Test report of manufacture to be supplied.				
30	30	1060.00	Running Metre	31.00	32860.00	AT Par	32860.00
			Description:- Placing of DWC/RCC/GI pipes/ PVC /polyfin channel along with collars in trenches at places of track and road crossings, platform cuttings etc. also for straight cable laying. (Cable laying is covered separately.)				
31	31	14.00	Numbers	2186.00	30604.00	AT Par	30604.00
			Description:- Supply & installation of FRP/SMC based Earth Chamber Suitable for taking load of 2MT.{Drawing as per Drg. No.19-D5 -D6-D7 or latest ,To be got approved from Engineer In Charge before supply}				
32	32	6.00	Numbers	4370.00	26220.00	AT Par	26220.00
			Description:- Shifting of existing full location boxes coming in the alignment of new line. The work includes losing & removal of soil around location boxes by excavating soil around foundation, making of pit for shifting of location box horizontally opposite to railway track up to 0.5 to 1.0 mtr. This includes loosening of existing cable coils without any damage. The excavated soil shall be back filled after shifting of Location Boxes. Location box shall be shifted by push method with the help of jacks or by crane by contractors own expenditure under instructions of engineer in-charge at site. The work may affect train working hence the work shall be done as per margin only or during traffic block only.				
33	33	6.00	Numbers	3380.00	20280.00	AT Par	20280.00
			Description:- Shifting of existing half location boxes coming in the alignment of new line. The work includes losing & removal of soil around location boxes by excavating soil around foundation, making of pit for shifting of location box horizontally opposite to railway This includes loosening of existing cable coils without any damage. The excavated soil shall be back filled after shifting of Location Boxes. Location box shall be shifted by push method with the help of jacks or by crane by contractors own expenditure under instructions of engineer in-charge at site. The work may affect train working hence the work shall be done as per margin only or during traffic block only.				
34	34	2.00	Kilometre	14404.00	28808.00	AT Par	28808.00
			Description:- Shifting of Exposed cables. The item includes Removal of exposed cable from existing trench & laying the same in new trenches.				
35	35	4000.00	Running Metre	32.00	128000.00	AT Par	128000.00
			Description:- Tracing of cable route for old buriedall type S&T cable including OFCwith accuracy +/-0.5 Meter, usingcontractors own Equipments & manPower and preparation of cableroute plan in reference to OHE Mast& Centre of Track on Hard and Softcopy. With GPS positioning of cableroute every 25 mtr or less.				
36	36	20.00	Day	8716.00	174320.00	AT Par	174320.00
			Description:- Tracing & Securing buried underground S&T cables including OFC by team of minimum 5 persons with dedicated vehicle (MUV) in a team(minimum one technician/jointer),during Eng. digging work by JCB's -to provide supervisory work, such as marking, shifting, securing, jointing,restoring etc. (Cable joints & termination taken as separate schedule Item). Information for the deputing team for above work will be provided by Railway Engineer incharge 08 hours prior to requirement. They will pre checkroute and will do Chuna marking for digging work.Note-Necessary arrangement of Team / required material movement to the desired location as per instruction of engineer in charge to be provide bycontractor. The contractor needs to arrange "n" nos. of teams as per the Railway Requirement.				
37	37	2.00	Kilometre	46974.00	93948.00	AT Par	93948.00
			Description:- "Supply of HDPE Ducts 40/33 mm dia as per RDSO/SPN/TC/45/2013 , Rev. 2.0 ,Amendment 3.0 or latest. Each km / Bundle of HDPE duct should have 2 no End Plugs, 2 no Cables ealing plugs, 2 no plastic couplers(5-6 thread) slipfit/push fit type. {The duct should be supplied in accordance with the latest WR Telecom Policy, dated January 1, 2025 or latest. Each colour of duct shall be supplied as specified by the Engineer-in-Charge }."				
38	38	100.00	Metre	329.00	32900.00	AT Par	32900.00
			Description:- Supply of 110 mm dia HDPE pipe.{ ISI Mark - IS no. 4984:2016 or the latest }.				
39	39	6.00	Numbers	3724.00	22344.00	AT Par	22344.00
			Description:- Supply of Straight Joint Enclosures (SJC) complete with all accessories as per GR/OJC/02/02 Sept 2003 for 48 fiber, Make- Raychem - FOSC-400-B4-A-BJL-4-H -48 , 3M or Similar only, as per instruction and approval of Engineer In charge.				
40	40	6.00	Numbers	2054.00	12324.00	AT Par	12324.00
			Description:- Supply of Thermo shrink Universal Jointing kit for Quad Cable (Straight/Derivation) as per RDSO IRS/TC-77/2012 revision 3 With latest Amd.				

**DYCSTE-C-RTM-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-RTM-122-2026-27

Closing Date/Time: 29/06/2026 15:00

41	41	2.00	Kilometre	6049.00	12098.00	AT Par	12098.00	
	Description:- Transportation and Laying of HDPE pipe as per approved cable route plan in the excavated trench, taking due care while transporting and laying the same in the trenches or other protective works. Both the end of duct should be sealed with end plugs before laying.							
42	42	2.00	Kilometre	11263.00	22526.00	AT Par	22526.00	
	Description:- Blowing of OFC through HDPE duct & protective work (elicited in above item) already provided. Where it is not feasible to blow OFC due to curves, road/track crossings, bridges or for any other reason, OFC shall be drawn /laid manually as per standard procedure. All the equipments and machinery required shall be arranged by the contractor at his own cost. In case OFC is to be laid adopting 'Direct in trench' method then this item shall be paid as per accepted rate of item of this schedule. OFC and HDPE pipe shall be supplied by the railway.							
43	43	6.00	Numbers	6131.00	36786.00	AT Par	36786.00	
	Description:- Preparation, splicing, making and installation of OFC straight through joints with enclosure/ LIU termination. Splicing should be done by trained person, the losses shall not exceed beyond the prescribed limit. If losses exceed the prescribed limit, the contractor have to re-splice free of cost.							
44	44	2.00	Kilometre	4608.00	9216.00	AT Par	9216.00	
	Description:- Transporation and laying of 6 Quad/PIJF cables in Trenches/ GI pipe/RCC pipe/DWC pipe, Trunking etc as per approved cable route Plan and instruction of Site Engineer.							
45	45	6.00	Numbers	1017.00	6102.00	AT Par	6102.00	
	Description:- Execution of Straight/Derivation/EC Joint on Quad/PIJF Cables as per instruction by site engineer.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () B-Supply & Execution of S&T Items for Provision of Stabling Lines in NC Yard.							3031471.00	
1	1	10.00	Numbers	3571.00	35710.00	AT Par	35710.00	
	Description:- Earth Electrode as per Drg. No. CSTE / 6091.							
2	2	10.00	Numbers	4961.00	49610.00	AT Par	49610.00	
	Description:- Installation of Earth Electrode including MS flat for clamp etc. and connection to signallingequipments, lever frames, apparatus cases, signal, relay rack, block instrument, etc. as per technical specification given. This item includes digging of pit in earth 3 M deep & fixing earth electrodepipe, casting o f cement concrete enclosure & cover a s per RDSO/SPN/ 197/2016.Soiltreatment to be done as perstd. practice. This item includes provision of MS Flat, Earth lead wires and Soldering of lead wires. The other end of the wire is to be connected t o block equipment, power equipment, cable sheath, and signals etc. as per site requirements. 7strand GI wire shall be used as earth lead wire. Supply of earth electrode is covered in other Item').							
3	3	10.00	Numbers	10583.00	105830.00	AT Par	105830.00	
	Description:- Maintenance Free Earth Electrode of length 3m, including supply of 3 bags of Earth enhancement material for earthing (10KGs /bag) for each electrode & other accessories as per Drg. No. SDO / RDSO/ E&B /001 and RDSO Spec No. RDSO / SPN/197/2008.							
4	4	10.00	Numbers	1416.00	14160.00	AT Par	14160.00	
	Description:- Installation of Maintenance Free Earth Electrode for Maintenance Free Earth spec of RDSO/SPN/197/2008.							
5	5	200.00	Numbers	71.00	14200.00	AT Par	14200.00	
	Description:- ARA Terminal blocks with links made of PBT Spec No.s/75/2006 (Rev - 2) with latest amendments and RDSO Drg.No.SA-23741A Alt.4.							
6	6	200.00	Numbers	13.00	2600.00	AT Par	2600.00	
	Description:- Fixing of ARA Terminals /Screw less connectors and fuse blocks on phenolic laminated sheets and fixing by stainless steel/brass nuts & bolts. This includes provision of two additional holes on the board on either side for cable conductor entry.							
7	7	5000.00	Numbers	4.00	20000.00	AT Par	20000.00	
	Description:- Termination of outdoor cables, main cables laid in location boxes, Cable termination rack etc. at both ends on ARA terminal or on 8 way terminals or on screw less connectors. Both ends of a cable core terminated shall be counted as one terminal. This includes all associated works of pulling out the cable from underground, peeling off insulation, dressing of cable core supported on sting rod with contractor's own material. The work shall be done as per instructions of Rly engineer at site.							
	8	2.00	cum	1847.00	3694.00	AT Par	3694.00	

**DYCS-TE-C-RTM-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-RTM-122-2026-27

Closing Date/Time: 29/06/2026 15:00

8	Description:- Providing brick masonry in ratio 1:6 cement and mortar including plastering with 1:4 cement and sand mixture both sides, 20 mm thick each with contractor's owned class II bricks, including excavation, curing, grouting, bolting etc. wherever required. Bricks sand and cement to be supplied by the contractor.						
9	9	10.00	cum	3975.00	39750.00	AT Par	39750.00
	Description:- Cement concrete work for miscellaneous items in the ratio 1 : 3 : 6. Item includes excavation, ramming, curing and plastering with cement & sand mixture (aggregate not exceeding 3.8 cm.) (Aggregate cement & sand to be supplied by the contractor).						
10	10	2.00	cum	136.00	272.00	AT Par	272.00
	Description:- Earthwork in filling in embankment, guide bunds, around buried type abutments, bridge gaps, trolley refuges, rain bunds if provided, platforms etc. with earth excavated from outside railway boundary entirely arranged by the contractor at his own cost as per RDSO's latest guidelines and specifications and special condition of contract including all leads, royalty, lifts, ascents, descents, crossing of nallahs or any other obstructions. The rates shall include all dressing of bank to final profile, demarcation and setting out of profile, site clearance, removing of shrubs, roots of vegetation growth, heavy grass, benching of existing slope of old bank, all handling/re-handling. Taxes, Octroi and royalty etc. as a complete job. Cut trees shall be property of railways and to be deposited in the railway godown unless specified otherwise in the Special conditions of contract.						
11	11	280.00	Man-Days	555.00	155400.00	AT Par	155400.00
	Description:- "As and when required by the Engineer in charge arranging /providing of labors for various safety related works such as protection of track etc. with contractor's T&P, equipment, hand signal flags, spanners, hammers, etc. as per specification special conditions and detailed scope of work as furnished in the tender and directed by the engineer incharge."						
12	12	4.00	Numbers	13442.00	53768.00	AT Par	53768.00
	Description:- Apparatus Case Single NE Rly Type as per Drg. No.W. Rly/SW/47/68 Alt-A, fitted with two no.s of E Type lock (ward No will be specified by Engineer-in Charge) as per RDSO Drg. No. SA 3376/3473 and Key to Drg. No. 3377. Note: This item includes the supply & fixing of 2 No.s E Type Lock fitted on both doors, along with two Keys.						
13	13	2.00	Numbers	8524.00	17048.00	AT Par	17048.00
	Description:- Apparatus Case half NE Rly Type as per Drg. No. W. Rly/SW/47/68 Alt-A fitted two no.s E Type lock of (ward No will be specified by Engineer-in Charge) as per RDSO Drg. No. SA 3376/3473 and Key to Drg. No. 3377. Note: This item includes the supply & fixing of 2 No.s E Type Lock fitted on both doors, along with two Keys.						
14	Please see Item Breakup for details.				36720.00	AT Par	36720.00
	Description:- Excavation and Casting of Apparatus Case foundation with contractor's own materials including cement and anchor bolts of standard size. The required scaffolding Ferma etc. for Casting of foundation will have to be brought by the contractor at his own cost.						
15	Please see Item Breakup for details.				5192.00	AT Par	5192.00
	Description:- "Installation of Apparatus Cases with miniature 'E' type lock on CC foundation. This includes filling of location foundations with river bed sand and plastering on top of the sand. 'E' Type lock will be provided by Railway."						
16	Please see Item Breakup for details.				10352.00	AT Par	10352.00
	Description:- Fabrication and fixing of SMC sheet in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated string rods at the back side for cable support with contractor's own materials. The work shall be done as per Drg and arrangement similar to SK 783-1/2. With latest alterations & as per instructions of Rly engineer at site. Note: SMC sheet will be taken in place of phenolic laminated sheet.						
17	17	6.00	Numbers	210.00	1260.00	AT Par	1260.00
	Description:- "Preparation and fixing of location box board on 03 mm ACP sheet with size 12 x 18 size A 3 for location box including pasting of printed/painted vinyl sheet and lamination (printing/painting of location detail on vinyl sheet covered in schedule item separately)."						
18	Please see Item Breakup for details.				1432.00	AT Par	1432.00
	Description:- Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor's own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy paint will be supplied by Railways. NOTE: - The paint and primer should be from Asian Paints/ Nerolac / Dulux / Berger. The primer / enamel paints (Aluminum synthetic, black enamel, brilliant white and yellow) will be as per (IS 5660 of 1970) / (IS 2932 of 1974).						
19	19	4.00	Numbers	114.00	456.00	AT Par	456.00
	Description:- "Lettering / Numbering Termination particulars, equipments names etc., legibly and neatly inside location boxes. This includes supply of paints of Asian Paints/ Nerolac / Dulux / Berger make. Full Case."						
20	20	2.00	Numbers	78.00	156.00	AT Par	156.00
20							

**DYCSTE-C-RTM-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-RTM-122-2026-27

Closing Date/Time: 29/06/2026 15:00

		Description:- "Lettering / Numbering Termination particulars, equipments names etc., legibly and neatly inside location boxes. This includes supply of paints of Asian Paints/ Nerolac / Dulux / Berger make. Half Case."					
21	21	600.00	cum	258.00	154800.00	AT Par	154800.00
		Description:- Excavation of cable trench as per cable route plan, 1 Mtr. deep and of 0.3 Mtr. to 0.6 Mtr wide advised by Engineer-in-charge alongside the track in normal (all type) soil/strata, conforming to distances as per cable route plan and refilling. This work includes clearing of route from bushes etc., covering of cable laid in trench by loose soil for a layer of 50mm thickness approximately before covering by bricks. The work shall be done as per the extant practice on Western Railway and instructions of Railway Engineer at site. In case 1m depth of trench is not achievable due to site conditions, specific approval of JA grade officer will be required for each site where trench depth of 1m is not possible. Without the approval of JA Grade officer, no payment for trenching will be made for trench depth less than 1m.					
22	22	1000.00	Running Metre	1016.00	1016000.00	AT Par	1016000.00
		Description:- Horizontal direction drilling/boring without damage of surface road using Auger Machine. The bore shall be 150 mm Dia& shall be done at the depth of minimum 1200 mm from the ground level. The ground level shall be considered ignoring the bank height of the bank of the road. The length of the bore shall be minimum 4 Mtr long. The HDD with or without HDPE pipe as per direction of Engineer In charge. Note: HDPE pipe supply is taken as separate item. This item also includes cable laying (HDD boring).					
23	23	10.00	Numbers	1777.00	17770.00	AT Par	17770.00
		Description:- Double Walled Corrugated (DWC) HDPE Pipe with associated collars etc. as per RDSO Specification No. RDSO/SPN/204/2011 or latest anti-rodent & anti-oxidant and non-flame propagating type in 6 meters straight length and of size 120 mm outer dia,& 103.5 mm inner dia. . One of the following coupling arrangements should also be supplied with each pipe as per the site requirement. 1) Suitable snap fit coupler with rubber 'O- Ring 2) Spacers 3) Tees 4) Bend, 5) End-cap (The total quantity of above items is equal to no. of pipes supplied.) DWC pipe shall be marked at every 1 mtr length in such a way that manufacturer's name, vender name and year of manufacture can be easily identified. Color -Bright Orange; Min Weight = 4kg. Test Check by Consignee & Sample check by JAG officer.					
24	24	40000.00	Running Metre	9.00	360000.00	AT Par	360000.00
		Description:- Laying of S&T Cables of various cores/ pairs/ quads in trenches/ GI pipes/ RCC pipes/ DWC pipes/ Trucking. This also includes laying of cables in track crossings & road crossings. Item includes provision of labels of colored plastic adhesive tapes or any other identifiable material on each cable to give the cable number at each G.P.(Cables will be daggered before and after its laying by contractor under supervision of Railway Representative and he will submit the meggering report of each testing). Length of the cable laid includes the length of the cable coiled for termination purposes.					
25	25	20.00	Numbers	381.00	7620.00	AT Par	7620.00
		Description:- "Supply and installation of RCC cable route marker engraved and painted on both side along the route every 50mm and route diversion as per Drg. No 4014/00/CC4 or latest/ Stone marker."					
26	26	1.00	Numbers	18194.00	18194.00	AT Par	18194.00
		Description:- Digital low current clamp meter to measure current leaks (parasitic draw down to 1 mA) and electric loads from 1mA to 100 Amp AC/DC, Voltages from 0 to 600V AC/DC, small jaw size to measure current in signalling circuit, 4 digit display. Make -Fluke, GTC/KEW, Scope or superior with better specification as mentioned with all accessories like test lead, batteries and carrying case, sample may be got approved from consignee before supply.					
27	27	5000.00	Numbers	7.00	35000.00	AT Par	35000.00
		Description:- Provision of ferrules on Cable, As per the latest guideline of Railways, which includes all associated work like printing, identifying, fixing, etc.(POLICY NO-02/2024/latest).					
28	28	500.00	Numbers	54.00	27000.00	AT Par	27000.00
		Description:- Disconnect Terminal Block, Screw less type, 4-wire front entry (Two in-put & Two out-put) The colour will be decided by Engineer - in - Charge. (Preferably In Blue, Red & Grey Colors in the ratio of 1:2:3) . Make-Phoenix, Wago or Similar.					
29	29	225.00	Numbers	10.00	2250.00	AT Par	2250.00
		Description:- Supply of End plate for above item (I) 2.5mm/0.091 in thick as per site requirement.					
30	30	313.00	Numbers	10.00	3130.00	AT Par	3130.00
		Description:- Supply of End Stopper for above item (I) 10mm/0.0394 in width as per site requirement.					
31	31	17.00	Numbers	105.00	1785.00	AT Par	1785.00
		Description:- Supply of Carrier Rails for above 35mm x 7.5mm, 1mm/0.039 in thickness un-slotted type as per site requirement.					

**DYCSTE-C-RTM-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-RTM-122-2026-27

Closing Date/Time: 29/06/2026 15:00

32	32	10.00	Numbers	18.00	180.00	AT Par	180.00	
	Description:- Supply of Marker Card 100 Marking in One Card (10 rows *10 Columns)							
33	33	2.00	Numbers	9550.00	19100.00	AT Par	19100.00	
	Description:- Phenolic laminated Sheet, grade P3 in standard size of 1220 X 1220 x 20 mm as per spec. No IS 2036 of 1995 or latest. Test report of manufacture to be supplied.							
34	34	2.00	Numbers	4982.00	9964.00	AT Par	9964.00	
	Description:- Phenolic laminated Sheet, grade P3 in standard size of 1220 X 1220 x 10 mm as per spec. No IS 2036 of 1995 or latest. Test report of manufacture to be supplied.							
35	35	2060.00	Running Metre	31.00	63860.00	AT Par	63860.00	
	Description:- Placing of DWC/RCC/GI pipes/ PVC /polyfin channel along with collars in trenches at places of track and road crossings, platform cuttings etc. also for straight cable laying. (Cable laying is covered separately.)							
36	36	20.00	Numbers	2186.00	43720.00	AT Par	43720.00	
	Description:- Supply & installation of FRP/SMC based Earth Chamber Suitable for taking load of 2MT.{Drawing as per Drg. No.19-D5 -D6-D7 or latest ,To be got approved from Engineer In Charge before supply}							
37	37	6.00	Numbers	4370.00	26220.00	AT Par	26220.00	
	Description:- Shifting of existing full location boxes coming in the alignment of new line. The work includes losing & removal of soil around location boxes by excavating soil around foundation, making of pit for shifting of location box horizontally opposite to railway track up to 0.5 to 1.0 mtr. This includes losing of existing cable coils without any damage. The excavated soil shall be back filled after shifting of Location Boxes. Location box shall be shifted by push method with the help of jacks or by crane by contractors own expenditure under instructions of engineer in-charge at site. The work may affect train working hence the work shall be done as per margin only or during traffic block only.							
38	38	6.00	Numbers	3380.00	20280.00	AT Par	20280.00	
	Description:- Shifting of existing half location boxes coming in the alignment of new line. The work includes losing & removal of soil around location boxes by excavating soil around foundation, making of pit for shifting of location box horizontally opposite to railway This includes losing of existing cable coils without any damage. The excavated soil shall be back filled after shifting of Location Boxes. Location box shall be shifted by push method with the help of jacks or by crane by contractors own expenditure under instructions of engineer in-charge at site. The work may affect train working hence the work shall be done as per margin only or during traffic block only.							
39	39	6.00	Kilometre	14404.00	86424.00	AT Par	86424.00	
	Description:- Shifting of Exposed cables. The item includes Removal of exposed cable from existing trench & laying the same in new trenches.							
40	40	4000.00	Running Metre	32.00	128000.00	AT Par	128000.00	
	Description:- Tracing of cable route for old buriedall type S&T cable including OFCwith accuracy +/-0.5 Meter, usingcontractors own Equipments & manPower and preparation of cableroute plan in reference to OHE Mast& Centre of Track on Hard and Softcopy. With GPS positioning of cableroute every 25 mtr or less.							
41	41	20.00	Day	8716.00	174320.00	AT Par	174320.00	
	Description:- Tracing & Securing buried underground S&T cables including OFC by team of minimum 5 persons with dedicated vehicle (MUV) in a team(minimum one technician/jointer),during Eng. digging work by JCB's -to provide supervisory work, such as marking, shifting, securing, jointing,restoring etc. (Cable Joints & termination taken as separate schedule Item). Information for the deputing team for above work will be provided by Railway Engineer incharge 08 hours prior to requirement. They will pre checkroute and will do Chuna marking for digging work.Note-Necessary arrangement of Team / required material movement to the desired location as per instruction of engineer in charge to be provide bycontractor. The contractor needs to arrange "n" nos. of teams as per the Railway Requirement.							
42	42	2.00	Kilometre	46974.00	93948.00	AT Par	93948.00	
	Description:- "Supply of HDPE Ducts 40/33 mm dia as per RDSO/SPN/TC/45/2013 , Rev. 2.0 ,Amendment 3.0 or latest. Each km / Bundle of HDPE duct should have 2 no End Plugs, 2 no Cables ealing plugs, 2 no plastic couplers(5-6 thread) slipfit/push fit type. {The duct should be supplied in accordance with the latest WR Telecom Policy, dated January 1, 2025 or latest. Each colour of duct shall be supplied as specified by the Engineer-in-Charge }."							
43	43	100.00	Metre	329.00	32900.00	AT Par	32900.00	
	Description:- Supply of 110 mm dia HDPE pipe.{ ISI Mark - IS no. 4984:2016 or the latest }.							
44	44	6.00	Numbers	3724.00	22344.00	AT Par	22344.00	

**DYCSTE-C-RTM-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-RTM-122-2026-27

Closing Date/Time: 29/06/2026 15:00

	Description:- Supply of Straight Joint Enclosures (SJC) complete with all accessories as per GR/OJC/02/02 Sept 2003 for 48 fiber, Make- Raychem - FOSC-400-B4-A-BJL-4-H -48 , 3M or Similar only, as per instruction and approval of Engineer In charge.						
45	45	6.00	Numbers	2054.00	12324.00	AT Par	12324.00
	Description:- Supply of Thermo shrink Universal Jointing kit for Quad Cable (Straight/Derivation) as per RDSO IRS/TC-77/2012 revision 3 With latest Amd.						
46	46	2.00	Kilometre	6049.00	12098.00	AT Par	12098.00
	Description:- Transportation and Laying of HDPE pipe as per approved cable route plan in the excavated trench, taking due care while transporting and laying the same in the trenches or other protective works. Both the end of duct should be sealed with end plugs before laying.						
47	47	2.00	Kilometre	11263.00	22526.00	AT Par	22526.00
	Description:- Blowing of OFC through HDPE duct & protective work (elicited in above item) already provided. Where it is not feasible to blow OFC due to curves, road/track crossings, bridges or for any other reason, OFC shall be drawn /laid manually as per standard procedure. All the equipments and machinery required shall be arranged by the contractor at his own cost. In case OFC is to be laid adopting 'Direct in trench' method then this item shall be paid as per accepted rate of item of this schedule. OFC and HDPE pipe shall be supplied by the railway.						
48	48	6.00	Numbers	6131.00	36786.00	AT Par	36786.00
	Description:- Preparation, splicing, makingand installation of OFC straight through joints with enclosure/ LIU termination.Splicing should be done by trained person, the losses shall not exceed beyond the prescribed limit. If losses exceed the prescribed limit, the contractor have to re-splice free of cost.						
49	49	2.00	Kilometre	4608.00	9216.00	AT Par	9216.00
	Description:- Transporation and laying of 6 Quad/PIJF cables in Trenches/ GI pipe/RCC pipe/DWC pipe, Trunking etc as per approved cable route Plan and instruction of Site Engineer.						
50	50	6.00	Numbers	1017.00	6102.00	AT Par	6102.00
	Description:- Execution of Straight/Derivation/EC Joint on Quad/PIJF Cables as per instruction by site engineer.						

3. ITEM BREAKUP

Schedule	Schedule A-Supply & Execution of S& T Items for Provision of Stabling Line and Relocation of PQRS Siding in Loco Yard					
Item- 14	Excavation and Casting of Apparatus Case foundation with contractor's own materials including cement and anchor bolts of standard size. The required scaffolding Ferma etc. for Casting of foundation will have to be brought by the contractor at his own cost.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	(i)	"Single Case a s per Drg No S K 748 or CSTE/5074 or SSLocation"	Numbers	4.00	6677.00	26708.00
2	(ii)	"Half Case a s per Drg No S K 747 or CSTE/5074 or SSLocation."	Numbers	2.00	5006.00	10012.00
					Total	36720.00
Item- 15	"Installation of Apparatus Cases with miniature 'E' type lock on CC foundation. This includes filling of location foundations with river bed sand and plastering on top of the sand. 'E' Type lock will be provided by Railway."					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	(i)	Single Case	Numbers	4.00	999.00	3996.00
2	(ii)	Half Case	Numbers	2.00	598.00	1196.00
					Total	5192.00
Item- 16	Fabrication and fixing of SMC sheet in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated string rods at the back side for cable support with contractor's own materials. The work shall be done as per Drg and arrangement similar to SK 783-1/2. With latest alterations & as per instructions of Rly engineer at site. Note: SMC sheet will be taken in place of phenolic laminated sheet.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	(i)	Single Case	Numbers	4.00	2228.00	8912.00
2	(ii)	Half Case	Numbers	2.00	720.00	1440.00
					Total	10352.00

**DYCSTE-C-RTM-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-RTM-122-2026-27

Closing Date/Time: 29/06/2026 15:00

Item- 18	Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor's own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in- charge. Epoxy paint will be supplied by Railways. NOTE: - The paint and primer should be from Asian Paints/ Nerolac / Dulux / Berger. The primer / enamel paints (Aluminum synthetic, black enamel, brilliant white and yellow) will be as per (IS 5660 of 1970) / (IS 2932 of 1974).					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	(i)	Apparatus Case Full Size. (Outside & inside)	Numbers	4.00	250.00	1000.00
2	(ii)	Apparatus case Half Size. (Outside & inside)	Numbers	2.00	216.00	432.00
					Total	1432.00
Schedule	Schedule B-Supply & Execution of S&T Items for Provision of Stabling Lines in NC Yard.					
Item- 14	Excavation and Casting of Apparatus Case foundation with contractor's own materials including cement and anchor bolts of standard size. The required scaffolding Ferma etc. for Casting of foundation will have to be brought by the contractor at his own cost.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	(i)	"Single Case as per Drg No SK 748 or CSTE/5074 or SS Location"	Numbers	4.00	6677.00	26708.00
2	(ii)	"Half Case as per Drg No S K 747or CSTE/5074 or SS Location."	Numbers	2.00	5006.00	10012.00
					Total	36720.00
Item- 15	"Installation of Apparatus Cases with miniature 'E' type lock on CC foundation. This includes filling of location foundations with river bed sand and plastering on top of the sand. 'E' Type lock will be provided by Railway."					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	(i)	Single Case	Numbers	4.00	999.00	3996.00
2	(ii)	Half Case	Numbers	2.00	598.00	1196.00
					Total	5192.00
Item- 16	Fabrication and fixing of SMC sheet in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated string rods at the back side for cable support with contractor's own materials. The work shall be done as per Drg and arrangement similar to SK 783-1/2. With latest alterations & as per instructions of Rly engineer at site. Note: SMC sheet will be taken in place of phenolic laminated sheet.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	(i)	Single Case	Numbers	4.00	2228.00	8912.00
2	(ii)	Half Case	Numbers	2.00	720.00	1440.00
					Total	10352.00
Item- 18	Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor's own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in- charge. Epoxy paint will be supplied by Railways. NOTE: - The paint and primer should be from Asian Paints/ Nerolac / Dulux / Berger. The primer / enamel paints (Aluminum synthetic, black enamel, brilliant white and yellow) will be as per (IS 5660 of 1970) / (IS 2932 of 1974).					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	(i)	Apparatus Case Full Size. (Outside & inside)	Numbers	4.00	250.00	1000.00
2	(ii)	Apparatus case Half Size. (Outside & inside)	Numbers	2.00	216.00	432.00
					Total	1432.00

4. ELIGIBILITY CONDITIONS

Standard Financial Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
-------	-------------	-----------------------	-----------------	---------------------

**DYCSTE-C-RTM-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-RTM-122-2026-27

Closing Date/Time: 29/06/2026 15:00

1	The tenderer must have minimum average annual contractual turnover of V/N or V whichever is less; where V= Advertised value of the tender in Crore of Rupees N= Number of years prescribed for completion of work for which bids have been invited. The average annual contractual turnover shall be calculated as an average of "total contractual payments" in the previous three financial years, as per the audited balance sheet. However, in case balance sheet of the previous year is yet to be prepared/ audited, the audited balance sheet of the fourth previous year shall be considered for calculating average annual contractual turnover. The tenderers shall submit requisite information as per Annexure-VIB, along with copies of Audited Balance Sheets duly certified by the Chartered Accountant/ Certificate from Chartered Accountant duly supported by Audited Balance Sheet.	No	No	Allowed (Mandatory)
---	--	----	----	------------------------

Special Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Work of Similar Nature would mean - "Any Signaling work involving Outdoor work and/or addition and/or alteration in existing Indoor signaling system. OR Any CLS or RI or EI or TPWS or IBS or IBS or BPAC work involving Indoor and/or Outdoor. Similar work to include Indoor if the tendered work involves addition and/or alteration in existing Indoor signaling system and Outdoor if the tendered work involves Outdoor work. OR Any Such work involving activities as given in the name of the tendered work."	No	No	Allowed (Mandatory)

Standard Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer must have successfully completed or substantially completed any one of the following categories of work(s) during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: (i) Three similar works each costing not less than the amount equal to 30% of advertised value of the tender, or (ii) Two similar works each costing not less than the amount equal to 40% of advertised value of the tender, or (iii) One similar work costing not less than the amount equal to 60% of advertised value of the tender.	No	No	Allowed (Mandatory)

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.
3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.
5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.
6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.
7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.
8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.
9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.

**DYCSTE-C-RTM-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-RTM-122-2026-27

Closing Date/Time: 29/06/2026 15:00

10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)
----	---

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description
1	Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. (Click here to download the Format of Self Certification)

5. COMPLIANCE

Commercial-Compliance

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Rates are inclusive of all taxes/octroi, license fees, royalty charges, GST, and other legally leviable charges by the State, Central Government, and/or any other local authority.	No	No	Not Allowed
2	Central Government/State Government/Local bodies, Sales tax/Commercial tax/GST at the rate prescribed by the Government of India/Madhya Pradesh state government for works contracts will be recovered from the bills from time to time for works carried out in the state of Madhya Pradesh, as per the extant instruction on the subject.	No	No	Not Allowed
3	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)

General Instructions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Please visit the website https://www.ireps.gov.in frequently till the closing date and time for any updates.	No	No	Not Allowed
2	Please download the Standard General Conditions of Contract and all the Advanced Correction Slips from www.indianrailways.gov.in .	No	No	Not Allowed
3	It shall not be obligatory on the said authority to accept the lowest tender, and no tenderer/tenderers shall demand any explanation for the cause of rejection of his/their tender.	No	No	Not Allowed
4	If the tenderers deliberately gives/give wrong information in his/their tender or creates/create circumstances for the acceptance of his/their tender, the Railway reserves the right to reject such tender at any stage.	No	No	Not Allowed
5	The Railway reserves the right not to invite tenders for any of the railway work or works or to invite open or limited tenders and when tenders are called, to accept a tender in whole or in part or reject any tender or all tenders without assigning reasons for such action.	No	No	Not Allowed
6	Tenderers are advised to visit the site before the rate Quote.	No	No	Not Allowed

Special Conditions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Unless specifically mentioned in the schedule of rates all materials required for execution of work will be supplied by the contractor free of cost as per standard specifications and approved by the Engineer-in-charge.	No	No	Not Allowed

**DYCSTE-C-RTM-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-RTM-122-2026-27

Closing Date/Time: 29/06/2026 15:00

2	All works are to be done as per the programme fixed by the Engineer-in-charge or his authorised representative and as per their direction only.	No	No	Not Allowed
3	All materials to be supplied by the contractor should be approved by the Engineer-in-Charge before use in the work.	No	No	Not Allowed
4	No compensation for any accident whatsoever will be paid by the Railway.	No	No	Not Allowed
5	Contractor shall not start any work without the presence of the railway supervisor at the site. In case the contractor's representative starts any work in the absence of the railway Supervisor, it shall be treated as unauthorised and illegal and shall be liable for action.	No	No	Not Allowed
6	The Contractor, with the help of his Engineer or Diploma holder, as the case may be, shall make necessary Drawings, sketches, plotting, etc., as desired by the Engineer-in-charge. No extra cost shall be claimed on this account.	No	No	Not Allowed
7	The work will be executed under the supervision of the Railway Engineer-in-charge or his authorized representative at the site.	No	No	Not Allowed
8	The agency should depute a trained and certified supervisor, duly certified by ADSTE/C.	No	No	Not Allowed
9	The Contractor should make available all the necessary tools, plants, and equipment for the execution of the above work at the site during the execution of the work. A competency certificate for JCB/HDD Operator is required to be obtained from the Railways.	No	No	Not Allowed
10	The vehicles and equipment of contractors can be drafted by the Railway Administration in case of Accidents or Natural calamities involving human lives, and payment in respect of that would be made by operating the item as a non-scheduled item.	No	No	Not Allowed
11	The tenderer or contractor will have to execute the work, taking necessary precautions for the safety of workers, passengers, traffic, etc.	No	No	Not Allowed
12	Materials are required to be supplied as per work progress at site. Looking to the requirements of the materials at site, only necessary Materials to be supplied. The schedule for material supply may change as per site requirement as advised by competent authority. Before supplying any materials, prior approval of Competent authority is required to be taken by contractor. Materials for which prior approval of competent authority have not been taken by contractor such materials will not be accepted by consignee.	No	No	Not Allowed

6. Documents attached with tender

S.No.	Document Name	Document Description
1	TD_122.pdf	Tender Document

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

Signed By: RAVI SHANKAR TIWARI

Designation : Dy.CSTE CONST. RTM