

**DYCSTE-C-RTM-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-RTM-123-2026-27

Closing Date/Time: 29/06/2026 15:00

Dy.CSTE/C/RTM acting for and on behalf of The President of India invites E-Tenders against Tender No **SnT-C-RTM-123-2026-27** Closing Date/Time 29/06/2026 15:00 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

1. NIT HEADER

Name of Work	Supply, Installation, Testing, and Commissioning of Telecom gears along with Utility Shifting, Trenching, Laying, Jointing, and Termination of OFC & Six Quad cables in Naikheri - Chintaman Ganesh section , in connection with Ujjain bypass New BG line work of Ratlam Division, Western Railway (M.P).		
Bidding type	Normal Tender		
Tender Type	Open	Bidding System	Single Packet System
Tender Closing Date Time	29/06/2026 15:00	Date Time Of Uploading Tender	28/05/2026 10:18
Pre-Bid Conference Required	No	Pre-Bid Conference Date Time	Not Applicable
Advertised Value	15303674.00	Tendering Section	TENDERING
Bidding Style	Single Rate for Tender	Bidding Unit	Above/Below/Par
Earnest Money (Rs.)	306100.00	Validity of Offer (Days)	60
Tender Doc. Cost (Rs.)	0.00	Period of Completion	12 Months
Contract Type	Works - General	Contract Category	Expenditure
Bidding Start Date	15/06/2026		
Are JV allowed to bid	No	Number of JV Member Allowed	0
Are Consortium allowed to bid	No	Number of Consortium Member Allowed	0
Ranking Order For Bids	Lowest to Highest	Expenditure Type	Capital (Works)

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A-Supply & Execution of S&T Items							15303674.00	
1	1	360.00	Man-Days	631.00	227160.00	AT Par	227160.00	
	Description:- Skilled man power to be provided by contractor for Engg. JCBs working to provide marking & supervisory work for the S&T cables during digging work by JCB's and repairing /restoring/jointing of cables, if damaged Cables & Joints Material will be provided by railway. While Chuna marking will be done by his/her Chuna will provided by contractor information for deputing skilled man power for above work will be provided by Railway Engineer incharge before 24 hours from commencement of digging by JCBs. They will check cables route by Cable route tracer and will do chuna marking and will show the cables (on rough sketch) available in a small length approximate 50-100 meters of digging. Note- Minimum two man will be provided at a time including Cable joiner, they will stay whole time during JCB digging work. (The CV to be got approved by Railway).							
2	Please see Item Breakup for details.				191300.00	AT Par	191300.00	
	Description:- Supply & fixing of GI troughing & Channel on girder bridges for carrying cables. Fixing of channel with Girder to be done with hook/ 'J' bolts of suitable size to held the load of the troughing as per Drg. No. CSTE/3004 and CSTE/3006.							
3	3	2.00	Numbers	47333.00	94666.00	AT Par	94666.00	
	Description:- Supply of Optical Line Interface card (SOT-18) for Tejas make TJ-1400 model STM equipment without SFPs. Make- TEJAS .(Warranty Period - Upto 12 months from the date of supply)							
4	4	2.00	Numbers	5129.00	10258.00	AT Par	10258.00	
	Description:- Supply of E-1 branching cards suitable for existing PrimaryDigital Mux installed in the section as per instructions of Engineer in charge. {Approval required before supply}.							
5	5	2.00	Numbers	20213.00	40426.00	AT Par	40426.00	
	Description:- Supply & Installation of Power Supply Distribution Box along with MCB/Fuse as per specification and requirement given by Site Engineer. Make- 3M, Havells, ABB or superior.							
6	6	100.00	Running Metre	559.00	55900.00	AT Par	55900.00	

**DYCSTE-C-RTM-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-RTM-123-2026-27

Closing Date/Time: 29/06/2026 15:00

	Description:- Medium Class G.I. Pipes to IS: 1239 (Pt.)-2004 or latest; 100 mm dia. (int. Dia) 3.65 mm thick or above with coupling. G.I. pipes shall have ISI mark on it and contractor should submit manufacturer's test certificate of G.I. pipes.						
	7	20.00	Numbers	1628.00	32560.00	AT Par	32560.00
7	Description:- Double Walled Corrugated (DWC) HDPE Pipe with associated collars etc. as per RDSO Specification No. RDSO/SPN/204/2011 or latest anti-rodent & anti-oxidant and non-flame propagating type in 6 meters straight length and of size 120 mm outer dia & 103.5 mm inner dia. One of the following coupling arrangements should also be supplied with each pipe as per the site requirement. (1) Suitable snap fit coupler with rubber 'O- Ring (2) Spacers (3) Tees (4) Bend, (5) End-cap (The total quantity of above items is equal to no. of pipes supplied.) DWC pipe shall be marked at every 1 mtr length in such a way that manufacturer's name, vender name and year of manufacture can be easily identified. Color -Bright Orange; Min Weight = 4kg. Test Check by Consignee & Sample check by JAG officer.						
	8	1000.00	Metre	294.00	294000.00	AT Par	294000.00
8	Description:- Supply of SPLIT DWC pipe confirming to RDSO/SPN/204/2011 Ver. 1.1 or latest RDSO specification, Non metallic, corrugated, multiwalled, normal duty, pliable, without protection against chemical attack and Non flame propagating in 2 meter length of size 200 mm outer dia & 175 mm inner dia. (Permitted tolerance in dia = +/-2mm).						
	9	1.00	Set	53129.00	53129.00	AT Par	53129.00
9	Description:- Supply of Maintenance free VRLA secondary cells duly charged of 48V 200AH and each 2.0V when fully charged 200AH capacity along with accessories i.e. inter sell connectivity links/float. 4 Nos. insulators for each cell 24 Nos. of cell per set as per RDSO Spec. IRS/S/93/96A with latest amendments with cubicle steel/hylem tray battery rack to install/house batteries. {Item shall be procured from RDSO approved vendors only}.						
	10	1.00	Numbers	58906.00	58906.00	AT Par	58906.00
10	Description:- Supply of 48V, 50A battery Charger for Telecom use as per RDSO/TL/23/99/Ver 4.0 or latest in N+1 configuration using 3 Modules of 25A with automatic switching between the modules for two sets of 200 AH Battery. It shall be equipped with surge and lightening protection of Class-B & C. {Item shall be procured from RDSO approved vendors only}.						
	11	2.00	Numbers	29920.00	59840.00	AT Par	59840.00
11	Description:- Supply of 19" covered racks, Vero President /Rittel/D-link/Valrack make or similar having the size of approximately 2.2 meters. (42U) height X 800mm width x 800mm depth and duly approved by the engineer in charge of the work. The rack shall be complete with all fittings for housing SDH/MPLS equipment, primary Muxes, DDF, MDF using krone module, and other equipment like runway ladders, etc. (fan tray, power supply arrangement 48V, etc.) completely wired and equipped with integrated protection modules for all channels as per technical specifications and other stipulations of tender document. It should be possible to lock all the equipment with only order wire telephone remaining outside the rack.						
	12	1.00	Numbers	88385.00	88385.00	AT Par	88385.00
12	Description:- Supply of Portable NMS complete with application software and all essential hardware for monitoring of existing OFC Network (It includes ALL in one PC, 128 GB Pen drive, Processor Type- Core i7, RAM -16 GB, Hard Drive- SSD 512 GB , Windows 11 and other accessories) as per instructions of Engineer incharge. Make -Dell /HP or similar.						
	13	45.00	Kilometre	44409.00	1998405.00	AT Par	1998405.00
13	Description:- "Supply of HDPE Ducts 40/33 mm dia as per RDSO/SPN/TC/45/2013 , Rev. 2.0 ,Amendment 3.0 or latest. Each km / Bundle of HDPE duct should have 2 no End Plugs, 2 no Cables ealing plugs, 2 no plastic couplers(5-6 thread) slipfit/push fit type. {The duct should be supplied in accordance with the latest WR Telecom Policy, dated January 1, 2025 or latest guideline issued.} Each colour of duct shall be supplied as specified by the Engineer-in-Charge }."						
	14	200.00	Metre	23.00	4600.00	AT Par	4600.00
14	Description:- Supply of 25 mm dia. HDPE pipe(TEC spec. No. G/CDS-08/02,Nov'04 or latest and as per IS4984 or better specifications) with accessories on wall orstructure/ in the trench, etc. for drawing of CAT-6/OFC cable/power cable in the same. All materials for jointing, fixing, clamping of HDPE pipe will be supplied by Contractor.						
	15	200.00	Metre	299.00	59800.00	AT Par	59800.00
15	Description:- Supply of 110 mm dia HDPE pipe. { ISI Mark - IS no. 4984:2016 or the latest }.						
	16	25.00	Numbers	3521.00	88025.00	AT Par	88025.00
16	Description:- Supply of Straight Joint Enclosures (SJC) complete with all accessories as per GR/OJC/02/02 Sept 2003 for 48 fiber, Make- Raychem - FOSC-400-B4-A-BJL-4-H -48 , 3M, AMPSON or Similar or Similar only, as per instruction and approval of Engineer In charge.						
	17	12.00	Numbers	20842.00	250104.00	AT Par	250104.00
17	Description:- Supply of Fiber Distribution management System size 1 U-2 U size (As per RDSO/IRS-TC-37/2000 (Ver-3) Amd-1 or latest) suitable for termination of 48 fibers. Make- 3M / RAYCHEM / Commscope or Similar as approved by the railway.						
	18	40.00	Numbers	555.00	22200.00	AT Par	22200.00

**DYCSTE-C-RTM-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-RTM-123-2026-27

Closing Date/Time: 29/06/2026 15:00

18	Description:- Supply of LC/SC/Euro PatchCords ranging from 1.5 meters to 10 meters in length, as per RDSO/SPN/TC/69/2007Rev.0, requirements/instructions of the Engineer-in-Charge.						
19	19	25.00	Numbers	1867.00	46675.00	AT Par	46675.00
19	Description:- Supply of Thermo shrink Universal Jointing kit for Quad Cable (Straight/Derivation) as per RDSO IRS/TC-77/2012 revision 3 With latest Amd.						
20	20	13.00	Numbers	1069.00	13897.00	AT Par	13897.00
20	Description:- Supply of VF tapping transformer as per RDSO spec IRS TC 76/2000 with amd 1 or latest suitable for underground quad cable circuits, magneto tele, emergency circuits.{Impedence-470:1120}.						
21	21	8.00	Numbers	888.00	7104.00	AT Par	7104.00
21	Description:- Supply of VF tapping transformer as per RDSO spec IRS TC 76/2000 with amd 1 or latest suitable for underground quad cable circuits, magneto tele, emergency circuits.{Impedance-470:600}.						
22	22	13.00	Numbers	2814.00	36582.00	AT Par	36582.00
22	Description:- Supply of Emergency control socket box (EC Socket box) Metallic Material without socket as per RDSO/SPN/44/2002 ver.2 with Amendment no. 02 or the latest amendment. {Material should be procured through RDSO approved source only}.						
23	23	13.00	Numbers	487.00	6331.00	AT Par	6331.00
23	Description:- Supply of 6 pin Emergency plug and socket flat type as per specification IRS:TC/42/87 or latest.{Material procured through RDSO approved source only}.						
24	24	8.00	Set	12767.00	102136.00	AT Par	102136.00
24	Description:- "Supply of Maintenance Free Earth as per RDSO/SPN/197/ 2008 or latest consisting of : (1) Copper bond steel electrode 3 Mtr long 17mm dia with copper bonding thickness of min. 250 micron & UL listed & marked-01 No. (2) Earth enhancement compound RDSO Approved in a sealed bag of 10 Kgs - 03 No.(3) Copper strip 150 x 25 x 6mm - 01 No.(4) Copper strip 200 x 25 x 6mm - 01 No. (5) Copper strip 300 x 25 x 6mm - 01 No. (6) 35 Sqmm Copper Cable to connect earth electrode to MEEB in duplicate - 10 Mtr Approx. (7) 16Sqmm multistrand single core PVC insulated copper cables to connect MEEB to SEEB & SPD - Min 10m(8) 10Sqmm multistrand single core PVC insulated copper cable to connect various equipment to SEEB (9) Cu Lugs (10) Earth Encloser RCC/FRP/PVC of suitable size as per instruction of the Engineer In-charge..{Material procured through RDSO approved source only}."						
25	25	1.00	Numbers	371399.00	371399.00	AT Par	371399.00
25	Description:- Supply of Automatic fusion splicer, fully automatic, RTC microprocessor controlled (Arc fusion type) splicer with video display, warm image processing, heat oven, fiber fixture, battery backup, high precision fiber cleaver,stripping tool and other accessories of Fuzikura 88S+/Swift/Sumitomo, or Similar, along with sufficient no. of splice protection sleevesand iso propyl alcohol to be supplied for test splice. {Compliant to TEC specification No.TECGR / TX / OSM-001/04 Sept.,2012 or latest with all accessories}.						
26	26	1.00	Numbers	273583.00	273583.00	AT Par	273583.00
26	Description:- Supply of OTDR suitable for 1310/1550 nm, with resolution of 60 cm, dynamic range of 42/40 dB or better, Specification, along with all other accessories, AC Adapter/Charger, Rechargeable Li-Ion battery, Manual, hard & soft carrying case, VFL Facility, internal memory, USB /Ethernet facility, compatible with LC, FC, SC, etc. Make- Yokogawa model- AQ1210 (1215E), EXFO, VIAVI, or better. {Compliant to TEC specification No. GR/TX/OTD-01/04 APR-2010 with latest amendments in force at the time of tender opening with all accessories. Authorized dealer certificate required along with equipment}.						
27	27	1.00	Numbers	35962.00	35962.00	AT Par	35962.00
27	Description:- Supply of Optical Power Metersuitable for testing ofFiber,850/1310/1550 nmcalibrated wavelength, single& multi mode operation,measurement range+3dBm/better, 0.01 dB resolution, NIST traceable,Germanium Zeo/Set Ref, CEcertified,270 Hz, 1 kHz, 2 kHzTone identification asapproved by the site incharge. {Make-OLP-35V2JDSU/latest, EXFO-EPM-50-50, GAO Tek or better}.						
28	28	1.00	Numbers	50222.00	50222.00	AT Par	50222.00
28	Description:- Supply of digital Psophometer ,Make Aplab Moda No-1072 or latest.						
	29	1.00	Set	122948.00	122948.00	AT Par	122948.00

**DYCS-TE-C-RTM-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-RTM-123-2026-27

Closing Date/Time: 29/06/2026 15:00

29	Description:- Supply of OFC Maintenance tool kit Compliant to TEC Spec No-G/OMS/01/01 April 94 or latest. One set consisting of the following- (1) Philips/Flipe/CICO/Motwani Digital Multimeter 4-1/2 digit with LCD display- (1 No). (2) Rotary duct cutter for cutting ducts (with replaceable blade)- (2 No). (3) Utility Knife - (2 No). (4) Cable slitter - (1 No). (5) Tubing cutter for cable armour - (1 No) (6) Bare fibre adaptor - (1 No) (7) Miller/Fujikura/proskit high precision stripper for fibre buffer - (3 No) (8) Pocket cleaver Fujikura (CT -08) - (1 No) (9) Mechanical splice joint set (1 set consisting of 6 nos.) (10) Ceramic scissor CSI - (2 No) (11) LC & SC adaptor with 0 dB loss - (25 No) (12) Optical fibre terminal V groove - (2 No) (13) Earth resistance measuring instruments with all accessories range 0.1 to 100 Ohm (14) Megger (A) 500V-1 No, (B) 100V- (1 No) (15) Loose tube stripper- (1 No) (16) Cord stripping plier- (1 No) (17) Krone Tool - (1 No) (18) Isopropyl Alcohol - (1 L) (19) Napkin- (500 No) (20) LC & SC attenuator with 5/10 dB loss - [(40 No (20 -20 each))] (21) Laser Distance Meter 100m Range- (01 No) (22) Visual Fault Locator pen type (range-30 km)- (01 No) (23) Fiber Protection Sleeves, 60/40mm- (200/200 No each) (24) LC to LC Connector- 20 No. (25) LAN Tester- 1 Set.						
30	30	1.00	Numbers	25094.00	25094.00	AT Par	25094.00
	Description:- Supply of Digital Transmission Measuring Set Kit, complete with Tone Generator & DB Meter as per IRS TC 43-87 with amendment - 1 or latest. It should have a facility to measure dB loss at 2 kHz also.						
31	31	1.00	Numbers	23179.00	23179.00	AT Par	23179.00
	Description:- Supply of Cross Talk Measurement Set as per IRS: TC 45-88 with latest Amd . It should have a facility to measure cross-talk at 150 kHz, also.						
32	32	1.00	Numbers	12405.00	12405.00	AT Par	12405.00
	Description:- Supply of Digital Earth Resistance tester, three-terminal type with LED display, 1999 count, KOICO model 5600 / Metravi/ Mecor or better as approved by the engineer in charge.						
33	33	1.00	Numbers	3875.00	3875.00	AT Par	3875.00
	Description:- Supply of Road Measuring Cycle, made of Aluminum with 05 digit counter, foldable with the bag.						
34	34	1.00	Numbers	2335.00	2335.00	AT Par	2335.00
	Description:- Supply of 4/2 wire Emergency portable control telephone IRS TC: 03 TC-75/99 with amendment 1&2 or latest along with standard length line cord and 6 pin plug as per RDSO Spec no. IRS TC 42/87 or latest.						
35	35	1.00	Numbers	460148.00	460148.00	AT Par	460148.00
	Description:- Supply of Cable Route Locator/Tracer set suitable for detecting underground armored, Telecom, Power, and signaling Cables with LCD graphics, Display active/passive modes, and depth range and technical specification of Model RD-8200 G /MRT/3M/Techno-AC or better as approved by the Engineer in charge. {It must have at least a 10 W transmitter and a built-in Li-ion battery cum charging facility for both transmitter & receiver, along with other accessories}.						
36	36	1.00	Numbers	139575.00	139575.00	AT Par	139575.00
	Description:- Supply of Cable fault locator with low insulation meter for cable testing of cable fault location in telecom twisted 6 Quad cable, Railway signalling cable, power cable up to 20 km. Make- Radio detection/MTR / 3M/Tellogica/Stanlay, or similar.						
37	37	1.00	Set	12078.00	12078.00	AT Par	12078.00
	Description:- Supply of Tool kit for telecommunication maintenance with a small size canvas bag with the following items:- (1) Combination Plier 8". (2) Long Nose Plier (Round nose) 6", (3) Wire Stripper Plier 6", (4) Screw Driver set (5 pieces), (5) Hexa with frame 12", (6) Double Open end D spanner set (6 to 32 mm), (7) Adjustable Spanner set 8", (8) Ball pin Hammer (200 gm), (9) Side Cutting Plier 6", (10) Soldering iron (Soldering make or similar) (11) Torch cell LED (3 cell) (Eveready, Geep or similar), (12) Auto Ranging Digital Multimeter (Meeco/Rishabh, Koico or similar) (13) Krone Tool (Krone make or similar) (14) Wago Slotted Screw driver, Insertion & Extraction Tool- 1 Set. (15) HDMI, RJ 11 & RJ 45 Cable Continuity Tester- 01 Set. (16) Quad/PJF cable Cable Continuity Tester/buzzer- 02 no. (17) Drill Machine- (Lithium-ion Impact Drill Cordless 18+1+1 Torque Settings)- 01 (18) wrapping tool- 04 All Tool items 1 to 9 of Taparia/Godrej/Jhalani make or similar.						
38	38	14.00	Numbers	559.00	7826.00	AT Par	7826.00
	Description:- Supply of 2 wire Push Button Telephones with CLI suitable for connecting the way side equipment and the system mentioned above as per DOT/TEC specifications TEC/GR/CP/Tele/002/05 2010 with latest Amd & from DOT/TEC approved sources						
39	39	20.00	Numbers	1907.00	38140.00	AT Par	38140.00
	Description:- Supply of Magneto telephone Desk Type Electronic (Push Button) as per Specification No. TC/79/2000 or latest Amd, Warranty Period - Upto 30 months from the date of supply.						
40	40	2.00	Numbers	215.00	430.00	AT Par	430.00
	Description:- Supply of Electric Board with following accessories- (i) Fuse Indicator- 01 No. (ii) Fuse- 01 No. (iii) Three Nos of 3 Pin socket (Male & Female) of 5 Ampere with ON-OFF Switch. (iv) One No of Power Socket. (v) Five meter Long Power Cable.						
41	41	100.00	Metre	933.00	93300.00	AT Par	93300.00

**DYCSTE-C-RTM-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-RTM-123-2026-27

Closing Date/Time: 29/06/2026 15:00

			Description:- Supply of Galvanised iron trunking , perforated cable tray with the cover of the same materials as per site incharge of Size 150mm * 50 mm * 1.6 mm including supply of channel, angle iron, brackets unit, nuts, bolts of proper size Complete, etc.				
42	42	8.00	Numbers	6731.00	53848.00	AT Par	53848.00
			Description:- Supply of 24V/48V Type 3 SPD/ Class D for data/communication line, Iimp 5KA (10/350 micro sec), In 5KA (8/20 micro sec), I max 20 KA, Indicative type (LED indication), and pluggable module for easy maintenance. Confirming RDSO/SPN/144/2006 or latest. Make-CITEL, Phoenix, OBO, or similar.				
43	43	2.00	Numbers	13159.00	26318.00	AT Par	26318.00
			Description:- Supply of Type 3 SPD/ Class D for coaxial line for RF, VHF, Iimp 1KA (10/350 micro sec), In 5KA (8/20 micro sec), I max 20 KA, having afrequency range of DC-3.5GHz and Removable GDT for easy maintenance. Confirming RDSO / SPN / TC /98/2011. Make-CITEL, Phoenix, OBO, or similar.				
44	44	400.00	Numbers	51.00	20400.00	AT Par	20400.00
			Description:- Disconnect Terminal Block, Screw less type, 4-wire front entry (Two in-put & Two out-put) The colour will be decided by Engineer - in - Charge. (Preferably In Blue, Red & Grey Colors in the ratio of 1:2:3) .				
45	45	40.00	Numbers	10.00	400.00	AT Par	400.00
			Description:- Supply of End plate for above item (I) 2.5mm/0.091 in thick as per site requirement.				
46	46	40.00	Numbers	10.00	400.00	AT Par	400.00
			Description:- Supply of End Stopper for above item (I) 10mm/0.0394 in width as per site requirement.				
47	47	4.00	Metre	98.00	392.00	AT Par	392.00
			Description:- Supply of Carrier Rails for above 35mm x 7.5mm, 1mm/0.039 in thickness un-slotted type as per site requirement.				
48	48	1.00	Numbers	4290.00	4290.00	AT Par	4290.00
			Description:- Phenolic laminated Sheet, grade P3 in standard size of 1220 X 1220 x 10 mm as per spec. No IS 2036 of 1995 or latest. Test report of manufacture to be supplied.				
49	49	20.00	Kilometre	888.00	17760.00	AT Par	17760.00
			Description:- Cable Route Survey & Preparation of as built final Cable Route Plan and other Plans (for OFC as well as other Telcom cables) on Auto cad for the whole section. One set will be supplied by contractor after joint survey and will be approved by Site Engineer of Railway. It includes changes during execution which shall be incorporate in the same set. After execution of work and approval from site engg after all chnages, all plans/documents on tracing paper along with Six prints of cable route plan . Jointing and splicing schedule, cable hut wiring diagram etc. in good quality folder shall be supplied by contractor. The contractor shall also supply the auto cad documents in CD/pendrive.				
50	50	4680.00	cum	195.00	912600.00	AT Par	912600.00
			Description:- Excavation of trench 300 mm wide at the bottom and 1.2 meters deep in all types of soils including clearing of trees, bushes, etc., and refilling of cable trench by excavated soil and ramming after laying of HDPE DUCT (laying of HDPE/DWC & 6 Quad. cables, PIJF cables, etc., will be paid under different items of the schedule). Where desired dimensions of trenches cannot be achieved proportionate payment will be made as decided by the Engineer-in-charge of the Railway at site. The trenching outside the station limits i.e.) between the home signal of station 'A' and to home signal of station 'B' may be done manually or by machine, as per the directions of the site in charge. In no case, the payment will be made for the trench of higher dimensions than the dimensions mentioned above.				
51	51	10000.00	Metre	677.00	6770000.00	AT Par	6770000.00
			Description:- Manual / Machine horizontal auger boring/drilling of 100mm dia Horizontal Bore across the Railway Track/ Across Road at LC gates/ in section as per requirement by Boring method at a depth of 1.65 mm from the ground level/ ground level to be considered ignoring the bank height of the bank/road etc, as per the instructions of Engineer in charge at site/as per drg No.RAILTEL/SR/OFC/2008/10 or latest.				
52	52	10.00	cum	272.00	2720.00	AT Par	2720.00
			Description:- Digging of trench 1.2 M deep from rail flange/ road level and, 0.3 Mtr to 0.6 Mtr wide and back filling after placing of DWC/ RCC/GI pipe. (Placing o f DWC/RCC/GI pipe covered separately).The ballast disturbed be screened and dressed as required by Engineer-in-charge or his representatives and road tarred immediately. For track crossing, Drg. No. CSTE/3644 Pg.7 of 11 and for Road Crossing, Drg. No. CSTE/3644 Pg. 5 of 11 are to be followed.				
53	53	10.00	cum	472.00	4720.00	AT Par	4720.00
			Description:- Digging of cable trench 0.3 Mtr. Deep and 0.3 Mtr. Wide on Asphalted Platform / Road / Hard rocky area. Refilling with earth leveling o f trenches & restoring the original surface of trenches.				
	54	100.00	cum	387.00	38700.00	AT Par	38700.00

**DYCSTE-C-RTM-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-RTM-123-2026-27

Closing Date/Time: 29/06/2026 15:00

54	Description:- Cutting of Hard rock in trenches /Preparation of cable way/Chase 150 mm wide at the bottom and 300 mm deep in hard rock (Drg prepared by contactor & approved by Engineer In charge) for laying of S&T cables where minimum required depth not possible & which is verified and agreed by Engineer In charge of the work or his representative shall be made as per Drg. No RE/S&T/ALD/SK/301/85. refilling of the same with concrete mixture of 1:3:6 from top of the cable way/ chase. Payment of concrete will be made separately through a separate item in the schedule of work.						
55	55	2220.00	Running Metre	28.00	62160.00	AT Par	62160.00
	Description:- Placing of DWC/RCC/GI pipes/split DWC along with collars in trenches at places of track and road crossings, platform cuttings etc.						
56	56	4.00	cum	3055.00	12220.00	AT Par	12220.00
	Description:- Cement concrete work for miscellaneous items i n the ratio 1 : 3 : 6 . Item includes excavation, ramming, curing and plastering with cement & sand mixture (aggregate not exceeding 3.8 cm.) (Aggregate cement & sand to be supplied by the contractor).						
57	57	2.00	cum	1675.00	3350.00	AT Par	3350.00
	Description:- Providing brick masonry in ratio 1:6 cement and mortar including plastering with 1:4 cement and sand mixture both sides, 20 mm thick each with contractor's owned class II bricks, including excavation, curing, grouting, bolting etc.wherever required. Bricks sand and cement to be supplied by the contractor.						
58	58	10.00	Day	948.00	9480.00	AT Par	9480.00
	Description:- Provision of Power supply arrangement, with contractors own Generating sets, capacity 5 KVA or above as per requirement of Station Signalling load, for testing of Signalling system in the case of irregular Local power supply /under capacity AT,s supply system at station.{Day=per Set/Day}.						
59	59	1.00	Set	1829.00	1829.00	AT Par	1829.00
	Description:- Installation, Wiring Testing and commissioning of Battery Charger and Maintenance Free VRLA Battery set at each station. This includes DC Bus bar,Power wire of suitable gauge, Casing/Caping, and other materials as per instruction of Site Engineer.						
60	60	1.00	Set	16263.00	16263.00	AT Par	16263.00
	Description:- Supply, Installation, testing and commissioning of surge protection cum safety device (Class B + Class C) suitable for single phase for Telecom Equipment as per RDSO specification No. RDSO/SPN/TC/ 98/2011, Rev. 0 with Amendment No.1 or latest.						
61	61	2.00	Numbers	2501.00	5002.00	AT Par	5002.00
	Description:- Installation of 19 " rack with necessary accessories.						
62	62	45.00	Kilometre	5719.00	257355.00	AT Par	257355.00
	Description:- Transportation and Laying of HDPE pipe as per approved cable route plan in the excavated trench, taking due care while transporting and laying the same in the trenches or other protective works. Both the end of duct should be sealed with end plugs before laying.						
63	63	45.00	Kilometre	10648.00	479160.00	AT Par	479160.00
	Description:- Blowing of OFC through HDPE duct & protective work (elicited in above item) already provided. Where it is not feasible to blow OFC due to curves, road/track crossings, bridges or for any other reason, OFC shall be drawn /laid manually as per standard procedure. All the equipments and machinery required shall be arranged by the contractor at his own cost. In case OFC is to be laid adopting 'Direct in trench' method then this item shall be paid as per accepted rate of item of this schedule. OFC and HDPE pipe shall be supplied by the railway.						
64	64	25.00	Numbers	5796.00	144900.00	AT Par	144900.00
	Description:- Preparation, splicing, makingand installation of OFC straight through joints with enclosure/ LIU termination.Splicing should be done by trained person, the losses shall not exceed beyond the prescribed limit. If losses exceed the prescribed limit, the contractor have to re-splice free of cost.						
65	65	2.00	Numbers	4451.00	8902.00	AT Par	8902.00
	Description:- Supply and installation of rack mountable LIU along with all accessories suitable for 24 F mono mode fibre. LIU supplied should be of slider type and as per instruction of Site engineer. Make-D-link, Commscope, Raychem, 3M, or similar.						
66	66	12.00	Numbers	3481.00	41772.00	AT Par	41772.00
	Description:- Installation of fiber distribution management system (Supply covered above) with all installation materials, restoration wall, floor etc., to original condition, splicing and termination of 48 fiber cable (With all materials), routing/dressing fibers as per instruction Engineer in-charge.						
67	67	1.00	Numbers	12385.00	12385.00	AT Par	12385.00

**DYCSSTE-C-RTM-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-RTM-123-2026-27

Closing Date/Time: 29/06/2026 15:00

				Description:- End to end testing of all fiber of the optical fibre cable laid under above items between Station/Cable Huts/OC & other locations. All required equipments, tools and plants shall be arranged by the contractor. Five number of printout of traces in folders of OFC parameters/ results, The per kilometer link loss shall be as per the policy/technical circulars issued by the railways from time to time.			
68	68	13.00	Kilometre	4357.00	56641.00	AT Par	56641.00
				Description:- Transportation and laying of 6 Quad/PIJF cables in Trenches/ GI pipe/RCC pipe/DWC pipe, Trunking etc as per approved cable route Plan and instruction of Site Engineer.			
69	69	25.00	Numbers	961.00	24025.00	AT Par	24025.00
				Description:- Execution of Straight/Derivation/EC Jointon Quad/PIJF Cables as per instructions by the site engineer. All the material required for the work is to be arranged by the contractor himself at his own cost, except for the Thermo Shrinkable Joint Kit. After jointing the cable through tests such as insulation test, continuity test, cable losses etc., to be carried out jointly with the Railway Engineer. If any defect or damage is observed during jointing, the contractor has to redo the joint free of cost.			
70	70	13.00	Numbers	2899.00	37687.00	AT Par	37687.00
				Description:- Fabrication and erection of EC socket box assembly as per the directions of the Engineer-in-Charge. This includes- Supply and transportation of posts of the required size as per Drawing No. DRM/S&T/RTM/2007/1 or latest revision or as per instruction of engineer in charge, Excavation of pits, fixing of EC socket boxes, and erection of the complete assembly at site, Termination of 6-Quad/PIJF cables onto the 6-pin EC socket strips inside the box. In addition to the above, the center pins of the EC sockets shall be terminated using a dedicated pair from the 6-Quad cable (derived through the tail PIJF cable) across the entire block section.			
71	71	13.00	Numbers	618.00	8034.00	AT Par	8034.00
				Description:- Painting of emergency socket assembly, and rail post by supplying one coat of red oxide as base colour and then painting the assembly as per zebra painting in black and white colours of 150 mm width.			
72	72	10.00	Numbers	4837.00	48370.00	AT Par	48370.00
				Description:- Supply and installation of RCC pre-fabricated OFC jointing Pits as per DRG. No-RDSO/TCDO/COP-21 (a)/ latest. The material shall be supplied as per the engineer in charge's instructions.			
73	73	400.00	Numbers	337.00	134800.00	AT Par	134800.00
				Description:- Supply, fixing, painting, and installation of RCC cable route marker "TELECOM" engraved and painted on both sides along the route every 50 m and route diversion as per DRG. NO. RDSO/TCDO/COP-22 (a) / as per direction of site in charge.			
74	74	8.00	Numbers	4940.00	39520.00	AT Par	39520.00
				Description:- Installation of Maintenance free Earth Electrode as per RDSO/SPN/197/2008 or Latest.			
75	75	4.00	Numbers	2967.00	11868.00	AT Par	11868.00
				Description:- Supply and fixing 20 pairs metallic DP box with locking arrangement's, krone/wagoframe /modules along with other accessories.			
76	76	14.00	Set	71.00	994.00	AT Par	994.00
				Description:- Installation of DTMF/way side Telephone in all stations, LC Gate, SP, SSP, & TSS. This includes supply and fixing of DP, PVC Channel, Telephone Bracket and laying/Termination of Switchboard Cable.			
77	77	100.00	Metre	318.00	31800.00	AT Par	31800.00
				Description:- Execution of erection of galvanized iron trunking, perforated cable tray as per site in charge. Fitting of support at an interval of 1mtr including laying of cables inside the trough and other materials as required for the work shall be supplied by the contractor.			
78	78	400.00	Numbers	12.00	4800.00	AT Par	4800.00
				Description:- Fixing of Screw less connectors on phenolic laminated sheets and fixing by stainless steel/brass nuts & bolts. This includes provision of two additional holes on the board on either side for cable conductor entry.			
79	79	1.00	Numbers	681.00	681.00	AT Par	681.00
				Description:- Fabrication and fixing of phenolic laminated sheet of size 10mm thick in Rack by providing all fixtures as per Railway Drawing including all accessories with contractor's own materials.			
80	80	20.00	Kilometre	24112.00	482240.00	AT Par	482240.00
				Description:- Preparation of cable route of buried S&T Cable using Radio Detector 8200GS or similar model GPS Model and DGPS for Trench per km. for existing cable as per the instruction of Engineer in-charge. Submission of report in KMZ file format, soft copy only. In open line section. (or other than yard section). (Kilometre = Track Kilometre)			

3. ITEM BREAKUP

**DYCSTE-C-RTM-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-RTM-123-2026-27

Closing Date/Time: 29/06/2026 15:00

Schedule A-Supply & Execution of S&T Items						
Item- 2	Supply & fixing of GI troughing & Channel on girder bridges for carrying cables. Fixing of channel with Girder to be done with hook/ 'J' bolts of suitable size to held the load of the troughing as per Drg. No. CSTE/3004 and CSTE/3006.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	(i)	Supply and fixing of GI channel of size 100 mm x 50 mm x 06 mm, 1.2 Mtr. Long	Numbers	100.00	767.00	76700.00
2	(ii)	Supply and fixing of GI troughing of size 150mm x 200 mm x 2000mm	Running Metre	100.00	1146.00	114600.00
					Total	191300.00

4. ELIGIBILITY CONDITIONS

Standard Financial Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer must have minimum average annual contractual turnover of V/N or V whichever is less; where V= Advertised value of the tender in Crore of Rupees N= Number of years prescribed for completion of work for which bids have been invited. The average annual contractual turnover shall be calculated as an average of "total contractual payments" in the previous three financial years, as per the audited balance sheet. However, in case balance sheet of the previous year is yet to be prepared/ audited, the audited balance sheet of the fourth previous year shall be considered for calculating average annual contractual turnover. The tenderers shall submit requisite information as per Annexure-VIB, along with copies of Audited Balance Sheets duly certified by the Chartered Accountant/ Certificate from Chartered Accountant duly supported by Audited Balance Sheet.	No	No	Allowed (Mandatory)

Special Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Work of a Similar Nature would mean- " Any work of OFC / Quad / Telecom Cable. "	No	No	Allowed (Mandatory)

Standard Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer must have successfully completed or substantially completed any one of the following categories of work(s) during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: (i) Three similar works each costing not less than the amount equal to 30% of advertised value of the tender, or (ii) Two similar works each costing not less than the amount equal to 40% of advertised value of the tender, or (iii) One similar work costing not less than the amount equal to 60% of advertised value of the tender.	No	No	Allowed (Mandatory)

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.
3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.
5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.

**DYCSTE-C-RTM-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-RTM-123-2026-27

Closing Date/Time: 29/06/2026 15:00

6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.
7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.
8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.
9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.
10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description
1	Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. (Click here to download the Format of Self Certification)

5. COMPLIANCE

Commercial-Compliance

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Rates are inclusive of all taxes/octroi, license fees, royalty charges, GST, and other legally leviable charges by the State, Central Government, and/or any other local authority.	No	No	Not Allowed
2	Central Government/State Government/Local bodies, Sales tax/Commercial tax/GST at the rate prescribed by the Government of India/Madhya Pradesh state government for works contracts will be recovered from the bills from time to time for works carried out in the state of Madhya Pradesh, as per the extant instruction on the subject.	No	No	Allowed (Mandatory)
3	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)

General Instructions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Please visit the website https://www.ireps.gov.in frequently till the closing date and time for any updates.	No	No	Not Allowed
2	Please download the Standard General Conditions of Contract and all the Advanced Correction Slips from www.indianrailways.gov.in .	No	No	Not Allowed
3	It shall not be obligatory on the said authority to accept the lowest tender, and no tenderer/tenderers shall demand any explanation for the cause of rejection of his/their tender.	No	No	Not Allowed
4	If the tenderers deliberately give/give wrong information in his/their tender or creates/create circumstances for the acceptance of his/their tender, the Railway reserves the right to reject such tender at any stage.	No	No	Not Allowed

**DYCSTE-C-RTM-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-RTM-123-2026-27

Closing Date/Time: 29/06/2026 15:00

5	The Railway reserves the right not to invite tenders for any of the railway work or works or to invite open or limited tenders and when tenders are called, to accept a tender in whole or in part or reject any tender or all tenders without assigning reasons for such action.	No	No	Not Allowed
6	All materials to be supplied by the contractor should be approved by the Engineer-in-Charge before use in the work.	No	No	Not Allowed

Special Conditions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Unless specifically mentioned in the schedule of rates all materials required for execution of work will be supplied by the contractor free of cost as per standard specifications and approved by the Engineer-in-charge.	No	No	Not Allowed
2	All works are to be done as per the programme fixed by the Engineer-in-charge or his authorised representative and as per their direction only.	No	No	Not Allowed
3	All materials to be supplied by the contractor should be approved by the Engineer-in-Charge before use in the work.	No	No	Not Allowed
4	No compensation for any accident whatsoever will be paid by the Railway.	No	No	Not Allowed
5	Contractor shall not start any work without the presence of the railway supervisor at the site. In case the contractor's representative starts any work in the absence of the railway Supervisor, it shall be treated as unauthorised and illegal and shall be liable for action.	No	No	Not Allowed
6	The Contractor, with the help of his Engineer or Diploma holder, as the case may be, shall make necessary Drawings, sketches, plotting, etc., as desired by the Engineer-in-charge. No extra cost shall be claimed on this account.	No	No	Not Allowed
7	The work will be executed under the supervision of the Railway Engineer-in-charge or his authorized representative at the site.	No	No	Not Allowed
8	The agency should depute a trained and certified supervisor, duly certified by ADSTE/C.	No	No	Not Allowed
9	The Contractor should make available all the necessary tools, plants, and equipment for the execution of the above work at the site during the execution of the work. A competency certificate for JCB/HDD Operator is required to be obtained from the Railways.	No	No	Not Allowed
10	The vehicles and equipment of contractors can be drafted by the Railway Administration in case of accidents or natural calamities involving human lives, and payment in respect of that would be made by operating the item as a non-scheduled item.	No	No	Not Allowed
11	The tenderer or contractor will have to execute the work, taking necessary precautions for the safety of workers, passengers, traffic, etc.	No	No	Not Allowed
12	Materials are required to be supplied as per work progress at site. Looking to the requirements of the materials at site, only necessary Materials to be supplied. The schedule for material supply may change as per site requirement as advised by the competent authority. Before supplying any materials, prior approval of the Competent Authority is required to be taken by the contractor. Materials for which prior approval of competent authority has not been taken by the contractor such materials will not be accepted by consignee.	No	No	Not Allowed

6. Documents attached with tender

S.No.	Document Name	Document Description
1	TD_123.pdf	Tender Document

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions

**DYCSTE-C-RTM-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SnT-C-RTM-123-2026-27

Closing Date/Time: 29/06/2026 15:00

thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

Signed By: RAVI SHANKAR TIWARI

Designation : Dy.CSTE CONST. RTM