

**VADODARA DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SandT_BRC_26-27_01_SIG-R

Closing Date/Time: 25/06/2026 15:00

Sr.DSTE/Co-ord/BRC acting for and on behalf of The President of India invites E-Tenders against Tender No **SandT_BRC_26-27_01_SIG-R** Closing Date/Time 25/06/2026 15:00 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

1. NIT HEADER

Name of Work	Supply, installation, testing, alteration in Electronic Interlocking (M/s Siemens make), indoor and outdoor works in connection with the Engineering works of (1) BRC Division: Creation of Siding Facilities for working of Heavy Duty Track Machines at Ankleshwar, Kapadvanj & Pratapnagar. (2) Vadodara Yard: Providing Starter Signal for Despatch of Trains to Vadodara, Ahmedabad and Godhra Side.		
Bidding type	Normal Tender		
Tender Type	Open	Bidding System	Single Packet System
Tender Closing Date Time	25/06/2026 15:00	Date Time Of Uploading Tender	29/05/2026 13:35
Pre-Bid Conference Required	No	Pre-Bid Conference Date Time	Not Applicable
Advertised Value	31348638.29	Tendering Section	WORKS
Bidding Style	Single Rate for Each Schedule	Bidding Unit	
Earnest Money (Rs.)	627000.00	Validity of Offer (Days)	60
Tender Doc. Cost (Rs.)	0.00	Period of Completion	8 Months
Contract Type	Works - General	Contract Category	Expenditure
Bidding Start Date	11/06/2026		
Are JV allowed to bid	No	Number of JV Member Allowed	0
Are Consortium allowed to bid	No	Number of Consortium Member Allowed	0
Ranking Order For Bids	Lowest to Highest	Expenditure Type	Capital (Works)

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A-Supply Items (BRCY STARTER SIGNAL (SOR RATES))							1642496.90	Above/ Below/Par
1	A1	1.00	Numbers	970.00	970.00	AT Par	970.00	
	Description:- Supply of Completion SIP in Original tracing along with Auto CAD copy in Pen Drive and Six set copies after approval.- More than four line station							
2	A2	1.00	Numbers	1044.00	1044.00	AT Par	1044.00	
	Description:- Supply of completions ST/LT/TOC in original tracing along with AutoCAD copies in Pen Drive and six set copies after approval.- More than four line station							
3	A3	7.00	Numbers	10895.41	76267.87	AT Par	76267.87	
	Description:- Main Signal Post Tubular 140 mm Dia, 5.6 Mtr Length as per IRS: S-6/81 or Latest & RDSO Drg. No. SA-24625 (Advance).							
4	A4	7.00	Set	3251.33	22759.31	AT Par	22759.31	
	Description:- "1. CI Base (As per IRS S-10 & RDSO Drg. No. 2011/M With latest assembly). 2. Pinnacle. 3. Ladder Assembly, as per RDSO Drg. No. SA-23156, with Base, Ladder Guards, Platform, Front Maintenance Platform, MS Supporting bracket to Support Ladder. 4. Signal Front Staging Complete Assembly for CLS Unit. 5. Signal back staging as per extent WR Practice."							
5	A5	7.00	Numbers	615.59	4309.13	AT Par	4309.13	
	Description:- Supply of signal no plate as per Drg no CSTE Drg No CSTE/6186.							
	B5	7.00	Numbers	8338.74	58371.18	AT Par	58371.18	

**VADODARA DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SandT_BRC_26-27_01_SIG-R

Closing Date/Time: 25/06/2026 15:00

5	Description:- Erection of CLS Post with base and signal unit on top or on OFF set Bracket, fixing of front and back staging, ladder and guards with contractor's own brackets and fixing materials. This also includes erection of auxiliary signals like calling on, shunt signal if any... The work shall be done as per instructions of Rly engineer at site. It also includes provision & fixing of maintenance platform as per design given by Engineer -In-Charge at site. It also includes supply of padlock for signal units and cable termination box. X' arms to be provided by the contractor till the signals are introduced. The Item includes cutting of Signal post if required by Site In charge. 2/3/4 aspect signal unit mounted directly on signal post.						
6	A6	6.00	Numbers	4439.28	26635.68	AT Par	26635.68
	Description:- Offset brackets for Main Signal, made of tubular steel, outer diameter 140 mm, thickness of pipe 4.5 mm. horizontal length of pipe 545 mm & vertical length of pipe 324 mm with fixing arrangement on Main Signal post as per Drawing No SW/554/G/R.						
7	A7	7.00	Numbers	28577.72	200044.04	AT Par	200044.04
	Description:- Non Metallic (FRP) color light signal housing multi-unit type for railway signaling suitable for RE area TWO Aspects. Complete without lenses, lamps and signal transformer as per RDSO DRG. No. SA 23001/A/M Adv. Alt- S and as per SPEC. No. RDSO/SPN/194/2006 (Vol. 1.0) or latest and FRP material as per RDSO SPEC. No. RDSO/SPN/151/1997 or latest.						
8	A8	6.00	Numbers	3359.74	20158.44	AT Par	20158.44
	Description:- Position Light Shunt Signal Unit Complete, with offset bracket, hood, Cover etc. as per Drg. No. SA-23840 suitable for LED Signal Lighting Unit. (Supply of LED Unit is not covered in this item).						
9	A9	5.00	Numbers	1345.93	6729.65	AT Par	6729.65
	Description:- Point insulation Complete set as per RDSO Specification IRS: S-40/84 for Switch bracket, Split-Stretcher bar & Gauge tie plates (52 Kg/60Kg as per site requirement).						
10	A10	20.00	Numbers	1120.65	22413.00	AT Par	22413.00
	Description:- Track Lead Junction Boxes as per C.Rly Drg. No.RST 11509 made from fiber glass/SMC/FRP along with terminal blocks.						
11	A11	10.00	Numbers	3523.27	35232.70	AT Par	35232.70
	Description:- Track feed battery chargers, 110V AC input, 2 to 6/10 V DC Output; as per Specn. No. IRS.S 89/ 2013 with latest amendments. Charger shall be suitable for charging 80 AH battery.						
12	A12	20.00	Numbers	2129.53	42590.60	AT Par	42590.60
	Description:- Choke Coil for Single Rail Track Circuit on 25 KV 50 Hz AC Electrified Section as per Spec No IRS S 65/1983 with latest amendments.						
13	A13	30.00	Numbers	2213.81	66414.30	AT Par	66414.30
	Description:- Low maintenance Lead acid secondary cell 2V/80 AH (Track feed Battery), shelf mounting type conforming to IRS:S- 88/2004 or latest (uncharged).						
14	A14	10.00	Numbers	978.46	9784.60	AT Par	9784.60
	Description:- Adjustable Track Feed Resistance disc type 30 ohms as per RDSO Drg. No. SA 20166/M (Adv.) with latest amendments (with Phenolic molded base).						
15	A15	18.00	Numbers	5859.41	105469.38	AT Par	105469.38
	Description:- DC neutral line relay QNA1K (QSA3), AC immune, DC neutral line 24V, 6F/6B contacts, complete with plug board, retaining clip and connectors. Conforming to BRS930A, (as applicable) IRS: S34& IRS: S23 or latest.						
16	A16	14.00	Numbers	5613.10	78583.40	AT Par	78583.40
	Description:- Universal AC ECR of Q series, type "QECX61" suitable for AC LED all signal aspect, Front & back contact Metal to Carbon type complete with plug board retaining clip & connectors conforming to Spec STS/E/Relays/AC Lit LED Signal/09/2002, BRS: 941A, IRS: S34 and IRS: S23 (as applicable).						
17	A17	10.00	Numbers	5421.40	54214.00	AT Par	54214.00
	Description:- Miniature, Plug in Type, DC Neutral ,Line Relay QSPA1, 24V DC, Slow to Pick up AC Immunized, 8F-4B Contact, Code ABDEJ Spec:BRS:933A ; IRS S 34 ; IRS S 23;IRS S 60-78.						
18	A18	10.00	Set	4878.90	48789.00	AT Par	48789.00
	Description:- Miniature, Plug in Type, M to C,DC Neutral ,Track relay, ACI, Style QTA2, 9 Ohm, 2F-1B contact, Code - FGHKX Spec : BRS :939-A & 966 (Appx-F2) & IRS : S-23, S-23,S-34 & 60.						
19	A19	10.00	Numbers	5393.68	53936.80	AT Par	53936.80
	Description:- Miniature, Plug in type, M to C, AC immunized, DC biased Track Relay, 2F-2B contacts, style QBAT-9 ohms. Code ABEJX Spec:- RDSO/SPN/84 Ver. 2 : IRS -S@ 45"44@IRS-S-23, IRS-S@ 45<45@ 78.						
20	A20	18.00	Numbers	18.60	334.80	AT Par	334.80
	Description:- Indicative type Fuse suitable to G type fuse base/holder of capacity 0.63 A - 3.0 A. (System, Rapid, Malnad or RBCO make or similar).						
21	A21	18.00	Numbers	50.99	917.82	AT Par	917.82

**VADODARA DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SandT_BRC_26-27_01_SIG-R

Closing Date/Time: 25/06/2026 15:00

22	A22	8.00	Numbers	34.44	275.52	AT Par	275.52	
	Description:- Indicative type Fuse base/ holder with cap, suitable to G type fuse of capacity 0.63A - 3.0A. (System, Rapid, Malnad or RBCO make or similar).							
23	A23	20.00	Numbers	129.41	2588.20	AT Par	2588.20	
	Description:- Indicative type Fuse Without holder 6A (System, Rapid or Malnad or RBCO make or similar) as per IRS: S-80/92.							
24	A24	100.00	Numbers	58.53	5853.00	AT Par	5853.00	
	Description:- Disconnect Terminal Block, Screw less type, as per RDSO Spec. No. RDSO/SPN/189/2004. With the latest amendments.- Disconnect Terminal Block, Screw less type, 4-wire front entry (Two in-put & Two out-put) The color will be decided by Engineer - in - Charge. (Preferably In Blue, Red & Grey Colors in the ratio of 1:2:3). as per RDSO Spec. No. RDSO/SPN/189/2004. With latest amendments. Note: Make to be approved by Railway before supply.							
25	A25	10.00	Numbers	11.07	110.70	AT Par	110.70	
	Description:- Disconnect Terminal Block, Screw less type, as per RDSO Spec. No. RDSO/SPN/189/2004. With the latest amendments.- Supply of End plate 2.5mm/0.091 in thick as per site requirement.							
26	A26	20.00	Numbers	10.86	217.20	AT Par	217.20	
	Description:- Disconnect Terminal Block, Screw less type, as per RDSO Spec. No. RDSO/SPN/189/2004. With the latest amendments.- Supply of End Stopper 10mm/0.0394 in width as per site requirement.							
27	A27	1.00	Numbers	113.88	113.88	AT Par	113.88	
	Description:- Disconnect Terminal Block, Screw less type, as per RDSO Spec. No. RDSO/SPN/189/2004. With the latest amendments.- Supply of Carrier Rails for above 35mm x 7.5mm, 1mm/0.039 in thickness un-slotted type as per site requirement.							
28	A28	100.00	Numbers	75.00	7500.00	AT Par	7500.00	
	Description:- ARA Terminal blocks with links made of PBT Spec No.s/75/2006 (Rev - 2) with latest amendments and RDSO Drg.No.SA-23741A Alt.4.							
29	A29	5.00	Numbers	51998.06	259990.30	AT Par	259990.30	
	Description:- SS Location box made of Spl Grade SS 304 of size as per Drg. No. DRM/SG/945 dtd 03.03.2011 (Half app. Case) or latest. Manufacturer's certificate in regard to grade of stainless steel and its protection level shall be submitted at the time of supply.							
30	A30	5.00	Numbers	59855.98	299279.90	AT Par	299279.90	
	Description:- SS Location box made of Spl Grade SS 304 of size as per Drg. No. DRM/SG/948 dt. 26.04.2011 (Single app. Case) or latest. Manufacturer's certificate in regard to grade of stainless steel and its protection level shall be submitted at the time of supply.							
31	A31	8.00	Numbers	5388.67	43109.36	AT Par	43109.36	
	Description:- IS 13410: Glass Reinforced Polyester Sheet Moulding Compounds (SMC) Size of Sheet : 1000x1000x8							
32	A32	0.50	Kilometre	5548.54	2774.27	AT Par	2774.27	
	Description:- Single core multi-strand wire 0.5 sq.mm. (16 conductor each dia. 0.2mm), as per IRS 76/89 (Amd3) or latest.							
33	A33	0.50	Kilometre	33366.21	16683.10	AT Par	16683.10	
	Description:- Flexible cable (Power wire), multi-strand copper conductors cross section 1x6 Sq.mm. (85 conductor each diameter 0.30 +/- 0.01) as per IS 694/1990 with insulation thickness of 0.80 mm nominal conductor resistance 3.30 ohms/km and test parameters are as per IRS(S)76/89 or latest.							
34	A34	0.50	Kilometre	136063.55	68031.77	AT Par	68031.77	
	Description:- Flexible cable (Power wire), multi-strand copper conductors cross section (1x16Sq.mm).101 Conductors each diameter 0.45 +/- 0.01 as per IS 694/2010 with insulation thickness of 1.2mm nominal conductor resistance 1.127 Ohms/Km and test parameters as per IRS(S) 76/89 or latest.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () B-Execution Items (BRC Y STARTER SIGNAL) (SOR ITEMS Except Item No. 30)							18749075.94	Above/ Below/P ar
	B1	1.00	Per Alteration	3134490.9 9	3134490.99	AT Par	3134490.99	

**VADODARA DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SandT_BRC_26-27_01_SIG-R

Closing Date/Time: 25/06/2026 15:00

1	Description:- Modification/Alteration in existing EI (Electronic Interlocking) as per latest RDSO guidelines/TAN. It includes: Design and modification in existing Interface and Interlocking circuits and logic of EI system including modification in the VDU(Video Display Unit)/ LCP(Local Control panel)/ CCIP (Control cum Indication Panel), Maintenance terminal (MPC), Data Logger, Relay rack wiring. The complete work should comply with the latest RDSO specifications and guidelines and as per approved SIP and circuit diagrams. All the material (Interface cards / relays / wiring material / connectors / fuses / communication devices etc.) shall be provided by the contractor. The work also includes the supply of modified Selection table, Interface Circuits, VDU/ LCP/CCIP diagram etc. to suit the modified SIP. It also includes the carrying out of FAT, SAT (as applicable) jointly with Railways and satisfactory commissioning. All plans/drawings/circuits etc. should be prepared on AUTO CAD, soft copy to be supplied on Pen Drive and 06 sets of hard copies also to be supplied.- Alteration involving modification from 11 up to 20 routes.						
2	B2	8.00	Per Route	313449.10	2507592.80	AT Par	2507592.80
	Description:- Modification/Alteration in existing EI (Electronic Interlocking) as per latest RDSO guidelines/TAN. It includes: Design and modification in existing Interface and Interlocking circuits and logic of EI system including modification in the VDU(Video Display Unit)/ LCP(Local Control panel)/ CCIP (Control cum Indication Panel), Maintenance terminal (MPC), Data Logger, Relay rack wiring. The complete work should comply with the latest RDSO specifications and guidelines and as per approved SIP and circuit diagrams. All the material (Interface cards / relays / wiring material / connectors / fuses / communication devices etc.) shall be provided by the contractor. The work also includes the supply of modified Selection table, Interface Circuits, VDU/ LCP/CCIP diagram etc. to suit the modified SIP. It also includes the carrying out of FAT, SAT (as applicable) jointly with Railways and satisfactory commissioning. All plans/drawings/circuits etc. should be prepared on AUTO CAD, soft copy to be supplied on Pen Drive and 06 sets of hard copies also to be supplied.- Alteration more than 20 routes.						
3	B3	1.00	Station	4795.00	4795.00	AT Par	4795.00
	Description:- Design of Existing ST/LT/TOC/RCC (Alteration) & submission of Three paper copies for approval.- More than four line station						
4	B4	7.00	Numbers	12887.18	90210.26	AT Par	90210.26
	Description:- Excavation and Casting of foundation for main signal post as per CSTE/3122 (WR) with contractor's own materials including cement and anchor bolts of standard size. The required scaffolding Ferma etc. for Casting of foundation will have to be brought by the contractor at his own cost.						
6	B6	6.00	Numbers	1930.03	11580.18	AT Par	11580.18
	Description:- Erection of Position Light shunt signal on Offset bracket on main signal.						
7	B7	5.00	Numbers	22354.53	111772.65	AT Par	111772.65
	Description:- Fixing of Electrical Point Machine on the extended sleepers at points as per std. practice and as per RDSO Drg No. SA 91 51-52 or 9710 or 9161 as per section of rails used. Item includes fixing switch extension bracket, providing insulation for switch extension bracket, fixing ground connection, adjusting opening of the switches and adjusting the point machine with crank handle. The item also includes : (i) Complete material for installation like ground-connections, switch extension brackets, point insulation material, I pipes, wiring materials, various fixing nuts & bolts including castle nuts, spring washers (ii) All smithy & fitting works required at site for complete installation. (iii) Installation of gauge tie plate & providing insulation for gauge tie plate (Insulation in William Stretcher Bar will be Provide by Railways). (iv) Wiring inside the point machine, insertion and termination of tail cable in point machine and junction boxes / location box /cable hut as per extent practice on WR and the instruction of Railway Engineer at site. (v) Supply and fixing of suitable size GI pipes with flange for taking cable into point machine. Note ; The ground connections shall be suitable to the Point Machines as specified by Engineer-in-charge and shall be suitable to the point lay out i.e. 60 Kg. / 52 Kg / 90R as per yard layout. Electrical Point Machine and M-6 / Screw less terminals will be supplied by Railways / covered in Schedule separately.						
8	B8	10.00	Per Track Circuit	6667.03	66670.30	AT Par	66670.30
	Description:- Fixing and wiring of DC track circuit equipments i.e. track feed charger, resistance, track relay, battery, PPTC fuses etc., in the Apparatus Case and battery box as per standard practice. Termination of tail cable on M 6 / Screw less terminals WAGO or FINOLEX or similar approved make terminals/ fuse blocks / HRC fuse. Item includes testing /commissioning of track circuit. Complete wiring material (including PPTC fuses) which are not covered in Schedule will be supplied by contractor. (Supply of Track feed battery charger, track feed battery, resistances & 'B' type choke & Track relays will be supplied by Railways / covered in Schedule separately).						
	B9	10.00	Set	7328.72	73287.20	AT Par	73287.20

**VADODARA DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SandT_BRC_26-27_01_SIG-R

Closing Date/Time: 25/06/2026 15:00

9	Description:- Installation of DC track circuits covering points zones also. The item includes provision of continuity bonds of seven strand PVC jacketed wire/ GI wire 8 SWG on rail joints after drilling bond-hole of 7.0/7.1/7.2mm Dia (double bond with sleeves and rail clips are to be provided at each rail joint), insertion of insulated block joint, fixing of Track lead Junction box on MS angle two numbers of size 40X40X5 mm 1200 mm length for track feed/ jumper / track relay ends of track CCTs (as per double TLJB arrangements) and also for fixing jumper cables as per insulation diagram WR Drg No. CSTE/6055 and standard practice, making rail connections through suitable insulated sleeves from Track lead Junction box at TF, jumper & TR end with seven strand PVC jacketed wire /GI wire 8 SWG, rail clips for fixing bond wire on the TLJB as per standard practice, termination of tail cables on bootleg terminals etc. TF/TR wiring shall be fixed on the suitable arrangement on PRC sleepers with the help of hooks. Hooks shall be provided on PRC sleepers with the help of suitable steel bracket. This item also includes fixing & supply of channel pins etc. The item also includes supply of MS angles/ trestles, GI wire 8 SWG / seven strand PVC jacketed wire, hooks, rail clips etc.						
10	B10	30.00	Numbers	376.10	11283.00	AT Par	11283.00
	Description:- Charging of Lead Acid Batteries (2V 80AH) with contractors' own battery grade sulphuric acid and distilled water with a minimum of two charge-discharge cycles, installation of charged batteries in groups & their connection & wiring. The work shall be done as per the extant practice of W.Rly & instruction of the Engineer-in-charge. Detailed measurements of initial charging shall be recorded jointly by the contractor & Rly's site-in-charge.						
11	B11	20.00	Numbers	1391.31	27826.20	AT Par	27826.20
	Description:- Erection, Fitting and Rail connection of Track Lead Junction Box on two supports (M.S.angle) with contractor's fixing material and PVC jacketed wire for track lead connection including angles of size 40 x 40 x 5 mm 1200 mm length This will include drilling of holes for track lead/side connections on rail. The work shall be done as per Drg. No. S&T/Const./JHS/T 115 & instructions of Rly engineer at site.						
12	B12	38.00	Numbers	366.58	13930.04	AT Par	13930.04
	Description:- Fixing & wiring of QNA1 / QNA1K relays for GPR Circuit in apparatus case as per Standard practice. Fixing and wiring material shall be supplied by the contractor.						
13	B13	1200.00	Numbers	13.19	15828.00	AT Par	15828.00
	Description:- Circuit wiring/jumpering as per circuit diagrams in the relay racks/IDF rack tag blocks. This includes preparation of Jumper sheets by wire man duly checked by firm's site supervisor & wire to wire testing as per circuit diagram. Any wrong jumper done by wireman will not be paid & correction shall be done free of cost. Jumper wires will be issued by Railways. Good quality solder resin core to be supplied by contractor for soldering of Jumper wires. Soldering of jumper wires to be done after completion of testing by Railways.						
14	B14	100.00	Numbers	22.75	2275.00	AT Par	2275.00
	Description:- Fixing of ARA Terminals /Screw less connectors and fuse blocks on phenolic laminated sheets and fixing by stainless steel/brass nuts & bolts. This includes provision of two additional holes on the board on either side for cable conductor entry.						
15	B15	200.00	Numbers	23.70	4740.00	AT Par	4740.00
	Description:- Termination of outdoor cables, main cables laid in location boxes, Cable termination rack etc. at both ends on ARA terminal or on 8 way terminals or on screw less connectors. Both ends of a cable core terminated shall be counted as one terminal. This includes all associated works of pulling out the cable from underground, peeling off insulation, dressing of cable core supported on sting rod with contractor's own material. The work shall be done as per instructions of Rly engineer at site.						
16	B16	7.00	Numbers	382.17	2675.19	AT Par	2675.19
	Description:- Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor's own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy paint will be supplied by Railways. NOTE: - The paint and primer should be from Asian Paints/ Nerolac / Dulux / Berger. The primer / enamel paints (Aluminum synthetic, black enamel, brilliant white and yellow) will be as per (IS 5660 of 1970) / (IS 2932 of 1974).- Main Signal Post with Signal Units, Surface base and complete fittings as per Western Railways standard practice.						
17	B17	20.00	Numbers	65.78	1315.60	AT Par	1315.60
	Description:- Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor's own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy paint will be supplied by Railways. NOTE: - The paint and primer should be from Asian Paints/ Nerolac / Dulux / Berger. The primer / enamel paints (Aluminum synthetic, black enamel, brilliant white and yellow) will be as per (IS 5660 of 1970) / (IS 2932 of 1974).- Track Lead Junction Box. (Black enamel outside only).						
	B18	5.00	Numbers	112.56	562.80	AT Par	562.80

**VADODARA DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SandT_BRC_26-27_01_SIG-R

Closing Date/Time: 25/06/2026 15:00

18	Description:- Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor's own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy paint will be supplied by Railways. NOTE: - The paint and primer should be from Asian Paints/ Nerolac / Dulux / Berger. The primer / enamel paints (Aluminum synthetic, black enamel, brilliant white and yellow) will be as per (IS 5660 of 1970) / (IS 2932 of 1974).- Point Machine with ground connections complete (Point Machine with Black enamel only outside and ground connections with Red Oxide).						
19	B19	1.00	cum	2061.36	2061.36	AT Par	2061.36
	Description:- Providing brick masonry in ratio 1:6 cement and mortar including plastering with 1:4 cement and sand mixture both sides, 20 mm thick each with contractor's owned class II bricks, including excavation, curing, grouting, bolting etc. wherever required. Bricks sand and cement to be supplied by the contractor.						
20	B20	1.00	cum	6259.00	6259.00	AT Par	6259.00
	Description:- Cement concrete work for miscellaneous items in the ratio 1: 3: 6. Item includes excavation, ramming, curing and plastering with cement & sand mixture (aggregate not exceeding 3.8 cm.) (Aggregate cement & sand to be supplied by the contractor).						
21	B21	10.00	cum	154.51	1545.10	AT Par	1545.10
	Description:- Earthwork in filling in embankment, guide bunds, around buried type abutments, bridge gaps, trolley refuges, rain bunds if provided, platforms etc. with earth excavated from outside railway boundary entirely arranged by the contractor at his own cost as per RDSO's latest guidelines and specifications and special condition of contract including all leads, royalty, lifts, ascents, descents, crossing of nallahs or any other obstructions. The rates shall include all dressing of bank to final profile, demarcation and setting out of profile, site clearance, removing of shrubs, roots of vegetation growth, heavy grass, benching of existing slope of old bank, all handling/re-handling. Taxes, Octroi and royalty etc. as a complete job. Cut trees shall be property of railways and to be deposited in the railway godown unless specified otherwise in the Special conditions of contract.						
22	B22	6.00	Per Unit	1062.82	6376.92	AT Par	6376.92
	Description:- Dismantling / Releasing of existing Signaling Gears. One Signalling gear will be all parts of one signal (consisting of CLS unit, Signal post along with base) or lever frame (5 levers set), or one point (consisting of all parts of a mechanical point, point machine, ground connections etc.) or one track circuits (consisting of battery box & other parts of DC Track circuit / AFTC /DAC) or one Block instruments or One Lifting Barrier or One Location Box etc. .This includes the cost of transportation of release materials to store depot or as decided by consignee in charge. This work to be done by contactors with his own vehicle and labour. (Per unit means Per Gear).						
23	B23	20.00	cum	605.41	12108.20	AT Par	12108.20
	Description:- Dismantling of Concrete foundation/ Demolishing RCC/CC/Stone work /Cutting Tar/ carpentering/ CC Flooring / Precast concrete slab/ Brick work including leading the debris inside Railway limit or outside Railway limit as directed by site in charge. This work to be done by contactors with his own vehicle and labour.						
24	B24	5.00	Numbers	7162.63	35813.15	AT Par	35813.15
	Description:- Excavation and Casting of Apparatus Case foundation with contractor's own materials including cement and anchor bolts of standard size. The required scaffolding Ferma etc. for Casting of foundation will have to be brought by the contractor at his own cost.- Single Case as per Drg No SK 748 or CSTE/5074 or SS Location						
25	B25	5.00	Numbers	5487.86	27439.30	AT Par	27439.30
	Description:- Excavation and Casting of Apparatus Case foundation with contractor's own materials including cement and anchor bolts of standard size. The required scaffolding Ferma etc. for Casting of foundation will have to be brought by the contractor at his own cost.- Half Case as per Drg No SK 747or CSTE/5074 or SS Location.						
26	B26	5.00	Numbers	1076.29	5381.45	AT Par	5381.45
	Description:- Installation of Apparatus Cases with miniature 'E' type lock on CC foundation. This includes filling of location foundations with river bed sand and plastering on top of the sand. 'E' Type lock will be provided by Railway.- Single Case						
27	B27	5.00	Numbers	657.15	3285.75	AT Par	3285.75
	Description:- Installation of Apparatus Cases with miniature 'E' type lock on CC foundation. This includes filling of location foundations with river bed sand and plastering on top of the sand. 'E' Type lock will be provided by Railway.- Half Case						
28	B28	5.00	Numbers	2445.36	12226.80	AT Par	12226.80
	Description:- Fabrication and fixing of SMC sheet in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated string rods at the back side for cable support with contractor's own materials. The work shall be done as per Drg and arrangement similar to SK 783-1/2. With latest alterations & as per instructions of Rly engineer at site.Note: SMC sheet will be taken in place of phenolic laminated sheet.- Single Case						
	B29	5.00	Numbers	777.78	3888.90	AT Par	3888.90

**VADODARA DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SandT_BRC_26-27_01_SIG-R

Closing Date/Time: 25/06/2026 15:00

29	Description:- Fabrication and fixing of SMC sheet in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated string rods at the back side for cable support with contractor's own materials. The work shall be done as per Drg and arrangement similar to SK 783-1/2. With latest alterations & as per instructions of Rly engineer at site. Note: SMC sheet will be taken in place of phenolic laminated sheet.- Half Case							
30	B30	5000.00	Numbers	1015.15	5075750.00	AT Par	5075750.00	
	Description:- Supply and placing of trunking and capping (RCC duct) of 500mm width as per DRG No.SDO/Cable laying/007(annexure-10) as detailed in document no.RDSO/SI/G/2010 Ver.1.1 or latest on guidelines on signalling cable laying.							
31	B31	1500.00	cum	839.00	1258500.00	AT Par	1258500.00	
	Description:- Excavation of cable trench as per cable route plan, 1 Mtr. deep and of 0.3 Mtr. to 0.6 Mtr wide advised by Engineer-in-charge alongside the track in normal (all type) soil/strata, conforming to distances as per cable route plan and refilling. This work includes clearing of route from bushes etc., covering of cable laid in trench by loose soil for a layer of 50mm thickness approximately before covering by bricks. The work shall be done as per the extant practice on Western Railway and instructions of Railway Engineer at site. In case 1m depth of trench is not achievable due to site conditions, specific approval of JA grade officer will be required for each site where trench depth of 1m is not possible. Without the approval of JA Grade officer, no payment for trenching will be made for trench depth less than 1m.							
32	B32	5000.00	Metre	1187.85	5939250.00	AT Par	5939250.00	
	Description:- Horizontal direction drilling/boring without damage of surface road using Auger Machine. The bore shall be 150 mm Dia & shall be done at the depth of minimum 1200 mm from the ground level. The ground level shall be considered ignoring the bank height of the bank of the road. The length of the bore shall be minimum 4 Mtr long. The HDD with or without HDPE pipe as per direction of Engineer In charge. Note: HDPE pipe supply is taken as separate item. This item also includes cable laying (HDD boring).							
33	B33	25000.00	Running Metre	9.37	234250.00	AT Par	234250.00	
	Description:- Laying of S&T Cables of various cores/ pairs/ quads in trenches/ GI pipes/ RCC pipes/ DWC pipes/ Trucking. This also includes laying of cables in track crossings & road crossings. Item includes provision of labels of colored plastic adhesive tapes or any other identifiable material on each cable to give the cable number at each G.P.(Cables will be daggered before and after its laying by contractor under supervision of Railway Representative and he will submit the meggering report of each testing). Length of the cable laid includes the length of the cable coiled for termination purposes.							
34	B34	30.00	Numbers	412.66	12379.80	AT Par	12379.80	
	Description:- Supply and installation of RCC cable route marker engraved and painted on both side along the route every 50mm and route diversion as per Drg. No 4014/00/CC4 or latest/ Stone marker.							
35	B35	25.00	Each	1269.00	31725.00	AT Par	31725.00	
	Description:- "Correspondence Test of Signalling Gears (Points, Signals, Track Circuits, ICC, BPAC etc.) during Rolling Block /Disconnections/ NI Note: Contactor/Firm should provide sufficient Manpower with Workable tools & Equipments." (Unit may be read as Per Gear)							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A1-Supply of MSDAC (SOR ITEM) (TMC SIDING AKV)							628391.42	Above/ Below/Par
1	C1	2.00	Per Detection Point (DP)	314195.71	628391.42	AT Par	628391.42	
	Description:- Supply of Multi Section Digital Axle Counter (MSDAC) for mentioned detection Point by the purchased & track Section as per SIP, complete with all accessories, cable required with each track device & card viz. Axle detectors, Track Side Electronics/DAC field units, Central Evaluator (Central Evaluator unit should be housed in a pre-fabricated rack to be supplied along with the system), reset unit, Relay unit, Event Logger & Diagnostic terminals, etc. Required for different Detection Points & Track Sections as per RDSO Specifications No. RDSO/SPN/176/2013, Ver.3 or latest and OEM/ manufacturer's specification and as per Annexures. (Quantity 01 No. = 01 DP) Inspection Authority: RDSO. Note:- As per WR's Policy No 03/2024 Para No. 3.4.2 .e .iv "VDU/Reset box can be used for resetting. At Stations having more than 10 Track sections, the Railway propose to use a separate VDU-based resetting system. Such a VDU-based system if using a PC, it must be industrial grade".							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit

**VADODARA DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SandT_BRC_26-27_01_SIG-R

Closing Date/Time: 25/06/2026 15:00

Schedule () A2-Other Supply items (SOR ITEMS) (TMC SIDING AKV)							1345716.75	Above/ Below/P ar
1	D1	3.00	Numbers	4530.07	13590.21	AT Par	13590.21	
	Description:- Position Light Shunt Signal Unit Complete with Post (made of GI Pipe of 80 mm Diameter Medium Class IS Spec. No. IS: 1239 Pt. 1/1990) Base, Hood, and Cover, etc. as per Drg. No. SA-23840, Signal Number Plate, suitable for LED Signal Lighting Unit. (Supply of LED Unit is not covered in this item).							
2	D2	2.00	Numbers	3523.27	7046.54	AT Par	7046.54	
	Description:- Supply of DC Track Circuit Accessories as follows :-- Track feed battery chargers, 110V AC input, 2 to 6/10 V DC Output; as per Specn. No. IRS.S 89/ 2013 with latest amendments. Charger shall be suitable for charging 80 AH battery.							
3	D3	2.00	Numbers	2129.53	4259.06	AT Par	4259.06	
	Description:- Supply of DC Track Circuit Accessories as follows :-- Choke Coil for Single Rail Track Circuit on 25 KV 50 Hz AC Electrified Section as per Spec No IRS S 65/1983 with latest amendments.							
4	D4	3.00	Numbers	2213.81	6641.43	AT Par	6641.43	
	Description:- Supply of DC Track Circuit Accessories as follows :-- Low maintenance Lead acid secondary cell 2V/80 AH (Track feed Battery), shelf mounting type conforming to IRS:S- 88/2004 or latest (uncharged).							
5	D5	2.00	Numbers	978.46	1956.92	AT Par	1956.92	
	Description:- Supply of DC Track Circuit Accessories as follows :-- Adjustable Track Feed Resistance disc type 30 ohms as per RDSO Drg. No. SA 20166/M (Adv.) with latest amendments (with Phenolic molded base).							
6	D6	2.00	Numbers	1120.65	2241.30	AT Par	2241.30	
	Description:- Provision of Field accessories of DC Track Circuits- Track Lead Junction Boxes as per C.Rly Drg. No.RST 11509 made from fiber glass/SMC/FRP along with terminal blocks.							
7	D7	1.00	Set	144043.40	144043.40	AT Par	144043.40	
	Description:- Supply of Tools Kit for Digital Axle Counter (Multi section/Single section). (MSDAC comply to the RDSO spec. No. RDSO/SPN/176/2013/Ver.3 or latest and manufacturer's specification and SSDAC comply to the RDSO/SPN/177/2012,Ver.3 or latest respectively). The tool kit shall be minimum equipped with the following equipments: (i) All mechanical tools shall be of reputed make like Tapania/Bosch etc. (ii) Digital multimeter true RMS type of make Fluke 189 or similar reputed make with probe set - 1 No. (iii) Adjustable torque wrenches 25-135 N/mtr with 13 mm and 19 mm inserts- 1 set (iv) Set of spanners screw drivers and soldering iron - 1 set (v) Dummy wheel - 1 No. (vi) Marking Jig - 1 No. (vii) Adapter card - 1 No. (viii) Extended wired socket to interface with diag No. stic plug - 1 No. (viii) Selector switch on panel base - 1 No. (ix) DAC EC card puller etc.							
8	D8	4.00	Numbers	4284.48	17137.92	AT Par	17137.92	
	Description:- Miniature, Plug-in Type, DC Neutral Line, Non AC Immunized Relay, Style QN1, 24 V DC, 8F-8B/12F-4BContact, Code ABCDF/ABCDE Spec: BRS: 930; IRS S 34; IRS S 23.							
9	D9	8.00	Numbers	5576.04	44608.32	AT Par	44608.32	
	Description:- Miniature, Plug-in Type, DC Neutral Line AC Immunized Relay, Style QNA1, 24 V DC, 8F-8B/12F-4BContact, Code ABDGH/ABDFH Spec: BRS: 931A; IRS S 34; IRS S 23; IRS S 60-78.							
10	D10	8.00	Numbers	5859.41	46875.28	AT Par	46875.28	
	Description:- DC neutral line relay QNA1K (QSA3), AC immune, DC neutral line 24V, 6F/6B contacts, complete with plug board, retaining clip and connectors. Conforming to BRS930A, (as applicable) IRS: S34& IRS: S23 or latest.							
11	D11	2.00	Numbers	5613.10	11226.20	AT Par	11226.20	
	Description:- Universal AC ECR of Q series, type "QECX61" suitable for AC LED all signal aspect, Front & back contact Metal to Carbon type complete with plug board retaining clip & connectors conforming to Spec STS/E/Relays/AC Lit LED Signal/09/2002, BRS: 941A, IRS: S34 and IRS: S23 (as applicable).							
12	D12	4.00	Numbers	7390.44	29561.76	AT Par	29561.76	
	Description:- Miniature, Plug-in Type, DC Neutral Line Magnetically Latched Relay, Style QL1, 24 V DC, 11F-4B Contact, Code ABDEG Spec: BRS:935A ; IRSS 34 ; IRS S 23.							
13	D13	1.00	Numbers	5421.40	5421.40	AT Par	5421.40	
	Description:- Miniature, Plug in Type, DC Neutral ,Line Relay QSPA1, 24V DC, Slow to Pick up AC Immunized, 8F-4B Contact, Code ABDEJ Spec:BRS:933A ; IRS S 34 ; IRS S 23;IRS S 60-78.							
14	D14	1.00	Set	4878.90	4878.90	AT Par	4878.90	
	Description:- Miniature, Plug in Type, M to C,DC Neutral ,Track relay, ACI, Style QTA2, 9 Ohm, 2F-1B contact, Code - FGHKX Spec : BRS :939-A & 966 (Appx-F2) & IRS : S-23, S-23,S-34 & 60.							
15	D15	1.00	Numbers	9743.97	9743.97	AT Par	9743.97	

**VADODARA DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SandT_BRC_26-27_01_SIG-R

Closing Date/Time: 25/06/2026 15:00

	Description:- Key Lock Relay working on 24V DC, AC immunize with different ward combinations (Three ward plates to be supplied with each relay). Key ward shall be specified by engineer incharge as per requirement.							
16	D16	4.00	Numbers	129.41	517.64	AT Par	517.64	
	Description:- Cartridge fuse block made of PBT as per RDSO Drg No SA-23748 Alt 4 & Spec No IRS S 75/2006 with the latest amendment. The fuse block shall be suitable for round-head type voltage fuses. This also includes the supply of equivalent no of ND type Fuses of 2A capacity as per specification IRS S-78/92.							
17	D17	20.00	Numbers	31.93	638.60	AT Par	638.60	
	Description:- D type fuse block non indicating type low voltage non deteriorating fuse base suitable for fuse link of capacity 2A/6A/10A as per specification IRS:S-80/92 or latest Quantity break up of each type of fuse block will be specified by Engineer in-charge.							
18	D18	20.00	Numbers	34.86	697.20	AT Par	697.20	
	Description:- D type fuse link non indicating type low voltage non detonating, capacity 2A/6A/10A as per specification IRS: S-80/92 or latest. Quantity break up of each type of fuse block will be specified by Engineer in-charge.							
19	D19	10.00	Numbers	10403.08	104030.80	AT Par	104030.80	
	Description:- Maintenance Free Earth Electrode of length 3m, including supply of 3 bags of Earth enhancement material for earthing (10KGs /bag) for each electrode & other accessories as per Drg. No. SDO / RDSO/ E&B/001 and RDSO Spec No. RDSO / SPN/197/2008.							
20	D20	480.00	Numbers	75.00	36000.00	AT Par	36000.00	
	Description:- ARA Terminal blocks with links made of PBT Spec No.s/75/2006 (Rev - 2) with latest amendments and RDSO Drg.No.SA-23741A Alt.4.							
21	D21	2.00	Numbers	51998.06	103996.12	AT Par	103996.12	
	Description:- SS Location box made of Spl Grade SS 304 of size as per Drg. No. DRM/SG/945 dtd 03.03.2011 (Half app. Case) or latest. Manufacturer's certificate in regard to grade of stainless steel and its protection level shall be submitted at the time of supply.							
22	D22	12.00	Numbers	59855.98	718271.76	AT Par	718271.76	
	Description:- SS Location box made of Spl Grade SS 304 of size as per Drg. No. DRM/SG/948 dt. 26.04.2011 (Single app. Case) or latest. Manufacturer's certificate in regard to grade of stainless steel and its protection level shall be submitted at the time of supply.							
23	D23	6.00	Numbers	5388.67	32332.02	AT Par	32332.02	
	Description:- IS 13410: Glass Reinforced Polyester Sheet Moulding Compounds (SMC) Size of Sheet : 1000x1000x8							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () B1-Execution items (SOR items) (TMC SIDING AKV)							8982957.28	Above/ Below/P ar
1	E1	1.00	Station	570471.00	570471.00	AT Par	570471.00	
	Description:- Re-Design of EI Systems after FAT/SAT with related to application logic & Interface Circuit. Note:-After FAT/SAT either Minimum 2 functional gear (Addition/Deletion of point/signal/Track) or modification in TOC minimum 5 routes in accordance of 3.47, 5.16 and other issues.							
2	E2	1.00	Per Alteration	3134490.99	3134490.99	AT Par	3134490.99	
	Description:- Modification/Alteration in existing EI (Electronic Interlocking) as per latest RDSO guidelines/TAN. It includes: Design and modification in existing Interface and Interlocking circuits and logic of EI system including modification in the VDU(Video Display Unit)/ LCP(Local Control panel)/ CCIP (Control cum Indication Panel), Maintenance terminal (MPC), Data Logger, Relay rack wiring. The complete work should comply with the latest RDSO specifications and guidelines and as per approved SIP and circuit diagrams. All the material (Interface cards / relays / wiring material / connectors / fuses / communication devices etc.) shall be provided by the contractor. The work also includes the supply of modified Selection table, Interface Circuits, VDU/ LCP/CCIP diagram etc. to suit the modified SIP. It also includes the carrying out of FAT, SAT (as applicable) jointly with Railways and satisfactory commissioning. All plans/drawings/circuits etc. should be prepared on AUTO CAD, soft copy to be supplied on Pen Drive and 06 sets of hard copies also to be supplied.- Alteration involving modification from 11 up to 20 routes.							
3	E3	1.00	Station	4795.00	4795.00	AT Par	4795.00	
	Description:- Design of Existing ST/LT/TOC/RCC (Alteration) & submission of Three paper copies for approval.- More than four line station							
	E4	10.00	Sheet	392.00	3920.00	AT Par	3920.00	

**VADODARA DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SandT_BRC_26-27_01_SIG-R

Closing Date/Time: 25/06/2026 15:00

4				Description:- Design of existing Circuit Diagrams consisting wiring/Logic diagram, contact analysis, fuse detail, Input/output bit chart, VDU diagram, Interface etc. (Alteration) submission of Three paper copies for approval.			
5	E5	1.00	Numbers	53506.00	53506.00	AT Par	53506.00
				Description:- Design and supply SWR Diagram on standard tracing paper of 95grams for each station. Corrected version of SWR plans after checked & approved by Rly's 25 Ferro copies will be supply for each of the plans. For stations having more than 4 lines			
6	E6	3.00	Numbers	6139.76	18419.28	AT Par	18419.28
				Description:- Foundation, Erection & Installation of Shunt Signal.- Excavation and Casting of foundation for Shunt Signal as per Drg. No. CSTE/6090 with Contractor's own materials including Cement and Anchor Bolts of Standard Size. The required scaffolding, Ferma etc. for Casting of foundation will have to be brought by the Contractor at his own cost.			
7	E7	3.00	Numbers	4169.37	12508.11	AT Par	12508.11
				Description:- Foundation, Erection & Installation of Shunt Signal.- Erection of Position Light Shunt signal with Base, Post, and Signal unit. Wiring & Fixing of Number Plate .The work shall be done as per instructions of Rly engineer at site.			
8	E8	2.00	Numbers	22354.53	44709.06	AT Par	44709.06
				Description:- Fixing of Electrical Point Machine on the extended sleepers at points as per std. practice and as per RDSO Drg No. SA 91 51-52 or 9710 or 9161 as per section of rails used. Item includes fixing switch extension bracket, providing insulation for switch extension bracket, fixing ground connection, adjusting opening of the switches and adjusting the point machine with crank handle. The item also includes : (i) Complete material for installation like ground-connections, switch extension brackets, point insulation material, I pipes, wiring materials, various fixing nuts & bolts including castle nuts, spring washers (ii) All smithy & fitting works required at site for complete installation. (iii) Installation of gauge tie plate & providing insulation for gauge tie plate (Insulation in William Stretcher Bar will be Provide by Railways). (iv) Wiring inside the point machine, insertion and termination of tail cable in point machine and junction boxes / location box /cable hut as per extent practice on WR and the instruction of Railway Engineer at site. (v) Supply and fixing of suitable size GI pipes with flange for taking cable into point machine. Note ; The ground connections shall be suitable to the Point Machines as specified by Engineer-in-charge and shall be suitable to the point lay out i.e. 60 Kg. / 52 Kg / 90R as per yard layout. Electrical Point Machine and M-6 / Screw less terminals will be supplied by Railways / covered in Schedule separately.			
9	E9	1.00	Per Track Circuit	6667.03	6667.03	AT Par	6667.03
				Description:- Fixing and wiring of DC track circuit equipments i.e. track feed charger, resistance, track relay, battery, PPTC fuses etc., in the Apparatus Case and battery box as per standard practice. Termination of tail cable on M 6 / Screw less terminals WAGO or FINOLEX or similar approved make terminals/ fuse blocks / HRC fuse. Item includes testing /commissioning of track circuit. Complete wiring material (including PPTC fuses) which are not covered in Schedule will be supplied by contractor. (Supply of Track feed battery charger, track feed battery, resistances & 'B' type choke & Track relays will be supplied by Railways / covered in Schedule separately).			
10	E10	1.00	Set	7328.72	7328.72	AT Par	7328.72
				Description:- Installation of DC track circuits covering points zones also. The item includes provision of continuity bonds of seven strand PVC jacketed wire/ GI wire 8 SWG on rail joints after drilling bond-hole of 7.0/7.1/7.2mm Dia (double bond with sleeves and rail clips are to be provided at each rail joint), insertion of insulated block joint, fixing of Track lead Junction box on MS angle two numbers of size 40X40X5 mm 1200 mm length for track feed/ jumper / track relay ends of track CCTs (as per double TLJB arrangements) and also for fixing jumper cables as per insulation diagram WR Drg No. CSTE/6055 and standard practice, making rail connections through suitable insulated sleeves from Track lead Junction box at TF, jumper & TR end with seven strand PVC jacketed wire /GI wire 8 SWG, rail clips for fixing bond wire on the TLJB as per standard practice, termination of tail cables on bootleg terminals etc. TF/TR wiring shall be fixed on the suitable arrangement on PRC sleepers with the help of hooks. Hooks shall be provided on PRC sleepers with the help of suitable steel bracket. This item also includes fixing & supply of channel pins etc. The item also includes supply of MS angles/ trestles, GI wire 8 SWG / seven strand PVC jacketed wire, hooks, rail clips etc.			
11	E11	3.00	Numbers	376.10	1128.30	AT Par	1128.30
				Description:- Charging of Lead Acid Batteries (2V 80AH) with contractors' own battery grade sulphuric acid and distilled water with a minimum of two charge-discharge cycles, installation of charged batteries in groups & their connection & wiring. The work shall be done as per the extant practice of W.Rly & instruction of the Engineer-in-charge. Detailed measurements of initial charging shall be recorded jointly by the contractor & Rly's site-in-charge.			
12	E12	2.00	Set	185.47	370.94	AT Par	370.94
				Description:- Provision of bonding with GI wire 4mm Dia (8 SWG) for track jumper & fish plate joints bonds. This will include drilling of 7.0/7.1/7.2 mm Dia holes in rails (4 Nos.) and provision of two jumpers for each bond, clipping of bonds etc. with contractors own tools as per instruction of Rly. Engineer at site.			
	E13	2.00	Numbers	1391.31	2782.62	AT Par	2782.62

**VADODARA DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SandT_BRC_26-27_01_SIG-R

Closing Date/Time: 25/06/2026 15:00

13	Description:- Erection, Fitting and Rail connection of Track Lead Junction Box on two supports (M.S.angle) with contractor's fixing material and PVC jacketed wire for track lead connection including angles of size 40 x 40 x 5 mm 1200 mm length This will include drilling of holes for track lead/side connections on rail. The work shall be done as per Drg. No. S&T/Const./JHS/T 115 & instructions of Rly engineer at site.							
14	E14	2.00	Per Detection Point (DP)	15648.00	31296.00	AT Par	31296.00	
14	Description:- Installation of track device (double rail contact) including digging of trench, track crossing, laying of anti-rodent, anti-oxidant & non-flame propagating type Double Walled Corrugated (DWC) pipe as per IS- 14930 part- I or II or latest and all other accessories as per site requirement to be for laying of transmitter and receiver cable. The item also includes installation of EJB / Track side Electronics including foundation & earthing as per OEM's guidelines and Technical requirement & specification with their own material. NOTE: Installation / programming / configuration / commissioning of Axle counter equipment to be carried out in accordance with latest guidelines issued by Railways/RDSO preferably by Authorized representative of OEM.							
15	E15	1.00	Numbers	11984.00	11984.00	AT Par	11984.00	
15	Description:- Installation of Central Evaluator of axle Counter, wiring from CT rack to Central Evaluator, installation and wiring of the reset box, LV box (if required) and associated power supply wiring. This includes supply of shielded cable of required conductor size for wiring between CT rack to evaluator rack, all other wires, power supply cable and wiring materials. The power supply cable from power room to Central Evaluator should not be less than 10 sq.mm PVC wire. Earthing as per OEM's guidelines & specification with their own material. This also includes painting and writing work on evaluator as per site requirement. NOTE: Installation /programming / configuration / commissioning of Axle counter equipment to be carried out in accordance with latest guidelines issued by Railways/ RDSO preferably by Authorised representative of OEM.							
16	E16	1.00	Station	6954.45	6954.45	AT Par	6954.45	
16	Description:- Installation, wiring & testing / commissioning of Axle Counter's Reset Box of all types in Cabin/Panel room and wiring the same to integrate with the Axle counter as per the instructions of Railway Engineer at site. This includes laying & termination of cable if any form Panel Room/Axle Counter room /Relay room to Reset Box in DWC pipe / existing ladder.(When reset box is shifted from existing building to new building).							
17	E17	28.00	Numbers	366.58	10264.24	AT Par	10264.24	
17	Description:- Fixing & wiring of QNA1 / QNA1K relays for GPR Circuit in apparatus case as per Standard practice. Fixing and wiring material shall be supplied by the contractor.							
18	E18	1.00	Numbers	5186.41	5186.41	AT Par	5186.41	
18	Description:- Fixing of KLCR and its without this includes supply of MS sheet box for fixing of KLCR relay along with push button etc. (KLCR will be supplied by Railway).							
19	E19	1.00	Numbers	1536.49	1536.49	AT Par	1536.49	
19	Description:- Supply and fixing of CH/KLCR boxes appropriate size in field / in location boxes / in SM office / at LC gate as per site condition. It should be made of Hylam /wooden (teak wood) of high quality as per requirement. Item includes supply of any minor bracket nuts, bolts and hole drilling MS angle, MS plate etc. It also includes fixing of KLCR relays in the boxes. Prior approval to be taken from Engg. In charge before supply of box.							
20	E20	10.00	Numbers	1456.79	14567.90	AT Par	14567.90	
20	Description:- Installation of Maintenance Free Earth Electrode for Maintenance Free Earth spec of RDSO/SPN/197/2008.							
21	E21	480.00	Numbers	22.75	10920.00	AT Par	10920.00	
21	Description:- Fixing of ARA Terminals /Screw less connectors and fuse blocks on phenolic laminated sheets and fixing by stainless steel/brass nuts & bolts. This includes provision of two additional holes on the board on either side for cable conductor entry.							
22	E22	480.00	Numbers	23.70	11376.00	AT Par	11376.00	
22	Description:- Termination of outdoor cables, main cables laid in location boxes, Cable termination rack etc. at both ends on ARA terminal or on 8 way terminals or on screw less connectors. Both ends of a cable core terminated shall be counted as one terminal. This includes all associated works of pulling out the cable from underground, peeling off insulation, dressing of cable core supported on sting rod with contractor's own material. The work shall be done as per instructions of Rly engineer at site.							
23	E23	3.00	Numbers	231.00	693.00	AT Par	693.00	
23	Description:- Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor's own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy paint will be supplied by Railways. NOTE: - The paint and primer should be from Asian Paints/ Nerolac / Dulux / Berger. The primer / enamel paints (Aluminum synthetic, black enamel, brilliant white and yellow) will be as per (IS 5660 of 1970) / (IS 2932 of 1974).- Shunt signal post with signal unit, surface base as per Western Railway's Standard Practice.							

**VADODARA DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SandT_BRC_26-27_01_SIG-R

Closing Date/Time: 25/06/2026 15:00

24	E24	2.00	Numbers	65.78	131.56	AT Par	131.56	
	Description:- Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor's own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy paint will be supplied by Railways. NOTE: - The paint and primer should be from Asian Paints/ Nerolac / Dulux / Berger. The primer / enamel paints (Aluminum synthetic, black enamel, brilliant white and yellow) will be as per (IS 5660 of 1970) / (IS 2932 of 1974).- Track Lead Junction Box. (Black enamel outside only).							
25	E25	1.00	Numbers	112.56	112.56	AT Par	112.56	
	Description:- Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor's own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy paint will be supplied by Railways. NOTE: - The paint and primer should be from Asian Paints/ Nerolac / Dulux / Berger. The primer / enamel paints (Aluminum synthetic, black enamel, brilliant white and yellow) will be as per (IS 5660 of 1970) / (IS 2932 of 1974).- Point Machine with ground connections complete (Point Machine with Black enamel only outside and ground connections with Red Oxide).							
26	E26	12.00	Numbers	7162.63	85951.56	AT Par	85951.56	
	Description:- Excavation and Casting of Apparatus Case foundation with contractor's own materials including cement and anchor bolts of standard size. The required scaffolding Ferma etc. for Casting of foundation will have to be brought by the contractor at his own cost.- Single Case as per Drg No SK 748 or CSTE/5074 or SS Location							
27	E27	2.00	Numbers	5487.86	10975.72	AT Par	10975.72	
	Description:- Excavation and Casting of Apparatus Case foundation with contractor's own materials including cement and anchor bolts of standard size. The required scaffolding Ferma etc. for Casting of foundation will have to be brought by the contractor at his own cost.- Half Case as per Drg No SK 747or CSTE/5074 or SS Location.							
28	E28	12.00	Numbers	1076.29	12915.48	AT Par	12915.48	
	Description:- Installation of Apparatus Cases with miniature 'E' type lock on CC foundation. This includes filling of location foundations with river bed sand and plastering on top of the sand. 'E' Type lock will be provided by Railway.- Single Case							
29	E29	2.00	Numbers	657.15	1314.30	AT Par	1314.30	
	Description:- Installation of Apparatus Cases with miniature 'E' type lock on CC foundation. This includes filling of location foundations with river bed sand and plastering on top of the sand. 'E' Type lock will be provided by Railway.- Half Case							
30	E30	12.00	Numbers	2445.36	29344.32	AT Par	29344.32	
	Description:- Fabrication and fixing of SMC sheet in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated string rods at the back side for cable support with contractor's own materials. The work shall be done as per Drg and arrangement similar to SK 783-1/2. With latest alterations & as per instructions of Rly engineer at site.Note: SMC sheet will be taken in place of phenolic laminated sheet.- Single Case							
31	E31	2.00	Numbers	777.78	1555.56	AT Par	1555.56	
	Description:- Fabrication and fixing of SMC sheet in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated string rods at the back side for cable support with contractor's own materials. The work shall be done as per Drg and arrangement similar to SK 783-1/2. With latest alterations & as per instructions of Rly engineer at site.Note: SMC sheet will be taken in place of phenolic laminated sheet.- Half Case							
32	E32	12.00	Numbers	129.26	1551.12	AT Par	1551.12	
	Description:- Lettering / Numbering Termination particulars, equipments names etc., legibly and neatly inside location boxes. This includes supply of paints of Asian Paints/ Nerolac / Dulux / Berger make. Full Case.							
33	E33	2.00	Numbers	88.18	176.36	AT Par	176.36	
	Description:- Lettering / Numbering Termination particulars, equipments names etc., legibly and neatly inside location boxes. This includes supply of paints of Asian Paints/ Nerolac / Dulux / Berger make. Half Case.							
34	E34	1000.00	Metre	1900.08	1900080.00	AT Par	1900080.00	
	Description:- Supply and fixing of polyolefin cable channel (Injection Moulded Plastic cable Duct) of size width 100/200 mm, height 155/230 internal/external, length 1 meter produced of polyolefin with fire, protection class K-1 in accordance with DIN 53438 part all for laying signaling/telecom cables, channel attachable to each other with male female swallowtail connectors and having suitable detachable cover including supply of all fixing materials like Brackets, etc. , as per RDSO STS/E/cable laying Precise Vol-IV and as per technical specifications.							
	E35	300.00	cum	839.00	251700.00	AT Par	251700.00	

**VADODARA DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SandT_BRC_26-27_01_SIG-R

Closing Date/Time: 25/06/2026 15:00

35	Description:- Excavation of cable trench as per cable route plan, 1 Mtr. deep and of 0.3 Mtr. to 0.6 Mtr wide advised by Engineer-in-charge alongside the track in normal (all type) soil/strata, conforming to distances as per cable route plan and refilling. This work includes clearing of route from bushes etc., covering of cable laid in trench by loose soil for a layer of 50mm thickness approximately before covering by bricks. The work shall be done as per the extant practice on Western Railway and instructions of Railway Engineer at site. In case 1m depth of trench is not achievable due to site conditions, specific approval of JA grade officer will be required for each site where trench depth of 1m is not possible. Without the approval of JA Grade officer, no payment for trenching will be made for trench depth less than 1m.							
36	E36	2000.00	Metre	1187.85	2375700.00	AT Par	2375700.00	
	Description:- Horizontal direction drilling/boring without damage of surface road using Auger Machine. The bore shall be 150 mm Dia & shall be done at the depth of minimum 1200 mm from the ground level. The ground level shall be considered ignoring the bank height of the bank of the road. The length of the bore shall be minimum 4 Mtr long. The HDD with or without HDPE pipe as per direction of Engineer In charge. Note: HDPE pipe supply is taken as separate item. This item also includes cable laying (HDD boring).							
37	E37	36000.00	Running Metre	9.37	337320.00	AT Par	337320.00	
	Description:- Laying of S&T Cables of various cores/ pairs/ quads in trenches/ GI pipes/ RCC pipes/ DWC pipes/ Trucking. This also includes laying of cables in track crossings & road crossings. Item includes provision of labels of colored plastic adhesive tapes or any other identifiable material on each cable to give the cable number at each G.P.(Cables will be daggered before and after its laying by contractor under supervision of Railway Representative and he will submit the meggering report of each testing). Length of the cable laid includes the length of the cable coiled for termination purposes.							
38	E38	20.00	Numbers	412.66	8253.20	AT Par	8253.20	
	Description:- Supply and installation of RCC cable route marker engraved and painted on both side along the route every 50mm and route diversion as per Drg. No 4014/00/CC4 or latest/ Stone marker.							

3. ITEM BREAKUP

No item break up added

4. ELIGIBILITY CONDITIONS

Standard Financial Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer must have minimum average annual contractual turnover of V/N or 'V' whichever is less; where V= Advertised value of the tender in crores of Rupees N= Number of years prescribed for completion of work for which bids have been invited. The average annual contractual turnover shall be calculated as an average of "total contractual payments" in the previous three financial years, as per the audited balance sheet. However, in case balance sheet of the previous year is yet to be prepared/ audited, the audited balance sheet of the fourth previous year shall be considered for calculating average annual contractual turnover. The tenderers shall submit requisite information as per Annexure-VIB, along with copies of Audited Balance Sheets duly certified by the Chartered Accountant/ Certificate from Chartered Accountant duly supported by Audited Balance Sheet	No	No	Allowed (Mandatory)

Standard Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
-------	-------------	-----------------------	-----------------	---------------------

**VADODARA DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SandT_BRC_26-27_01_SIG-R

Closing Date/Time: 25/06/2026 15:00

1	The tenderer must have successfully completed or substantially completed any of the following during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: Three similar works each costing not less than the amount equal to 30% of advertised value of the tender, or Two similar works each costing not less than the amount equal to 40% of advertised value of the tender, or One similar work each costing not less than the amount equal to 60% of advertised value of the tender. NOTE: Work experience certificate from private individual shall not be considered. However, in addition to work experience certificates issued by any Govt. Organisation, work experience certificate issued by Public listed company having average annual turnover of Rs 500 crore and above in last 3 financial years excluding the current financial year, listed on National Stock Exchange or Bombay Stock Exchange, incorporated/registered atleast 5 years prior to the date of closing of tender, shall also be considered provided the work experience certificate has been issued by a person authorized by the Public listed company to issue such certificates. In case tenderer submits work experience certificate issued by public listed company, the tenderer shall also submit along with work experience certificate, the relevant copy of work order, bill of quantities, bill wise details of payment received duly certified by Chartered Accountant, TDS certificates for all payments received and copy of final/last bill paid by company in support of above work experience certificate.	No	No	Allowed (Mandatory)
1.1	Defination of Similar Work :- Any Signaling work involving Outdoor work and/or addition and/or alteration in existing Indoor signaling system. OR Any CLS or RI or EI or TPWS or IBS or ABS or BPAC work involving Indoor and/or Outdoor. Similar work to include Indoor if the tendered work involves addition and/or alteration in existing Indoor signaling system and Outdoor if the tendered work involves Outdoor work. OR Any such work involving activities as given in the name of the tendered work.	No	No	Not Allowed

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.
3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.
5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.
6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.
7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.
8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.
9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.
10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description
-------	-------------

**VADODARA DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SandT_BRC_26-27_01_SIG-R

Closing Date/Time: 25/06/2026 15:00

1	Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. (Click here to download the Format of Self Certification)
---	---

5. COMPLIANCE

Check Lst

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	As per Tender document attached.	No	No	Not Allowed

Commercial-Compliance

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	As per Tender document attached.	No	No	Allowed (Mandatory)
2	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)

General Instructions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	As per Tender document attached.	No	No	Not Allowed

Special Conditions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	As per Tender document attached.	No	No	Not Allowed
2	Annexure-V(A) as per GCC to be uploaded - This certificate is to be given by attorney/authorized signatory/each member of Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc	No	No	Not Allowed

Technical-Compliances

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Annexure-V(A) as per GCC to be uploaded - This certificate is to be given by attorney/authorized signatory/each member of Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc	No	No	Allowed (Mandatory)

**VADODARA DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SandT_BRC_26-27_01_SIG-R

Closing Date/Time: 25/06/2026 15:00

2	Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under: 1.I/we the tenderer (s) am/are signing this document after carefully reading the contents. 2.I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof. 3.I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us. 4.I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements. 5.I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us. 6.I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us. 7.I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust. 8.I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected. 9.I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year. 10.I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)	No	No	Allowed (Mandatory)
3	As per Tender document attached.	No	No	Allowed (Mandatory)

Undertakings

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	As per Tender document attached.	No	No	Not Allowed

6. Documents attached with tender

S.No.	Document Name	Document Description
1	TDoc-26-27-01-SIG-R_1.pdf	Tender Document
2	IRSEM-AppendixII_compressed.pdf	IRSEM DRAWINGS
3	AKVTENTSIP_compressed.pdf	SIP 1
4	BRCYSIPTENT_compressed.pdf	SIP 2
5	RevisedTANonEarthingBondingetcSnTInstallation.pdf	Earthing TAN
6	2025-07-29-TAN3012VER4_250804_205106.pdf	EI TAN
7	CSTE6294.pdf	CSTE 3294
8	PolicyforPenaltyoncablecuts_Downloadedcopy.pdf	CABLE CUT PENALTY
9	CONSIGNEEINSPECTIONGUIDELINES.pdf	Consignee inspection guidelines

**VADODARA DIVISION-S AND T/WESTERN RLY
TENDER DOCUMENT**

Tender No: SandT_BRC_26-27_01_SIG-R

Closing Date/Time: 25/06/2026 15:00

10	Earthingchecklist1.pdf	EARTHING CHECKLIST
----	------------------------	--------------------

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

Signed By: HARSHIT JAIN

Designation : DSTE/W-I/BRC