

**PUNE DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-PA-SNT-WKS-S-2026-06

Closing Date/Time: 22/06/2026 15:00

Sr.DSTE/Pune acting for and on behalf of The President of India invites E-Tenders against Tender No **CR-PA-SNT-WKS-S-2026-06** Closing Date/Time 22/06/2026 15:00 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

1. NIT HEADER

Name of Work	Signal and Telecommunication work in connection with proposed construction of ROB in lieu of LC gate no.09 at Km. 224/4-5, LC gate no.10 at Km.229/7-8 and LC gate no.10A at Km. 239/0-1 in Pune-Daund section and LC gate no.38 at km 137/9-10 in Pune-Lonavala section.		
Bidding type	Normal Tender		
Tender Type	Open	Bidding System	Single Packet System
Tender Closing Date Time	22/06/2026 15:00	Date Time Of Uploading Tender	29/05/2026 16:37
Pre-Bid Conference Required	No	Pre-Bid Conference Date Time	Not Applicable
Advertised Value	10814733.35	Tendering Section	SIGNAL
Bidding Style	Single Rate for Each Schedule	Bidding Unit	
Earnest Money (Rs.)	216300.00	Validity of Offer (Days)	60
Tender Doc. Cost (Rs.)	0.00	Period of Completion	9 Months
Contract Type	Works - General	Contract Category	Expenditure
Bidding Start Date	08/06/2026		
Are JV allowed to bid	No	Number of JV Member Allowed	0
Are Consortium allowed to bid	No	Number of Consortium Member Allowed	0
Ranking Order For Bids	Lowest to Highest	Expenditure Type	Capital (Works)

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A-Supply Portion (SOR items)							3407034.15	Above/ Below/ Par
1	1	1.00	Kilometre	13905.34	13905.34	AT Par	13905.34	
	Description:- Supply of Indoor Jumper Wire ATC 1 x 1 mm dia. conforming to IRS 76/89 (Amd.3) or latest. (Inspection by Consignee)							
2	2	1.00	Kilometre	51284.29	51284.29	AT Par	51284.29	
	Description:- Supply of PVC flexible copper cable single core multistrand 1 x 2.5 Sq.mm (50 conductor each diameter 0.25 +/- 0.01) as per IS 694/2010 with latest amendment if any.with insulation thickness of 0.70mm nominal conductor resistance 7.98 ohms/Km and test parameters are as per IRS (S)76/89 (Amd.3). (Inspection by RDSO)							
3	3	28.00	Numbers	5506.62	154185.36	AT Par	154185.36	
	Description:- Supply of Phenolic 10mm thick sheet, grade P3 in standard size of 1.22X1.22 Mtr as per spec. No IS 2036 of 1995. (Inspection by Consignee)							
4	4	2600.00	Numbers	76.15	197990.00	AT Par	197990.00	
	Description:- Supply of ARA Terminal blocks with links made of PBT Specn No.IRS/75/2006 (Rev - 2) with latest amendments and RDSO Drg. No. SA-23741A Alt.4. (Inspection by RDSO)							
5	5	1200.00	Numbers	170.89	205068.00	AT Par	205068.00	
	Description:- Supply of cartridge fuse block made of PBT as per RDSO Drg. No. SA-23748 Alt.4 & Spec. No. IRS S-75/2006 with latest amendment. Fuse block shall be suitable for round head type voltage fuses. (Inspection by RDSO)							
6	6	1200.00	Numbers	73.55	88260.00	AT Par	88260.00	
	Description:- Supply of round head type non deteriorating type low voltage cartridge fuse as per Specn No IRS/S/78/92 with latest amendments. 2A/4A/6A/10A capacity. (Inspection by RDSO)							
7	7	28.00	Numbers	35.04	981.12	AT Par	981.12	

**PUNE DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-PA-SNT-WKS-S-2026-06

Closing Date/Time: 22/06/2026 15:00

	Description:- Supply of Tik-tak, piano type switches,5 A (as per IS Specification). (Inspection by Consignee)							
8	8	28.00	Numbers	242.12	6779.36	AT Par	6779.36	
	Description:- Supply of three pole plug and socket 5 Amp (as per IS Specification). (Inspection by Consignee)							
9	9	20.00	Numbers	16801.57	336031.40	AT Par	336031.40	
	Description:- Supply of Apparatus Case with godown locks with detachable handle on both the doors. Single Case as per Drg. No. SK 783-1 & 2 with latest alteration. (Inspection by Consignee)							
10	10	8.00	Numbers	13481.01	107848.08	AT Par	107848.08	
	Description:- Supply of Apparatus Case with godown locks with detachable handle on both the doors. Half Case as per Drg. No. SK 783-1 & 2 with latest alteration. (Inspection by Consignee)							
11	11	12.00	Numbers	1214.88	14578.56	AT Par	14578.56	
	Description:- Supply of earth electrode assembly as per Drg.No.CR/S&T/SK-815. (Inspection by Consignee)							
12	12	4000.00	Metre	49.73	198920.00	AT Par	198920.00	
	Description:- Supply of PVC jacketed wire rope for Track Lead connections. PVC jacketed wire rope should be of Galvanised steel wire rope 6 mm dia (6x19 stranded wire with steel core of 6 mm dia) sheathed with PVC 2mm wall thickness, overall thickness being 10 mm. PVC sheath should be made of type 6 compound as per IS 5831 of 1984 Reaffirmed 2001 and steel wire rope as per IS: 2266:2019. Reclaimed or recycled material should not be used. (Inspection by Consignee)							
13	13	288.00	Metre	1079.54	310907.52	AT Par	310907.52	
	Description:- Supply of GI pipe, inner dia. 100 mm dia. B-class as per spec. No.IS 1239 PT. 1/2004 or latest with sockets and fittings (TATA/JINDAL/ZENITH BIRLA make). (Inspection by Consignee)							
14	14	288.00	Metre	337.11	97087.68	AT Par	97087.68	
	Description:- Supply of DWC HDPE pipe with one snap fit coupler and 'O' ring conforming to IS 14930 (part 2 : 2001), Non metallic, normal duty, pliable, without protection against chemical attack and fire resistant, anti rodent, in 6 meter length of size 120 mm outer dia & 100 mm inner dia. (Inspection by Consignee)							
15	15	5000.00	Numbers	232.30	1161500.00	AT Par	1161500.00	
	Description:- Supply of RCC pipes half round of size 150 mm dia outer and 100 mm dia internal 1 mtr long matching to IS No. 458/2003 amendment-1 with Rev.4. (Inspection by Consignee)							
16	16	40.00	Numbers	3137.93	125517.20	AT Par	125517.20	
	Description:- Supply of Thermo shrink Cable Jointing kit (Reinforced) TSF-2 type generally conforming to RDSO specification RDSO/SPN/TC/57/2015 Rev 1 with modified kit contents as per CSTE's Specification No.CR/SPN/TC/57(A)/2015 Dt. 06.01.2015(Table-A) to be suitable for jointing both 10/20/50 pair PIJF and 4/6 Quad cables along with sub-kit (Table-B) for armour continuity. (Inspection by Consignee)							
17	17	4.00	Kilometre	84047.56	336190.24	AT Par	336190.24	
	Description:- Supply of Permanently Lubricated HDPE Telecom duct of size 50/42 mm and accessories as per latest Specification TEC GR No. GR/TX/CDS-008/03/March 11 with latest amendment" for OFC cable of size 24 fibre armoured in length of 1000 mtrs/roll. Duct to be supplied from TEC approved sources. (Inspection by RITES)							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () B-Execution portion (SOR items)							4796785.66	Above/ Below/P ar
1	1	1500.00	Per Unit	13.71	20565.00	AT Par	20565.00	
	Description:- Circuit wiring/jumpering as per circuit diagrams in the relay racks/IDF rack tagblocks. This includes preparation of Jumper sheets by wire man duly checked by firm's site supervisor & wire to wire testing as per circuit diagram. Any wrong jumper done by wireman will not be paid & correction shall be done free of cost. Jumper wires will be issued by Railways. Good quality solder rosin core (18 SWG PHILCO/KHOSLA MAKE) to be supplied by contractor for soldering of Jumper wires. Soldering of jumper wires to be done after completion of testing by Railways. (Unit may be read as Jumper) (Inspection by Consignee)							
2	2	150.00	Per Unit	348.69	52303.50	AT Par	52303.50	
	Description:- Relay Contact break test of indoor relay wiring. Contractor shall depute Engineer, Supervisor & wiremen technically qualified to carryout contact break testing as per approved circuit diagrams. Firm Engineer to sign circuit diagrams for break testing after carrying out the test in presence of Railway's site supervisor/Engineer. (Unit may be read as A3 Size circuit per Sheet) (Inspection by Consignee)							
	3	2.00	Lot	51163.61	102327.22	AT Par	102327.22	

**PUNE DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-PA-SNT-WKS-S-2026-06

Closing Date/Time: 22/06/2026 15:00

3	Description:- Design and supply of Detailed Signalling Circuits including Panel diagram(if required) , Route section Plan , Selection Table , Fuse & Negative Tag. Analysis , Contact analysis , Relay Rack Arrangement and wire count sheets etc. in A3 size.Completion circuit shall be plotted in AutoCAD. The contractor shall initially supply 2 sets of circuits duly signed by the circuit designer having substantial experience on design side for making such circuits, complete for approval of Railways. Railways will return one set of circuit to the contractor duly approved with alterations /corrections, if any. The contractor shall incorporate Railway's alterations/corrections in the original tracings & CD without any deviation and submit two copies of the modified circuits. Original tracings so modified & final CD complete in all respects alongwith 6 sets of final approved circuits (out of which one set shall be supplied in transparent bags. Only two sheets of circuits shall be placed in one bag each) shall be submitted to the Railways in case there are no further alteration suggested by Railways. This also includes modification in yard. for IBS/ABS/LC Gate (Inspection by Consignee)						
4	4	2.00	Lot	2880.51	5761.02	AT Par	5761.02
	Description:- Preparation of final ammonia prints of diagrams in A-3 size after tracings are approved by Railways, in four sets for final submission with one set of diagram in transparent polythene bag/lamination (only two sheets shall be placed in one polythene bag/laminated each). Every set shall be set in a plastic folder of A3 size and of good quality. The final approved tracings will be handed over to contractor by railway for this purpose and contractor will return back the same after taking out the prints for stations having less than 20 routes. for IBS/ABS/LC Gate (Inspection by Consignee)						
5	5	20.00	Numbers	2361.58	47231.60	AT Par	47231.60
	Description:- Fabrication and fixing of phenolic laminated/Fibre glass sheet in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated/with PVC pipe covered string rods at the back side for cable support with contractor's own materials. The work shall be done as per drg and arrangement similar to SK 783-1 & 2 with latest alterations & as per instructions of Rly engineer at site. Single Case (Inspection by Consignee)						
6	6	8.00	Numbers	2081.61	16652.88	AT Par	16652.88
	Description:- Fabrication and fixing of phenolic laminated/Fibre glass sheet in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated/with PVC pipe covered string rods at the back side for cable support with contractor's own materials. The work shall be done as per drg and arrangement similar to SK 783-1 & 2 with latest alterations & as per instructions of Rly engineer at site. Half Case (Inspection by Consignee)						
7	7	20.00	Numbers	509.30	10186.00	AT Par	10186.00
	Description:- Fixing of cutting in relay bases & wiring of relays with Contractors own material obtained from approved sources in location box as per the instructions of Engineer in charge. (Inspection by Consignee)						
8	8	2600.00	Per Conductor	14.74	38324.00	AT Par	38324.00
	Description:- Fixing of ARA Terminals and fuse blocks on phenolic laminated sheets and fixing by stainless steel/brass nuts & bolts.This includes provision of two additional holes on the board on either side for cable conductor entry. (Inspection by Consignee)						
9	9	5200.00	Per Conductor	11.09	57668.00	AT Par	57668.00
	Description:- Termination of cable cores on ARA terminal/fuse blocks, 8 way terminals block/ Wago terminal in the apparatus Cases/ cable termination rack.This includes all associated works of pulling out the cable from underground. The work shall be done as per location plans and instructions of Rly engineer at site. (Inspection by Consignee)						
10	10	20.00	Numbers	10369.35	207387.00	AT Par	207387.00
	Description:- Excavation and Casting of Apparatus Case foundation with contractors Anchor bolts, cement, ballast and other materials. The required scaffolding Ferma etc. for Casting of foundation will have to be brought by the contractor at his own cost - Single Case as per Drg. No. SK-803. (Inspection by Consignee)						
11	11	8.00	Numbers	10166.84	81334.72	AT Par	81334.72
	Description:- Excavation and Casting of Apparatus Case foundation with contractors Anchor bolts, cement, ballast and other materials. The required scaffolding Ferma etc. for Casting of foundation will have to be brought by the contractor at his own cost - Half Case as per Drg. No. SK-804. (Inspection by Consignee)						
12	12	20.00	Numbers	1151.61	23032.20	AT Par	23032.20
	Description:- Erection of Apparatus Cases. This includes filling of location foundations and plastering. Single Case (Inspection by Consignee)						
13	13	8.00	Numbers	883.49	7067.92	AT Par	7067.92
	Description:- Erection of Apparatus Cases. This includes filling of location foundations and plastering. Half Case (Inspection by Consignee)						
14	14	20.00	Numbers	1687.78	33755.60	AT Par	33755.60

**PUNE DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-PA-SNT-WKS-S-2026-06

Closing Date/Time: 22/06/2026 15:00

14	Description:- Installation of Eqpt. (Relays, resistance, chargers batteries etc.as applicable) & wiring of the same in apparatus Cases as per location diagrams & circuit diagrams, as per Instruction of site incharge and practice. Single Case (Inspection by Consignee)						
15	15	8.00	Numbers	1146.94	9175.52	AT Par	9175.52
	Description:- Installation of Eqpt. (Relays, resistance, chargers batteries etc.as applicable) & wiring of the same in apparatus Cases as per location diagrams & circuit diagrams, as per Instruction of site incharge and practice. Half Case (Inspection by Consignee)						
16	16	12.00	Numbers	2908.63	34903.56	AT Par	34903.56
	Description:- Installation of earth electrode assembly as per Drg.No.RE/S&T/SIG/Tender/SK726/85 including earth wire connected through GI wire 8 SWG supported on M.S. flat of size 6mm x 40 mm to earth electrode as per drg. No. CR/S&T/SK-815 for sigg. Equipment such as lever frames, apparatus case, signals, relay racks,block insurments, and etc. as per RE manual. The earth value should be less than 10 Ohms including the lead wire. The value should be measured in presence of Rly. supervisor. It should be documented and painted on earth enclosure made of concrete. (Only earth electrode will be supplied by Railway). All other material required for provision of earthing will be brought by the contractor. (Inspection by Consignee)						
17	17	2000.00	cum	367.07	734140.00	AT Par	734140.00
	Description:- Excavation of cable trench as per cable route plan, 1.0 mt. deep and 300mm wide along side the track in normal soil/strata, conforming to distances as per cable route plan and refilling after cable laying. This work includes covering of cable laid in trench by loose soil for a layer of 50 mm thickness after clearing of route, bushes, etc. It shall be ensured that top of the cables laid is at a depth of 0.8 m or more. If it is less, then the width and depth shall be suitably increased and accordingly proportionate payment shall be made. In case depth of trench is not achievable due to site conditions proportionate payment will be made as per procedure. The work shall be done as per the extant practice on Central Railway and instructions of Railway Engineer at site. Drg. No. SK-805. (Inspection by Consignee)						
18	18	190.00	cum	611.79	116240.10	AT Par	116240.10
	Description:- Excavation of cable trench as per cable route plan,1.0 mt. deep and 300mm wide along side the track in hard soil, conforming to distances as per cable route plan and refilling after cable laying. This work includes covering of cable laid in trench by loose soil for a layer of 50mm thickness after clearing of route,bushes etc. It shall be ensured that top of the cables laid is at a depth of 0.8m or more. If it is less, then the width and depth shall be suitably increased and accordingly proportionate payment shall be made. In case depth of trench is not achievable due to site conditions proportionate payment will be maden as per procedure. The work shall be done as per the extant practice on Central Railway and instructions of Railway Engineer at site. Drg. No. SK-805. (Inspection by Consignee)						
19	19	200.00	cum	3058.96	611792.00	AT Par	611792.00
	Description:- Cutting of all types of Roads/ platforms (ecxcept concrete type) for trenching and excavation to depth of 300mm X 300mm wide approx. and refilling after laying of RCC/GI /DWC pipe & to restore them to original condition. The work shall be done as per extant practice on C.Rly & instructions of Rly engineer at site. Drg. No. SK-807. (Inspection by Consignee)						
20	20	288.00	Metre	73.38	21133.44	AT Par	21133.44
	Description:- Fixing of GI pipes for crossing the culverts, bridges etc. and concreting of ends with brick masonry at both ends as per the instruction of Rly engineer at site. (Inspection by Consignee)						
21	21	200.00	cum	671.12	134224.00	AT Par	134224.00
	Description:- Digging of trench 1.0 M deep from rail flange/road level (for LC) and 0.3 Mtrs. to 0.6 Mtrs wide and back filling after placing of DWC/RCC/GI pipe.(Placing of DWC/RCC/GI pipe coverd separately. The ballast disturbed be screened and dressed as required by Engineer-in-charge or his representatives and road tarred immediately. Drg. No. SK-806. (Inspection by Consignee)						
22	22	288.00	Metre	59.62	17170.56	AT Par	17170.56
	Description:- Laying of DWC/RCC pipes alongwith collars in trenches at places of track and road crossings, platform cuttings etc. (Inspection by Consignee)						
23	23	36.00	Kilometre	5450.97	196234.92	AT Par	196234.92
	Description:- Laying of signalling/Power/Telecom cable of various cores/sizes in trenches. (Inspection by Consignee)						
24	24	170.00	cum	5589.55	950223.50	AT Par	950223.50
	Description:- Wherever depth of 0.5M cable trench is not feasible, cable shall be protected as under:- Preparation of cement mixture 1:3:6 with contractor's own materials and spreading cement concrete mixture layer of 100 mm thick over the already laid cables in the excavated trench. (Inspection by Consignee)						
25	25	40.00	Numbers	1745.04	69801.60	AT Par	69801.60
	Description:- Making of Thermoshrink straightht through/derivation/ transformer /PIJF cable joint for underground jelly filled cable 6 quad/4quad/20 pair 10 pair etc. PIJF cable as per the instruction of Rly engineer at site. (Inspection by Consignee)						
	26	300.00	Metre	3003.33	900999.00	AT Par	900999.00

**PUNE DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-PA-SNT-WKS-S-2026-06

Closing Date/Time: 22/06/2026 15:00

26	Description:- Horizontal boring of cable duct of minimum 2.0 Mtr. depth alongwith laying of 120mm HDPE pipe for track crossing with minimum depth reckoned from the bottom of the rail/road crossing with minimum depth reckoned from ground level. The work shall be done as per extant practice & instructions of site Engineer. Prepration of site for Horizontal boring shall be carried out in presence of Railway Representative. HDPE will be supplied by Railways. Note:- Contractor shall provide all material required for boring and adequate nos. of labours for proper laying of cables into the bore. Cable shall be laid cautiously so that it should not get damage due to rough handling & pressure on cable. (Inspection by Consignee)							
27	27	5000.00	Metre	41.07	205350.00	AT Par	205350.00	
	Description:- Laying of RCC half round cement pipe of approximate size (Pipe of 150 mm x 1 mtr long) inside the trench after laying of cable. Pipes shall be placed as per directives of engineer. (Inspection by Consignee)							
28	28	20.00	Numbers	456.68	9133.60	AT Par	9133.60	
	Description:- Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor's own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy paint will be supplied by Railways. NOTE:- The paint and primer should be from M/s Asian paints Co. Ltd. The paints will be primer (IS 5660 of 1970) the Aluminium synthetic black enamel (IS 2932 of 1974) brilliant white and yellow Painting two coats of enamel paint over one coat of primer. Apparatus Cases Full size. (Inspection by Consignee)							
29	29	8.00	Numbers	342.94	2743.52	AT Par	2743.52	
	Description:- Painting of two coats of synthetic enamel paint over one coat of primer on the following after scraping & cleaning surface wherever necessary with contractor's own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy paint will be supplied by Railways. NOTE:- The paint and primer should be from M/s Asian paints Co. Ltd. The paints will be primer (IS 5660 of 1970) the Aluminium synthetic black enamel (IS 2932 of 1974) brilliant white and yellow Painting two coats of enamel paint over one coat of primer. Apparatus Cases Half size. (Inspection by Consignee)							
30	30	20.00	Numbers	276.39	5527.80	AT Par	5527.80	
	Description:- Lettering / Numbering Termination particulars, equipments names etc., legibly and neatly inside location boxes. Full Case. (Inspection by Consignee)							
31	31	8.00	Numbers	157.35	1258.80	AT Par	1258.80	
	Description:- Lettering / Numbering Termination particulars, equipments names etc., legibly and neatly inside location boxes. Half Case. (Inspection by Consignee)							
32	32	4.00	Kilometre	5464.60	21858.40	AT Par	21858.40	
	Description:- Laying of HDPE duct in trench and its protective work as per direction of site engineer. (Inspection by Consignee)							
33	33	4.00	Kilometre	12819.67	51278.68	AT Par	51278.68	
	Description:- Blowing/Drawing of OFC cable in HDPE/DWC duct and protective work, as per direction of site engineer. (Inspection by Consignee)							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () C-Supply & Execution portion (Non-SOR items)							2610913.54	Above/ Below/Par
1	1	4.00	Job	6126.40	24505.60	AT Par	24505.60	
	Description:- Excavation for OFC PIT for cable jointing of size 1.5 M X 1.5 M X 1.2 M for all type of soils, the section back filling the pit and ramming after jointing, provision of brick walling the four walls and bottom of PIT with RCC slab, back filling with earth and ramming per drawing N.B All the materials included cement required for the above will be supplied by the tenderer. (Inspection by Consignee)							
2	2	1.00	Numbers	69099.33	69099.33	AT Par	69099.33	
	Description:- Supply of Electronics LC Gate Telephone system as per spec no-RDSO/SPN/TC-51/2011 Rev 3.0 or latest of make EPSILON or BENTRON. This includes - (1) Master Telephone with inbuilt voice logging facility one number, (2) Slave Telephone three numbers & (3) 24V DC Power Supply Unit with 2 nos. SMF battery one nos. (Inspection by Consignee)							
3	3	300.00	Metre	672.75	201825.00	AT Par	201825.00	
	Description:- Supply of 110mm HDPE pipe for laying in Horizontal Borrying. (Inspection by Consignee)							
4	4	1.00	Numbers	60475.80	60475.80	AT Par	60475.80	
	Description:- Supply of Optical Time Domain Reflectometer (OTDR) Fluke / Deviser/ Techtest / Vevai / Fibershot. (Inspection by Consignee)							
	5	2.00	Numbers	29595.94	59191.88	AT Par	59191.88	

**PUNE DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-PA-SNT-WKS-S-2026-06

Closing Date/Time: 22/06/2026 15:00

5	Description:- Supply of AC and DC low current clamp meterwith range 1mA to 100 A; make GTC CM 100 orsimilar model from make Fluke, Rishab, Motwaneor similar. (Inspection by Consignee)						
6	6	18.00	Numbers	26985.40	485737.20	AT Par	485737.20
6	Description:- Supply of digital earth tester of Motwane makemodel DET-20 or similar. (Inspection by Consignee)						
7	7	5.00	Numbers	10015.89	50079.45	AT Par	50079.45
7	Description:- Supply of True RMS DigitalMultimeter, 4000 Count, Voltage:1000V AC/DC. Make Fluke 17B+ orDI-LOG 9206 or Megger Modelno.AVO410. (Inspection by Consignee)						
8	8	3050.00	Metre	24.90	75945.00	AT Par	75945.00
8	Description:- Supply of UTP CAT-6 cable in a roll of 305 meter and make Siemen/ Systemax / Panduit/ Tyco/ Krone/ AMP or similar. ACCEPTED MAKE BRAND-FINOLEX (Inspection by Consignee)						
9	9	13.00	Numbers	19300.30	250903.90	AT Par	250903.90
9	Description:- Supply, preparation, splicing and installation of straight joint for 48 fibers along with enclosures with heat shrinkable splice protection sleeve as per TEC/GR/TX/OJC-002/03/APR-2010 or latest. Splice losses in no case should be more than 0.1 dB. (Inspection by Consignee)						
10	10	2.00	Numbers	413768.31	827536.62	AT Par	827536.62
10	Description:- Supply of GPS tagging featured cable route locator/tracer set suitable for detecting underground armoured optic fiber cable (OFC) and signalling cables with LCD Graphc Display active/passive modes and depth range. 3M-10 M. Model STLOC10 GPS make Stanlay or equivalent. (Inspection by RITES)						
11	11	3.00	Numbers	54906.72	164720.16	AT Par	164720.16
11	Description:- Battery operated High performance LED area with 3000 lumens output light weight & unbreakable as per specification attached (1) Product specification M18 HAL -+ M18 NRG 502B (2) Article No. 493345123 (3) Battery compatibility all Milwaukee M18 Batteries (4) Battery capacity (Ah) 5.0 (5) Battery type Li ion (6) No of Battery charger supplied 01 No. (7) Full Battey charging time 59 min (8) Max light output 3000/1500/650 (9) Max run time battery 2/4/9 hr. (10) No. of batteries supplied 2 Nos. (11) Voltage (AC) (V) 220-240 (12) Voltage (DC) (V) 18 (13) Wight with battery pack (kg) 3 (14) One year onsite warranty, installation & training free of cost make Eibenstock/Milwaukee or equivalent. (Inspection by Consignee)						
12	12	2.00	Set	38940.00	77880.00	AT Par	77880.00
12	Description:- Axle Counter Cable Conductor's Earth resistance Sensing Unit, Microcontroller Based for 24 Nos. conductors with metering facility for one conductor at a time.as per attached technical specification. (Inspection by Consignee)						
13	13	4.00	Numbers	65753.40	263013.60	AT Par	263013.60
13	Description:- Supply of maintenance console as per specification mentioned in Chapter 3.1. (Inspection by Consignee)						

3. ITEM BREAKUP

No item break up added

4. ELIGIBILITY CONDITIONS

Standard Financial Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	For Standard Financial Criteria, please refer Para No.1.1.2 of Chapter-I of Tender Document [Also refer to the Para 10.2 of the Tender Form (Second Sheet) of GCC April-2022] and Advance Correction Slip no.1 issued by Railway Board vide letter no.2022/CE-I/CT/GCC-2022/Policy dated 14.07.2022, same is re-iterated below: The tenderer must have minimum average annual contractual turnover of V/N or 'V' whichever is less; where V= Advertised value of the tender in crores of Rupees N= Number of years prescribed for completion of work for which bids have been invited. The average annual contractual turnover shall be calculated as an average of "total contractual payments" in the previous three financial years, as per the audited balance sheet. However, in case balance sheet of the previous year is yet to be prepared/ audited, the audited balance sheet of the fourth previous year shall be considered for calculating average annual contractual turnover. The tenderers shall submit requisite information as per Annexure-VIB of GCC April-2022, along with copies of Audited Balance Sheets duly certified by the Chartered Accountant/ Certificate from Chartered Accountant duly supported by Audited Balance Sheet.	No	No	Allowed (Mandatory)

**PUNE DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-PA-SNT-WKS-S-2026-06

Closing Date/Time: 22/06/2026 15:00

Standard Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	For Standard Technical Criteria, please refer Para No.1.1.1 of Chapter-I of Tender Document [Also refer to the Para 10.1 of the Tender Form (Second Sheet) of GCC April-2022].	No	No	Allowed (Mandatory)
1.1	Defination of Similar Work :- "Trenching cable laying location and signal foundation / erection / termination / wiring in connection with any signaling work". OR "Any Indoor or combined indoor/outdoor signaling including supply, installation, testing and commissioning of relay interlocking (RRI/PI) system for passenger carrying lines".	No	No	Not Allowed

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.
3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.
5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.
6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.
7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.
8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.
9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.
10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description
1	Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. (Click here to download the Format of Self Certification)

5. COMPLIANCE

Commercial-Compliance

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)

**PUNE DIVISION-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-PA-SNT-WKS-S-2026-06

Closing Date/Time: 22/06/2026 15:00

General Instructions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Please refer to the attached documents - "Tender Document" and "GCC April 2022 with all ACS".	No	No	Not Allowed

Special Conditions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Please refer to the attached documents - "Tender Document" and "GCC April 2022 with all ACS".	No	No	Not Allowed

Undertakings

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	I/ We have visited the works site and I / We am / are aware of the site conditions.	No	No	Not Allowed

Custom

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	EFT Payment Details: Payment will be made through Electronic Fund Transfer system (RTGS/NEFT) only. Tenderer is requested to give their Bank Details in the PROFORMA given in the "Tender Document" for making payment through RTGS/NEFT. Tenderer should upload/attach the scan copy of this PROFORMA duly filled, signed and stamped at the time of submission of online tender (E-tender).	No	No	Allowed (Mandatory)

6. Documents attached with tender

S.No.	Document Name	Document Description
1	TenderDocument.pdf	Tender Document
2	GCC_April-2022_With_All_Correction_SlipsACS11.pdf	GCC April 2022 with all ACS

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

Signed By: PIYUSH PRABHAKAR KUMBHAR

Designation : DSTE/GSU/Pune